
GOVERNMENT OF INDIA


DEPARTMENT OF ARCHAEOLOGY

CENTRAL ARCHÆOLOGICAL LIBRARY

CALL No. 938,005/J.H.S. AGC. No. 25964

D.G.A. 79-GIPN St. ID. G. Amb. N. D. 57 -25-9-58-179,006.






LA do sur gis

THE JOURNAL

OF

HELLENIC STUDIES





The Society for the Promotion of Wellenic Studies .

THE JOURNAL

OF

HELLENIC STUDIES

25964

938.005 VOLUME XVIII. (1898)

J. H. S.



PUBLISHED BY THE COUNCIL, AND SOLD ON THEIR BEHALF

BY

MACMILLAN AND CO., LIMITED, ST. MARTIN'S STREET, LONDON, W.C.

MIDOCOXQVIII

The Rights of Translation and Reproduction are Reserved

LIBRARY, NEW JOINE.

Acc. No. 25969

Date. 21-2-57

Call No. 938-955/ J-H-5

XXX

RICHARD CLAY AND SONS, LIMITED, LONDON AND BUNGAY.

CONTENTS.

Rules of the Society List of Officers and Members					
List of Officers and Members Proceedings of the Society, 1897-8 Proceedings of the Cambridge Branch of the Society Additions to the Library List of Periodical Publications in the Library List of the Mystae (Plates I - III.) Some Corrections and Additions List of Periodical Publications in the Library List of the Mystae (Plates I - III.) List of Periodical Publications of the British School at Melos the Holl of the Mystae (Plates I - III.) List of Periodical Publications of the British School at Melos the Holl of the Mystae (Plates I - III.) List of Periodical Publications of the British School at Melos the Holl of the Mystae (Plates I - III.) List of Periodical Publications of Publication of Publications of Publications of Publications of School of Publications of Pu	Rules of the Society		ix		
Proceedings of the Society, 1897-8					
Proceedings of the Cambridge Branch of the Society Additions to the Library List of Periodical Publications in the Library ANDERSON (J. G. C.) The Text of the Homeric Hymns Part V. 23 ANDERSON (J. G. C.) Some Corrections and Additions Bosanquer (R. C.) Excavations of the British School at Melos the Hall of the Mystae (Plates IHI.) Bosanguer (R. C.) Excavations of the British School at Melos the Hall of the Mystae (Plates IHI.) Bosanguer (R. C.) Notes on Pylos and Sphaeteria Boures Burnows (R. W.) The Arabs in Asia Minor (041-750), from Arabia Sources Burnows (R. M.) Pylos and Sphaeteria (Plates VIIX.) Mr. G. B. Grundy on Pylos and Sphaeteria. 345 Bury (J. B.) The Double City of Megalopolis Gardner (E. A.) A Head in the possession of Philip Nelson, Esq. M.B. (Plate XI.) Grundy (G. B.) A Suggested Characteristic in Thukydidas' Work Battles, Ancient and Modern 332 HILL (G. F.) A Dedication to Artemis Source Sull. MYARS (J. L.) See Paton (W. R.) Paron (W. R.) and Myraes (J. L.) On Some Karian and Hellenic Oil-Presses 200 PREDICE (P. Coin-types of some Kilkian Cities (Plates XII. XIII.) MYRES (J. L.) See Paton (W. R.) Paron (W. R.) and Myraes (J. L.) On Some Karian and Hellenic Oil-Presses 200 PREDICE (P. C.) The Gamo of Morra 129 Richards (G. C.) Archaeology in Greece, 1897–1898 328 Satrin (A. H.) Illustrations to Bacchylides (Plate XIV.) 267 VERRALL (A. W.) Death and the Horse 133 WHITE (B. E.) Women in Ptolomaic Egypt 258 WOODHOUSE (W. J.) Fine Grocks at Plataia 351 WHITE (R. E.) Women in Ptolomaic Egypt 258 WOODHOUSE (W. J.) The Grocks at Plataia 359 Vonke (V. W.) Inscriptions from Eastern Asia Minor 366 John Of Subjects (Vols, xviii.) 351			-		
Additions to the Library			200		
List of Periodical Publications in the Library Alam (T. W.) The Text of the Homeric Hymns Part V. 33 Anderson (J. G. C.) A Summer in Phrygia: Part II. (Plates IV. V.) 34 Some Corrections and Additions 340 Bosanquer (R. C.) Excavations of the British School at Melos, the Hall of the Mystae (Plates IIII.) 60 Notes on Pylos and Sphaeteria 155 Breogs (E. W.) The Arabs in Asia Minor (041-750), from Arabic Sources 182 Buersows (R. M.) Pyles and Sphaeteria (Plates VIIX.) 147 Mr. C. B. Grundy on Pylos and Sphaeteria 345 Bury (J. B.) The Double City of Megalopotia 156 Gardiner (E. A.) A Head in the possession of Philip Nelson, Esq. M.B. (Plate XI.) 141 Gardiner (P.) Boress and Oreithyla on a late Attic Vase (Plates VI.) 136 Grundy (G. B.) A Suggested Characteristic in Thukydides Work 218 HILL (G. F.) A Dedication to Artemis 302 HILL (G. F.) A Dedication to Artemis 302 HILL (G. F.) Coin-types of some Killkian Cities (Plates XII. XIII.) 161 Myrres (J. I.) See Payor (W. B.) Payor (W. R.) and Myrres (J. L.) On Some Karian and Hellenic Oil-Presses 200 Presses					
ACLEN (T. W.) The Text of the Homeric Hymns Part V. 23 Anderson (J. G. C.) A Summer in Phrygis: Part II. (Plates IV., V.). 81 Besanquet (R. C.) Excavations and Additions 140 Besanquet (R. C.) Excavations of the British School at Melos: the Holl of the Mystae (Plates LIII.) 60 Notes on Pylos and Sphaeteria 155 Brooms (E. W.) The Arabs in Asia Minor (041-750), from Arabic Sources. 182 Buerows (R. M.) Pylos and Sphaeteria (Plates VIIX.) 147 Mr. G. B. Grundy on Pylos and Sphaeteria 345 Buer (J. B.) The Double City of Megalopoits 15 Gardene (E. A.) A Head in the possession of Philip Nelson, Esq., M.B. (Plate XII.) 141 Greds (P.) Boress and Oreithyla on a late Attic Vase (Plates VI.) 156 Grundy (G. B.) A Suggested Characteristic in Thukydides Work 218 Battles, Ancient and Modern 232 Hill (G. F.) A Deflication to Artemis 302 Imboor Blumer (F.) Coin-types of some Kilikian Cities (Plates XII., XIII.) 161 Myres (J. I.) See Paton (W. R.) Payon (W. R.) and Myres (J. L.) On Some Karian and Hellenic Oil-Presses 209 Perdale (A. H.) Death and the Horse 129 Richards (G. C.) Archaeology in Greece, 1897–1898 328 Smith (A. H.) Death and the Horse 129 Walters (H. B.) On some Black-figured Vases recently acquired by the British Museum (Plates XVXVII.) 281 White (J. F.) Note on some Attic Stalai 133 White (R. E.) Women in Ptolemaic Egypt 288 Woodhouse (W. J.) The Grocks at Plataia 383					
ANDERSON (J. G. C.) A Summer in Phrygia: Part II. (Plates IV., V.). 81					
Besanquet (R. C.) Exervations of the British School at Melos the Holl of the Mystae (Plates 1—111.) Brooss (E. W.). The Arabs in Asia Minor (041–750), from Arabic Sources. Buerows (R. M.) Pylos and Sphacteria (Plates VII.—X.) Mr. G. B. Grundy on Pylos and Sphacteria. 345 Buey (J. B.) The Double City of Megalopoits. A Head in the pessession of Philip Nelson, Esq., M.B. (Plate XI.). Gandner (P.) Boress and Oreithyia on a late Attic Vase (Plates VI.) Grundy (G. B.) A Suggested Characteristic in Thukydides Work. Battles, Ancient and Modern. 322 HILL (G. F.) A Dedication to Artemis. Sources. XIIL. Myraes (J. L.) See Paton (W. B.) Payon (W. R.) and Myraes (J. L.) On Some Karian and Hellenic Oil-Presses. Perdairs (G. C.) Sarri (A. H.) Ulustrations to Bacchylides (Plate XIV.) Verball (A. W.) Death and the Horse. 1 Walters (H. B.) On some Black-figured Vases recently acquired by the British Museum (Plates XVXVII.) White (J. F.) Note on some Attic Stelat. Wooddnove (W. J.) The Greeks at Plataia. Sources. 360 Sarri (A. E.) Wooddnove (W. J.) The Greeks at Plataia. Sources. 361 Sources.					
Besanquet (R. C.) Exervations of the British School at Melos the Hall of the Mystae (Plates L-III.) Notes on Pylos and Sphacteria Buscors (E. W.) The Arabs in Asia Minor (941-750), from Arabic Sources. Buscows (R. M.) Pylos and Sphacteria (Plates VII.—X.) Mr. G. B. Grundy on Pylos and Sphacteria. 345 Busy (J. B.) The Double City of Megalopolis 15 Gardener (E. A.) A Head in the possession of Philip Nelson, Esq., M.B. (Plate XI.) Green and Oreithyla on a late Attic Vase (Plate VI.) Green (P.) Boreas and Oreithyla on a late Attic Vase (Plate VI.) Battles, Ancient and Modern Battles, Ancient and Modern Battles, Ancient and Modern Battles, Ancient and Modern Sage Paron (W. R.) Myrrs (J. L.) See Paron (W. R.) Paron (W. R.) and Myrrs (J. L.) Presses 200 Perentalizer (P. F.) The Game of Morra Bignards (G. C.) Archaeology in Greece, 1897-1898 328 Sattle (A. H.) Uerrali (A. H.) Uerrali (A. W.) Death and the Horse Walters (H. B.) On some Black-figured Vases recently acquired by the British Misseum (Plates XV.—XVII.) White (J. F.) Note on some Attic Stelat White (V. W.) Inscriptions from Eastern Asia Minor 305 Index of Subjects (Vols, xvii., xviii.) 535			LOUIS .		
Holl of the Mystae (Plates 1111.)	Day a vortem (B) (C)		10.4%		
Runder (E. W.) The Arabs in Asia Minor (041-750), from Arabic Sources 182 Burrows (R. M.) Pylos and Sphacteria (Plates VII.—X.) 147 Mr. G. B. Grundy on Pylos and Sphacteria 345 Bury (J. B.) The Double City of Megalopolis 15 Gardner (E. A.) A Head in the possession of Philip Nelson, Esq., M.B. (Plate XI.). 141 Gardner (P.) Borass and Oreithyts on a late Attic Vase (Plate VI.) 136 Grundy (G. B.). A Suggested Characteristic in Thinkydidas' Work. 218 Battles, Ancient and Modern 232 Hill (G. F.) A Delication to Artemis 302 Imnoor-Bilmer (F.). Coin-types of some Kilkian Cities (Plates XII XIII.) 161 Myrrs (J. I.). See Pator (W. B.) Payor (W. R.) and Myrrs (J. L.) On Some Karian and Hellenic Oil-Presses 200 Prediction to Bacchylides (Plate XIV.) 267 Richards (G. C.) Archaeology in Greece, 1897–1898 328 Saith (A. H.) Illustrations to Bacchylides (Plate XIV.) 267 Verball (A. W.) Death and the Horse 1 Walters (H. B.) On some Black-figured Vases recently acquired by the British Misseum (Plates XV.—XVII.) 281 White (J. F.) Note on some Attic Stelat 133 White (R. E.) Women in Ptolomaic Egypt 238 Woodhouse (W. J.) The Greeks at Platain 33 Yomes (V. W.) Inscriptions from Eastern Asia Minor 306 Index of Subjects (Vols, xvii., xviii.) 353	TENNAGUET (W. 10)		160		
BROCHS (E. W.)					
Burrows (R. M.) Pylos and Sphacteria (Plates.VII.—X.) 147 "Mr. G. B. Grundy on Pylos and Sphacteria	FF (FF) 1/77		Earer		
BUBBOWS (R. M.) Pylos and Sphaeteria (Plates.VII.—X.) 147 Mr. G. B. Grundy on Pylos and Sphaeteria. 345 BURY (J. B.) The Double City of Megalopolis 15 Gardner (E. A.) A Head in the possession of Philip Nelson, Esq., M.B. (Plate XI.) 141 Gardner (P.) Boreas and Oreithyia on a late Attic Vase (Plate VI.) 136 Gardner (P.) A Suggested Characteristic in Thinkydides Work 218 Battles, Ancient and Modern 232 Hill (G. F.) A Dedication to Artemis 302 fanoor-Bilwer (F.) Coin-types of some Kilikian Cities (Plates XII. XIII.) 161 Myres (J. I.) See Parox (W. R.) Parox (W. R.) and Myres (J. L.) On Some Karian and Hellenic Oil-Presses 209 Prindards (G. C.) Archaeology in Greece, 1897—1898 328 Sarri (A. H.) Illustrations to Bacchylides (Plate XIV.) 267 Verrail (A. W.) Death and the Horse 1 Walters (H. B.) On some Black-figured Vases recently acquired by the British Museum (Plates XV.—XVII.) 281 White (J. F.) Note on some Attic Stelai 133 White (R. E.) Women in Ptolemaic Egypt 258 Woodhouse (W. J.) The Greeks at Plataiai 336 Index of Subjects (Vols, xvii., xviii.) 353	THOORS (To selling	A SECOND PROPERTY OF THE PROPE	100		
Mr. G. B. Grundy on Pylos and Spharteria	Management was linear a		1000		
BURY (J. B.) The Double City of Megalopolis	STATE OF STA				
Gardner (E. A.) A Head in the possession of Philip Nelson, Esq., M.B. (Plate XI.)					
M.B. (Plate XI.)	A CONTRACTOR OF THE CONTRACTOR		133		
GRINDNER (P.) Boreas and Oreithyia on a late Attic Vase (Plate VI.) GRUNDY (G. B.) A Suggested Characteristic in Thukydides' Work. 218 Battles, Ancient and Modern	GARDNER (IS. A.)		2.11		
Grundy (G. B.) A Suggested Characteristic in Thukydides Work. 218 Battles, Ancient and Modern 232 Hill (G. F.) A Dedication to Artemis 302 Imnoor-Bilder (F.) Coin-types of some Kilikian Cities (Plates XII. XIII.) 161 Myres (J. I.) See Paton (W. R.) Paton (W. R.) and Myres (J. L.) On Some Karian and Hollenic Oil- Presses 209 Perdatzet (P. F.) The Game of Morra 129 Richards (G. C.) Archaeology in Greece, 1897–1898 328 Seith (A. H.) Illustrations to Bacchylides (Plate XIV.) 267 Verrall (A. W.) Death and the Horse 1 Walters (H. B.) On some Black-figured Vases recently acquired by the British Misseum (Plates XV.—XVII.) 281 White (J. F.) Note on some Attic Stelat 133 White (R. E.) Women in Ptolemaic Egypt 238 Woodhouse (W. J.) The Greeks at Platain 306 Index of Subjects (Vols, xviii.) 353		M.B. (Plate XI.)	141		
GRUNDY (G. B.) A Suggested Characteristic in Thukydides' Work. 218 Battles, Ancient and Modern	GIHDNER (P.)		1.175.07		
Hill. (G. F.) A Dedication to Artemis So2 Innoop-Bildmen (F.) Coin-types of some Kilikian Cities (Plates XII XIII.) Myres (J. I) Paron (W. R.) Paron (W. R.) Paron (W. R.) Persses Cop Person (W. R.) The Game of Morra Richards (G. C.) Archaeology in Greece, 1897—1898 Softh (A. H.) Ullustrations to Bacchylides (Plate XIV.) Verrall (A. W.) Death and the Horse Walters (H. B.) On some Black-figured Vases recently acquired by the British Museum (Plates XV.—XVII.) White (J. F.) Note on some Attic Stelan White (R. E.) Woodhouse (W. J.) The Greeks at Plataini Yomes (V. W.) Inscriptions from Eastern Asia Minor 306 Index of Subjects (Vols. xvii., xviii.)					
Hill. (G. F.) A Dedication to Artemis	GRUNDY (G. B.)				
Innoop-Bilumer (F.) Coin-types of some Kilikian Cities (Plates XII XIII.) XIII.) Myres (J. I) See Paton (W. R.) Paton (W. R.) and Myres (J. L.) On Some Karian and Hollenic Oil- Presses 200 Perdenizer (P. F.) The Game of Morra 129 Richards (G. C.) Archaeology in Greece, 1897—1898 328 Serth (A. H.) Illustrations to Bacchylides (Plate XIV.) 267 Verrall (A. W.) Death and the Horse 1 Walters (H. B.) On some Black-figured Vases recently acquired by the British Museum (Plates XV.—XVII.) 281 White (J. F.) Note on some Attic Stelan 133 White (R. E.) Women in Ptolemaic Egypt 238 Woodhouse (W. J.) The Greeks at Plataini 33 Yomes (V. W.) Inscriptions from Eastern Asia Minor 306 Index of Subjects (Vols. xvii., xviii.) 353					
MYRES (J. I.) See Paton (W. R.)			302		
Myres (J. I.) See Paton (W. R.) Paton (W. R.) and Myres (J. L.) On Some Karian and Hellenic Oil- Presses 200 Perdelect (P. F.) The Game of Morra 129 Richards (G. C.) Archaeology in Greece, 1897–1898 328 Seith (A. H.) Illustrations to Bacchylides (Plate XIV.) 267 Verball (A. W.) Death and the Horse 11 Walters (H. B.) On some Black-figured Vases recently acquired by the British Museum (Plates XV.—XVII.) 281 White (J. F.) Note on some Attic Stelat 133 White (R. E.) Women in Ptolemaic Egypt 238 Woodhouse (W. J.) The Greeks at Plataini 33 Yorke (V. W.) Inscriptions from Eastern Asia Mimor 306 Index of Subjects (Vols. xvii., xviii.) 353	IMBOOF-BIUMER (P.)		-		
PATON (W. R.) and Myres (J. L.) On Some Karian and Hellenic Oil- Presses			101		
Presses	Мунка (J. 1)				
PREDRIZET (P. F.) The Game of Morra	PATON (W. R.) and MYRES (J. L.) On Some Karian and Hellenic Oil-				
RICHARDS (G. C.) Archaeology in Greece, 1897–1898			1000		
RICHARDS (G. C.) Archaeology in Greece, 1897-1898	PERDRIZET (P. F.)				
VERBALL (A. W.) Death and the Horse		Archaeology in Greece, 1897-1898			
VERBAIL (A. W.) Death and the Horse 1 WALTERS (H. B.) On some Black-figured Vases recently acquired by the British Museum (Plates XV.—XVII.) 281 WHITE (J. F.) Note on some Attic Stelar 133 WHITE (R. E.) Women in Ptolemaic Egypt 238 WOODHOUSE (W. J.) The Grocks at Plataini 30 YORKE (V. W.) Inscriptions from Eastern Asia Minor 306 Index of Subjects (Vols. xvii., xviii.) 353	Sarrii (A. H.)	Illustrations to Bacchylides (Plate XIV.)	267		
WALTERS (H. B.) On some Black-figured Vases recently acquired by the British Museum (Plates XVXVII.) 281 WHITE (J. F.) Note on some Attic Stelat 133 WHITE (R. E.) Women in Ptolemaic Egypt 238 WOODHOUSE (W. J.) The Greeks at Plataini 30 YOBES (V. W.) Inscriptions from Eastern Asia Mimor 306 Index of Subjects (Vols. xviii., xviii.) 353		Death and the Horse	1		
the British Museum (Plates XV.—XVII.) 281 White (J. F.) Note on some Attic Stelat 133 White (R. E.) Women in Ptolemaic Egypt 238 Woodnouse (W. J.) The Greeks at Plataini 33 Yours (V. W.) Inscriptions from Eastern Asia Minor 306 Index of Subjects (Vols. xvii., xviii.) 353		On some Black-figured Vases recently acquired by			
WHITE (R. E.) Women in Ptolemaic Egypt 238 WOODHOUSE (W. J.) The Greeks at Plataini 33 Young (V. W.) Inscriptions from Eastern Asia Minor 306 Index of Subjects (Vols. xvii., xviii.) 353	THE STREET STREET	the British Museum (Plates XVXVII.)	281		
WHITE (R. E.) Women in Ptolemaic Egypt 238 WOODHOUSE (W. J.) The Greeks at Plataini	WHITE (J. F.)	Note on some Attic Stelar	133		
WOODHOUSE (W. J.) The Greeks at Plataini 33 Young (V. W.) Inscriptions from Eastern Asia Minor 306 Index of Subjects (Vols. xviii., xviii.)			238		
Young (V. W.) Inscriptions from Eastern Asia Minor 306 Index of Subjects (Vols. xviii.) 353			33		
Index of Subjects (Vols. xvii., xviii.) 353			306		
			353		
Greek Index (Vois xviii, xviii.) 261			361		

LIST OF PLATES.

- L. Mosaic at Melos:
- IL , (Detail : Gazelle).
- III. .. (Detail: Cock).
- IV. Map of Phrygia Paroreios. (Inset: the Phrygo-Lydian Frontier.)
- V. Map of the District round Synnada.
- VL Boreas and Oreithyia, (Vase in the Ashmolean Museum)
- VII. Views of Pylos and Sphacteria.
- VIII. Views of Pylos.
 - IX. Views of Pylos.
 - X. Views of Sphacteria.
 - XL Head in the possession of Philip Nelson, Esq., M.B.
- XII. XIII. Cilician Coins,
 - XIV. Theseus and Amphitrite.
 - XV. The Sacrifice of Polyxena.
 - XVI. The Departure of a Warrior.
 - XVII. (1) Combat over Fallen Warrior,
 - (2) Kyathos by Nikosthenes.

LIST OF ILLUSTRATIONS IN THE TEXT.

		PAGE
Map of the Battle-field of Plataiai	200	34
Tyche and Plutus (from the Hall of the Mystae, Meles)	37.5	60
Site of the Hall of the Mystae, Melos: View from E. end	209.1	62
n n n n m and m u W. n m	146	65
Pavement in ,, ,, ,, ,, Key Plan		67
e in it is in Theorytion	***	72
Statue of Hierophant	*(0	7.4
Marble Basis " " " " " " " " " " " " " " " " " "	100	76
Bust of Aurelia Euposia " " " " " " " " " " " " " " " " " " "	333	72
Morra: Gold Ring (Imperial Ottoman Museum)	1598	129
from R.F. Hydria (Działynski)	÷iv.	130
Bronze Figure from Foggia (B.M.)	1000	131
Gold Ring (B. M.)	100	132
Kratev in Ashmolean Museum (Reverse)	30	137
Plan of the makade Impa on Sphacteria	- 0 44	153
Wall on Sphaeteria	77.7	154
Oil-Press at Arginanta in Kalymnes	. Est	210
Press-Beds from Karia, Tripoli, and Kalymnos	1,00	212
Hellenic Fortress and Oil-Press at Emporio in Kalymnos	ide	213
Press-Bod from Lykastos, Crete	555	214
Press-Bed at Klimatovúni in Melos	- 555	213
Weightstones for Oil-Presses	- 20	210
Crossus on Pyre (Vase in Louvre)	3 111	268
Death of Meleager (Vase at Naples)		976

CONTENTS.

		-
Thebe on Cadmos Vase of Asstean	410	271
Daughters of Proctos (Vase at Naples)	949	978
Heracles and Lion (Vase in B.M.)	hen.	374
Heracles Sacrificing (Vase at St. Petersburg)		275
Theseus Receiving Wreath from Amphitrite (Vase at Bologna)	790	277
Thesens and Poseidon (Vase in Bibl. Nat. Paris)	77	278
(Vase in Collection of Princess di Tricase)	***	279
Ship of Theseus (Seene from François Vase)	P-970	280
Corinthian b.f. Oenochoe (B.M.)) ice	283
Peloponnesian b.f. Amphora: Reverse (B.M.)	6.00	283
Athenian b.f. Kantharos (B.M.)	r int	282
'Kleiumeister' Kylix, with Arming of Warriors (B.M.)	eig.	293
B.F. Amphora: Heroes Playing at Draughts (B.M.)	144	204
Herakles and Kerberos on h.f. Amphora (B.M.)	194	295
Herakies and Geryon on b.f. Kylix (B.M.)	No.	299
Panathemaic Amphoriskos (B.M.)	No.	300
Stater of Sieyon: Reverse (B.M.)	-	303

RULES

OF THE

Society for the Promotion of Bellenic Studies.

- r. THE objects of this Society shall be as follows :-
- I. To advance the study of Greek language, literature, and art, and to illustrate the history of the Greek race in the ancient, Byzantine and Neo-Hellenic periods, by the publication of memoirs and unedited documents or monuments in a Journal to be issued periodically.
- II. To collect drawings, facsimiles, transcripts, plans, and photographs of Greek inscriptions, MSS., works of art, ancient sites and remains, and with this view to invite travellers to communicate to the Society notes or sketches of archæological and topographical interest.
- III. To organise means by which members of the Society may have increased facilities for visiting ancient sites and pursuing archæological researches in countries which, at any time, have been the sites of Hellenic civilization.
- 2. The Society shall consist of a President, Vice-Presidents, a Council, a Treasurer, one or more Secretaries, and Ordinary Members. All officers of the Society shall be chosen from among its Members, and shall be ex officio members of the Council.
- 3. The President shall preside at all General Ordinary, or Special Meetings of the Society, and of the Council or of any Committee at which he is present. In case of the absence of the President, one of the Vice-Presidents shall preside in his stead, and in the absence of the Vice-Presidents the Treasurer. In the absence of the Treasurer the Council or Committee shall appoint one of their Members to preside.

- 4. The funds and other property of the Society shall be administered and applied by the Council in such manner as they shall consider most conducive to the objects of the Society: in the Council shall also be vested the control of all publications issued by the Society, and the general management of all its affairs and concerns. The number of the Council shall not exceed fifty.
- 5. The Treasurer shall receive, on account of the Society, all subscriptions, donations, or other moneys accruing to the funds thereof, and shall make all payments ordered by the Council. All cheques shall be signed by the Treasurer and countersigned by the Secretary.
- In the absence of the Treasurer the Council may direct that cheques may be signed by two members of Council and countersigned by the Secretary.
- 7. The Council shall meet as often as they may deem necessary for the despatch of business.
- 8. Due notice of every such Meeting shall be sent to each Member of the Council, by a summons signed by the Secretary.
- g. Three Members of the Council, provided not more than one of the three present be a permanent officer of the Society, shall be a quorum.
- to. All questions before the Council shall be determined by a majority of votes. The Chairman to have a casting vote.
- tr. The Council shall prepare an Annual Report, to be submitted to the Annual Meeting of the Society.
- 12. The Secretary shall give notice in writing to each Member of the Council of the ordinary days of meeting of the Council, and shall have authority to summon a Special and Extraordinary Meeting of the Council on a requisition signed by at least four Members of the Council.
- 13. Two Auditors, not being Members of the Council, shall be elected by the Society in each year.
- 14 A General Meeting of the Society shall be held in London in June of each year, when the Reports of the Council and of the Auditors shall be read, the Council, Officers, and Auditors for the ensuing year elected, and any other business recommended by the Council discussed

and determined. Meetings of the Society for the reading of papers may be held at such times as the Council may fix, due notice being given to Members.

- 15. The President, Vice-Presidents, Treasurer, Secretaries, and Council shall be elected by the Members of the Society at the Annual Meeting.
- to. The President and Vice-Presidents shall be appointed for one year, after which they shall be eligible for re-election at the Annual Meeting.
- 17. One-third of the Council shall retire every year, but the Members so retiring shall be eligible for re-election at the Annual Meeting.
- 18. The Treasurer and Secretaries shall hold their offices during the pleasure of the Council.
- 19. The elections of the Officers, Council, and Auditors, at the Annual Meeting, shall be by a majority of the votes of those present. The Chairman of the Meeting shall have a casting vote. The mode in which the vote shall be taken shall be determined by the President and Council.
- 20. Every Member of the Society shall be summoned to the Annual Meeting by notice issued at least one month before it is held.
- 21. All motions made at the Annual Meeting shall be in writing and shall be signed by the mover and seconder. No motion shall be submitted unless notice of it has been given to the Secretary at least three weeks before the Annual Meeting.
- 22. Upon any vacancy in the Presidency, occurring between the Annual Elections, one of the Vice-Presidents shall be elected by the Council to officiate as President until the next Annual Meeting.
- 23. All vacancies among the other Officers of the Society occurring between the same dates shall in like manner be provisionally filled up by the Council until the next Annual Meeting.
- 24. The names of all candidates wishing to become Members of the Society shall be submitted to a Meeting of the Council, and at their next Meeting the Council shall proceed to the election of candidates so proposed: no such election to be valid unless the candidate receives the votes of the majority of those present.

- 25. The Annual Subscription of Members shall be one guinea, payable and due on the 1st of January each year; this annual subscription may be compounded for by a payment of £15 15s., entitling compounders to be Members of the Society for life, without further payment. All Members elected on or after January 1, 1894, shall pay on election an entrance fee of one guinea.
- 26. The payment of the Annual Subscription, or of the Life Composition, entitles each Member to receive a copy of the ordinary publications of the Society.
- 27. When any Member of the Society shall be six months in arrear of his Annual Subscription, the Secretary or Treasurer shall remind him of the arrears due, and in case of non-payment thereof within six months after date of such notice, such defaulting. Member shall cease to be a Member of the Society, unless the Council make an order to the contrary.
- 28 Members intending to leave the Society must send a formal notice of resignation to the Secretary on or before January 1; otherwise they will be held liable for the subscription for the current year.
- Member of the Society, a Special Meeting of the Council shall be held to consider the case, and if at such Meeting at least two-thirds of the Members present shall concur in a resolution for the expulsion of such Member of the Society, the President shall submit the same for confirmation at a General Meeting of the Society specially summoned for this purpose, and if the decision of the Council be confirmed by a majority at the General Meeting, notice shall be given to that effect to the Member in question, who shall thereupon cease to be a Member of the Society.
- 30. The Council shall have power to nominate British or Foreign Honorary Members. The number of British Honorary Members shall not exceed ten.
- 31. Ladies shall be eligible as Ordinary Members of the Society, and when elected shall be entitled to the same privileges as other Ordinary Members.
- 32. No change shall be made in the Rules of the Society unless at least a fortnight before the Annual Meeting specific notice be given to every Member of the Society of the changes proposed.

RULES FOR THE USE OF THE LIBRARY

AT 22, ALBEMARUE STREET.

- I. THAT the Library be administered by the Library Committee, which shall be composed of not less than four members, two of whom shall form a quorum.
- II. That the custody and arrangement of the Library be in the hands of the Librarian and Assistant Librarian, subject to the control of the Committee, and in accordance with Regulations drawn up by the said Committee and approved by the Council.
- III. That all books, periodicals, plans, photographs, &c., be received by the Librarian, Assistant Librarian or Secretary and reported to the Council at their next meeting.
- IV. That every book or periodical sent to the Society be at once stamped with the Society's name.
- V. That all the Society's books be entered in a Catalogue to be kept by the Librarian, and that in this Catalogue such books, &c., as are not to be lent out be specified.
- VI. That, except on Christmas Day, Good Friday, and on Bank Holidays, the Library be accessible to Members on all week days from eleven A.M. to six P.M. (Saturdays, 11 A.M. to 2 P.M.), when either the Assistant-Librarian, or in her absence some responsible person, shall be in attendance. Until further notice, however, the Library shall be closed for the vacation from July 20 to August 31 (inclusive).
- VII. That the Society's books (with exceptions hereinafter to be specified) be lent to Members under the following conditions:—
 - (t) That the number of volumes lent at any one time to each Member shall not exceed three.
 - (2) That the time during which such book or books may be kept shall not exceed one month.
 - (3) That no books be sent beyond the limits of the United Kingdom:
 - VIII. That the manner in which books are lent shall be as follows:-
 - (1) That all requests for the loan of books be addressed to the Librarian.
 - (2) That the Librarian shall record all such requests, and lend out the books in the order of application.
 - (3) That in each case the name of the book and of the borrower be inscribed, with the date, in a special register to be kept by the Librarian.
 - (4) Should a book not be returned within the period specified, the Librarian may reclaim it.

- (5) All expenses of carriage to and fro shall be borne by the borrower,
- (6) All books are due for return to the Library before the summer vacation.

IX. That no book falling under the following categories be lent out under any circumstances:-

- (1) Unbound books.
- (2) Detached plates, plans, photographs, and the like.
- (3) Books considered too valuable for transmission.
- (4) New books within one month of their coming into the Library,

X. That new books may be borrowed for one week only, if they have been more than one month and less than three months in the Library.

XI. That in the case of a book being kept beyond the stated time the borrower be liable to a fine of one shilling for each week after application has been made by the Librarian for its return, and if a book is lost the borrower be bound to replace it.

The Library Committee.

MR. TALFOURD ELV.

PROF. ERNEST GARDNER.

PROF. PERCY GARDNER.

MISS JANE HARRISON, LL.D.

MR. WALTER LEAF, Litt.D.

MR. GEORGE MACMILLAN (Hon. Sec.).

MR. ERNEST MYERS.

MR. J. L. MYRES.

MR. ARTHUR HAMILTON SMITH. (Hon. Librarian),

MRS. S. ARTHUR STRONG, LL.D.

Assistant Librarian, MISS FANNY JOHNSON, to whom, at 23, Albemarle Street, applications for books may be addressed.

SIR E. MAUNDE THOMPSON, K.C.B., D.C.L.

SESSION 1808-1809.

General Meetings will be held in the Rooms of the Royal Asiatic Society, 22, Albemaric Street, London, W., for the reading of Papers and for Discussion, at 5 F.M. on the following days:—

1898. Thursday, November 3rd. 1899. Thursday, February 23rd. Thursday, April 27th.

Thursday, June 29th (Annual).

The Council will meet at 4.30 p.m. on each of the above days,

THE SOCIETY FOR THE PROMOTION OF HELLENIC STUDIES

OFFICERS AND COUNCIL FOR 1898-1899.

President.

PROFESSOR E. C. JERR, LITE.D., D.C.L., LL.D., M.F.

Vice-Presidents.

PROF. S. H. BUTCHES, LOTY, D. LLD
PROF. INGRAM RYWATER, LOTY, D.
REV. PROF. LEWIS CAMPBELL, LLD.
MR. ARTHUR J. EVANS.
MR. SIBNEY COLVIN
PROF. PERCY GARDNER, LOTY, D.
MR. D. B. MONRO, LOTT D., LLD., Provest of Octob
College, Oxford.
MR. A. S. MURRAY, LLD.

PROF. H. F. PELHAM, Freiders of Diany Colog-(Major).

R. F. C. FENROSK, F.R.S., D.C.L., LL.D.
PROF. W. ST. RAMEAY, D.C.L.

MR. J. E. SANDYS, LITTLD.

MRY. PROF. A. H. SAYCE, LL.D.

MRY. PROF. A. H. SAYCE, LL.D.

MRY. MILLIAN BETHOMPSON, K.C.S., D.C.L.

REV. H. F. TOZER.

PROF. E. Y. TYHRELL, LITTLD., D.C.L.

· Council.

PROF. W. C. J. ANDERSON
HEV. A. G. BATHEE
MN. R. CARR BOSANQUET.
MR. A. B. COGE.
ME. H. G. DAKYNS,
MR. LOUIS DYEN.
MN. FALFOURD ELY.
LADY EVANS.
PROF BRNEST A. GARDNER.
MR. E. F. GRENFELL.
MISS JANE HARRISON, LL.D.
MR. J. W. HEADLAM.
MR. G. F. HILL.
MR. D. O. HOGARTH.
SIR HENRYL HOWORTH, K.C.LE., M.P., F.R.S
MR. H. STUART JONES.
MR. F. D. KENYON.

MR. WALTER LEAF, LITT.D. MR. WILLIAM LORING ME O E MARINDIN REV. PROT. JOSEPH MAYOR, LITTLE MR J A R; MUNRO. PROF. G. G. A. MUERAY. MR. ERNEST MYERS. MR. J. L. MYRES MISS EMILY PENROSE. MR. G. H. RENDALL, LITT. D. PROF. WILLIAM RIDGEWAY. MR. R. W. SCHULTZ. MR. CECIL SHITH, LL.D. MR. A. HAMILTON SMITH. MRS. S. ARTHUR STRONG, EL.D. MR. H. B. WALTERS.

Hon. Treasurer.

MR. DOUGLAS W. FRESHFIELD.

Hon. Secretary.

MR GEORGE A MACMILLAN, ST. MARTIN'S STREET, W.C.

Assistant Secretary.

MR. W. KISHAGI

Hon, Librarian.

the present of an exercise

Assistant Librarian.

MIES FANNY JOHNSON

Acting Editorial Committee,

PROF. ERNEST GARDNER

MA G. F. HILL.

MRIV. G. KESYON

Consultative Editorial Committee.

PROFESSOR JEER | PROFESSOR BYWATER | SIR E. MAUNDE THOMPSON | MR. SIDNEY COLVINand Mr. D. O. HOOARTH (ex officio), as Director of the British School at Achains.

Auditors for 1898-99.

MR. ARTHUR J. BUTLER.

MR STEPHEN SPRING-BILL, C.S.

Bankers.

MESSES, ROBARTS, LUBBOCE & CO. 15, LOMBARD STREET.

CAMBRIDGE BRANCH

OF

THE SOCIETY FOR THE PROMOTION OF HELLENIC STUDIES.

OFFICERS AND COMMITTEE FOR 1898-1899.

Chairman.

PROF. R. C. JEHR, LITT. D., D.C.L., LL.D., M.P.

Vice-Chairman-

MR. J. E. SANDYS, LITT.D.

Committee.

ME. J. G. FRAZER, L.L.D. PROF. EBNEST A. GARDNER. Mz. HENRY JACESON, LITT.D. MR. M. R. JAMES, LITT.D. PROF. W. RIDGEWAY. MR. E. E. SIKES.

MR. ARTHUR THLEY.

MR. A. W. VERRALL, LITT.D.

MR. C. WALDSTEIN, LITT.D.

Mon. Sectetarg.

MR. ANTHUE BERNARD COOK, TRINITY COLLEGE.

HONORARY MEMBERS.

HIS MAJESTY THE KING OF THE HELLENES, & M. le Secretaire du Roi des Hellenes, Athons, Greece.

Prof. Friedrich August Otto Benndorf, The University, Vienna.

Sir Alfred Billotti, K.C.B., H.B.M. Consul for Crete,

Prof. D. Comparetti, Istituto di Studii Superiori, Fiorence.

M. Alexander Contostavlos, Athens

Pent, A. Conze, Kaiverl. Deutsches Archueologisches institut, Cornelius-tr., II., Berlin.

Mr. George Dennis c'o Lloyds Bank, Limited, 16, St Jamer's Street, S.W.

Prof. Wilhelm Dörpfeld, Ph.D., Director of the German Archivological Institute, Athens.

Monsieur L'Abbé Duchesne, Ecole Françaixe, Rome.

Monaieur P. Foucart, 13, Rus de Tournon, Paris.

Prof. Adolf Fartwangler, The University, Munich. Monsieur J. Gennadius, 21, Hyde Park Place, W.

His Excellency Hamdy Bey, Keeper of the Museum of Antiquities, Constantinople,

Prof. W. Helbig, Villa Lante, Kome.

Monsieur Homolle, Director of the French School, Athens,

Monsieur P. Kavvadlas, Ephor-General of Antiquities, Athens, Greece.

Prof. A. Kirchhoff, The University, Berlin.

Prot. U. Köhler, The University, Berlin.

Prof. S. A. Kumanudes, The University, Atkens.

Prof. A. Michaelis, University, Stratchurg.

Prof. E. Petersen, Institute Archeologico Germanico, Monte Tarpea, Rome.

LIST OF MEMBERS.

* Original Members. † Life Members.

The other Members have been elected by the Council since the Inaugural Meeting:

Abhott, Evelyn, Balliol College, Oxford.

†Abercrombie, Dr. John, 23, Upper Wimpole Street, W.

Abram, Edward, t, Middle Temple Lune, E.C.

Adam, James, Emmanuel College, Cambridge.

Adams, Miss Mary G., 43, Campden Hill Square, Kensington, W.

Agnew, Philip L., 18, Gloncester Square, W.

Aingur, A. C., Eton College, Windsor.

Ainger, Rev. Canon, Master's House, The Temple, E.C.

† Alnslie, R. St. John, The School, Sedbergh.

Alford, Rev. B. H., St. Luke's Vicarage, Nutford Place, W.

Allbutt, Professor T. Clifford, M.D., F.R.S., Chawer Rand, Cambridge.

Allen, T. W., Queen's College, Oxford.

Amherst, Lord, Didlington Hall, Brandon, Suffolk.

Anderson, J. G. C., Lincoln College, Oxford.

Anderson, J. R., Lairbeck, Kerwick,

Anderson, Prof. W. C. F. (Council), Firth College, Sheffield.

Anderton, Hasil, Public Library, Newcastle-on-Tyne

*Antrobus, Rev. Frederick, The Oratory, S.W.

Apostolides, S.,

Archer-Hod, R. D., Trinity College, Cambridge.

tArkwright, W., Adbury House, Newbury.

Awdry, Herbert, Wellington College, Berks.

Bagley, Mrs. John, Washington Avenue, Detroit, Michigan.

Bailey, J. C., 118, Ashley Gardens, S.W.

Baker, F. B., The College, Great Malvern.

Baker, H. T., New College, Oxford.

Baker, Rev. William, D.D., Merchant Taylors' School, E.C.

*Balfour, Right Hon. A. J., M.P., 4, Carlton Gardens, S.W. *Balfour, Right Hon. G. W., M.P., 24, Addison Road, W. Ball, Sidney, St. John's College, Oxford. +Barlow, Miss Annie E. F., Greenthorne, Edgworth, Bolton. Barlow, Mrs., to, Wimpole Street, W. Barnewall, Sie Reginald A., Barn. 23, Cliveden Place, Eaton Square, S.W. Barnsley, Sidney H., Penbury, near Cirencester. Barran, J. N., Weetwood, Leeds. Bather, Rev. Arthur George (Council), & Kingsgule Street, Winchester. Bayfield, Rev. M. A., Eastdourne College, Eastbourne. Beare, Prof. J. Ivane, v. Trinity College, Dublin. Beaumont, Somerset, Shere, near Guildford. Beebee, M. J. L. New Travellers Club, 97, Piccadilly, W. Benn, Affred W., 70, Vla Carour, Florence. Benschoten, J. C. van, Wesleyan University, Middletown, Conn., U.S.A. Bennett, S. A., Audley House, Richmond. Survey. Bent, Mrs. Theodote, 13, Great Cumberland Place, 1V. Bevan, E. R., Bickford-Smith, R. A. H., 98, Palace Gardens Terrace, W. Bienkowski, Pmf. von P., Retoryka, 15. Krabm Bikeias, Demettins, 50, fine de Varenne, Paris. . Hishop, Major Tuice, 28, Albany, Pleadilly, W. Blomfield, Sir A. W., A.R.A., 6, Montagu Place, Montagu Square, W.C. Blomfield, Mrs. Massie, Port House, Alexandria, Egypt. Biumenfeld, Ralph Drew, 64, Cheyne Court, Chelsen, S. W. Bodington, Prof. N., Principal of the Yorkshire College, Leeds. Bond, Edward, M.P., Elm Bank, Hampitead, N.W. Besauquet, Rev. V. C. T., The Hermitage, Uplyme, Denon. Bosanquet, R. Carr (Council), Ruch Hall, Almoick, Northumberland, Bosdari, Count Alessandro di, 20, Gresmenor Square, W. Bongatsos, Christan Ch., Alexandria, Egypt, Bousfield, William, 20, Hyde Park Gate, S. W. Boyd, Rev. Henry, D.D., Principal of Hertford College, Oxford. Boys, Rev. H. A., North Cadbury Rectory, Bath. Bracaley, Rev. H. R., The Precentary, Lincoln. Bramwell, Miss, 73, Chester Square, S. W. Branteghem, A. van, 29, Queen Annies Gate, S.W. Brinton, Hubert, Eton College, Windsor Bruadbent, H., Eton College, Windsor. Brock, Mrs., 115; Adelaide Road, South Humpstead, N.W. *Brodie, E. H., Grasendale, Malvern. Brooke, Rev. A. E., King's College, Cambridge. Brooke, Rev. Stopford A., I Manchester Square, W. Brooks, E. W., 28, Great Grmond Street, W.C. Brooksbank, Mrs., Leigh Place, Godstone. Brown, Horace T., F.R.S., 32, Nevern Square, South Kensington, S. W. Brown, Prof. G. Baldwin, The University, Edinburgh, Brown, Walter, z. Albert Square, Great Yarmouth. *Bryce, The Right Hon. James, D.C.1., M.P., 54, Portland Place, W. Buck, G. M., City of London School, E.C. Buller, Lady Audrey, 29, Bruton Street, W. Bulwer, Sir Henry, K.C.B., 11, South Street, Park Lane, W. Burge, Hubert M. Ummersity Callege, Oxford. Burgh, W. de, University Extension College, Reading. Burnet, Prof. J., 1, Alexandra Place, St. Andrews, N.A. Burrows, Prof. Ronald, University College, Cardiff. Burton, Sir F. W., 43, Argyll Road, Kensington, W. Bury, Prof. J. B., Trinity College, Dublin.

Butcher, Prof. S. H., Litt.D., LL.D. (V.P.), 27, Palmerston Place, Edinburgh.

† Bate, The Marquis of, K.T., St. John's Lodge, Regent's Park, N.W.

Butler, Arthur J., Wood End, Weybridge.

*Butler, The Rev. H. M., D.D., Master of Trinity College, Combridge,

Huxton, F. W., 42, Grosvenor Gardens, S. W.

Buxton, Mrs. Alfred W., 32, Great Cumberland Place, W.

Bywater, Prof. Ingram (V.P.), 93, Ontlow Square, S. W.

Bywater, Mrs., 93, Ouslow Squarr, S. W.

Calcutta, The Right Rev. the Lord Bishop of, The Palace, Calcutta.

Calvert, Rev. Thomas,

Calvocoressi, L. M., Mexers. Ralle Bros., Mellor's Buildings, Exchange Street East, Liverpool.

Campbell, Rev. Prof. Lewis (V.P.), 33, Campden House Chambers, W.

Campbell, Mrs. Lewis, 35, Campden House Chambers, W.

Capes, Rev. W. W., Bramshott, Liphook, Hants.

Carapános, Constantin, Député, Athens

Carey, Miss, 13, Coloneum Terrace, Regent's Park, N.W.

*Carlisle, A. D., Haileybury College, Hertford.

Carlisle, Miss Helen, Houndhill, Marchington, Stafford.

Carmichael, Sir T. D. Gibson, Castlegraig, Dolphinton, N. S.

Carr, Rev. A., Addington Vicaroge, Craydon.

Cast, H. Wildon, 25, Cumberland Terrace, Regent's Park, N.W.

Carter, Prof. Frank. McGill University, Montreat.

Carthew, Miss, 15a, Kensington Palace Gardens, W.

Carrwright, T. B.,

Case, Miss Janet. 5 Windmill Hill, Hampstead, S.W.

Cates, Arthur, 12, York Terrace, Regent's Park, N. W.

Cave, Lawrence T., 13, Loundis Square, S. W.

Chambers, C. Gore, Hertford House, De Parry's Avenue, Bedford.

Chambers, Charles D., The Steps, Bromsgrove, Worcastershire.

Chance, Frederick, 51, Prince's Gate, S.W.

Chavasse, A. S., Kempsoy, Worcestershire, †Chawner, G., King's College, Cambridge,

Chawner, W., Master of Emmanuel College, Cambridge.

Cheetham, J. C. M., Eyford Park, Bourton-on-the Water, R.S.O., Gloncestershirs.

Cheetham, J. Frederick, Eastwood, Staleybridge.

Christian, J. Henry, 18, Devonshirs Place, Portland Place, W.

Christian, Rev. G., Redgate, Uppingham,

Christie, Miss Annie, I, Westbourne Terrace, W.

*Christie; R. C., Ribsslen, Bagshot, Surrey. Churchill, E. L., Eton College, Windsor.

Clark, Charles R.R., ejo E. P. Warren, Esq., 18, Cowley Street, Westminster, S.W.

tClark-Maxwell, Rev. W. Gilchrist, Clunbury Vicaroge, Aslon-on-Clem, Salop.

Clarke, Joseph Thucher, 3, College Road, Harrow, N.W.

Clarke, Somers, 22; Whitchall Court, S.W.

† Clauson, A. C., 12, Park Place Villas, Paddington, W.

Clay, C. F., 38, Great Ormand Street, W.C.

Clerke, Miss Agnes, 68. Reachiffe Square, S.W.

Cobbold, Felix T., The Lodge, Felixstown, Suffolk.

*Cobham, C. Delaval, H.B.M. Commissioner, Larnaca, Cyprus.

Colby, Rev. Dr., 12. Hillsborough Terrace, Hfracombe.

Cole, A. C., 64, Portland Place, W.

Colfox, William, Westmend, Bridgort.

Collins, Miss F. H., 3, Bramham Gardens, South Kensington, S.W.

Colvill, Miss Helen H., Overdale, Shortlands, Kent,

Colvin, Sidney (V.P.), British Museum, W.C.

Compton, Rev. W. C., The College, Doner.

Consul, B. M., The Vorkshire College, Leeds,

*Constantinides, Prof. M., Coundourlotes Street, Munychia, Petraeus, Athens.

Conway, Sir W. M., The Red House, 21, Hornton Street, W.

Conybears, F. C., 13, Norham Gardens, Oxford.

Cook, Arthur Bernard (Council), Trinity College, Cambridge.

Cookson, C., Magdalen College, Oxford.

Cookson, Sir C. A., C.B., H.B.M. Consul, Alextradria.

Corbet, His Honour Eustace K., Native Court of Appeal, Cairo.

Cordery, J. G., C.S.I., 63, Goldington Road, Bedfard.

Corgialegno, M., 21, Pembridge Gardens, W.

Courtenay, Miss, 34, Brompton Square, S.W.

Courtney, W. L., 53, Helsits Park, N. W.

Cowper, The Right Hon. Earl, K.G., Panshanger, Hertford.

Craik, George Lillie, 2, West Halkin Street, S. W.

Crewdson, Wilson, The Barons, Reigate.

Crooke, W., Westleigh, Arterberry Road, Wimbledon, S.W.

†Crossman, C. S., The College, Winchester.

Crowfoot, J. W., Bishop's Hostel, Lincoln.

Cruickshank, Rev. A. H., The College, Winchester.

Cust, H. J. C., St. James' Lodge, Delahay Street, S. W.

Cust, Lionel. The Crescent, Windser.

Cust, Miss Anna Maria, 63, Elm Park Gardens, Fulkam Road, S. W.

Cust, Miss Beatrice, 13, Eccleston Square, S.W.

Dabis, Miss, Holloway Callege, Egham, Surrey.

Dakyns, H. G. (Conncil), Higher Coombe, Haslemers, Surrey.

Danson, F. C., B., Liverpool and London Chambers, Liverpool.

Darbishire, B. V., Trinity College, Oxford.

David, Rev. W. H., Kelly College, Tavistock.

Davidson, H. O. D., Harrosv, N.W.

Davies, Prof. G. A., University College, Liverpool.

Davies, Rev. Gerald S., Charterhouse, Godalming.

Delamarre, Jules, 4, Impasso Royer-Collard, Paris.

De Saumarez, Lord, Shrubland Park, Coddenham, Suffolk.

Dickson Miss Isabel A., Dunnichen House, Forfar.

Dill, Prof. S., Montpelier, Malone Road, Belfast.

Dobson, Miss, 77, Harcourt Terrace, Redcliffe Square, S.W.

Donaldson, James, LL.D., Principal of The University, St. Andrews.

Donaldson, Rev. S. A., Eton College, Windsor.

Draper, W. H., 52, Doughty Street, W.C.

Drummond, Allan, 7, Ennismore Gordens, S. W.

Duchataux, M. V., 12, Rue de l'Echauderie, à Reims.

Dulin, Prof. von, University, Heidelberg.

Dake, Roger, 8, Neville Terrace, Ouslow Gardens, S.W.

Dunham, Miss, 37, East Thirty-Sixth Street, New York,

Dunlap, Miss Mabel Gordon, c/o Messra Brown, Shipley & Co., Founder's Court. Lothoury, E.C.

Durham, The Right Rev. The Lord Bishop of, Authland Castle, Bishop Authland.

Dyer, Louis (Council), Sunbury Lodge, Banbury Road, Oxford.

Eatl, Mrs. A. G., Ferox Hall, Tonbridge.

Earp, F. R., King's College, Cambridge.

Edmonds, C. D., Emmanuel College, Cambridge.

Edwards, G. M., Sidney Sussex College, Cambridge.

Egerton, Mrs. Hugh, 11, Tite Street, Chelsea, S.W.

+Egerton, Sir Edwin H., K.C.B., H.B.M. Minister, British Legation, Athens, Greece.

Egerton, Miss M., Whitwich Hall, York.

Eld, Rev. F. J., Polstend Rectory, Colchester.

† Ellis, Prof. Robinson, Trinity College, Oxford.

Elwell, Levi H., Amherst College, Amherst, Mass.

Ely, Talfourd (Council), 73, Parliament Hill Road, Hampstead, N.W.

Emens, Edgar A., Syracuse University, New York.

Eumorfopoulo, N., 1, Kenzington Park Gardens, W.

Evans, A. J. (V. P.), Ashmolean Museum, Oxford.

Evans, Sir John, K.C.B., D.C.L., F.R.S., Nath Mills, Hems! Hempstead.

†Evans, Lady (Council), Nash Mills, Homel Hompstead.

Eve, H. W., 37, Gordon Square, W.C.

Ewart, Miss Mary A., 68, Albert Hall Mansions, 5.14.

Fanshawe, Reginald, 53, Canying's Road, Clifton, Brittal.

Farnell, L. R., Exeter College, Oxford. Farrar, Rev. Canon A. S., Durkam.

Farside, William, Thorps Hall, Robin Hood's Bay, Vorkskire.

*Fearon, Rev. W. A., D.D., The College, Winchester.

Fenning, W. D., Haileybury College, Hertford.

Field, Rev. T., Radley College, Abingdon.

Fisher, H. A. I., New College, Oxford.

Fisher, Miss Edith S., 21, Chapel Street, Belgrave Square, S.W.

† Fitzmaurice, Lady Edmond, 2, Green Street, Grownener Square, W.

Flather, J. H., 52 Rateman Street, Cambridge,

Flower, Wickham, Old Sman House, Chelsen Embankment, S.W.

+Forbes, W. H., Balliol College, Oxford.

Ford, The Right Hon. Sir Francis Clare, G.C.B., G.C.M.G., 17, Park Lans, W. Fowler, Harold N., Ph.D., Western Reserve University, Cleveland, Ohio, U.S. A.

*Fowler, Rev. Professor, President of Corpus Christi College, Oxford

Fowler, W. Warde, Lincoln College, Deford.

Franklin, T. M., St. Hilary, Cowbridge, S. Wales. Frazer, J. G., Trinity College, Cambridge.

Freeman, C. E., Parkhouse, Southborough, Tunbridge Wells.

Freeman, W. George, Lee Street, Plumstead.

*Freshfield, Douglas W. (Hon. Treasurer), 1, Airlie Gardens, Campdon Hill, W.

Freshfield, Edwin, LLD., 31, Old Jewry, E.C.

Freston, Henry W., Parkfield, Prestwich, Lancoshire.

Fry, Right Hon. Sir Edward, Fatland House, Failand, near Bristol.

*Fry, F. J., Everyley, Leigh Wood, Clifton. Fullerton, W. Morton, Rue Vignon, Paris.

†Furley, J. S., 10, College Street, Winchester.

Furneaux, L. R., Rossall School, Fleetwood.

Furneaux, Rev. W. M., Repton Hall, Burton-on-Trent.

Gardner, Miss Alice, The Old Hall, Neumham College, Cambridge.

+Gardner, Prof. Ernest A. (Council), Radnor Cottags, Sandgate.

* † Gardner, Prof. Percy, Litt. D. (V.P.), 12, Canterbury Road, Oxford.

Gardner, Samuel, Oakhurst, Harrow-on-the-Hill.

Gardner, W. Amory, Groton, Marzachusetts, U.S.A.

Garnett, Mrs. Terrell, 3, Queen Anne's Gate, S.W.

Gatliff, Hamilton, 11, Euton Square, S.W.

Geddes, Sir W. D., Principal of the University, Aberdeen.

Geikle, Sir Archibald, F.R.S., 10, Chester Terrace, Regent's Park, N.W.

Gibson, Mrs. Margaret D., Castle-brue, Chesterton Road Cambridge.

Giles, P., Emmanuel College, Cambridge.

Gilkes, A. H., The College, Dulwish, S.E.

Gilliat, Rev. E., Harrow, N.W.

Glazebrook, Rev. M. G., Clifton College, Bristol.

Godden, Miss Gertrude M., Ridgfield, Wimbledon.

Gonino, Miss G., 90, Warwick Street, Warwick Square, S.W.

Goodhart, A. M., Eton College, Windsor,

Goodwin, Prof. W. W., D.C.L., Harvard College, Cambridge, Mass., U.S.A.

Gow, James, Litt. D., High School, Nottingham.

Gower, Lord Ronald, 27, Trebovir Road, Earl's Court, S.W.

Granger, F. S., University College, Nottingham.

Graves, A. S., St. Martin's, Cambridge.

Gray, Rev. H. B., Bradfield College, Berks.

Green, G. Buckland, The Academy, Edinburgh.

Green, Mrs. J. R., 14, Kensington Square, W. Greenwell, Rev. Canon, F.R.S., Durham.

Grenfell, B. P. (Council), Queen's College, Oxford.

Griffith, G., Harrow, N. W.

Griffith, Miss Mary E., 4, Bramham Gardens, S. W.

Grundy, George Beardoo, 27, St. Margaret's Road, Oxford.

Gurney, Miss Amelia, 69, Envismore Gardens, S.W.

Hadow, W. H., Worcester College, Oxford.

Haigh, A. E., 2, Crick Road, Oxford.

Hales, Rev. C. T., Aysgarth School, Newton-le-Willows, R.S.O. Yorks

Hall-Dare, Francis,

Hall, Roy. F. H., Oriel College, Oxford.

Hall, Rev. F. J., Northaw Place, Potter's Bar, Herts.

Hall, F. W., St John's College, Oxford.

Hall, Harry Reginald, 13, Chalcot Gardens, N. IV.

Hall, Miss S. E., 37, York Street Chambers, Bryanston Square, W.

Hallam, G. H., The Park, Harrow, N. W. Hammond, B. E., Trinity College, Cambridge.

Hardie, Prof. W. Ross, The University, Edinhurgh.

Hardwich, J. M., The School, Durham;

Harrison, Miss J. E., LL.D. (Council), 6, Chenles Street Chambers, W.C.

Harrower, Prof. John, The University, Aberdeen;

Haslam, S., The School, Uppingham.

Haussoullier, B., 8, Rue Sainte-Céale, Paris.

Haverfield, F. J., Christ Church, Oxford. Hawes, Miss E. P., 89, Oxford Terrace, W.

Hay, C. A., 127, Harley Street, W. Hay, A. T., The College, Brighton.

Haynes, Miss Lucy, 7, Thornton Hill, Wimbledon.

Hayter, Angelo G. K., 74, Adelaide Road, N. W.

Headlam, Rev. A. C., Welwyn Vicarage, Herts.

Headlam, C. E. S., Trinity Hall, Cambridge.

Headlam, J. W. (Council), 6, Eldon Road, Kenzington. W.

Headlam, W. G., King's Callege, Cambridge.

Heard, Rev. W. A., Fetter College, Edinburgh. Heathcote, W. E., Raund Coppics, Ivor Heath, Uxbridge.

Heberden, C. B., Principal of Brasenose College, Oxford.

Hedgcock, Mrs. Harrison, 21, Caversham Read, N. IV. Hereford, The Lord Bishop of, The Palace, Hereford.

Herschell, The Right Hon. Lord, 46, Gresvener Gardens, S.W.

Heyer, G., The College, Weymouth,

Hicks, Rev. E. L., 21, Leaf Square, Pendleton, Manchester.

Higgins, Alfred, 16; King Street, Partman Square, W.

+Hill, Arthur, British Vice-Consul, Athens, Greece.

Hill, George F. (Council), British Museum, W.C. Hobbouse, Rev. Walter, The School House, Durham.

Hodgson, F. C., Abbotsford Ville, Twickenham.

+ Hodgson, J. Stewart, 7, Hill Street, Berkeley Square, W.

Hogarth, David G. (Council), British Archaelogical School, Athens. Holiday, Henry, Oak True House, Branch Hill, Hampstead, N. W.

Holland, Miss Emily, 27, Hamsfield Road, Wimbledon.

Hopgood, Harold B., 17, Spring Gardens, S.W.

Hopkinson, J. H., University College, Oxford.

Hoppin, J. C., c o J. S. Mergan & Co., 22, Old Broad Street, E.C.

Hornby, Rev. J. J., D.D., Provest of Eton College, Windsor,

+ Hort, Arthur F., Aboyns, Harrow.

Housley, Samuel J., Gymadal, Waterlow Road, Epsom.

Howorth, Sir Henry H., K C.I.E., M.P. (Council), 30, Collingham Pince, S.W.

Huddart, Rev. G. A. W., Kirklington Rectory, Bedale, Vorks.

Huddilston, J. H., Ph.D., Beres, Okto, U.S.A. Hügel, Baron Friedrich von. 4, Holford Road, Hampstead, N.W. Huish, Marcus B., 21, Essex Villas, Kennington, IV. Hulse, Miss Caroline M. Humphreys, Robert Heavy, Royal Societies Club, 63, St. James Street, S. H. Hunt, A. S., Queen's College, Oxford. Hutchinson, Sir J. T., (Chief Justice of Cyprus), Nicosia, Cyprus Hutchinson, Miss W. U. L., 69, Langridge Road, S.W. Hutton, Miss C. A., Huyshe, Wentworth, ' Dully Graphic' Office, Milford Lane, Strand W. Image, Selwyn, 6, Southampton Street, Bloomsbury, W.C. lonides, Alex, A., t, Holland Park, IV. louides, Luke A., 47, Marless Road, Kennington, W. Jackson, Rev. Blomfield, 29. Methlenburgh Square, W.C. Jackson, Henry, Litt. D., Trinity College. Cambridge Jackson, Miss Rose, Longstene, Hastemere. Jackson, Rev. W. W., Rector of Exeter College, Oxford. James, A. C. Eton College, Windows. "James, The Rev. H. A., D. D., School House, Rugby. James, Lunel, St Preer's College, Radley, Abingdon. James, M. R., Litt.D., King's College, Cambridge. James, Rev. S. R., The College, Matuern. Januaris, A. N., Ph.D., The University, St. Andrews, N.B. Jeans, Rev. G. E., Shorwell, Newport, Lile of Wight. *Jehb, Prof. R. C., D.C.L., I.L.D., Litt.D., M.P. (President), Springfield, Newsham, Cambridge. Jenkinson, F. J. H., Trinity College, Cambridge. Jenner, Miss Lucy A., 39, Addison Road, Kensington, W. Jevons, F. B., The Castle, Duckam. Jex-Blake, Miss, Girton College, Cambridge, Joacium, Miss M., Highlands, Haslemore, Surrey. Jobling, G. C., 5, Park Villas, Cheltenham. Jones, H. Stuart (Council), Trinity College, Oxford. Karo, George, 19, Piazza del Carmine, Firenze, Italy. Keene, Prof. Charles H., Queen's College, Cork, Keep, R. P., Ph.D., Free Academy, Norwich, Conn., U.S.A. Kelly, Charles Arthur, 30, Chepme Walk, Chelsen, S. W. Keltie, J. S., Glendroon House, Compayne Gardens, Hampstead, N.W. Kennedy, Rev. John, Grammar School, Aldenham, Elstree, Herts. Kenyon, F. G. (Council), British Museum, W.C. Ker, Prof. W. P., 95, Gower Street, W.C. Kerr, Prof. Alexander, Madison, Wisconsin, U.S.A. Keser, Dr. J., 11, Harley Street, Canandish Square, W. Kieffer, Prof. John B., 232, Lancaster Avenue, Laucuster, Pa., U.S.A. King, J. E., Grammar School, Manchetter. King, Rev. J. R., St. Veter's Vicarage, Oxford. King, Mrs. Wilson, 19, Highfield Road, Edghaston, Hirmingham. Knowles, James, Queen Anne's Ladge, St. James' Park, S. W. Krohn, H.: A., 103, Canusan Street, E.C. Lambros, Spiridion, Athens. Lang, Andrew, LL D. 1, Murlos Rd., Kennington, W. *Ling, Sir K. Hamilton, K.C.M.G., The Ottoman Bank, Constantinople. Lathbury, Miss, 19, Lingfield Road, Wimbledon, S.W. Lautour, Miss de, 85, Harcourt Terrace, Redeliffe Square, S.W. Lawrence, Sir Edwin, Bart., M.P., 13, Carlton House Terrace, S.W. Leaf, Mrs. C. J., Beechwood, Tunbridge Wells. Leaf, Herbert, The Green, Marlhorough.

Leaf, Walter, Litt. Dr. (Council), 6, Succes Place, Regent's Park, N.W.

Lecky, Mrs., 38. Onslow Gardens, S. W.

Leeper, Alexander, Warden of Trinity College, Melhourne. Leigh, Rev. A. Austen, Provost of King's Cullege, Cumbridge. Leigh, W. Austen, z. Norfolk Crescent, Hyde Park, W. Lewis, Harry, 5, Argyll Road, Kensington, W. † Lewis, Mrs. S. S., Castle-brue, Chesterton Road, Combridge. †Lewis, Prof. T. Hayter, 12, Kenzington Gurdens Square, W. Lewis-Poole, D., Royal Societies Club, 63, St. James Street, S.W. *Leycester, Mrs. Rafe, b. Cheyne Walk, S. W. Lindley, Miss Julia, to, Kidbrook Terrace, Shooter's Hill Rd., S.E. Lindley, William, to, Kidbrook Terrace, Shooter's Hill Rd., S.E. Lingen, The Right Hon. Lord, K.C.B., 13, Wetherby Gardens, S.W. Lingen, Lady, 13, Wetherby Gardens, S.W. Lister, Hon. Reginald, British Embassy, Constantinople. Litchfield, R. B., 31, Kensington Square, W. Lloyd, Miss A. M., Caytherps Hall, Grantkam. Lock, Rev W., Keble College, Oxford. London, The Right Rev. the Lord Bishop of, The Palace Fulham, S.W. Long, Prof. Albert Limerick, Robert College, Constantinople. +Loring, William (Council), 2, Hare Court, Temple, E.C. *Lubbock, The Right Hon. Sir John, Bart., M.P., High Elms, Hayes, Kent. Luce, Rev. E., 9, Royal Crescent, Brighton. Lupton, J. M., The College, Marlborough. Luxmoure, H. E., Eton College, Windsor. Lythgoe, A. M., 15, Warland Buildings, Harvard College, Cambridge, Mass. Lyttelton, Mon. and Rev. E., Haileybury College, Hertford. *Macan, R. W., University College, Oxford. McAnally, H. W. W., War Office, Pall Mall, S. W. McDantel, J. H., Hobart College, Geneva, N.Y. Macdonald, George, The University, Glasgow. Macdonald, Miss Louisa, Women's College, Sydney University, Sydney, N.S. W. Macdonell, W. R., LL.D., Coleat, Bycullah Park, Enfield. MacEwen, Rev. Alex. Robertson, 25, Woodstide Place, Glasgow. Macgillivray, J. Pittendrigh, Ravelslow Elms, Mursayfield, Edinburgh-McKechney, Mrs. W. C., 3. Berkeley Place, Wimbledon, S.W. Mackennal, Miss E. M., Beechwood, Bowdon, Cheshire. Mackenrie, Duncan, British School, Athens. MacLehose, James J., 61, St. Vincent Street, Glasgow. Macmillan, Mrs. Alexander, Bramshott Chase, Shottermill, Survey. *Macmillan, George A. (Hon. Sec.), St. Martin's Street, W.C. Macmillan, Mrs. George A., 19, Earl's Terrace, Kensington, W. † Macnaghten, Hugh, Eton College, Windsor. Macnaghten, The Right Hon. Lord, 3, New Square, Lincoln's Inn, W.C. McPherson, Miss Florence, Bank House, Maghull, Liverpool. Magrath, Rev. J. R., Provest of Queen's College, Oxford. Mahady, Rev. Prof. J. P., D.D., D.C.L., Trinity College, Dublin. Muidstone, The Viscountess, Hurstmanceaux Place, Hailsham, Susser. Mano, Constantin, Balliol College, Oxford. Manos, Grégoire, Greek Legation, Vienna. Marchant, E. C., St. Paul's School, West Kenzington, W. † Marindin, G. E. (Council), Broomfield, Frensham, Farnham, Marquand, Prof. Allan, Princeton College, New Jersey. Marsh, E., 28, Bruion Street, W.

†Marquand, Prof. Allan, Princeton College, New Jersey.

Marsh, E., 28, Bruton Street, W.

Marshall, R., 31, The Waldrons, Croydon.

Marshall, T., Highheld, Chapel Allerton, Leeds.

Martin, Charles B., The College, Oberlin, Ohio, U.S.A.

†Martin, R. B., M.P., 10, Hill Street, W.

†Maryn, Edward, Tillyra Castle, Ardrahan, County Galway.

Maron, H. C. F., Haileybury College, Hersford.

Matheson, P. E., New College, Oxford.

Mayrogordato, Pandell, South Sea House, Threadneadle St., E.C.

Maynard, H. L., Junior School, Westward He, N. Devon.

Mayor, Rev. Prof. Joseph B. (Council), Queensgate House, Kingston Hill, Surrey,

Mayor, R. G., Education Department, Whitehall, S.W.

Merry, Rev. W. W., Rector of Lincoln College, Oxford.

Millies, P., 95, Rouleward St. Michel, Paris.

Millington, Miss M. V. 27, Norland Square, W.

Milne, J. Grafton, Mansfield House, Canning Town, E.

Milner, Ills Excellency Sir Alfred, G.C.B., Government House, Capetown, S. Africa.

Miner, Miss Julia, 18, Sussex Square, Hyde Park, W.

Minns, Ellis H., Weston, Southumpton. Mitchell, C. W., 195, Queen's Gate, S. W.

†Mocatta, F. D., 9, Connaught Place, Edgware Road, W.

Moline, Miss J. R., 172, Church Street, Stoke Newington, N.

Monk, C. J., M.P., 5, Buckingham Gate, S.W.

Monro, D.B. (V.P.), Provost of Oriel College, Oxford.

Monson, His Excellency the Right Hon. Sir E. J., G.C.B., G.C.M.G., H.E.M. Ambassador, Paris.

Morgan, Miss Sarah, c/o Miss Colville, Overdale, Shortlands, Kent.

Morice, Rev. F. D., Mount Vernon, Woking.

Morley, The Right Hon, the Earl of, 11, Princes Gardens, S.W.

Morris, J. E., The Grummar School, Bedford.

Morrison, F. A. C., 3, Great Charles Street, Birmingham.

† Morshead, E. D. A., The College, Winchester,

Moss, Rev. H W., The School, Shrewsbury.

Monle, C. W., Corpus Christi College, Cambridge

Mount, Rev. C. B., 14, Norham Road, Oxford.

Mount, J. T., Eton College, Windsor.

Mudie, Mrs., Hudleigh, Marcsfield Gardens, Hampstrad, N. W.

Munro, J. A. R. (Connell), Lincoin College, Oxford.

Marray, A. S., L.L.D. (V.P.), British Museum, W.C.

Murray, Prof. G. G. A. (Council), 5, The University, Glasgraw.

*†Mycrs, Einest (Council), Bruckenside, Chislehurst.

†Myres, J. Liuton (Council), Christ Church, Oxford. Nact. Council L. The Admiralty, S.W.

Natl, Courad J., The Admiralty, S.W. Nairu, J. A., Trinity College, Cambridge.

Nell, R. A., Pembroke College, Cambridge.

Newman, W. L., Pittville Lawn, Cheltenham.

Nicholson, Sir Charles, Bart., The Grange, Tetteridge, iterts.

O'Connor, Arthur, M.P., 5, Essex Court, Temple, E.C.

Ohnefalsch-Richter, Dr. Max, 14. Wharfedale Street, Earl's Court, S.W.

Ommanney, Admiral Sir Erasınus K., 29, Connaught Square, W.

Orminton, Miss F. M., Girls' High School, Lealn.

†Oxford, The Right Rev. the Lord Bishop of, Cuddendon Palace, Wheatley, Oxon.

Page, T. E., Charterhouse, Gudalming.

Pallis, Alexander, Tatol, Sefton Park, Liverpool.

Parry, Rev. O. H., 5, Salem Hill, Sunderland.

Parry, Rev. R. St. J., Trinity College, Cambridge.

Paton, James Morton, Wesleyan University, Middletown, Conn., U.S.A.

Paton, W. R., British Post Office, Smyrna.

Pears, Edwin, 2, Rue de la Banque. Constantinople.

Peckover, Miss Alexandrina, Bank House, Wishach.

Peers, C. R., Harrow Weald Vicarage, Stanmore, Middlesex.

Pelle, John, Litt.D., Master of Christ's College, Cambridge.

Pelham, Hon. Mrs. Arthur, Moorcroft, Monmonth.

Pelham, Professor H. F. (V.P.), President of Trinity College, Oxford.

Pember, E. H., Q.C., Vicar's Hill, near Lymington, Hants.

*Penrose, F. C., F.R.S., (V.P.), Colebyfield, Wimbledon, S.W.

Penrose, Miss Emily (Council), Royal Holloway College, Egham. † Percival, F. W., 2, Southwich Place, Hyde Park Square, W. Perry, Prof. E. D., Columbia University, New York City, U.S.A. Philips, Mrs. Herbert, Sutton Oaks, Maccle) field. Pirle, Miss A. A., Sunnybank House, Old Aberdeen. Pirie, Miss Emily, Countesswell House, Aberdeenshire. † Platt, Prof. Arthur, 23, Possys Square, W. Plicker, Miss S. C., 4, Vanburgh Terrace, Blackheath. Pollock, Sir Frederick, Bart., 48, Great Cumberland Place, W. † Pond, Prof. C. A. M., University College, Auchland, New Zealand. Port, Dr. H., 48, Finsbury Square, E.C. Porter, Miss Sarah, Farmington, Connecticut, U.S.A. Postgate, Prof. J. P., Trinity College, Cambridge. Powell, Sir F. S., Bart., M.P., I, Cambridge Square, Hyde Park, IV, Powell, John U., St. John's College, Oxford. Poynter, Sir Edward J., P.R.A., 28, Albert Gate, S.W. Protor, A., Belfield, Weymouth. Prickard, A. O., New College, Oxford, Proctor, R. G. C., British Museum, W.C. Prothero, Prof. G. W., The University, Edinburgh. Peyor, Francis R., Woodfield, Hatfield, Herts. . l'aychan, A., 38, Boulevard de Courcelles, Paris. Radeliffe, W. W., Fontkill, East Grinstead, Sussex. Radford, Dr. W. T., Sidmouth. t Raleigh, Miss Katherine A., Terrick Houte, Tring. *Raili, Pandeli, 17, Belgrupe Square, S. W. † Ralli, Mrs. Stephen A., 32, Park Lane, H. Ramsay, Prof. W. M. D.C.L. (V.P.), The University, Aberdeen, Rawlins, F. H., Eton College, Windsor. Rawnsley, W. F., Parkhill, Lyndhurst, Hauls. Reece, Miss Dora, 26, Bullingham Munsion, Pitt Street, Kensington, W. Reid, J. S., Litt. D., Cainer College, Cambridge. Reinach, Salomon, 31, Rus de Berlin, Paris. Rendall, Rev. F., 82, Philipsach Gardens, S.W. †Rendall, G. H., Litt, D. (Council), Charterhouse, Godalming. Renieri, M. Mario, Athens. Richards, Kev. G. C., Oriel College, Oxford. Richards, F., Kingswood School, Buth. Richards, H., Wadham College, Oxford. Richmond, Sir W. B., K.C.B., R.A., Hevor Lodge, West End, Hammersmith, W. Ridgeway, Prof. W. (Council), Fon Ditton, Cambridge. Ridley, Sir Edward, 48, Lennex Gardens, S. W. Rigg, Herbert A., 12, Stanhope Place, Hyde Park, W. Robb, Mrs., 46, Rutland Gate, S.W.

Roberts, Rev. E. S., Caine College, Cumbridge.

Robertz, Professor W. Rhys, University College of North Wales, Bangor. Robertson, Charles, Redfern, Colinton Road, Edinburgh.

Robertson, Rev. Archibald, King's College, Strand, W.C. Robinson, T. P. G., Askfield, Rothsay Place, Redford.

Rochester, The Right Rev. the Lord Bishop of, Rishop's House, Kennington ParkRoad, S. F.

Rogers, Major-General, 14, St. Margaret's Road, St. Leonards-on-Sea, Rome, W., Oxford Lodge, Wimbledon Common, S.W.

†Rosebery, The Right Hon, the Earl of, K.G., 58, Berkeley Square, W. Rotton, J. F., 3, Bollons, West Brompton, S.W.

Roundell, C. S., Dorfold Hall, Nantwick.

Rous, Lieux-Colonel, Worstead House, Norwick,

†Rouse, W. H. D., 4, Bilton Road, Rugby.

Rubie, Rev. Alfred E., The Royal Naval School, Eltham, S.E. Rucker, Miss S. C. 4, Vanburgh Terrace, Blackheath.

Runtz, Ernest, 22, Moorgoute Street, E.C. Rushbrooke, W. G., 13, Catheart Hill, Highgale, N. Rutherford, Rev. W. Camian, LL.D. 19, Diam's Yard, Westminster, S.W. Ryle, Rev. Prof. H. E. D.D., President of Queens' College, Cambridge. Samuel, Mrs. Sylvester, 80, Onslow Gardens, S.W. Samuelson, Sir B., Bart., 56, Princes Gate, S. Kentington, S. H . Sandwith, T. B., C.B., 29, Bramham Gardens, Earl's Court, S. W. Sandya, J. E., Litt. D. (V.P.), St. John's College, Cumbridge Sandys, Mrs., Merton House, Cambridge. Savage-Armstrong, Prof. G. F., Queen's College, Cark. *Sayce, Rev. Prof. A. H., Ll., D. (V.P.), 4, Whitehall Court, S.W. †Scaramanga, A. P., 18, Barkston Gardens, S. Kensington, S.W. Schilizzi, John S., 6, Cromwell Houses, S. Konzington, S.W. Schultz, R. Weir (Council), 6, Mandeville Place, W. Schuster, Ernest, 12, Harrington Gardens, S. W. Scouloudi, Stephanos, Athens, Greece. Scall, Miss Sara A, 1100, M. Street, N.W., Washington, D.C. Seaman, Owen, Tower House, West Hill, Pulmer, S. II. Seebohm, Hugh, The Hermitage, Hitchin. Seltmann, E. J., Whitgift, Sutton, Survey. + Selwyn, Rev. E. C., School House, Uppingham. +Sendall, Sir Walter J., K.C.M.G., Colonial Office, S. W., Seymour, Prof. Thomas D., Vale College, Newhaven, U.S. A. Shadwell, C. L., Oriel College, Oxford. Sharkey, J. A., Christ's Callege, Cambridge. Sharpe, Miss, Harold House, Lansdowne Road, W. Shewan, Alexander, cto Messes. W. Watson and Co., 27, Leadenhall Street, E.C. Shuckburgh, E. S., Granchester, Cambridge. Sidgwick, Archur, Corpus Christi Callege, Osford. Sidgwick, Prof. Henry, Litt.D., Trialty College, Cambridge. Sikes, Edward Ernest, St. John's College, Cambridge. Simpson, H. B., 18, Brompton Square, S. W. Sinclair, Captain H. M., R.E., Junior United Service Club, S.W. *Skrine, H. D., Charreton Mange, Bath. *Skrine, Rev. J. H., Trinity College, Glenalmond, Perthehire. Smedley, J. F., 62, Warwick Street, Belgrave Road, S.W. Smith, A. Hamilton (Council), 121, Bedford Court Mansions, Redford Avenue, W.C. Smith, Cecil, LL.D. (Conneil), 18, Earl's Terrace, Kensington, W. Smith, F. E. J., 2, Tanfield Court, Inner Temple, E.C. Smith, Prof. Goldwin, The Grange, Teconto, Canada. Smith, H. Babington, C.S.L., Stokeleigh, Queen's Road, Weybridge. Smith, J. A., Balliel College, Oxford, Smith, R. Elsey, 7. Gardan Street, Gardon Square, W.C. Smith, Reginald J., Q.C. 11, Hyde Park Street, W. Smith, W. G., St. John's College, Oxford. . TSnow, T. C., St. John's College, Oxford. Somerset, Arthur, Castle Goring, Worthing. Sounenschein, Frot. E. A., Greenfield Cottage, Harborne, Birmingham, Southwell, The Right Rev. the Bishop of, Thurgarian Priory, Southwell. Spiers, Phene, Carlton Chambers, 12, Regent Street, W. Spooner, Rev. W. A., New College, Oxford. Spring-Rice, S. E., C.B., 1, Bryanston Place, Bryanston Square, W. Stannus, Hugh, 6t, Larkhall Rise, Clapham, S.W. Stanton, Charles H., Field Place, Strend, Glaucesterchire. Starham, H. Heathcote, 40, Gower Street, W.C. Stawell, Miss Melian, Newnham College, Cambridge. Steele, Dr., 33, Via S. Gallo, Florence. Sterrett, J. R. Sitlington, Amhurst College, Amhurst, Mass., U.S.A.

Stevenson, Miss E. C., 13, Randolph Crescent, Edinburgh.

Stewart, Prof. J. A., Christ Church, Oxford. Stillman, W. J., 50, Vin S. Raillie, Rome. Stillwell, James, t, Victoria Park, Daver. Stogdon, J., Harrow, N.W. Stokes, Miss Margaret, Carrig Brone, Lowth, co. Publin. Stone, E. W., Eton College, Windsor. Stone, Rev. E. D., Hillingdon, Uxbridge. Strachan-Davidson, J. L., Ralliol College, Oxford. Stretton, Gilbert W., The College, Dubwich, S.E. Strong, Mrs. 5, Arthur, LL.D. (Council), 36, Greswener Road, S.W. Sturgla, Julian R. Elvington, Eyethorne, Dover-Sturgis, Russell, 307, East 17th Street, New York. Sullivan, John, Keform Club, Pall Matt. S.W. Sutr, Watson, 57, Old Broad Street, E.C. Swanwick, Miss Anna, 23, Cumberland Terrace, N. W. Tait, C. W. A., Clifton College, Bristol. Tuncock, Rev. C. C., Leeb, Kirkby Loundale. Tarbell, Prof. F. B., University of Chicago, Chicago, Ill., U.S.A. Tarn, W. W., 13, Norfolk Square, Hyde Park, W. Tarring, C. J., Chief Justice of Grenada, West Vadies, Tatton, R. G., Passmore Edwards Settlement, Tabistock Place, W.C. Taylor, Rev. Charles, D.D., Master of St. John's College, Cambridge. Thompson, A. Douglas, Litt.D., The University, Edinhurgh. *Thompson, Sir E. M., K.C.B., D.C.L. (V.P.), British Museum, W.C. Thompson, E. S., Christ's College, Cambridge, Thompson, F. E., The Cottage, Preshute, Marthorough. Thompson, Henry F. H., 35, Wimpole Street, W. Thompson, J. Eyre, 8, Stone Buildings, Lincoln's Inn, W.C. Thursheld, J. R., Fryth, Great Berkhamstead. Tilley, Arthur, King's College, Cambridge, Tottenham, H. R., St. John's College, Cambridge. * Tozer, Rev. H. F. (V.P.), 18; Norham Gardens, Oxford. †Truell, H. P., F.R.C.S., Clonmannon, Ashlord, Co. Wickley. Tubbs, Prof. M. A., University College, Auckland, New Zealand. Tuckerman, Mrs. Mary F., 12, Incopo da Diacceto, Florence. * Tuckett, F. F., Frenchay, near Bristol. Tudeer, Dr. Emil, Helsingfors, Finland. [Turnbull, Mrs. Peveril, Sandy-Brook Hall; Ashbourne. Tylor, Prof. E. B., D.C.L., F.R.S., The Museum House, Oxford. Tyrrell, Prof. R. Y., Litt.D., D.C.L. (V.P.), Trinity College, Dublin. Underhill, G. E., Magdaten College, Oxford, Unwin, T. Fisher, 10, Hereford Square, S.W. Upcott, L. E., The College, Marlhorough. "Valetta, J. N., 16. Durham Terrace, Westbourne Park, W. Valieri, Octavius, z, Kensington Park Gardens, W. Vanderbyl, Mrs. Philip, 51, Porchester Terrare, W. Vardy, Rev. A. R., King Edward's School, Birmingham. Vaughan, E. L., Etan College, Windsor. Venning, Miss Rosamond, 6. Balcombe Street, Dorset Square, N.W. Verrall, A. W., Litt.D., Trinity College, Cambridge. Verrall, Mrs. A. W., Schuyn Gardens, Cambridge. Vincent, Sir Edgar, K.C.M.G., Esher Place, Survey.

t Vlasto, T. A., Boucevaine, Sefton Park, Liverpool.

t Wackernagel, Prof. Jacob, Steinanberg, 5, Bille.

t Wagner, Henry, 13, Half Moon Street, W.

t Waldstein, Prof. Charles, Ph.D., Litt.D., King's College, Cambridge.

Walford, Mrs. Neville, Warlegh, Tamerion Foliot, Crosen Hill, R.S.O., South Denon.

Walker, Rev. F. A., D.D., Dun Mallard, Shootop Hill, Brondesbury, N.W.

Walters, Henry Beanchamp (Council), British Museum, W.C.

Wantage, Lord, K.C.B., V.C., 2, Carlton Gardens S.W.

Ward, John, F.S.A., Lengrente Belfast,

Ward, T. H., 25, Grosvenor Place, S. W.

Warr, Prof. G. C., 16, Earl's Torrace, Kensington, W.

Warre, Rev. Edmond, D.D., Eton College, Windsor.

Warren, T. H., President of Magdaten College, Oxford.

Warren, E. P., Lewis House, Lewes, Sussex. Waterhouse, Edwin, Feldemore, near Dorking.

Waterhouse, Miss M. E., 59, Edge Lane, Liverpool.

Watson, Mrs., Burnopheld, Co. Durhum.

*Way, Rev. J. P., The Hall, Rossall, Fleetroood.

+ Weber, F. P., M.D., 19, Harley Street, W.

Weber, Hermann, M.D., 10, Grosioner Street, W.

Wedd, N., King's College, Cambridge.

Weekes, G. A., Sidney Summer College, Cambridge.

Weir, Miss Edith, 4, Fregnal, Hampetent, N.W.

Weld-Blandell, Herbert, 7. Park Place, St. James's. S.W.

Wells, J., Wadham College, Oxford.

Westvott, Rev. F. B., School House, Sherborne.

Westlake, Prof. J., L.L.D., The River Moure, Chelvea Embanhment, S. H.

Wheeler, James R., Ph.D., Columbia College, New York City, U.S.A.

White, Mrs. Andrew, American Embassy, Berlin.

White, Prof. J. W., Cambridge, Massachusetts, U.S.A.

White, J. N., Reckland, Waterford.

White, John Forbes, LL.D., Craigetsy, Dunitie.

Whitehead, R. R., Box 144, Santa Barbara, California, U.S.A.

Whitehouse, F. Cope, 8. Cleveland Row, St. James', S. W.

Wickes, Miss J. K., 23, Belaine Road, South Hampstead, N.W.

Wickham, The Very Rev. E. C., The Deanery, Lincoln.

Wilkins, Rev. George, 30, Trinity College, Dublin.

Wilkins, Prof. A. S., L.L.D., Litt.D., The Owens College, Manchester.

Williamson, J. W., Limusol, Cyprus.

Willson, S. B. Wynn, St. John's College, Cambridge,

Wilson, Donald, Wavertree, Severley Road, Hull.

Wilson, H. C. B., New Cottege, Oxford. Wilson, Harry, 447, Oxford Street, W.

Windley, Rev. H. C., St. Chad's, Bensham, Gateshead-on-Tyne.

Winkworth, Mrs., Holly Lodge, Campden Hill, 18.

Wiseman, Rev. Henry John, Clifton College, Bristol.

Wood, Rev. W. S., Ufford Rectory, Stamford,

Woodhouse, W. J., I, Garfield Terrace, Garth Road, Rangur, N. Wales.

t Woods, Rev. H. G., Festining, N. Wales,

Woodward, Miss M. C., Lywood, Scaton, Devon.

+Wren, Walter, 7, Power Square, W.

Wright, Prof., John Henry, Cambridge, Mais, U.S.A.

Wright, Sir R. S. 14, St. James's Place, S. W.

tWright, W. Aldis, Vice-Master, Trinits College, Cambridge.

+ Wyndham, Rev. Francis M., St. Mary of the Angels, Westmorelana Road, Bayeswater, W.

† Wyse, W., Trinity College, Cambridge.

Yates, Rev. S. A. Thumpson, 43, Phillimore Gardens, W.

Yorke, V. W., Forthampton Court, Temberbury.

"Young, Rev. Canon E. M., Rothbury, Northumberland.

Yule, Miss Amy F., Tarradale House, Ross shire, Scotland.

LIST OF SUBSCRIBERS TO THE JOURNAL OF HELLENIC STUDIES.

The University Library, Attendion. The University College of Waies, Aborth, ith. The Carnegie Free Library, Allechen, Pa., U.S.A. The Amherst College Library, Amherst, Mass. The Andover Theological Seminary, Andover, Mass., U.S.A. The Peabody Institute, Itallimers, U.S.A. The Johns Hopkins Library, Bullimere. The Enoch Pratt Library, Bollimars The Royal Museum Library, Berlin.
The Royal Library, Berlin.
The Central Free Library, Ratcliffe Place, Hirmingham () D. Mullins, Esq.) The Mason Science College, Wirmingham. The Public Library, Boston, U.S.A. The Boston Athenaum, Roston, U.S.A.
The University Library, Breslaw.
The Library of Clifton College, Cultan, Bristol. The University Library, California.
The Harvard College Library, Cambridge, Muss., U.S.A.
† The University Library, Cambridge.
The Library of Trinny College, Cambridge. The Library of St. John's College, Cambridge, y The Library of King's College, Cambridge The Fitzwilliam Archaeological Museum, Cambridge. The Girton College Library, Cambridge,
The University College of South Wales, Cardiff.
The University of Chicago Press, Chicago, Illinois.
The Lewis Institute, Chicago, Illinois.
The University Library, Christiania, Norway.
The Library of Camerbury College, Christianich, N.Z. The Public Library, Cincinnati, U.S.A.
The Adelbert College, Cleveland, Okio, U.S.A.
The University of Colorado, U.S.A. The University Library of State of Missouri, Columbia, Missouri, U.S.A. The Public Library, Detroit The Royal Museum of Casts, Dresden, †The Library of Trinity College, Dublia, The National Library of Ireland, Dublin. The King's Inns Library, Dublin. The Royal Irish Academy, Dublin.
The University College, Dundes.
The Durham Cathedral Library, Durham. The Advocates' Library, Edinburgh. The University Library, Erkingen The University Library, breiburg in Baden, Germany. The Philologische Seminar, Gieren. The University Library, Glosgo The Ducal Library, Gotha (Dr. W. Pertsch). The University Library, Göttingen. The Royal University Library, Greiftwala. The Dartmouth College Library, Hanovar, U.S.A. The University Library, Heidelberg (Dr. Zaugmeister). The School Library, Harrow, V.W. The Cornell University Library, Whats, N. V. The University Library, Jena. The Royal and University Library, Kanagsharg. The University of Kansas, Laurence, U.S.A. The Loods Library, Commercial Street, Leeds.
The Public Library, Leeds.
The Bibliothèque Universitaire, 3, Rue des Fleurs, Lille, Nova. The Free Library, Liverpool.
The University College, Liverpool.
The British Museum, W.C. The Department of Greek and Roman Antiquities, British Museum, W.C. The Library of University College, Landon.
The Athenaeum Chio, Pall Mall, Landon, S. H.
The Barlington Fine Arts Club, Savile Row, Landon, W.
The Library of St. Pan's School, West Kensington, W.
The Lendon Library, St. James's Square, London, S. W.
The Reform Club, Pall Mall, Landon, S. W.

The Royal Institution, Albemarle Street, IV.

```
The Library, Westminster School, S. W.
The Oxford and Cambridge Club, Pall Mall, c.o. Mezers. Harrison & Sono, 59, Pall Mall. The Foreign Architectural Book Society (T. H. Watson, Esq.), 9, Nattingham Place, W.
The Sion College Library, Victoria Embankment, E.C. The College Library, Dulwich, S.E.
The City Library, Lowell, Mass., U.S.A.
The Bibliothèque Universitaire, Polais Saint Pierrs, Lyons.
The Whitworth Institute, Manchester.
The Chetham's Library, Hunts Bank, Manchester.
The Grammar School, Manchester
The Grammar School, Manchester
The Royal University Library, Marburg.
The Public Library, Melbourne, Victoria (cia Messys, Melville, Mullen & Ca.).
The Library of the University of Milan, Milan,
 The McGill University Library, Montreal (C. H. Gould, Esq.)
 The Königliche Paulioische Bibliothek, Munster, L.W.
 The Royal Library, Munich.
The Archaelogical Seminary, Munich.
 The University of Nebraska, Nebraska, U.S. A.
 The Forbes Library, Northampton, U.S.A.
The Free Public Library, Newark, New Jersey.
The Newberry Library, Newberry, U.S.A.
The Library of Yale College, Newberren.
 The Free Public Library, Jersey City, New Jersey, U.S. A. The Astor Library, New York.
  The New York State Library, Albahy, New York. The Library of Columbia University, New York.
 The Hamilton College Library, Clinton, New York.
The Metropolitan Museum of Art, New York.
  The Library of the College of the City of New York, New York.
The Bodleian Library, Oxford.
  The Library of All Souls College, Oxford.
The Library of Wordester College, Oxford.
  The Library of Ballioi College, Oxford.
The Library of Christchurch, Oxford.
The Library of Exeter College, Oxford.
The Library of St. John's College, Oxford.
  The Library of New College, Oxford
  The Library of Oriel College, Oxford.
The Library of Queen's College, Oxford.
The Library of Trinity College, Oxford.
  The Library of University College, Oxford.
   The Union Society, Oxford.
The University Galleries, Oxford.
   The Bibliothèque de l'Institut de France, Paris.
   The Bibliothèque de l'Université de France, Pares
   The Bibliothèque des Musées Nationaux, Paris
   The Bibliothèque Nationale de Paris, Poris.
   The Ecole Normale Supérieur, Paris
   The Library Company, Philadelphia.
The Library of the University of Pennsylvania, Philadelphia, Pa., U.S.A.
   The Vassar Library, Poughkeepsie, N.Y.
The Archaeological Seminary, The University, Progue (Dr. Wilhelm Klein).
    The Bibliothèque de l'Université, Renner,
   The Library of Brown University, Previdence, Rhade Island, U.S.A.
The American School of Classical Studies, Rome, Italy.
The Rossell Library, Resall, Fleetowad (the Rev. W. H. E. Worship).
The School Reading Room, Rughy, care of Mr. A. I. Lawrence.
The St. Louis Mercantile Library, St. Lenis, U.S.A.
The Royal Library, Stockholm (Messes, Samson & Wallin).
The Archaeological Museum, The University, Strainburg (per Prof. Michaelis).
The Imperial University and National Library, Strainburg
    The Free Public Library and Museum, Preston.
    The Free Library, Sydney, New South Wales.
The University Library, Syracuse, New York
The University Library, Toronto.
The Library of the University of Illinois, Urbana, Illinois.
     The Boys' Library, Eton College, Winasor.
     The Library of Eton College, Windsor.
The Bibliothèque Publique, Winterthier, (Dr. Imboef-Blumer).
     The Free Library, Workster, Mass., U.S.A.
     The Williams College Library, Williamstown, Mass., U.S.A.
                                            I Libraries elalming outles under the Copyright Ash.
```

LIST OF JOURNALS, &c., RECEIVED IN EXCHANGE FOR THE JOURNAL OF HELLENIC STUDIES.

American Journal of Archicology (Professor J. M. Paton, Middleton, Connecticut U.S.A.)

Analecta Bollandiana, Société des Bollandistes, 14, Rue des Ursulines, Bruxelles, Bulletin de Correspondance Hellénique (published by the French School at Athons). Bullettino della Commissione Archeologica Commaie di Roma (Prof. Catti, Musco Capitolino, Rome).

Ephemeris Archaiologike, Athens.

Jahrbach of German Imperial Archaeological Institute, Cornellusstrasse No. 2 II.

Jahreshefte des Österreichischen Archäologischen Institutes Turkenstrasse, 4, Vienna

Journal of the Royal Institute of British Architects, 9, Conduit Street, W. Journal International d'Archéologie Numismatique (M. J. N. Svorones, Musée

National, Athens). Mclanges d'Histoire et d'Archéologie, published by the French School at Rome. Mirtheilungen of the German Imperial Archaeological Institute at Athens.

Mittheilungen of the German Imperial Archaeological Institute at Rome.

Mnemosyne (care of Mr. E. J. Brill), Leiden, Holland

Numismatic Chronisle, 22, Albemarle Street.

Philologus. Zeitschrift für das klassische Altertum (cure of Dietrich'sche Verlags-Buchhandlung, Göttingen).

Praktika of the Athenian Archaeological Society.

Proceedings of the Hellenic Philological Syllogos, Constantinople. Publications of the Imperial Archaeological Commission, St. Petersburg,

Revue Archéologique, Paris (per M. Georges Perrot, 45, rus a Ulm).

Revue des Études Grecques, Publication Trimestrielle de l'Association pour l'Encouragement des Études Grecques en France, Paris.

Transactions of the American School, Athens.

Transactions of the Cambridge Philological Society and Journal of Philology

SESSION 1897-98.

THE First General Meeting was held on November 4th, 1897, Mr. Talfourd Ely in the chair.

Prof. E. Gardner read a paper on a vase which he was kindly permitted to publish by the authorities of the Harrow School Museum. It was the gem of the collection presented to that museum by Sir G. Wilkinson; it could be identified from description with a vase of which a tracing existed in the apparatus of the German Institute at Rome, and which was found at The main subject of the vase was the combat between Vitorchiano. Caeneus and the Centaurs: this scene was represented with extraordinary life and vigour. The foreshortening of the body of one of the Centaurs, seen from behind like the horse in the Issus mosaic, was a very bold experiment in drawing; and the faces, especially that of this same Centaur, were marked by a skill in rendering character and expression hardly ever surpassed or even equalled in Greek vase painting. The vase could only belong to the very finest school and period-to the later style of the cycle of Euphronius; in the works of this master and his associates many similar characteristics could be found, and especially in those vases assigned by Dr. Hartwig to Onesimus. Proceeding to discuss the myth, Prof. Gardner pointed out the inconsistencies of the accepted tradition, both with itself and with artistic representations. Accepting Mannhardt's explanation of the battle of the Centaurs and Lapiths as derived from the common present belief that the devastation wrought by storms is the result of a conflict between the spirits of the wood, he looked for the origin of the Caeneus story in rites connected with such spirits, and pointed out evidence that the tale of the burial of Caeneus was derived from one of those human sacrifices that so often seem to have been associated with pine trees in Greece [J.H.S. vol. xvii. p. 294].—Mr. G. B. Grundy then read a paper on Salamis. He expressed surprise that the main thesis of Prof. Goodwin's paper. published in the Journal of the Archaeological Institute of America in 1882-3, had not been accepted in recent histories of Greece. He thought, however, that Prof. Goodwin had failed to show that Herodotus's account is, as it stands, in favour of that scheme of the battle for which Prof. Goodwin argues. Herodotus seems to have had at his disposal information which was in its essential characteristics similar to the first-hand information of Aeschylus and the second-hand information of Diodorus, but to have used it mistakenly. He antedates the first movement of the Persian d

fleet to the Strait to the afternoon instead of the night before the battle, describes the movements in the night in terms of the movements in the next day's battle, and has consequently nothing to say of the main movements in the battle itself.

The Second General Meeting was held on February 24th, 1898, Prof.

Jebb, President, in the chair.

Mr. R. C. Bosanquet exhibited and described Mr. Clark's drawings of the fine mosaic found in Melos by members of the British School at Athens.-Prof. Ridgeway gave an address on some of the contents of his forthcoming book, 'The Early Age of Greece.' He briefly repeated the results at which he had arrived in his paper What People made the Objects called Mycenaean?' (Journal of Hellenic Studies, 1896) in which he had maintained that these objects were the outcome of a people who had occupied the mainland of Greece and the islands from a very remote period, and who were in full occupation when the Achaeans entered Greece, as described by Homer and the later Greek authors. These earlier inhabitants of Greece were the people called by the Greeks themselves the Pelasgians. He pointed out that so good an archaeologist as M. Salomon Reinach had become a convert to this doctrine. On the other hand, Prof. Percy Gardner, in his 'Sculptured Monuments,' published since the appearance of his (Prof. Ridgeway's) paper, still adhered to the old Achaean theory, though 'with trepidation,' giving as his chief reason that he followed 'the sober judgment' of M. Perrot. Prof. Ridgeway then examined the arguments given by M. Perrot, on which, of course, Prof. Gardner's belief was based. He first pointed out that it was unfair to M. Perrot, who had written in 1894, before the new doctrine had appeared, to pin him to the views which he then held. M. Perrot, desiring to get evidence that the Achaeans had been settled in the Mediterranean from a remote epoch, gives as his proofs of this (1) that the Eteocretes were Achaeans, though it happens that in Homer, Od., xix. 177 segg, these peoples are explicitly distinguished; (2) that the people called Aquaiousha in an inscription of the fifth year of Merenptah I. are the Achaeans. Prof. Ridgeway pointed out that by the earliest reckoning (Flinders Petrie) this would be about 1200 B.C., and by the latest possible (Torr) about 1025 B.C. Now, as by the traditional Greek chronology the Achaeans had entered Greece about 1250 B.C., there was not the slightest ground for believing that they were in Greece before that time. Finally, he asked if the identity of Achaioi and the Aquaiousha was a bit more certain than that between Ucalegon (proximus ardet) and Judy O'Callaghan in the Irish epic known as 'Lanigan's Ball.' He then pointed out that M. Perrot, Prof. P. Gardner, and Dr. Leaf were all believers in the truth of the Greek tradition that the Pelasgians were the older inhabitants of Greece, and then referred to the great discrepancy between the Mycenaean culture, which was that of the Bronze Age, and that of the Homeric poems, which showed that of the Iron Age, and closely resembled that of the Hallstatt period of Central Europe. He pointed out that in both ancient and modern times the mass of the population of Greece and the Mediterranean sea-board was darkhaired, whilst the Achaeans of Homer are described as 'fair-haired.' He then stated his thesis that in the fair-haired Achaeans of Homer we have the earliest of those waves of fair-haired warriors from Upper Europe who swept down and conquered the black-haired indigenous population of the southern peninsulas, but in a few generations became enervated in the south and were absorbed in the conquered aborigines-such had been the fate of the Normans, Vandals, Visigoths, Gauls, etc. He then proposed to show that the social system, law of inheritance, and religion of the Homeric poems (as well as the armour, etc.) differed materially from those known in classical times in districts which the consensus of history declared to have been always occupied by a Pelasgian population, such as Arcadia, Attica, Crete, and the other islands, whilst, on the other hand, it corresponded to those of the fair-haired peoples of Central Europe. Thus in Homer we have strict monandry and descent through males, as among Teutonic peoples; but in the Pelasgic parts of Greece we have descent through women in ancient Athens, while among the Pelasgians of Thessaly it goes side by side with polyandry. Again, there is no trace of fetish in Homer, but the worship of fetish was notorious in Arcadia, Attica, etc. Totemism was also unknown to Homer; but in Attica and Arcadia, Cyprus and Scriphus, all Pelasgic, Mr. Lang, Mr. Frazer, and Prof. Robertson Smith had found many phenomena resembling those known among totemistic tribes at the present day. He thought that some things in Greece had been called totems which did not stand critical test, but there were several instances which seemed to defy explanation on any other principle. On the other hand, there was no trace of fetish or totem in the Teutonic peoples; hence the Achaeans resembled these peoples in social and religious system. He had only time to touch upon one or two gods. He showed that Poseidon was the god of the older population of Greece, having been driven gradually by Zeus and Apollo from Thessaly, Delphi, Attica, Argolis, and Delos, and that he is represented with dark hair, like the people who worshipped him, whilst Apollo, the new-comer from the land of the Hyperboreans, the way to which lay by the sources of the Danube, was golden-haired, like the fair-haired Achaeans, who, the speaker contended, had come from that region.-Prof. Jebb thanked the speaker in the name of the Society for his brilliant and suggestive address.-In the discussion which followed Prot. W. C. F. Anderson expressed doubt as to the use of arguments based upon pottery and armour in determining ethnical affinities, and questioned also whether those derived from matriarchal or patriarchal systems might not be pushed too far. It was hard to believe that a race so evidently important in early times as the Pelasgians could have entirely disappeared. Complicated systems of clans, etc., always connoted primitive conditions, not high civilization. Simplicity of system came with time.-Prof. Percy Gardner, while not prepared to deal off-hand with all the points raised, thought some of the views expressed

quite reasonable, though there were others which he could not accept. On the Mycenaean question he had not finally committed himself, but he was prepared to accept new light from whatever quarter it came. He could not. accept the broad distinction drawn between Homer and the later poets, and hesitated to believe that the brilliance of Attic intellect was due to an inferior race. These questions of race and religion seemed almost bottomless, and even appeals to archaeology might mislead. The description of Homer and Zeus as Achaean, the Attic poets and Poscidon as Pelasgic, was open to grave doubt.-Mr. Arthur Evans thought that the necessity of compression made Prof. Ridgeway's views rather difficult to follow. On the archaeological question, though most people would agree that the Mycenaean was a development of an earlier civilization, the evidence of its continuity was hardly yet as well established on the mainland of Greece as in the islands. The presumption, therefore, was in favour of its centre of gravity being the Aegean rather than Greece proper. As to the supposed descent of the Achaeans from the Danubian regions into Greece, he was inclined to believe that the flow had been in the opposite direction. If these fair-haired people were non-Aryan and barbaric, why did they speak only Greek, and diffuse that dialect from the Peloponnese to Cyprus? More precise information was still needed about the Achaeans, though they clearly represented the dominant element in Greece. Again, it was difficult to separate precisely the cults of Zeus and Poseidon. The latter had a close connexion with the Achaeans in their Italian colonies.--Mr. Farnell spoke of the address as very suggestive, and expressed his cordial agreement with Prof. Ridgeway's main position as to the light thrown by religion on ethnology. Clearly we had to reckon with the existence in Greece of a different and earlier race. If non-Aryan, as the speaker contended, the comparative rarity of totemism in Greece might be used as an argument. for most writers on that subject agreed that it was not found as a rule among any Aryan peoples, and if so found, belonged to an earlier non-Aryan race. But this and similar arguments from the matriarchal system must be used with caution. Thus uncouth forms of marriage and religion occurred in Pelasgic Arcadia, and female worship was undoubtedly found among Aryans. As to Poseidon, Mr. Farnell was open to conviction, but he had himself argued that the worship of Poseidon in Attica was a late introduction. If the Ionians were Pelasgians, then the Pelasgians must themselves have been a Greek stock.-Prof. Ridgeway expressed himself much gratified by the discussion, and said that the objections raised to his theory would for the most part be met in his forthcoming book, where the points ethnological, archaeological, and linguistic were all elaborately discussed.

The Third General Meeting was held on April 28th, 1898, Mr. Talfourd Ely in the chair,

Prof. W. C. F. Anderson read a paper 'On the March of Xerxes,' dealing with the country between the Hebrus and Mount Athos. His

account was based on a journey taken in the autumn of 1896 in company with Mr. J. A. R. Munro. It was illustrated with a number of lantern slides from negatives taken on the spot. The site of Doriscus lies somewhere near the modern town of Dede Agatch, but has not yet been found. The only ruins known in the district are those of Trajanopolis. The importance of the place as a base of supplies is still evident, for the corn of the fertile Hebrus valley and of Eastern Roumelia is shipped there in large quantities. The route of Xerxes from Doriscus is not easy to ascertain. The coast road through Maronia is difficult, and at the present time impassable. The Via Egnatia and the Turkish post road ran north of Mount Ismarus, and this may be taken as the natural main route. Herodotus speaks of Xerxes having adopted a triple line of advance, and if this is accepted his right wing must have marched up the Hebrus valley. the centre following the line of the Via Egnatia, and the left wing going by the coast. Even a twofold division cannot have been long maintained, for unless the mouth of the Buru Ghyul (Lake Bistonis) was bridged, both the centre and left wing must have passed along its northern shore, as the old roads and the new railway road between Gumuldjina and Xanthi do. In this case Abdera lies south of the main route, but not more than a day's journey from it. Further west, after the crossing of the Nestus, there is only one road between the mountains and the sea, the narrow ledge, or corniche, which leads to Cavalla (Neapolis). From Cavalla, the famous Symbolon Pass is the only way to the fertile plain of Philippi. Two roads lead from the plain of Philippi to the Strymon : the old Turkish post road, which passes Pravi and runs down the narrow Pierian valley, and the Via Egnatia, down the valley of the Anghista. According to Herodotus, Xerxes marched down the Pierian valley, but it is impossible to suppose that, with his large army, he can have neglected the easier marching route. Mining holes, scorize, and a prehistoric tower are still to be seen in the Pierian valley, near Mousthenia, which may be the site of Phagres mentioned by Herodotus. The mouth of the Strymon, with its lagoons, has no very ancient ruins to show, though the deserted storehouses at Tchai-aghazi prove that it was an important grain-distributing centre until the present century. It is the next natural base of supplies west of Doriscus, and as such was selected by Xerxes. From the mouth of the Strymon to the pass of Aulon the road runs along the shore at the foot of the Bisaltic mountains, no alternative route to Chalcidice being possible. It is, however, difficult to determine how Xerxes marched thence to Athos. The direct road south crosses the difficult range of Mount Stravenico. It is a mountain track, so little used that it cannot be found without a guide, and so steep that it can only be followed on foot. The natural route is south-west inland to Larigova and thence to Poligyro; but as the site of Stagirus is still undiscovered, it is impossible to say if this is the route Herodotus refers to, Brasidas advanced by the inland route when marching on Amphipolis. The site of Acanthus is marked by the old town walls, built of huge, wellcut blocks, which are plainly visible in the citadel rock and at many places

throughout the modern town of Hierisso. The canal is only a little over two hours distant, but owing to the suspicion of the military commander at Hierisso, the visit paid was short. The line of the canal is best seen from the hills on the south side of the isthmus, where a small stream has kept it from being as completely silted up as it is on the north side. It enters the sea on the south between two hills through what seems to be an artificial cutting. Near these hills are some blocks of a cyclopean wall, which, however, the monks are using as a quarry for building a monastery farm. These blocks perhaps mark the site of Sane,

The Annual Meeting was held on June 30, 1898, Prof. Jebb, President, in the chair.

The Hon. Secretary (Mr. George Macmillan) read the following Report on behalf of the Council.

The progress of the Society during the session just ended has been quite satisfactory. Two numbers of the Journal have been published as usual, and the meetings have been well attended and have led in most cases to good debates. This was notably so with Professor Ridgeway's address on the origin of the Achaeans on February 24th. At the following meeting on April 28th the magic lantern was introduced for the first time, and proved an attractive accompaniment of Professor W. C. F. Anderson's account of a journey along the route followed by the army of Xerxes.

The index to Volumes IX.—XVI. of the Journal of Hellenic Studies and to the Supplementary Papers, promised in last year's Report, is now nearly ready for issue.

In the course of the year it was found necessary to make some change in the editorial management of the Journal. Dr. Walter Leaf, who has for some years past been an active member of the Editorial Committee, desired to be relieved of his office owing to the pressure of other work, and Mr. Arthur Smith also, upon whom has fallen for many years the chief burden of preparing the illustrations, which form such an important feature in the Journal, intimated that he could no longer devote the time necessary to the work. The Council were fortunate enough to induce Mr. F. G. Kenyon to take Dr. Leaf's place on the Editorial Board, while Mr. G. F. Hill, of the Coins Department in the British Museum, consented, in consideration of a small honorarium, to take over the heaviest part of the editorial work, including the management of the illustrations. Mr. Arthur Smith kindly agreed to remain on the Committee for another year to assist the new Editors with his advice, so as to secure a continuity of administration. As a return for his great services both as an Editor of the Journal and as Hon. Librarian the Council elected Mr. Smith an Honorary Life Member of the Society, and the same distinction was conferred. konoris causa, upon Dr. Walter Leaf and Professor Percy Gardner, whose labours on behalf of the Journal have been so devoted and so invaluable. The Council feel sure that this recognition of services ungrudgingly rendered to the Society will meet with the hearty approval of all its Members.

The development of the Library during the past year has been particularly satisfactory, and it is believed that, owing to recent accessions, it now holds in its own class the first place among libraries from which books can be freely borrowed. A complete list of accessions was printed as usual in the last volume of the Journal, but it may be well to mention

here the most important items.

In November last the Trustees of the British Museum presented about fifty volumes of their publications, including the Catalogues of Greek Coins, the Description of the Ancient Marbles, Facsimiles of Greek Papyri, &c. The Society has also acquired by purchase or exchange the following among other important works: Mr. J. G. Frazer's translation with commentary of Pausanies: the Wiener Vorlegeblatter, 1889-91; Omont's Athènes au xvii Siècle; Januaris's Historical Greek Grammar, and the two volumes of the Dilettanti Society's Specimens of Autient Sculpture.

In April of the present year Miss Harrison generously placed a selection of more than 200 volumes from her own library on deposit with the Society. These include the earlier volumes of the Annali, Bullettino, and Monumenti Inediti of the German Archaeological Institute; also of the St. Petersburg Comptes Randus and of the Archaeologische Zeitung, together with a large number of valuable monographs on vases, &c. It is hoped that this collection will ultimately be incorporated with the Library of the Society. At present the books are catalogued in the general catalogue, but cannot be taken away from the Library.

The numbers of readers and borrowers of books show a steady increase, about 150 visits having been paid to the Library during the Session. The lantern slides continue to be in request, and a new slide catalogue with considerable additions has been issued in the last number of the Journal. Thanks are due to Miss Harrison and to Mr. Barclay Squire for donations of slides, and to Messrs. Herbert Awdry and Flinders

Petrie for permission to use special series of slides.

The Council have now under consideration a systematic scheme for extending the collection both of photographs and of lantern slides, and of making it more available. Further particulars will be announced in due course, but in the meantime members who are prepared to contribute either photographs or lantern slides are invited to communicate with Mr. J. L. Myres (at Christ Church, Oxford), who has the matter in hand.

In the year now ended, the Council have placed the finances of the Library on a definite footing by assigning to the Library Committee a sum of £75 for the expenses of the Library, apart from salaries and rent. If it is found that the arrangement can be continued, the progress of the Library will be more uniform and steady than it has been in the past.

It will be a satisfaction to members to learn that the British School at Athens, under its new director Mr. D. G. Hogarth, has had another successful season, and in particular has pursued with most encouraging results the important excavations in the island of Melos which were begun in 1896 under the direction of Mr. Cecil Smith. Some of the fruits of this excavation have already found their way into the Society's Journal and abundant material has accumulated for further papers. Meanwhile some preliminary accounts of this as of other work done by the School have appeared, or will shortly appear, in the School Annual.

Beyond the annual grants to the School at Athens the Society has not during the past season been called upon to contribute to work outside its own borders, except for a grant of £25 made to Mr. W. R. Paton for purposes of exploration in Asia Minor. The Society, however, successfully approached the Foreign Office in order to secure for two of its members, Mr. J. G. C. Anderson and Mr. J. W. Crowfoot, facilities for travel in Asia Minor. The thanks of the Society are due to the Secretary of State for Foreign Affairs for the readiness with which he listened to the

appeal for his good offices in this matter.

The Treasurer's Accounts show the financial position of the Society to be satisfactory. Ordinary receipts during the year were £789 against £816 during the financial year 1896-97. The receipts from Subscriptions, including arrears, amount to £626, against £636, and receipts from Libraries and for the purchase of back volumes £118, against £126. The receipts for loan of Lantern Slides amount to £4 15s, against £5, but

other items of ordinary income show no change.

The ordinary expenditure for the year amounts to £823, against £616. Payments for Rent £80, Insurance £15, Salaries £50, and Stationery, &c. £45, are practically the same as in the preceding year; the cost of purchases for the Library shows £93 against £94. The cost of the Journal, Vol. XVII., Parts 1 and 2, has amounted to £510, against £346. The usual grant of £100 was made to the British School at Athens, and £25 to Mr. W. R. Paton as previously mentioned. The balance carried forward at the close of the year under review amounted to £201, against £360 at the end of the previous financial year.

Since the entrance fee was imposed in January, 1894, about £120 have been received from this source, a very substantial addition to the Society's

income.

Thirty-one new members have been elected during the year, while thirty-eight have been lost by death or resignation. This shows a net decrease of 7, and brings the total number of members to 771, including 21 hon, members.

One new Library has joined the list of Subscribers, which now amounts to 134; or with the five Public Libraries to 139,

The Council have recently added to the list of Honorary Members. Professor Conze, of Berlin, Professor Benndorf, of Vienna, and Monsieur l'Abbé Duchesne, the Director of the French School in Rome. Among the members who have died in the course of the year special mention is due to the Rev. William Wayte, who had for many years been an active member of Council, and had also served the office of Hon. Librarian.

The Council can only in conclusion congratulate members upon the continued prosperity of the Society, while reminding them once more of the importance of bringing in fresh recruits, not only to make up for the inevitable losses by death or resignation, but if possible steadily to increase the number of members, and so also the power of the Society to carry out efficiently the objects for which it was founded. This reminder is the more necessary this year as there has actually been a slight falling off in the number of members.

The adoption of the Report was moved by Sir John Evans, seconded by the Rev. B. Jackson, and carried unanimously.

The former President and Vice-Presidents were re-elected, Mr. Arthur Evans being added to the latter. Mr. G. E. Marindin, Prof. A. B. Cook, and Mr. R. Carr Bosanquet were elected to vacancies on the Council.

M. Salomon Reinach communicated a new theory concerning the date, denomination, and restoration of the Melian Aphrodite. A document published in 1892 proved that the famous statue was discovered together with a dedicatory inscription bearing the name of Theodoridas, son of Daistratos. The same Theodoridas appeared to have dedicated the colossal. statue of Poseidon discovered in Melos in 1877, and now in Athens. Epigraphical evidence showed that Theodoridas lived about 370 B.C. M. Reinach also argued from a passage in Philochoros (300 B.C.), who mentions two colossal statues of Poseidon and Amphitrite in the island of Tenos. His conclusions were as follows:-(t) The so-called Melian Aphrodite was an Amphirrite (2) The statue now in the Louvre was coupled with the Poscidon now at Athens in a sanctuary erected by Theodoridas about 370 E.C. (3) The Aphrodite must be restored after the model of the Poseidon, with a sceptre or trident in the left hand raised, and grasping at the falling drapery with her right hand. (4) The hand holding an apple in the Louvre, and the inscription bearing the name of Agesandros, now lost, have nothing to do with the statue, in spite of Dr. Furtwängler's contention to the contrary. (5) The Amphitrite and Poseidon-works of the same atelier, but probably not of the same chisel-both belonged to the Attic School immediately following the epoch of Phidias. On the invitation of the President, who thanked M. Reinach for his eloquent and persuasive address, the speaker promised to write a paper on the subject for the Journal of Hellenic Studies. Mr. Penrose gave some account of a recent visit to Athens.

PROCEEDINGS OF THE CAMBRIDGE BRANCH OF THE HELLENIC SOCIETY.

Session 1897-8.

On Saturday, February 19th, 1898, a meeting was held at Dr. Verrall's house.

Two papers were communicated to the Society-one by Dr. Verrall entitled 'Herodotus on the Measurement of the Pyramids' (since printed in the Classical Review, xii. 195 ff.), the other by Mr. A. B. Cook 'On some archaeological points in Aeschylus's Eumenides.' Among the passages discussed in the latter were the following. (1) Aesch. Eum. 166-172. Here the Chorus of Furies angered against Apollo who has taken their victim under his protection exclaim: 'Youder is earth's centre-stone with the grim pollution of blood upon it. Seer as thou art, thou hast defiled thine inmost shrine with a stain upon its hearth, sped by thyself and summoned by none other: for, sinning against the law of gods, thou givest honour to men and-hast destroyed the ancient Fates.' We expect 'the ancient Furies, not 'the ancient Fates' (mahavyevers Molpas),- thou givest honour to Orestes and takest it from us the Furies.' Either then we must explain why Aeschylus when he meant Furies said Fates, or we must show that a reference to the Fates is not inappropriate. Those who regard Molpas as a substitution for Epivos can appeal to several passages in which the Furies are closely associated with the Fates: e.g. P.V. 515 f. where the question 'Who then guides the helm of Necessity?' is met by the answer Μοίραι τρίμορφοι μνήμονές τ' Ερινύες. Indeed Rapp in Roscher Lex. I. i. 1327 f. collects a good deal of evidence to prove that the Furies dispensed good and evil to men: 'tis their allotted task,' says Aeschylus in Eum. 930, 'to order all mortal matters.' Nevertheless the passages adduced do not warrant the assertion that Moipus could be used as an alternative name for Episos. The Furies, it is true, are called Knoes Epivose in Sept. 1055; but the Kipes there mentioned are not necessarily. not even probably, to be identified with the Moipar. Moreover, in the Eum. Aeschylus is at pains more than once to distinguish between the Furies and the Fates; in 961 the Furies address the Fates as their 'sisters' (ματροκασιγεήται), and in 724 a similar discrimination is implied. Can we then show that an allusion to the Fates as distinct from the Furies is not out of place? Several editors hold that the phrase thou hast destroyed the ancient Fates' means 'thou hast ere now allowed the Fates to be rubbed by the rescue of Alcestis from death,' and they point out that this exploit is alluded to later on in the play (723 f.). But would Aeschylus have left us to puzzle over the conundrum for more than 500 lines without hinting at the answer? Now it will be noticed that the whole passage abounds with topographical allusions to the temple at Delphi: the omphalos, the sacred coria mentioned also by Plutarch and Pausanias, the uvyos or 'advtum.' all show that the Furies' argument is- You, Apollo, by befriending a murderer are bringing defilement upon your own house and its contents." May we not then believe that, when Aeschylus speaks of 'the ancient Fates' in such a context, he means the statues of the Fates which stood in the cella of the temple at Delphi? Paus, x. 24, 4 says 'There stand, moreover, statues (ἀγάλματα) of two Fates, and in place of the third Zeus Moiragetes and Apollo Moiragetes are at their side.' Why 'two Fates,' not three? Weizsäcker (Rosch, Lex. II. iii 3001) suggests that the one presided over Birth, the other over Death: or possibly the one dispensed good luck, the other bad. At any rate Plutarch de si Delphico 2 quotes the number as a theological awepla, and from the absence of ancient tradition we may perhaps infer that the statues belonged to the remote and half-forgotton past; they were what Aeschylus calls them malavereis Mologi. (2) The Chorus, now appeased, bid farewell to the Aesch. Enm. oof ff. Athenians and the Athenian gods. Their final benediction is a double one, pronounced first upon the deries a lews (997) and then upon marres of sara πτόλιν, δαίμονές τε καί βροτοί, | Παλλάδος πόλιν νέμοντες (1015 ff.), so that a contrast between down and molie is possibly intended. However that may be, the description of the Athenian people given in the first benediction runs; 'All hail, ye townsfolk, seated near to Zeus, loved by the Parthenos ye love; for the lesson of wisdom ye have learnt at last. Yea, 'neath the covert of Pallas' wings ye win the reverence of the Father himself.' A recent edition of the play comments: "Seated near to Zeus"; fine and simple metaphor for the righteous people specially under divine protection. This interpretation, though sanctioned by Hermann, hardly commends itself. When Aeschylus described his audience as Ierap ημενοι Διός, would they not first think of the Acropolis just behind them where Zeus Policus had his statue, his altar, and his peculiar cult? Again, Παρθένου φίλος φίλοι. Athena was worshipped on the Acropolis as Parthenos long before Pheidias' master-piece was erected. A marble basis found there, recording a dedication Hapthirm... Adaptala, bears the signature of Kritios and Nesiotes (C.I.A. i. 374 = Roberts i. 91 no. 67) and allows us to suppose that as early as 460 B.C. or earlier (cp. Hom. hymn. xxviii. 1-3) this title was established. The Eum, was produced in 458 B.C., so that, if we find in the word Haptivov a reference to the local cult, we are not guilty of anachronism. Lastly, Παλλάδος δ' ὑπο πτεροίς. Is this a mere metaphor, or was there at the time a winged Pallas on the Akropolis? The type is rare, but not altogether unknown. Farnell, Cults of the Gr. States, i. 341 f. cites the

available evidence, and from the occurrence of a winged Athena on the Cnidian Treasury at Delphi (Bull. de corr, hell. xviii, 190) infers that it was already known in the archaic period. Aristoph, Av. 574-pace Paleythrows no light on the subject, the reference there (as in C.I.G. i. 150, 23, Schol, Dem. Timocr. 121) being to the golden Nike on the hand of Pheidias's Athena in the Hecatompedon, a statue constructed in 447-438 B.C., more than ten years after the appearance of the Eumenides. A similar slip is made by Mr. A. Sidgwick who understands Bpéras | τουμόν in Eum. 1024 f. of the chryselephantine Parthenos. (3) Aesch. Eum. 1028. The cloaks of crimson dye, worn during the solemn procession which was to escort the Furies, are to be explained by the prophylactic significance of the colour red. Among the inhabitants of the Gold Coast, who commonly wear white garments, red is reserved for mourning purposes (Ellis, The Tshi-speaking Peoples, 88, 89, 93, 156). In modern Germany the new-born infant has a band of red stuff attached to his arm to preserve him from witchcraft, and the cart-horse is protected against the evil eye by scraps of red material (Fritzsche on Theocr. ii. 2). Neapolitan charms are still made of red coral for luck. Analogous customs prevailed on classical soil in ancient days, Verg. Aen. lii. 405 ff. suggests a prophylactic virtue in the colour: 'purpureo velare comas adopertus amictu, | ne qua inter sanctos ignis in honore deorum | hostilis facies occurrat at omina turbet.' In the Geoponica, xv. 8, it is stated that bees, fields, houses, etc. can be secured against witchcraft by burying under the threshold various articles, including salt, cummin, squills, στέμμα έργον λευκού ή φοινικού, agnus castus, sacred herbs, brimstone, etc. Funeral stelar on Attic lebuthor are often decorated with red fillets, perhaps for the same reason. Pollux, iv. 119 f. says that on the comic stage the conventional garb for the young was φοινικίς ή μελαμπόρφυρον ιμάτιου, while certain classes of society were 'a band of purple' (rambion in more while gour) round the head. He tells us, ib. 116, that warriors or hunters on the stage were round their hands a knot or coil of the same colour (συστρεμμάτιον το πορφυρούν ή φοινικούν). In Theore, ii, 2, Simaitha, preparing her magic rites, bids Thestylis wreathe the jar with searlet wool. The Palatine Anthology (v. 204) describes an TuyE similarly bound mophupene duvou μαλακή τριγί Clement of Alexandria (strom. vii. 4, p. 843, Pott.) mentions among objects of superstitious veneration fpia scoppá in company with such prophylactics as salt, squills, brimstone and the like. The Greek magical papyri lay the same stress on the colour red. In pap, Parisimus, 2702 ff, a charm written on silver leaf is to be worn round the neck by means of φοινικίνη δίρματι. In pap. P. 69 ff. a wreath is to be entwined with a fillet of white wool εκ διαστημάτων δεδεμένων φοινικώ έρίω. In pap. A. 400 ff. a charm is to be fastened appart powiking. The red cloaks of Homeric heroes (Il. x. 133, Od. xiv. 500) and Spartan hoplites, the ruddle-cord of the Athenian assembly, the 'toga praetexta' of the Romans and their imperial purple, are all susceptible of the same explanation. Red or purple is in every case a prophylactic colour. Indeed it is possible that the reason in the background of all these customs is that red, being the colour of blood. was accepted as a conventional substitute for blood and was therefore

taboo: see F. B. Jevons, Introd Hist. Rel. pp. 67, 138, 140, 349.

On Wednesday, March 9th, 1898, the Antiquarian, Hellenic, and Philological Societies held a joint meeting, at which Monsieur P. F. Perdrizet delivered a lecture in French on the excavations at Delphi. The lecture was illustrated by a series of photographic slides; and many minor points, such as Monsieur Perdrizet's identification of Dionysus Bassareus on the Cnidian frieze, were followed with Interest and appreciation.

"THE JOURNAL OF HELLENIC STUDIES" ACCOUNT FOR THE YEAR ENDING 11st MAY, 1895.

207 1230 202 1230 203	582 10. 5
56 17 2 By Vol. XVII. Furts I. and II. Printing (including 515 13 3 Plate: District	
To Sales of Journal, July 1, 1896, to June 30, 1897 66 17 2 Balance, to Cash Account Balance, to Cash Account 515 13 3	\$ 01.8839

CASH ACCOUNT.

20 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 1 2 4 4 5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	21.5 21.5 21.5 21.5 21.5 21.5 21.5 21.5	ti di shiriy
7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	0	00	Print.
To Bahance at 31st May, 1897 - 1808 613 4 6 359 19 7 Iby Rent, one year to Dec. 1897 . Members Scheciptions, 1897 - 1808 613 4 6 359 19 7 . Salaries, American at 1 the state of the state	1. Library Account—Books and Furniture 2. Lantern Sides Account 2. Stationry, Peruge and Southy Petiting	Christian School at Athens 100 0 0 W. R. Pano Account Account Adapte of Journal Account	
359 19 7	0 51 20	2 0 0 2 2 2 0 0 2 3 4 5 10 0 0 0 2 3 4 5 10 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Zanis 17 11 Zani 6 2
6 6 4 613 4 6 63 13 0	10 1 8 1 6 1 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	9	To Ballence at Bankers, 313t May, 1898.
	Dividends on New South Water 34 per comt. Stock—Oct. 1, 1897	A.	= [

We have examined this account, computed it with the weachers and bankers' book, and find it correct. [ARTHINE JOHN BUTLER, DOUGLAS W. FRESHFILLD, Rev. Principles, 25th June, 1868. 25th June, 1898. A comparison with the receipts and expenditure of the last ten years is furnished by the following tables:—

ANALYSIS OF ANNUAL RECEIPTS FOR THE YEARS ENDING :-

	n May, 1854	n May,	i blay, 1891.	ti May,	er May, 1893.	30 May,	31 May, 1592.	ie May.	9: May. 1897.	n May,
Subscriptions	4- 545	532	4 585	£ 554	£. 364	£ 671	£ 678	645	£ 617	613
Arreary	3.7	26	39	16	.13	:44	14	9	4	13
Life Compositions	47	47	79	120	95	.79	50	63	15	.00
Libraries and Back Vels	122	96	118	233	161	186	122	117	126	118
Dividends	33	34	35	37	39.	43	4.3	43	43	43
Special Receipts	144	477.	600	2797	-30	10.	-1	just .		116
Laurentian MS.	32	11.	37	44	= 177	***	6840	100	144	000
Mr. D. G. Hogarth (Alex- andria Grant Refunded)	10	ura.	141	719	311	5.45	10.	30	0.02	1) dans
Loan of Lamern Slides	O.	15 hom	100	4	4	4	12	7	. 5	Tien
Cliches		ya.	144	-	Elm	- 01	like.		3	- want
Royalty on Sales of Photo-	1980	i in	. 5	5	2	.2	E)	1	-	*
Loun from Bankers	100	100	the	-1000	100	Upper 1	(20)	+44	443	142
Donations-J. Vansittart, Esq.	He	100	114	wite:	500	440	EL.	780	-61	100
E, H. Egerton, Esq	18.600	60.5	115	W-	111	5	140	are.	(in)	ion
Library, Mrs. Cohen	111	100.61	111	E	111	Teci	200	444	686	15
W. Arkwright, Esq.	_	man.	-	11.6	111	_isi	400	110	-3	644
	910	846	898	976	878	1,034	910	915	816	789
Balance from preceding year	253	42	15X	=55	239	259	214	169	340	360
	1,165	888	1,049	1,231	1,117	1,293	1,124	1,084	1,156	1,149

ANALYSIS OF ANNUAL EXPENDITURE FOR THE YEARS ENDING:-

	21 May,	st May.	31 May. 1851	31 May. 1892.	pe May, 1893	e8ga	ga May, abps.	n May, 1795	ge May, 1895-	ge May. 1898.
Rent	30	Z 30	4 30	35	50	73	% 80	80	80	80
Insurance	5	13	1.1	11	II.	11	15	15	15	15
Salaries	39	39	39	44	49	49	49	47	32	50
Library	15.	3	16	8	41	75	96	39	94	93
Lantern Slides Account	9.00	-919	1011	140	Alex	100	leas		-010	24
Stationery, Printing, and Postage	61	55	62	41	71	49	49	46	29	45
Cost of Journal (less sales)	*873	397	445	610	532	475	441	394	345	516
Grants	100	100	250	125	100	185	225	100	180	125
Investments	483	Contr.	46	100	034	158	664.	has	olet	- 111
EgyptExplorationFund-t, too copies of Mr. Hogarih's Report	-5-	1110		-	-91	*1-0	1000	23	L	
Loan Repairl	+115	101	1	- Mari	1500	110	12 N	FWE	100	1300
Photo Enlargements, Albums, Lantern Shdea, &c.	910		- 01	18	4	4		***	(new)	
Sandries	-r16	264 6.1	214	40.	7	696	777	***	248	277
Balance	I/123 42	737 151	794 255	992	858 259	1,079	955 169	744 340	796 360	945
	1,165	888	1,049	1,231	1,117	1;293	1,124	1,084	1,156	1,14

^{*} Includes cost of reprinting of Vols. IV. and V. (= £437) less the amount received from sales.

LIST OF BOOKS AND PAMPHLETS

ADDED TO THE

LIBRARY OF THE SQUIETY FOR THE PROMOTION OF HELLENIC STUDIES

JAN. 1-DEC. 1, 1898:

Aelianne, D	o natura anima	Hum. I	Ed R. Ho	reber.	2 vols.	8va.
	Leips. 1864, 6.					
Asschines.	Redo gegen Tim	archoe.	Griechisel	i. u. De	ntsch.	Trans.
by G. E.	Bansolar. Svo.	Leipsi	c. 1855.			
Aeschylus.	Agamemnon	Ed. T.	W. Peile.	Ind	edition.	Bro.
London.						
Ammianus.	Res Cestae.	Ed. V.	Gardthau	15611.	2 vols.	880.
	Leips. 1873, 5.					
	laber memoralis.		Woeflen.	Svo.	Teubn.,	Loips.
1879.						
Andocides.	Orationes, Ed.	F. Blass	8yo. 4	'oubn.,	Leips.	1871.
Anthologia C	Iraeca. 3 vols.	8vo. 7	feubna Le	ps. 18	84-90.	
Antiphon	Orationes et Fr	agmonta	Ed. F.	Blass.	Svo. "	Tenba,
Leips		2				
Apollonius I	thedius. Argon	autica.	Ed. R N	terkel.	Byo.	Tenha.,
Leips.						
	. Comoedine.	Ed. H. A	. Holden	STD.	London	1848.
4	Acharnenses	Ed. T.	Mitchell.	8vo.	London.	1835.
10	The Clouds	11	111	111	7.8.1	1838.
	The Frogs			100	86	1839.
n i	The Knights		33	- 66	93	1838.
	The Wasne	- 01	17	10.1	- 66	1835.
Athenaeu-	Deipnosophistas	Ed. 6	. Kalbel.	3-vols.	Bvo.	Teubu.,
	1887-90.	-				
	Poems, Ed.	F. G.	Kenyon.	8vo. 3	London.	1897.
(Presen			1000			

Bacehylides. The Posms of B. Facsimile of Papyrus DCCXXXIII. in the British Museum. Folio. London. 1897. (Presented.)

Benndorf (O.). Wiener Vorlegehlätter. 3 vols Folio. Vienna. 1889-91.

Bower MS. See Hoernle (A. F. R.).

British Museum. Terracotta Sarcopinagi, Greek and Etruscan, in the B. M., by A. S. Murray. Folio. London. 1898. (Presented.)

Brunck (R. F. P.). Analecta veterum poetarum Graecorum. 3 vols. 8vo. Strasburg. 1776.

Brunn (H.). Griechische Kunstgeschichte. Vol. II. Die archaische Kunst. 8vo. Munich. 1897.

Caesar. C. Julii Caesaris Commentarii de Bello Gallico et civili. Ed. F. Ondendorp. 8vo. Leipsic. 1805.

Catullus, Carmina Ed. L. Müller. Svo. Toubu., Loipe. 1880.

Couat (A.). La Poésie Alexandrine sous les trois premiers Ptolémées. 8vo. Paris. 1882.

Daremberg (Ch.) and E. Saglio. Dictionnaire des Antiquités grecques et romaines. No. 25 (- Io). 4to. Paris. 1898.

Dareste (R.), B. Hanssoullier and Th. Reinach. Recueil des Inscriptions juridiques grecques. 2 Serie, I. 8vo. Paris. 1898.

Demosthenes, Orationes, Ed. G. Dindorf, 3 vols. 3rd edition. 8vo. Teubn., Leips. 1874-9.

Diodorus Siculus, Bibliotheca Historica, Ed. L. Dindorf, 5 vols. 8vo. Toubu, Leips. 1866-8.

Dionysius (Hal.). Antiquitatum Romanarum quae supersunt. Ed. A. Kiessling. 2 vols. Svo. Leipsic. 1860, 70.

Durm (J.). Die Bankunst der Griechen. [Handbuch der Architektur, 2^{te} Theil, vol. I.]. 2nd edition. Svo. Darmstadt. 92.

Busebius. Opera. Ed. G. Dindorf. 4 vols 8vo. Teubu., Leips. 1867-71.

Eutropius. Breviarium Historiae Romanae. Ed. H. R. Distach, 2nd edition. 8vo. Teubn., Leips. 1883.

Flores. Epitamas de Tito Livio Bellorum omnium annorum DCC libri duo. Ed. C. Halm. 8vo. Teubn., Leips. 1879.

Fongères (G.). Mantinès et l'Arcadie orientale. 8vo. Paris 1898. (Presented.)

Furtwängler (A.) and H. I. Urlichs Denkmiller griechischer u. römischer Skulptur, Handausgabe Svo. Munich. 1898. (Presented.)

Gellius (A.). Noctes Attions. Ed. M. Hertz Svo. Teubu., Leips. 1877.

Gennadius (J.). Dr. Johnson as a Greciau (read before the Johnson Club). 8vc. pamphlet. 1898. (Presented.)

Grean Collection. Catalogue des Bronzes Antiques et des objets d'Art du Moyen Age et de la Renaissance. 410. Paris. 1885.

Grey (H.). Classics for the Million. 8vo. London. 1898. (Presented.)

Haussoullier (B.). See Dareste.

Hefele (C. J.). Patrum Apostelicorum Opera. 3rd edition. 8vo Tübingen. 1847.

Heliodorus. Heliodori Aethiopicorum libri decem. Ed. I. Bekker. Svo. Teulin, Leips. 1855.

Hephaestion. Hephaestionis Alexandrini Euchiridion. Ed. T. Gaisford. New edition. Svo. Leipnic. 1832.

Hermann (K. F.). Lehrbuch der griechischen Antiquitäten. Vol. IV., 1. Svo. Heidelberg, 1882.

4th edition. 3 vols. 8vo. Berlin. Herodotus, Ed. H. Stein. 1874-7.

Herodotus. Herodoti Halicarpasser Historiarum libri IX. Ed. T. Gaisford, 3rd edition. 3 vols. 8vo. Oxford. 1840.

Herodotus. Herodoteum Lexicon. See Schweighauser.

Historiae Augustae Scriptores VI. Edd. I. Casaubon, C. Salmasiuand J. Gruter. 2 vols. Svo. Liège, 1671. Hoernle (A. F. R.). Bower MS. Parts III.-VII. Folio. Calcutta.

1897. (Presented.)

Hogarth (D. G.). A wandering Scholar in the Levant, 2nd edition. 8vo. London 1506,

Holland (H.). Travels in the Ionian Isles, Albania, Thessaly, Macedonia, etc., during the years 1812 and 1813. 4to. London 1815.

Holm (A.). History of Greece translated from the Gorman. Vols. III. and IV. Svo. London, 1896, 8. (Presented.)

Homer, Carmina, Ed. F. H. Bothe, 3 vols. Svo. Leips, 1832-4. Hughes (T. S.). Travels in Greece and Albania. 2nd edition. 2 vols. Svo. London, 1830.

Isaous, Orationes, Ed. C. Scheibe, 8vo. Tenbn., Leips. 1860. Isocrates. Orationes. Translated by J. H. Freese. Vol. I. 8vo. London. 1894.

Jebb (R. C.). Homer. An Introduction to the Iliad and the Odyssey. 2nd edition. 8vo. Glasgow. 1887.

Justinus. Trogi Pompei Historiarum Philippicarum epitoma. Ed. J. Jeep. Svo. Teubn., Leips. 1859.

Juvenalis Satirae. Edd. Ruport and Koenig. Svo. London 1835. Kaibel (G.). Epigrammata Grasca ez lapidibus conlecta. 8vo. Berlin, 1878,

Klein (W.). Die griechischen Vasen mit Lieblingsinsahriften. 2nd edition. 8vo. Leipsie 1898.

Lenormant (Ch.) and J. de Witte. Elite de monuments ceramographiques. 4 vols. 4to. Paris. 1844-61.

Lewis (C. T.) and C. Short. Latin Dictionary founded on Andrews' edition of Freund's Latin Dictionary (revised). Imp. 8vo. Oxford. 1896.

Livius. Historiae Romanorum Ed. J. N. Madvig. 5 vols. 8vo. Copenhagen, 1861.

Loewy (E.). Inschriften Griechischer Bildhauer. 4tc. Leipsic. 1885.

K

Lucianus, L. Samosatonsis Opera. Ed. C. Jacobitz. 3 vols. Bvo. Tenbn., Leips. 1876-8.

Lucretius. De rerum natura libri sex. Ed. J. Bernnys. 8vo. Leipsic. 1852.

Lysias. Orationes ad codicem Palatinum nune denuo collatum. Ed. C. Scheibe. 2nd edition. Svo. Loipsic. 1876.

Macrobius: Ed. F. Eyssenhardt, Svo. Toubu., Leips. 1868.

Malmify (J. P.). History of Greek Classical Liberature. Vol. I. 8vo. London. 1880.

Martianus Capella, Ed. F. Eyssenhardt, svo. Toubn., Loips, 1866.

Meineke (A.). Fragmenta Comicorum Graecorum. Part I. Smaller edition. 8vo. Berlin. 1847.

Murray (A. S.). Greek Bronzes. [Portfolio, No. 36,] Syo. London, 1898.

Murray (A. S.) Terracotta Sarcophagi. See British Musoum.

Mythographi Gracci III, 1. See Psendo-Eratosthenes.

Nonus. Nonni Panopolitani Dionysiacorum libri XLVIII. Ed. A. Koechly. 2 vols. 8vo. Toubu., Leips. 1857, 8.

Omont (H.). Athènes au XVII^a. Siècle. Dessina des Sculptures du Parthonon, attribués à J. Carrey. Folio. Paris. 1898.

Ovidins. Fasti, Ed. T. Keightley, 8vo, London, 1839.

Pape (W.). Wörterhuch der griechischen Eigennamen. 3rd edition. Revised by G. E. Benseler. 2 vols. 8vo. Brunswick. 1884.

Pashley (R.). Travels in Crate. 2 vols. 8vo. London. 1837.

Patroni (G.). In Ceramica Antica nell' Italia Meridionale. [Attidell' Accad. , , , , di Napoli XIX, II.] 4to. Naples. 1897. (Presented.)

Patroni (G.). Un Dipinto Vascolaro della Racotta Santangelo nell' Museo Nazionale di Napoli. [Attl dell' Acad. . . , di Napoli XVII. II, No. 5.] 4to. Naples. 1894. (Presented.)

Patroni (G.). La Fibula nella Necropoli Siracusana del Fusco. [Bull. di paletnol. Ital. XXII. 1-3, 1896.] Svo. Parma. 1896. (Presented.)

Patroni (G.). La Scultura Greca Azentea e le statue dei Tirannicidi.
[Atti dell' Acad. . . . di Napoli XIX. II, No. 2.] 4to. Naplea.
1895. (Presented.)

Pauly, Real-Encyclopiidio der classischen Altertumswissenschaft. Ed G Wissowa. III. 1 (5^{to} Halfband), Royal Svo. Stuttgart. 1897.

Pausanias. Descriptio Gracciae. Ed. J. H. C. Schubart. 2 vols. 8vo. Teubn., Leips. 1875, 81.

Perrot (G.) and Ch. Chipiez. Histoire de l'Art, VII. La Gréce de l'Epopée. La Gréce Archaique (Le Temple). Ato. Paris, 1898.

Perrot (G.) and R. de Lasteyrie. Fondation Piot. Monuments et Mémoires publiés par l'Académie des Inscr. et Belles Lettres. IV. 2. 4to. Paris, 1898. Persius, Auli P. Flacel Satirarum liber. Ed. O. Jahn. 8vo. Leipsic. 1843.

Persius, Auli P. Satirac. Ed. Rupert and Koonig. 8vo. London. 1835.

Pindar, Carmina cum dependitorum fragmentis selectis. Ed. W. Christ. 2nd edition. Svo. Toubn., Leips. 1896.

Pindar. Carmina. Ed. W. G. Cookesloy. 2 vols. 4to. Eton. 1851.
Photo. Politice libri L.-X. Ed. G. Stallbaum. 2nd edition. 2 vols.
[Bibliotheca Gracca. Edd. F. Jacobs and V. G. F. Rost, XIII. 1,
2.] 8vo. Gotha and Erfurt. 1859.

Plantus, Comoediae, Ed. C. H. Weise. 2nd edition, 2 vols. 8vo. Edinburgh, Leipsic, 1847, S.

Plinius, C. Plini Secundi Naturalis Historiae libri XXXVIII. Ed. L. Janus. 2nd edition. 6 vols. 8vo. Tenbu., Leips. 1865-80.

Pintarchus, Vitae Parallelae, Ed. C. Sintenis, 5 vols. 8vo. Tenho., Leips. 1859-81.

Polybins. Historiae. Ed. T. Buttner-Wobst and L. Dindorf. 4 vols. 8vo. Teubn., Leips. 1866-82.

Porcher (E. A.). See Smith (R. M.).

Pottier (E.), La Peinture Industrielle chez les Grecs. 8vo. Paris. 1808.

Propertius, Carmina Ed. L. Miller. Svo. Teubn., Leips. 1880.

Pseudo-Eratosthenes. Catasterismi. Ed. A. Olivieri. Svo. Teubn.,

Leips. 1897.

Pullan (R. P.). See Texier (C.). Ruins of Asia Minor.

Reinach (S.). Réportoire de la Statuaire Grecque et Romaine, II. 1, 2. Sept mille statues antiques. Svo. Paris. 1898.

Reinach (Th.). Recueil des Inscriptions Ses Dareste (R.).

Rich (A.). Dictionary of Greek and Roman Antiquities. 4th edition. 8vo. London, 1874.

Robert (C.). Die Knochelspielerinnen des Alexandros [21th Hallisches Winckelmannsprogramm.] 4to. Halle */n. 1897. (Presented.)

Roscher (W. H.). Ausführliches Lexikon des Griechischen u. Römischen Mythologie. Parts 87, 38 (—Nike). 8vo. Leipsic 1898.

Sandwich (John, Earl of). A Voyage performed by the late Earl of S. round the Mediterraneau, written by himself, with memoirs... by John Cooke, M.A. 4to. London. 1799.

Schoemann (G. F.). A Dissertation on the assemblies of the Athenians, translated from the Latin of G. F. S. 8vo. Cambridge, 1838.

Schweighneuser (J.). Lexicon Herodoteum. Svo. Oxford. 1840.
Sences. Opera quae supersimt. Ed. F. Hause. 3 vols. 8vo.
Teubn., Leips. 1877-81.

Seneca. Oratorum et Bhetorum Sententiae, divisiones, colores. Ed. A. Kiessling. 8vo. Tenbr., Leips. 1872.

Seneca, Tragoedine. Ed. R. Peiper and G. Richter. Svo. Tenbr., Leips. 1867. Short (C.). Latin Dictionary. See Lewis (C. T.).

Smith (R. M.) and E. A. Percher. History of the recent discoveries at Cyrene made during an expedition to the Cyreneica in 1860-1.

Folio. London. 1864.

Sophocles. Tragocdiae. Ed. E. Wunder. 2nd edition. 2 vols. 8vo. Gotha and Erfurt. 1839, 1843.

Sophoeles, Ed. F. W. Schneidawin. 2nd edition. 8vo. Leipsic. 1853.

Teuffel (W. S.). History of Roman Literature, translated by W. Wagner. 2 vols. 8vo. London. 1873.

Texier (C.) and R. P. Pullan. The Principal Ruins of Asia Minor. Folio. London. 1865.

Thrakike Epsteris. 8vo. Athens. 1897. (Presented.)

Thucydides, Ed. J. Classen. 2nd edition. 4 vols. Svo. Berlin. 1873-7.

Thueydides. De Bello Peloponnesiaco libri octo. Ed. F. Goeller. 2 vols. 8vo. London. 1835.

Thueydides. History of the Peleponnesian War. Ed. T. Arnold. 2nd edition. 3 vols. 8vo. Oxford. 1840-2.

Tibullus. Ed. L. Müller. 8vo. Tenbu., Leips. 1880.

Urlichs (H. L.). See Furtwängler (A.). Denkmäler, &c.

Virgilius, Opera, Ed. C. G. Heyne, 8vo. London, 1834.

Westermann (A.). Mythographi. Scriptores Poeticae Historiae

Graeci, Svo. Branswick, 1843.
Wilamowitz-Moellendorf (U. v.). Bakchylides. Svo. Pamphlet
Berlin, 1898.

Winnefeld (H.). Karlsruhe, Grossh. Vereinigte Sammlangen. Beschreibung der Vasensammlung. 8vo. Karlsruhe. 1887.

Xenophon. Ed. L. Dindorf. Historia Graeca. 2nd edition.

" Scripta Minora. 2nd "
Institutio Cyri. 3rd "
Commentarii. 2nd "
8vo. Leipsic. 1850.

A LIST OF PERIODICAL PUBLICATIONS IN THE SOCIETY'S LIBRARY, DEC. 1, 1898.

American Journal of Archaeology. I—XI. 2nd Series. I. (1897.) American Journal of Philology. XIV.—XIX. 2. (1898.) Ameleta Bollandiana. XVII. 1—3. (1898.)

Annali dell' Instituto Archeologico, I.II.—I.VII. (1885.) End. [I.—I.VI. (1829—84) on deposit.]

Annuaire de l'Association des Études Grecques. XV.—XXI. (1887.) End.

Annual of the British School at Athens. 1894-5, 1895-6.

Antike Denkumeler des Archaeologischen Instituts. I .- II. 3.

Archaeological Institute of America. Reports I.—XVII. (1880—96.)

Papers of Institute; American Series. I.—V.; Classical Series.

L; Papers of American School at Athens. I .- V.

Archaeologische Zeitung. XXXVIII.—XLIII. (1885.) End. [I.— XXXVII. (1843—79) on deposit.]

Athenaion, L.-X. (1881.) End.

Berliner Philologische Wochenschrift. XI.-XVIII. (1898.)

Berliner Studien. L.-XVI. New Series. L.-III. 1. (1898.)

Bulletin de Correspondance Hellénique, I.-XXI. (1897.)

Bullettino della Commissione Archeologica Comunale. XXV.—XXVI. 2. (1898.) [XIV.—XVII. (1886—1889) on deposit.]

Bullettino dell' Instituto di Corrispondenza Archeologica, 1880-1885. End. [1829-1884 on deposit.]

Bursian's Jahresbericht über die Fortschritte d. classischen Altertumswissenschaft, Jahrg. L.—XXVI. 5, (1898.)

Byzantinische Zeitschrift, I.-VII. (1898.)

Cambridge Philological Society, Transactions I.—III. (1893); Proceedings L.—XLIV. (1897.)

Classical Review, I .- XII, 8, (1898.)

Commission Impériale Archéologique.

Compte Rendu. 1878—9 and 1882—8; Atlas 1878—1888. [Text and Atlas (1859—1881) on deposit.] Russian continuation viz.: "Materials," Nos. 4—20 (1890—96) and "Reports" for 1889—1894 (1892—1896). For General Index, 1859—1881, see Reimach's Bibl. des Monuments, III., p. 145.

Deltion of the Historical and Ethnographical Society of Greece, I.—II., V. 17, 18. (1896.)

Egypt Exploration Fund. Reports. 1895-1898.

Ephemeris Archaiologike. Third Series. 1884-1898, 2.

Göteborgs Högskolas Arsskrift, 1895, 1896, 1898.

Hellenikos Philologikos Syllogos (of Canstantinople). IV.—XVI. (1871—1885.) XX.—XXV. (1891—1895.)

Hermas XXVII.—XXXIII. 3. (1828.)

Institute (Royal) of British Architects. Proceedings, N.S. II.—IX. (V. Imperf.) (1886—1893). Transactions, 1880—1892. Journal, 3rd Series. I.—V. (1898.)

Jahrbunh d. Kais. Deutsch. Arch. Inst. I.—XIII. 3. (1898.)

Jahreshefte des Oesterreich. Arch. Inst. in Wien. I. 1, 2. (1898.)

Journal International d'Arch Numismatique. L. 1, 2. (1898.)

Journal of Classical and Sacred Philology. 1854-1857.

Journal of Hellenic Studies. L-XVIII. 1. (1898.) (Two cupies.)

Journal of Philology. J .- XXV, (1897.)

Journal of the Royal Asiatic Society. XII.-XIV. (1883.)

Melanges d'Archéologie et d'Histoire. L-XVIII. (1898.)

Mittheilungen d. Kais. Deutsch. Arch. Instituts. Athenische Abth. L-XXIII. 3. (1898.)

Mittheilungen d. Kais. Deutsch. Arch. Instituts. Römische Abth. I.—XIII. 3. (1898.)

Mittheilungen (Arch. Epigr.) aus Oesterreich-Ungarn. XVII.—XX. (1897.) End. Continued as Jahreshefte, etc. Mnemosyne. I,—XXVI. (1898.)

Monumenti Inediti dell' Instituto Archeologico. Xl. pl. 13-XII. (1885.) End. [I.—XI. on deposit.]

Monuments Grees, I.-II. (1897.) End.

Neue Philologische Rundschau. XIL-XVIII. (1898.)

Numismatic Chronicle. 1st Series. 1836 and 1848-54. Series. Vols. L-XX. Third Series. I.-XVIII. (1898.)

Parnassos (Philologikos Syllogos). Vols, I.-V., VI.-X. (Imperi.), and XL, XII. (1888). Epeteria L.-II. (1898.)

Philistor. I.—IV. (1863.) Philologus, Neue Folge. 47—57. 3. (1898.)

Praktika of the Athenian Archaeological Society. 1873-1808.

Revue Archéologique 2nd Series. I .- XXXIII., XLI., XLIII .-XLIV. (also XXXIV., XLII, imperf.). 3rd Series. I.—XXXIII. 1. (1898.)

Revue des Études Grecques. L-XL (1898.)

Revue de Philologie, XX.-XXII 3. (1898.)

Rheinisches Museum für Philologie. XLVII,-LIII. (1898.)

Wochenschrift für Klassische Philologie. XI.-XV. (1898.)

Periodicals 'on deposit' can only be consulted at the Library.



DEATH AND THE HORSE.

(klutómmlog, klutóg, élik etc.)

DID the Greeks, and in particular did the Homeric poets, associate Death with the Horse? The great impertance, in the archaeology of art and religion, of all associations connected with the grave, will perhaps give interest to a somewhat full discussion of this question, or rather of the single piece of evidence, upon which, so far as concerns Homer, the question seems to turn. Did the poets describe Hades, lord of Death, as 'lord of the goodly steeds'? Is this what they meant by κλυτόπωλος? It is the purpose of this paper to show that they did not, that this interpretation is involved in difficulties and impossibilities three-fold and four-fold, has for it neither reason nor

authority, and must, with all that depends upon it, be given up.

The first and perhaps sufficient objection is this. Before the epithet κλυτόπωλος could be referred to the horse, πώλος, it is plain, must have signified a horse. Now it is quite certain, though apparently not recognized, that to the composers of the Iliad and Odyssey no such word as πώλος horse was known. They used, it is true, the word to which, by a stretch of meaning and for convenience, that sense was given by their imitators and successors; but they knew it only and strictly in what seems to have been its primitive and etymological sense, a foul, a young horse under the mother. 'Chestnut horses (Twwove) hundred and fifty, all mares and many with their foals (πῶλοι) at their feet says Nestor in A 681; and see also T 222, 225. Against woxog horse the evidence is overwhelming. If these poets had known at all a word so irresistibly convenient as a synonym for immor beginning with a consonant, they must have used it, in the extant poems, not once but scores of times. This estimate is no mere conjecture; it is proved by experiment. The composers of the Hymns, imitators of 'Homer', but differing much in language and feeling, did, like the Attic poets, know montos (young horse) in a sense nearly equivalent to Towes, and accordingly with them horses are wokon twice, (those of Ares in 8, 7, and those of Selené in 30, 9), that is to say about once for ten times that the animal is mentioned. Now at this rate the Iliad alone should have given us wonder horse about forty times or more; 1 yet it

Ebeling's Lexicon s.z. My references and statistics are largely taken from this book,

Fers: le found there about 400 times; see though I may mention perhaps that I have read both Illad and Odyssey through with this subject in mind.

does not once. Nor does the Odyssey. We read, it is true, in ψ 246 how Athena detained at Oceanus the golden-through Morn, and would not let her yoke the swift-foot steeds that bring light to men, Lampos and Phaethon, the wôλοι that draw Morn.

'Ηω δ' αὐτε

ρύσατ' ἐπ' 'Ωκεάνφ χρυσόθρουου, οὐδ' ἔα Ιππους ζεύγνυσθ' ἀκύποδας, φάος ἀνθρώποισι φέροντας, [Δάμπον και Φαέθουθ', οἵτ' Ἡῶ πῶλοι ἄγουσι].

If we suppose this last verse to be of the true 'Homeric' age, we must translate it according to the use of that age, and must take the poet to mean, what is perhaps not inconceivable or unnatural, that the car of the young Morning is drawn by a team of foals. But it is an obvious and more probable supposition, that the verse is a mere note, satisfying that passion for names, to which poet-scholars were liable but backs were not, and that the author of the verse, using $\pi \hat{\omega} \lambda o_i$ as synonymous with $\tilde{\iota}_{\pi \pi o_i}$, simply betrays thereby his later date. To invent for this single passage a sense of $\pi \hat{\omega} \lambda o_i$, which Hind and Odyssey combine to reject and disprove, is not permissible; and it remains therefore true that by the composers of these poems $\pi \hat{\omega} \lambda o_i$ how was not used, which in the circumstances is equivalent to 'not known'.

If therefore in $\kappa\lambda\nu\nu\delta\pi\omega\lambda_0$, as used in the Riad, $\pi\tilde{\omega}\lambda_0$ s meant horse, it is a case of survival. We should have to assume that $\pi\tilde{\omega}\lambda_0$ s had once borne this meaning, as it did again in later poetry, and that in the compound, as a traditional epithet, this sense held its ground, although the corresponding sense of the simple had suffered in the age of 'Homer' an odd eclipse. Let us see whether the application of the compound admits this supposition.

That application is extremely peculiar. It is restricted not merely to Hades, but to Hades in one single phase and function, as receiver of the warrior's parting soul:—

'And for thee I say that slaughter and black Death shall come about here at my hands; vanquished by my spear thou shalt yield to me my glory and thy life to Hades klytopölos'

εύχος έμοι δώσειν, ψυχήν δ' 'Λίδι κλυτοπώλφ.'

Now when the poets so used κλυτάπωλος, surviving, er hypothesi, from a time when it meant of the goodly steeds, of what sense in it, if any, were they conscious? Or could they use it traditionally, without any question of the sense? Surely not. They may have so used, and probably did, διάκτορος άργειφόντης, as a description of Hermes. But then these words, or rather names, were free, for them, from any connexion of etymology. They do not, on the face of them, signify anything in the Greek of Homer; they are not in appearance formed from any elements to which separately Homer gives a sense. But κλυτόπωλος is. Of one meaning in Homeric language it was manifestly capable; it could mean 'of the famous foods'. How then, unless the elements of the word were

^{*} E 654, and similarly A 445, II 625.

capable of some other meaning, should this meaning be ignored; or how could the compound continue to be used in a connexion where, in its natural meaning, it was plainly absurd? The epithet χρυσηλάκατος, of the golden arrow, was retained, in its traditional connexion with Artemis, by the Homeric poets, although to them, by a restriction in the sense of ηλακάτη, it had come to signify of the golden distaff (δ 122, 131); because the new sense was in this connexion, though less appropriate, at least not impossible. And similar was the history of Ζεὐς τερπικέραυνος, transformed from the hurler of the thunder into the delighter in it. But when πῶλος horse had come to mean foal, and foal only, then 'Λίδης κλυτόπωλος, as an expression significant but now absurd, would naturally die. That it did not die is prima facie proof that it was not connected, and was not supposed to be, with the πῶλος which for Homer meant foal; and that in attributing to this πῶλος, by pure hypothesis, a use earlier than Homer, but for Homer extinct, in the sense of horse, we are on a wrong track.

Now in these circumstances it is instructive, and it should not be surprising, to find that, although to the Greeks of the classic and later times no other word makes was known, as a term in use, except that which primarily meant fool and subsequently also horse, nevertheless among students of Homer the best tradition affirmed that the termination of κλυτόπωλος (Aftige) had an origin and meaning totally different. Aristarchus, according to several witnesses, connected it with πωλεισθαι, to range, haunt, visit. The explanations of the epithet, which the witnesses deduce from this etymology, are certainly incredible, indeed preposterous. But this only goes to prove that the etymology itself, which they could not use, was not invented by them (nor by Aristarchus, if he is responsible for the explanations), but was a genuine inheritance from times when the language of the rhapsodists was not yet dead. And whether this was so or not, the etymology, as an etymology, is possible, correct, and Homeric. The verb wwwleques is Homeric, and to www.cougar the adjectival termination -www.os stands in the same relation as -πολος (in διόπολος, τρίπολος, δικάσπολος, άρφιπολος) to the parallel, cognate, and synonymous πολέσμαι. Before therefore, in order to interpret «λυτόπωλος, we assume a sense of -πωλος which Homer does not warrant, we are bound to try whether, with or without the assistance of Aristarchus, we can interpret it by the sense which he does.

The truth appears to be, that the little group of Homeric adjectives in -πωλος (for κλυτόπωλος is not unique) are all connected not with πώλος fool, and certainly not with πώλος horse, to Homer a row nihili, but with the root πωλ-ronge, which appears in πωλέομαι. The position in Homer of the nominal stem from this root, πωλο-, is exactly parallel to that of πόλο-; that is to say, neither appears in Homer as an independent substantive, though πόλος had elsewhere in Greek a long and illustrious descent; and both appear in Homer as terminations in a group of compound adjectives. The particular use of πωλέομαι, from which the most familiar of these adjectives originally came, is that which, as was indicated (according to the witnesses) by

Aristarchust, survives in the compound emimorlouas, when connected with

nctivity on the battle-field :-

αύταρ ο των άλλων έπεπωλείτο στίχας ανδρών then went he elsewhere ranging the warrior-ranks' (A 265). It refers to that rapid and incessant motion from place to place, which, in the loose, desultory, and undisciplined method of Homeric fighting, made so large a part of the fighter's power and When all depended, as it does in Homer, on catching your man in the instant of isolation or exposure, to be quick of movement, wimble in range was among the first of warlike qualities; and this is the quality which is claimed for the Phrygians (in general), when they are called aioλόπωλοι (I' 185, etc.), and for the Danaoi (in general), and the Myrmidons (in general), when they are called ταχύπωλοι. Even if it were legitimate and Homeric (which, let us repeat once more, it is not), to assume for these adjectives the element maker horse, that assumption would still be excluded by the use of them. The men of Agamemnon and Achilles, as a class or people, could not possibly be known or noted for their swift horses; for with few exceptions they had no horses at all. But as fighters they are noted for their quick range, their nimble movements in the field.

From the same stem probably came εύπωλος, the traditional epithet of Hios, though here a doubt arises, which for raximolog and alohomolog is not entertainable. It is possible to derive evawlos from wwwlos foal, and to connect it with the famous legend of the twelve foals, begotten by Boreas upon the mares of Erichthonios, son of Dardanos (T 220 foll.); and this we may even take to be so far true, as that the epithet, so interpreted, gave a likely But that the legend produced the epithet is not suggestion for the legend. likely, for then it would naturally have linked itself in poetic tradition with Dardania, which was the name of the place where the foals were born, and not with Hios, which (according to the legend itself, T 216) did not then exist, but was built, according to the prevalent account, long after, for Laomedon son of Ros. As a fact the city, which is correly over Dardania, and regularly Iliax; nor is the legend required to account for the phrase "Ιλιος εύπωλος, which meant originally just 'Hios, the pleasant haunt', from πωλο-, πωλέσμαι, as οἰόπολος χώρος 'a solitary haunt', and signified, like en parouevor etc., that the place was 'good to visit' and 'good to frequent', in short, a country agreeable for human habitation. the tradition of ancient scholarship preserved an obscure memory of this, when εὐπωλος (see Ebeling, s.v.) was translated, not incorrectly, by εὐγέως a pleasant land', and the like.

Apart from proper names, such as Εχέπωλος, which may mean anything or nothing, these are, I think, all the words in -πωλος, which Homer supplies,

except κλυτόπωλος itself. This, if it was really known and used by the poet or poets of the Iliad—we shall see presently the reason for the doubt—cannot be separated from αἰολόπωλος and ταχύπωλος. Hades, as κλυτόπωλος, must

¹ See Ebelling e.s. shortrahor — & "Aplorapyon fel rob shorten desiles shorter desidings s. r.h.

be 'Death, the famous ranger (of the battle-field)': and since, in fact, it is always the soul of the warrior slain upon the field, which this Hades receives, the conception is one which we may well accept as, at any rate, a stage in the history of the phrase. Compared with the irrelevant and impossible horses, it is no less superior on the poetic side than on the linguistic. But it

seems that we ought to look yet further.

For firstly, although from aiolómwlos and rayúmwlos it is not hard so to interpret κλυτόπωλος, it was not perhaps equally natural and obvious upon these lines to invent it. Both aloko- and raxv- are terms of motion, Not so khura-, and the coalition is thus less easy. like wwxo- itself. have we a perfectly satisfactory analogy in comolos or clorolos, which, strictly speaking, would justify only the rendering 'Death, famous for his haunt', famous, that is, for the place which he ranges or visits, an idea neither so clear as might be wished, nor so much to the purpose. Secondly, how does it come about, that this 'famous ranger' of the field is never so described when the breadth and rapidity of his range would be illustrated by the circumstances, never in scenes of wide, swift massacre, such as are so often presented, but only at the side of the single fallen man, over whom his enemy stands A 'fixed epithet' may be often misapplied, but it should scarcely 'These objections do nothing to hulp in the 'horses', to which the second applies even more strongly than to the 'range'; indeed it is impossible, as I think, to explain why, if khurónwhos had really referred to horses, it should never be linked by Homer to any of the numerous personages who are with him "famous for horses", and only to Hades, who, so far as appears, was not. But the objections justify a suspicion that we are not yet at the bottom of the matter; and since the capacities of πωλο- seem to be exhausted, it remains to see, whether anything more can be made of alutoan examination which as few Homeric words are more characteristic and important than khoros, will be interesting for its own sake.

In general the Epic use of khuros is simple and well defined.

(1) It is applied, according to the etymology, to persons, places, and the like, which are properly and literally 'heard of', famous, renowned. So Agamemnou, Argos, etc., etc. Even in this class however it appears, upon a more careful inspection, that some selective feeling, not apparent in the etymology, has affected the choice of objects. Not all renowned persons are in fact shured, nor those chiefly, or indeed at all, who are most plainly renowned; females, for example, hardly ever, neither goddesses nor women, not Penelope, not Holen, though more 'famous', one would think, than all the male sex together; of the gods some only, and those repeatedly, but chosen, if 'famo' were the question, with strange caprice,

(2) What the selective principle is, by what association the word was attracted and confined, appears plainly in the things, the objects not capable of personification, to which it belongs. It is said or implied in Lexico that κλυτός renowned is extended in Homer to the general sense of heauteous or goodly; but this statement is so inexact as to be practically false. How ill such large and vague expressions correspond with Homeric feeling about the

word, might appear sufficiently from the fact that Homer, using sauros incessantly, knows no such expression as, for example, where immos. Even the limitation that 'Homer uses it especially of the works of human skill' (Liddell & Scott), though mainly true, is both too wide and too narrow. When the word does not mean simply and literally renowned, it is applied solely to works of art, or rather to works of craft, human or divine, and among works of craft almost exclusively to a small and peculiar class. Arms (and more rarely clothes in general) are everywhere κλυτά, κλυτά τεύχεα, κλυτά είματα, houses are everywhere κλυτά, κλυτά δώματα, and so are, here and there rarely, one or two other things of the same kind, that is to say, products of eraft which directly manifest the power, dignity, and security of the person by whom the craft is possessed or commanded. The feeling which, whether known to the poets by observation or divined by imagination, the word expresses, is the admiration, respect, and worship attaching, in the rudimentary stage of civilisation, to craft and its possessors, to the empire of the metals, and the powers which depend upon it, good smith-work, good masonry, and good carpentry. That is why, with rare and dubious exceptions,1 males only are xautol; why "Hoastos (or 'Audiryoness) and Eurodinasos (not Possidon as such), who would be patrons, one of the smithy and the other, in his subterranean office, of the mine, are conspicuously xAutol; and lastly, why the instances of κλυτά τεύγεα (είματα) and κλυτά δώματα are more numerous than all other κλυτά together. So also the objects, when specified by which persons are entitled to the epithet, are almost always works of craft, and apparently never products of nature: κλυτόεργος, κλυτοτέχνης, κλυτότοξος, ναυσίκλυτος, δουρίkauvos. It is in later poetry, not in Homer, that we find such expressions as κλυτόδενδρος.

It is worth while, since this topic lies deep in the sources of Homeric feeling, to dwell for a moment upon the signal illustration of it offered by four pictures in the Odyssey, all intended to create wonder, and in a certain sense admiration, the dwellings of Calypso, of Circe, of the Phaeacians, and of the Laestrygons. If *λυτός, to Homeric ears, had signified only that sentiment of vague and general admiration, which belongs to the terms which we have to put for it, to beanteous, noble, goodly, glorious and the like, then, among these homes and their occupants, the epithet must belong plainly and conspicuously, though with some difference perhaps in the shade of it, to Calypso and to Circe; it must apply also to the Phaeacians, less strongly perhaps but not much less; while to the Laestrygons it must be altogether refused. The abode of Calypso is painted as the very ideal of natural goodliness, that of Circe as consummate in the luxuries of magic, Phaeacia as exquisite in art; but the land of the Laestrygons, where was no tillage, 'no signs of the labour of men and oxen, only we saw the smoke curling upwards

^{*} Even the very rare examples of a feminine shore's are not beyond suspicion (8 742, 422): *Aury apparently does not occur, a significant fact. In * 422 the unique shore's hackersfor may be an error (suggested by shore's

Erroriyans in the next line; for 8-6s 'Apprairs or the like. In B 742 it is easy to restore a masculate savry, and to account for the corruption of it.

from the land', is as dreary and repulsive as its people. But quite other, for Homer, are their claims to be whore. That is a matter not of beauty, but of craft. Calypeo is not akuros, nor her cave, trees, waters, nor any of the fair things that belong to her. Neither (which might more surprise us) is Circe, no, not though she has a house, a true palace (x 210 and passim), and that full of magnificent wonders. But this, if we have once felt the Homeric feeling about xhuros, is intelligible enough and quite right. Magic may be superior to 'craft', but it is not the same thing. Houses of men, and of gods too, when and because they are the works of cruft, are κλυτά δώματα: but the chambers of a witch, who could create serving-maids out of the fountains and streams (κ 350), need not be the product of craft at all; and accordingly the δώματα Klps775, though mentioned repeatedly and adorned with various epithets (τετυγμένα, καλά, even lepá or mystic), receive not once the familiar and regular Homeric epithet alera; nor does anything which the witch possesses. Phaeacians upon the same principle are of course exerci, and their works κλυτά, κλυτοί, αγάκλυτοι, and περίκλυτοι, themselves, their dress, houses, sanctuaries, etc., etc.; not because they are 'goodly', but because they are in all things artists, and their dwelling-place full of wonderful art. For the Laestrygons and their works, though assuredly not 'goodly', 'beautiful', or attractive in any way, are khurof and khurá no less, and indeed in this quality have a marked pre-eminence. The whole account of them and their country fills but 50 verses, as the Odyssean voyagers scarcely enter it and barely escape. Yet the epithel occurs three times (x 87 λιμένα κλυτόν, 112 κλυτά δώματα, 114 κλυτον 'Αντιφατήα), and is the first note, as it were, of Odysseus' impressions. And the reason, upon Homeric principles, is obvious. It is the 'artificial basin', with its plumb walls and projecting piers of wrought stone, which excites this awe in the beholders, and in Odysseus a salutary fear. It is the 'smooth road' and the 'high buildings' (103, 111), and the formidable weapons (121, 124), which show that Antiphates, king of the Laestrygons, commands to a supreme degree the resources of craft, and therefore, though cannibal, is empliatically kauros. Indeed it seems more than probable that 'Fargate of the Laestrygons' is, or originally was, a picture coloured, if not drawn, from the report of some terrified mariners, who, trading from lands of pasture and agriculture, saw for the first time some place, on the Euxine, may be, where metal-work was practised on a large scale; a sort of black country, where ' the smoke went up from the land', where the trolly, on paths of incredible facility, rolled down from the hills the wood for the furnace (* 162), where shifts so extended the hours of labour that 'night and day near met in one," and whence the visitor, roughly handled by the hard workmen and appalled by the signs of their skill and power, fled away to report that their figures were gigantic, and that they lived, like the Martians of Mr. Wells' romanco, on the flesh of men. Such at all events is in

^{1 - 85.} There is nothing Incomistent with this in the current suggestion, that the 'mosting of night and day 'refers to the brief summer rumour of this placemenon.

nights of the far-north. It would be on the Enxine that a Greek would probably first hear a

fact the Laestrygonian type; and it illustrates excellently the true Homeric sense of κλυτός, grand great, a word for us not really translatable, but approximating in effect to powerful or rather craftful, implying awe rather than mere admiration, and from all such terms as beauteous or goodly to be sharply sundered and distinguished. The gracious life of Acolus, and the hideous life of Antiphates, are passed alike in κλυτά δώματα (κ 60, 112), for this praise belongs to the 'brazen bulwark' and the 'shear stone', though it does not belong to the fairy's paradise nor to the witch's bower.

But against a general background of this shade, ascertained, as we must remember, by scores and scores of examples, three examples stand out in conspicuous disagreement, both with the general rule and with one another. Each offends against Homeric usage, and offends in a different way. They have long been observed for their peculiarity, and all receive special notice,

for instance, from Liddell and Scott

(1) Once, and once only, is broken the rule that natural things, products of nature, cannot be κλυτά. The herds of the Cyclops seem to be such (ε 308): καὶ τότε πῦρ ἀνέκαιε καὶ ἥμελγε κλυτὰ μῆλα.

(2) Once, and strangely, mankind as a whole seems to be a κλυτάν.
When Sleep has done his errand for Hera, he departs ἐπὶ κλυτὰ φῦλ' ἀν-

θρώπων (Ξ 361).

(3) Once, most strangely of all, the dead, universally, seem to be κλυτοί or κλυτά. Odysseus, at the entrance of the lower world, must address his

prayers to κλυτά έθνεα νεκρών (κ 526).

Now we have no right, until the severest scrutiny has shown that no other explanation is open, to assume, in the circumstances, that these three exceptions are genuine. The presumption against them is enormous. Take The epic poets mention hundreds and hundreds of times domestic animals such as Boes, alves, immor, koves, dies, uhla, almolia, etc., etc., and with many admiring epithets. The adjective xxuros, expressing as it does a peculiarly characteristic feeling, is one of their favourite words. If such phruses as κλυτοί βόες, κλυτά μήλα, had really been possible to their ears, what likelihood is there that we should be left with one single example? Why should the flocks of the Cyclops be selected for this praise, and what does it mean? To all the notions normally suggested by «λυτός, the life and manners of the Cyclops, a rude, easeful, sluttish simplicity without culture of any kind, present the extreme opposite. 'Celebrated' they were not, neither they nor anything of theirs, for they were cut off from the world and unknown; and as for their flocks, it does not appear that they differed from flocks in general. They are 'fat', they are 'fleecy'; but how should they exhibit the greatness of power and craft? Expositors have felt this so strongly as even to suggest that khurá here should mean noisy, loud; but that is a counsel of desperation.

To call mankind or the tribes of men κλυτά is so far at least more intelligible, as the quality so predicated is proper to beings who are men or manlike. But it does not belong to the type of man. It is essentially a trait of superiority and dominion. We are told that here it indicates the

superiority of mankind to the brutes. But why should this conception, than which surely none could be more alien from the general tone of the Epos, suddenly force itself upon the poet's mind, when contemplating mankind in a relation essentially unimal and common to the brutes? In relation to Stop, man is but a brute. Why then, because visited by Sleep, should man excite, for this once, the peculiar admiration expressed by exprés, or indeed any admiration at all?

And the dead? The fame, lordliness, power, craft of the dead! They are the silent, strengthless, forgotten, the—all which *\(\lambda\)\top are not. For though Lexico may say that this *\(\lambda\)\top \(\lambda\)\top \(\la

In short, these passages are not explicable, and the presumption is that they are erroneous, a presumption hard indeed to prove, but not incapable of proof. Suppose that the error were the same in all three. Suppose there were a word, which, while scarcely distinguishable from xxprox, fitted each of the three unconnected contexts, and supplied in each a fresh point. Could it be reasonably doubted, that this word, and not exerce, was the word employed? Such a word is extres, couched, bring down, the participial adjective from extto couch, related to κεκλιμένος conched as χύτος, φθίτος, and many other words of this poetic and archaic type, to κεχυμένος, έφθιμένος and the rest. flocks of the Cyclops, though not otherwise miraculous or marvellous, are remarkable in this, that they share at night the home of their master. It is the first thing that we hear of them; 'we saw a cave...near to the sea, and there And about it a high outer court many flocks and herds were used to sleep. was built with stones.....And a man was wont to sleep therein, of monstrous size, who shepherded his flocks alone and afar, and so on (+ 182). The males lay usually in the yard, but the females, 'all that he milked', actually within the cave (ib. 237), the filthiness of which is noted with epic simplicity (ib. 329); and the Cyclops lay among them, κείτ έντοσθ' άντροιο ταννσσάμενος δια μήλων (ib. 298); and these arrangements, it will be remembered, are of the first importance, not only to the colour of the tale, but to the It is therefore natural and to the purpose, that the narrator, his mind full of this picture, should describe how at morning, after Odysseus' first night there, the giant kindled the fire and milked his couched flocks' (wip άνέκαιε και ημέλης κλιτά μήλα, ib. 308), those, that is, who shared his bed, the word, more man-like than beast-like, glancing aptly at his beast-like habits. And it may be observed, that in the evenings, when the beasts have not been 'couched', it is not the ελιτά μήλα who are milked, but 'the ewes and bleating she-goats' (ib. 244, 341).

So again very properly Sleep, when he has finished the special employment for which he was summoned to Olympus by Hera, departs to the couches of mankind ($\delta \chi \epsilon \tau' \ \epsilon \pi l \ \kappa \lambda \iota \tau \dot{\alpha} \ \delta \bar{\nu} \lambda' \ \dot{\alpha} \nu \theta \rho \dot{\omega} \pi w \nu$), returns, that is to say, to his ordinary sphere and business. Where else should his visits be paid but to them that lie down'?

And among those that sleep, couch, and lie down, one class in particular receive the name, in Homeric language as in all others, specially and distinctively, those that have lain down for ever, κλιτὰ ἔθνεα νεκρῶν, the 'tribes of the couchéd dead'.

Now one of two things: either the exact and varied applicability of the word κλιτός to these three occasions, selected upon other grounds and without reference to such applicability, is accidental, or it proves that κλιτός was indeed the word there used. For myself, I hold the first alternative to be fantastically impossible, and therefore embrace the second, taking it as certain that the epic poets had a word κλιτός conched, which was liable (this is obviously true) to be confused with the homophonous κλυτός, and, being archaic in type and replaced in later language by other equivalents, has actually given way to κλυτός and disappeared. It was still alive and known, when these parts of the *Iliad* and *Odyssey* were composed; and we shall do well to consider whether we can trace it later.

As to the phrase from the Iliad, κλυτά φῦλ' ἀνθρώπων, we have some interesting evidence in the 'Pythian' part of the Hymn to Apollo, an imitative composition dating probably from the sixth century, later at any rate than the Epos in general, and bearing many marks of its lateness. Here we read, when Pytho is being recommended to Apollo for the site of his future oracle (270), 'There no fair chariots shall go the round, nor shall there be noise of swift-foot steeds about the fair-built altar; yet to that privacy (ka) ώς) the great peoples of men (ἀνθρώπων κλυτά φύλα) may bring gifts to Ié-paion, and thou with glad heart mayst receive the fair victims of men that dwell around (περικτιόνων ἀνθρώπων).' And again, the monster snake of Pytho 'did many a mischief among the great peoples of men' who came to the place as builders and worshippers (355). 'Whoever met her, became the prey of his fate.' And again, 'All sacrifices,' says Apollo (537) 'that the great peoples of men (περικλυτά φυλ' άνθρώπων) shall bring to me.' It is clear that the ear of this author had been caught, as well is might be, by the expression in this form, with khura; and he treats it exactly as traditional phrases from our own archaic and consecrated literature, sometimes no better founded or more significant, are dealt with by our own poets and preachers. He does his best, that is, to accommodate it with a proper context and meaning. With this purpose, he has changed the sense of φύλ' ανθρώπων, In the Itiad this means of course simply mankind, the human species, as dolar θεών means gods, and φύλα γυναικών the female sex. But in the Hymn conformably to later use, \$\phi \text{NA} a means peoples, nations, the inhabitants of that earth of which Pytho was supposed the centre. And further, since it is for the glory of the god that these tribes are brought into view, the epithet shord great, grand, mighty, has at least so much reflected propriety as is sufficient. for a consecrated formula. It is plain therefore that into this phrase, by the sixth century, κλυτά had already obtruded itself, though whether this was the form in which the phrase first attached itself to the worship of Delphi (or rather Pytho), is not so clear. There is reason to think (see Euripides, Iph. Taur. 1262) that there, as at other sanctuaries of oracular and medicinal deities, prescriptions were once sought by the method of sleeping in the sacred precinct, and communicated by dreams. The appearance in connexion with the gifts, which the ἀνθρώπων φῦλα were to bring, of the name Paion, of the snake, and of the need for quiet, bears a strong suggestion of this Asclepian usage, and of κλιτὰ φῦλ ἀνθρώπων, couched or sleeping men, as the primitive form belonging to it.

However in the sixth century κλυτά φῶλ' ἀνθρώπων somewhere certainly, and perhaps therefore in the Hind, had established itself. But in the Odyssey κλιτά μῆλα not κλυτά (and probably therefore also κλιτά ἔθνεα νεκρῶν) might still be read a century later. For Sophocles read it, and copied it in

this passage of the Ajac (372) :-

ω δύσμορος, θε χερί μέν μεθήκα τοὺς άλάστορας, έν δ' έλίκεσσι βουσί καὶ κλιτοῖς πεσών αἰπολίοις ἐρεμνὸν αἴμὶ ἔδευσα.

Wretch that I am, who suffered the accursed men to slip through my hands, but fell on coiled kine and couched flocks, and made their dark blood flow !" That he has here in mind the Homeric phrase there can be little doubt, but that he read and wrote khurd, khurois, is not easily credible. Even if such expressions as khurd almohia, fine herds', had been familiar to the Epos (where in fact nothing of the sort ever occurs), they would still not have been suitable for transplanting into the style of Sophocles. Largely as the Attic dramatists use the Epic vocabulary, especially of course in lyrics, it is not their habit (unless I am mistaken) to adopt from the Epos the conventional simplicity of its 'fixed epithets'; nor do they use Epic words without regard to the changes and restrictions of meaning, which they had since undergone. As an example of the first point we may note, that this seems to be the sole appearance in Attic drama, perhaps in any poetry not professedly imitating the Epic, of Dassey Boes. And the second point is well illustrated by the Sophoclean use of axerox itself. The use of it in Hemer, as we have seen, is strongly affected and limited by a special association, which, so far as we can trace, has little to do with the etymology. In Sophocles on the other hand the special, archaic feeling and significance is naturally lost; the etymology recovers its hold; and xxoros means simply glorious, famous in the strict sense. Thus in Ocd. Tyr. 172 the fruits of the earth (khuras xdoros) are her glory, and spoils are glorious in Ai. 177. It is the same generally speaking in Pindar, with whom, as might be expected, the word famous is a favourite. It

Pind. Pyth 9, 38 defu saveras xion al space- solar; is hardly explicable by this same of reynour, 4 for her is action unique manager saveras, or indeed by any other. That Apollo

seems then strange that Sophocles should introduce x\u00e4vros here in some vague sense, which, even if it were Homeric, would still not be Sophoclean, inasmuch as it is irrelevant to the context and the thing described. There seems not to be, either in the nature of the beasts which the Greek army had collected for food, or in the situation of Ajax, any reason why he should speak of them with admiration. But there is much reason why he should speak of them as conched or sleeping, for he had massacred them in the night.

an addition to their helplessness and his disgrace.

It will be noticed that Elizerar Bovai is translated above by coiled kine. as if parallel to 'couched flocks'. I believe that it is, or at least that Sophocles so intended; but this supposition is not necessary to a preference for xxcroic over khurois. In Homer chikes Boes, whatever the first word signified or had signified, practically means no more than kine, and Sophocles might have borrowed it bodily in this sense. What was the true, original sense is a question so remotely connected with our subject, that it cannot be treated here otherwise than summerily. It is clear (see for example Ebeling av.) that the Graeco-Roman scholars had no information on the point, and were justly dissatisfied with their guesses. The conditions apparently are (1) that the word should describe some bovine characteristic, universal and obvious; and (2) that it should be deducible from the notion curling, curled, curled up, coiled, for Exit exhibits this sense and no other, with peculiar distinctness, in all Greek from Homer downwards. Indeed it is scarcely too much to say, upon the facts, that to a Greek ear ελιξ cannot have conveyed anything else, and the question really is, Why did the Epos speak of kine as curled or coiled? The bovine horn (one interpretation) is not universally and specifically this, nor, if it were, would it make the beast such; its hair is not more that than that of many other animals, nor so much; and its 'rolling' or rather swinging guit, due mainly to the great bulk of the body in proportion to the supports, is not FALE at all, for the word describes shape, not movement, and the equivocal ' rolling' is an illegitimate bridge. The alleged rolling or turning of the feet might explain ela(modes, but not flaces: nor can I think it likely, whatever may be the scientific truth, that herdsmen and poets would have chosen a mark which, as anyone may prove by watching, is, in the common, slow motions of the creature, to say the least, not conspicuous. It remains however very probable that the two standing epithets eldinoses and duces are in some way connected. Is it possible-I put it only as a suggestion, which in any case, I believe, was favoured by Sophocles-that both were derived from the conchant posture, and pointed to the beast's manner and inveterate habit of lying down? Certainly nothing is more obviously characteristic, both the thing and the way of it. Whether a cow 'tucks up its feet', when it lies, more completely than a sheep or goat, I cannot say, but from the bulk of its body it seems to do so. It will often look, from a little distance, as if it had no

should speak, in this commercion, of his saverar xipa, plorious of firmous hand, has not been proved intelligible; and I believe that Pindar said saverar xipa (from saveras, and equivalent

to extreoras) with a meaning natural and obvious. Accomplies and Euripides scarcely use scores at all, and throw no light upon it.

legs at all. In stepping also, the curl of its lifted fore-leg is, for some reason, very conspicuous. And, as every one knows, it is always 'tucking up' and remaining 'tucked up' for hours together. Now the prefix είλι- points to a curling up as well as to a rolling along, perhaps more naturally. It seems therefore not impossible that είλιποδες originally meant this, and that είλιπος βόες, eviled kine, described the same thing from a slightly different point of view. Probably the epic poets scarcely felt in ελικες any separate significance at all; but we can less easily suppose this of Sophocles and his Athenian audience, who, if they took the view here propounded, had a case for it as students of Homer, and an excellent defence for the combination of ελικες βόες with κλιτὰ αἰπόλια.

Returning now to our theme, we have it, as the result of this long excursion, that the Epic vocabulary contained the word altrog, overlaid in script, as might be expected, by the familiar advros, which indeed may be called a mis-spelling of it. Like hundreds of other words, like most words of its class, it disappeared from the fully developed language, leaving ratios in the grammarians' ετερόκλιτος, εγκλιτικός, in εκκλιτος avoidable (Photius), and perhaps elsewhere. A traditional khurówskos is therefore ambiguous Now we have seen already that between these letters and *Acromwlos. xacros couched was a description proper to sleepers and to the dead, and further that it was applied to sleepers as receiving the visits of the personified Sleep. But further it can be shown that molo- (moleopas) was a proper term for the haunt or visit of such personages as Sleep and Death; for it is applied by Aeschylus to those of their kinsman the Dream. 'Visions of the night, coming ever to my maiden chamber (alel γαρ όψεις έννυχοι πωλεύμεναι ές παρθενώνας τους έμους...) says the Aeschylean Io (P.V. 672), adopting, as the archaic form shows, the language of some more ancient poet, Combining these elements, we have, in Hades κλιτόπωλος (quasi o mapa κλιτούς πωλούμενος), Death who frequenteth the fallen, who visiteth them that lie down, whose haunt is among such. For the form of the compound we may compare άγραυλος (ὁ ἐν άγροις αὐλιζόμενος), ἀνδρόστροφος (ὁ ἐπ' ανδρας στρεφόμενος), διδοφοίτης (ο φοιτών παρά του "Αιδην), δικάσπολος (à πολούμενος είς δίκας), etc. And since, when Death visits a person living. it is for the soul that he comes, it is natural that he should never appear as ελιτόπωλος except in the act of receiving it.

As for κλυτόπωλος, it may have existed in the Epos in the only sense there possible, famous for foals, but there is no proof of it. It might perhaps have been an epithet for Dardania, and it appears as such in one of the Lives of Homer', but with εύπωλου (already discussed) as a variant. But in truth it was not with such things as foals (or horses) that κλυτός was associated by genuinely Homeric minds, and the balance of likelihood is

The only sense, that is, in which the word could have been originally and deliberately invented. The reading "Arts shoreway, with the explanation "Death the ranger", must, I should think, go back, as an alternative, to the

fifth century at least, and may even, as an alternative, be 'Homeric'. But invention does not account wholly for its origin, which requires the co-operation of accident.

against their having known κλυτόπωλος at all. To later poets it was perfectly natural, and in the sense famous for horses. Pindar (fr. 289) applies it in this sense to Poseidon, but whether he got it from his own invention, from Homer, or elsewhere, there is nothing to show.

With the disappearance from Homer of Hades κλυτόπωλος disappears all reason (see Dr. Leaf on E 654) for thinking that by the Greeks, or at any rate by Homeric Greeks, Death and the Horse were associated. That Hades the god, like any other great personage, might use horses upon a suitable occasion, as for example to carry off Persephoné, goes without saying; but he was not thought, so far as appears, to use them much; and at all events between them and his function as Death, the Homeric imagination had not established any connexion. It is doubtful (but that is beyond our scope) whether the Greek imagination ever did.

A. W. VERRALL.

THE DOUBLE CITY OF MEGALOPOLIS.

- § 1. It is less easy to forgive Xenophon for telling us so little about the foundation of Megalopolis than for telling us nothing at all about the foundation of Messene. We would give much to know the details of the building of the city on the slopes of Ithome and the synoccism of Messenia; but Megalopolis, in its double character of a federate city and a federal capital, presented such complicated problems that the silence of those who could have best told us how those problems were solved is more aggravating than many of such silences to the curiosity of posterity. In this paper I propose to deal with one problem which seems never to have been quite realised.
- § 2. The investigation of the site conducted seven years ago by the British school confirmed, within less than half a mile, the statement of Polybins that the circumference of the walls was 50 stadis, and showed that the name Megalopolis was not so much a claim to unusual political importance for the new city as an appropriate expression of its unusual dimensions. The circuit of the walls, as traced by Mr. Loring, measured 46 stadia (or 471, if we add twice the breadth of the river).1 It is evident that the main reason for not selecting one of the older Arcadian towns as the centre of the Arcadian League, when it was founded in R.C. 371-0, was not, as Grote thought, their mutual jealousies, but rather their small size; and, on the other hand, the motive of the relatively large circuit of Megalopolis was its intended position as capital of the League. Strategically such a large circuit was a weak point, not only because there was more wall to defend, but also because, owing to the expense of building and the necessity of building quickly, a long wail could not be built as solidly and well as a short one. A comparison of the remains of the wall of Megalopolis with those of the wall of Mantinea brings

Emacutions at Megalopolis, 1890-1891 (J.H.S. Supp. 1, 1892), p. 114. Measuring the circuit myself on Mr. Loring's plan, I made it out to be nearly 20 stades longer. Having puzzled over this discrepancy, I discovered that he has suchdenially given a wrong scale for the stades (in

which 5 stades correspond to about 750 yards). For comparison it may be mentioned that the circuit of Thebes was 43 stades, that of Corinth (not including Acro-Corinth) 40, that of straggling unwalled Sparts 48.

into relief the second defect; 1 while the difficulty of defence is illustrated in the later history of the town.*

- § 3. We have not sufficient data to enable us to determine the population of Megalopolis. A statement of Diodorus which has been used for this purpose contains an unknown element. In his account of the siege of the city by Polysperchon, the historian states that the number of citizens, slaves, and févor who were able to take part in the defence was 15,000. Now (1) the Eéros are an unknown quantity, and (2) Diodorus does not tell us how old were the oldest, and how young the youngest, of those males, citizens and slaves, who bore arms in this emergency.2 Instead of attempting to deduce a definite figure, it is safer to infer the magnitude of the population relatively to the other cities of Areadia from the inscription in honour of the Athenian Phylarchus. This document has been generally supposed to belong to the third century, and to prove a revival of the Arcadian League. But it really belongs to the first years of the League,3 and may be fixed to the years B.C. 368-363.4 Of the fifty damiorgi of the Federation who are enumerated, ten are Megalopolitans and nine Mantineaus. The presumption is that this proportion roughly corresponds to the proportion of the respective populations of the two cities. Without pressing the inference too far, we may safely say that, if the only purpose of Megalopolis had been to synoecize the Maenalians and Parrhasians, a city one quarter as large again as Mantinea would have been ample for the need, with room to spare. But the area of Megalopolis is nearly four times that of Mantinea, It follows that the superfluous space was required for Federal purposes.
- § 4. When the fact is grasped that the magnitude of Megalopolis was determined by its double character, we are soon led on to perceive some difficulties which must have caused anxious and serious meditation to the Arcadian statesmen who conceived and carried out the plan of its founda-

1 Op. cit. p. 100.

Polybins, 5, 9%. Cp. below \$ 13.

* Dittenberger, Syll, n. 167.

This has been recognised by Dittenberger, ab., p. 961. orgi. The decree must have been prior to the secsation of Mantinea, and posterior to the accession of Hernea and Grehamenos. One of the reasons for assigning the later date was the Attle dialect of the inscription. It seems to me that this objection is answered by the inscriptions of Antioches on the fronts of the seat-backs in the Megalopolitan theatre.

There are only five Tegents, and we may infer that their town had declined in numbers. Beloch (Ion cot.) is wrong in his statement that Megalopolis sent as many delegates 'as Man-

tipra and Tegra together.'

* See below \$ 10.

^{*} Mr. Woodhouse (Recomine, p. 3) uses the figures of Diodorns, and arrives at 'a population of perhaps 65,000' (both freemen and slaves); Beloch (die Besölkerung der grindlichrondschen Hell, p. 122) calculates 60,000 from the same data; both essume that fire = peroson. Of course, in any case, the data and the inference refer to the population of the town along with the district (xdps. Diodor. 18, 70), and not the town alone. I doubt much whether we can implicitly trust the figures of Diodorus.

The limits are fixed by the pressure of Mantinean, Orchomenian, and Heraean dami-

^{*} Epaminondae often gets the credit for Magalopolis—without any svidence, I think, except the flourish of Pausanies, who says he might rightly be called the occist of Megalopolis. The fact that he was the actual occist of Messens,

tion. It was impossible to expect the Parrhasims and Maenalians, who now gave up their old tribal names and took the civic name of Megalopolitans, to undertake the responsibility of defending the whole line of fortification of a town which was far larger than their own needs required. And, on the other hand, the Pan-Arcadian League could not prudently place its buildings and its treasury at the mercy of one of its members. It was manifest that some precautions were necessary for the protection of the League, in case Megalopolis were ever induced to second.

The interests of the League, as well as the interests of the city, demanded that Megalopolis should be defended not only by the Megalopolitan state, but also by the Pan-Arcadian state; and the demand could be not only by the formation of a corps of federal troops. This is what was done. We find a band of 5,000 soldiers paid by the League, ready for service in any emergency, but quite distinct from the federal host, which gathered to march against an enemy when need called, but dispersed when the campaign was over. It is a legitimate inference that the constant duty of the Eparitoi, or a considerable part of that body, was to act as the garrison of Megalopolis. They were always available for emergencies elsewhere; but it was the existence of the Federal capital that in the first place rendered the formation of the Eparitoi indispensable.

But when the necessity of a Pan-Arcadian garrison for the Pan-Arcadian capital had been recognised, there were many contingencies and dangers arising out of the double character of the town, which it was of great moment to foresee and provide against.

§ 5. Megalopolis possessed one feature in common with the elder Mantinea, which King Agesipolis had rased to the ground. The river Ophia flowed through Mantinea, and by damming it up the Spartan king had succeeded in taking the town. When the Mantineans rebuilt the city in the same months which saw the foundation of Megalopolis, they took good care to keep the fatal river outside their walls by digging a second channel for it, so that the stream divided on the east side, and, embracing the city round about, reunited its waters again in the north-west. Then what had been a weakness became a strength. In the same way the Helisson flowed through Megalopolis: but here there was not the same danger, since the ground was hilly, and not a dead flat like the site of Mantinea. Many Greek cities, perhaps most, were built on rivers; but they were generally skirted or girt by them. It is no common thing to find a fortified city divided by a stream.

combined with the support which he gave to the organisation of the Aradian League, might easily ast effect the idea that he was responsible for Megalopolis too. With our present evidence we are bound, in my opinion, to give the credit of the idea to the Atcadian leaders who were active in organizing the federal state. The sending of Passmenes from Thebes to protect H.S.—VOL. XVIII.

the building of the city proves nothing. See Paux 8, 27, 2

Panamias cites Chidne and Mythese; 8, 30, 2. Dires flowing through Thebes is another instance, but the case is semmwhat different. There is no doubt that Dires was originally nutside the walls; the western extension of the city across the stream was comparatively late.

§ 6. It was this river which supplied the founders of the Pan-Arcadian city with a simple means of solving their problem. The meaning of Megalopolis began to dawn on me when I stood en one of the high benches in the theatre and, looking northward, felt driven to ask why the city had crossed the river. It would have been in accordance with the design of other Greek cities if the circuit had been entirely on the southern side of the Helisson, stretching south-eastward over the site of the modern town. Strategical considerations would have emphatically recommended this plan; for, if the northern wall had skirted the south bank of the river, the city would have been strengthened by an additional natural defence on the northern side. The inevitable inference is that there were cogent reasons of a political nature for disregarding the obvious considerations of strategy; and it is obvious that these reasons can only have been connected with the double character of the place. There is no difficulty in drawing the conclusion—

The Helisson divided the Pederate city from the Federal capital.

§ 7. The northern half of Megalopolis was the city of Megalopolis in the strict political sense. For its defence the Megalopolitan citizens were responsible, just as the Mantineans were responsible for the defence of Mantinea; and it was as exempt as Mantinea from Federal interference. The Agora was laid out on the north bank, and the Buleuterian was built beside it. This Hall of Council had nothing to do with the League; it was for exclusively Megalopolitan purposes. The councillors who met together there dealt with the affairs of the city; they were in no way concerned with the direction of the affairs of the Federation. When they went to take their place in the Federal Assembly and let their voice be heard in the discussion of Federal affairs, they were obliged to cross by bridge the river which divided their own city from the Federal capital of Arcadia.

The southern division of Megalopolis was Pan-Arcadian ground. Here were all the Federal buildings and offices. Here stood the great Hail of Council of Assembly, called the Thersilion, in front of the theatre, which might itself be used for holding the meetings of the Ten Thousand. Here the Arcadian citizens, who gathered from all parts of the land to the capital of the League, were lodged, whether in permanent dwelling places, or in temporary tents, like those which served the spectators at the Olympian festival. Here dwelled the Federal magistrates and officers for their term of office here were the Pan-Arcadian treasury and the Pan-Arcadian archives. Here too the Eparitoi must have had their quarters; and it was their duty, in case of an hostile assault, to defend the southern circuit of the walls. Here were ample spaces for the Arcadian throng to group themselves, the folk of each city, we may guess, in a quarter of its own, and to mix together, not only in

Paumaniso, 8, 30, 4.

A It is remarkable that no traces of an ancient bridge have been found, and it may be

questioned whether Megalopolis ever had a stone bridge. A wooden bridge seems the most probable hypothesis.

the debates of business, but in the festivities and annusements which would

accompany the national meetings.

These which he saw on the north side suggest no federal association. On the south he mentions seven: three of these (two to Asclepius, one to Artemis Agrotera) seem to have been still used, the other four were in ruins. Seeing this progress of decay, we cannot be surprised to find no mention of a sanctuary of federal significance, such as one may confidently assume to have existed during the federal period of the history of the city.

- § 8. By this arrangement the sejourners in the Federal capital, with those who came from time to time to attend the Assemblies, as well as the small number of permanent Federal officials, and the military garrison, had all the advantages of living in a city; while the Federation was secured against the danger of Megalopolitan encroachment, against all confusion between Megalopolitan and Pan-Arcadian rights, by the clear and unmistakable boundary of Helisson's stream. In case a party in Megalopolis should ever induce the city to desert the League -and this was a terrible contingency which the founders of the dual town had to face—the Pan-Arcadian capital would indeed be in a serious peril; but it would not without more ado pass into the hands of the seceders as must have been the case if there had been no physical barrier corresponding to the difference between Megalopolis as a sovran city and Megalopolis as a Federal capital. In such an event the garrison of the southern town could easily maintain itself against the northern until reinforcements from the Arcadian cities arrived; and northern and southern Megalopolis on either bank of their river might conceivably exist side by side, hostile and independent.
- § 9. Thus the river performed a twofold function. It was a barrier which preserved the distinction between the two characters of Megalopolis against obliteration or confusion; and it was also a military defence for the Federal capital against the possible revolt of the city to which it was locally attached. When Megalopolis was to be defended against a common enemy, the river was no hindrance to free communication between the Megalopolitan and the Pan-Arcadian sections of the garrison; one city, and not two, was besieged, one city, and not two, was defended. But, if the Arcadian League were ever threatened by the hostility of Megalopolis itself, then the river would assume a new aspect, and become the northern fortification of the Federal capital, the southern fortification of the revolting city; Megalopolis would break up into two adjacent towns. The Helisson served the purpose of a barrier, without obtruding that purpose as an artificial barrier would have done; the innocent river need not suggest to the dwellers on its northern bank that the Federal government had ever considered the possibility of their defection or the necessity of a line of defence against them.
- § 10. It has been pointed out above that a town one quarter as large again as Mantinea would have been of luxuriously ample size for Megalopolis.

if Megalopolis had not been the Federal capital. Now the northern city more than fulfils this condition; for it is about one third as large again as Mantinea. I have calculated the areas of Mantinea and the two Megalopolitan towns, by weighing them in accurate scales, as follows:—

Area of Mantines a 1,471,512 square yards or (1,230,247 square metres)

Area of Northern Megalopolis 1,977,488 square yards

Area of Scuthern Megalopolis 2,118,238 square yards

Total area of Megalopolis 4,090,724 square yards

§ 11. It is important to remember that the theatre was intended for Arcadia, and not merely for Megalopolis. It was a Federal building, and its construction must have been paid for out of Federal funds. This is proved (1) by its close connexion with the Federal Hall of Assembly-a connexion which is structural and not one of mere proximity; and (2) by its vast size, compared with the little theatre of Mantinea. The Hall of Assembly, affording standing room for 10,000, and the Theatre, capable of seating 20,000, were part of the same design. The Megalopolitans of course had the advantage of the theatre; when it was not required for Federal purposes, it was available for them; this was one of the advantages to set off against the disadvantages of their close union with the Federal capital. The inscriptions of Antiochus on the backs of the front seats, which belong to the first twenty years of the history of Megalopolis, accord with the Federal character of the theatre. Antiochus is probably the envoy whom the Arcadian League sent up to Susa in u.c. 367, Xenophon describes him as an Arcadian paneratiast; and he is probably the pencratiast of Lepreum mentioned by Pausanias.5 This hypothetical identity confirms the view that the benches which Antiochus dedicated in the theatre were a gift to the Pan-Arcadian League and not to the Megalopolitan city.

§ 12. The serious disadvantage in the position of the Megalopolitan state was the prospect which it had to face in case the League were weakened or dissolved. In the latter case the southern town would be thrown entirely into

The calculation depends on the plans of Meests. Fougetes and Loring.

² If Mantinea be trasted as an ellipse, the area (wab), calculated from M. Fougeres' statement of the lengths of the major and uninor axes, would give 1,136,680 metres. The fact that the clime is not perfect, being extremely blunted at one side, accounts for the difference in the results. My colleague, Mr. W. E. Thrift,

* if Polybins had known these measurements he might have used them for further illustration of the geometrical truth which he insists upon,

kindly helped me in these calculations.

that the relative sizes of two cities do not correspond to their circuits. The circuit of the wall of the southern town is a little less than 25 miles, that of the northern a little more than 3 miles. The entire circumference of the northern town is about 4 miles. The chromoference of Mantines is somewhat more than 25 miles (3,942 matres = 21 studes, 180 feet); see Fougères, 'Fouilles de Mantinée,' B.C.H. 1590, pp. 68-70.

^{* 19,700 :} H. W. Schultz in Excer. p. 41.

the hands of the Megalopolitans, and they would have to defend a town twice too large for them. And, if the richer and more powerful members seceded, the treasury would be no longer able to support an adequate Pan-Arcadian garrison, and in this case too the city would suffer. The defection of Mantinea was thus a serious blow to Megalopolis; and ten years after its foundation the city itself must have borne the chief burden in holding the League together. It was obviously to its interest to do so. The manner in which Demosthenes, when he advises Athens in a.c. 353-2 to support Megalopolis against Sparta, uses the terms 'Megalopolitans' and 'Arcadians' as almost synonymous, is highly significant.1 We do not know whether the Eparitot still survived in any shape, but we may be sure that the stress of defending the southern as well as the northern wall fell upon the citizens of Megalopolis. When the League was dissolved about thirty years later, the Federal side of Megalopolis, which had been ever becoming less and less important, finally disappeared; 2 the Pan-Areadian town south of the river was left to the Megalopolitans to deal with as they could or would; and they had at least the consolation of having undivided and undisputed possession of the great theatre and the adjoining stadion. The front seats could now be reserved for the magnates of Megalopolis, being no longer required for the magnates of Arcadia; and the wedges could be appropriated to the tribes of the city. We find tribal names inscribed on the backs of some of the front seat-backs. in letters which are ascribed to the second century B.C.; they represent the Megalopolitan, just as the inscription of Antiochus represents the Federal. stage in the history of the theatre.

§ 13. The deserted spaces of Megalopolis must have impressed visitors by a melancholy sense of the contrast between the high hopes and ambitious designs with which Lycomedes and his fellows had gone to work in founding the League, and the speedy decay and disappearance of the institution which they had called into being. The inhabitants within their unmanageable girth of wall must have sometimes felt with bitterness that they had been sacrificed to the fond dream of a perpetually united Arcadian nation. Mr. Freeman observes that though 'the great scheme of Lykomedes, the

city after its capture by Cleamanss in a.c. 2004, see Polybins, 5. 93. The disaster is distinctly ascribed to the size and emptiness (ve payettes nivers and the forming of the place. But there is no hint in Polybins that its population had decreased since the fourth century. The pillage by Cleomenes reduced the inhabitants to poverty (§ 2, rollier mir derdeinbut adreus bi caurifeir). One would have thought that it might have been feasible to build a new southern wall to the northern town, along the bank of the river, and pull down the fortifications of the southern town, thus leaving the theatre outside the walls. Before the time of Strabe (8, 8, 1) the Great City was 'a great wilderness. Cp. l'annanius, 8, 33, 1.

¹ Op. Domreth, Meg. 38 30, 31, 32, &c.

^{**} Hyperid., Dess. xvi. ed. Mass, where the critical words are unfortunately missing. The internal history of Arcadia is obscure after the battle of Mantinus. We find the Federal Assembly active in n.c. \$47 and \$44, hearing the placetings of Assembnes and Demosthemes (Dem. F.L. 32 10, 11, De Cov. § 79). In the war of Agis and Antipater, a.c. \$30, Megalopolis supported the Macedonian, and had almost all Arcadia against her (Asseh. Cics. § 165). Did Megalopolis at this crisis pretend to represent the League, and did hat opponents most for federal purposes at some other centro?

² Eleenr. pp. 123, 124.

[.] For the proposal to reduce the girth of the

most promising that any Grecian statesman had yet designed, had altogether fallen asunder, his labours were far from being wholly fruitless. He had given a model for the statesmen of later generations to follow. But he had also given a warning. The ingenious experiment of a double city was not tried again. If the Arcadian Megalopolis had never existed, it is not improbable that an Achaean Megalopolis would have been founded by Aratus.

J. B. BURY.

^{*} Federal Government, 2nd wt., pp. 161-2.

THE TEXT OF THE HOMERIC HYMNS.

PART V

APPRODITE.

This Hymn, whether from the simplicity of its narrative or from accident, presents fewer textual difficulties than any of the four larger compositions. Serious corruptions there are none, and the notes it is necessary to write are occasioned rather by the misplaced activity of critics than by real obscurities in the tradition.

Literature since 1886 is confined to the contributions of A. Ludwich, Rheinisches Museum 1888, p. 566, and R. Peppmüller, Philologus 1889 p. 13 sqq. Accounts of the Goddess (which however do not bear materially on the Hymn) are given by Roscher in the first volume of his Lexicon, Tümpel in the new Pauly-Wissawa, vol. 1, and by Mr. Farnell, Cults of Greek States, vol. 2.

13 ποιήσαι σάτινα καὶ άρματα ποικίλα χαλκώ.

Barnes conjectured σατίνας, which has been accepted, for the two other places where the word occurs (Eur. Hel. 1326 θηρῶν ὅτε ζυγίους | ζεύξασα θεὰ σατίνας Anacreon fr. 21. 12 νῦν δ' ἐπιβαίνει σατινέων) leave no doubt upon its gender or quantity. It is difficult to see what cause produced the omission of the sigma and the (presumable) prosody σατίνα. In the two passages just quoted there is no trace in any MS, of a neuter; Musgrave indeed corrected σατίνας from σατίναν, but ζυγίους makes the correction certain.

I have not kept Barnes' further suggestion $\tau\epsilon$ κa , seeing that the passages in which κa preserves its length before a vowel, though a small minority, are sufficient to guarantee the usage when the MSS, present it. They are in the Hymns, the following:

1 Dom. 275 δις είπουσα θεὰ μέγεθυς καὶ | είδος ἄμειψε 2 είδ. 424 Πάλλας τ' ἐγρεμάχη καὶ | 'Αρτεμες ἰσχέαιρα 3 Αρ. 198 άλλὰ μάλα μεγάλη τε ίδεῖν καὶ | είδος ἀγητή [ίδ. 203 μαρμαρυγαί τε ποδῶν καὶ | εὐκλώστοιο χετῶνος] [ίδ. 423 καὶ Θρύον 'Αλφειοῖο πόρον καὶ | εὔκτιτον Αἶπυ]

4 Αρίστ. 13 ποιήσαι σατίνα[ς] καὶ | ἄρματα ποικίλα χαλκῷ 5 ib. 82 παρθένοι άδμήτη μέγεθος καὶ | είδος όμοίη [τε καὶ ρ plerique] cf. 1 and 3. 6 ib. 113 γλῶσσαν δ' ὑμετέρην καὶ | ἡμετέρην σάφα οίδα [contra ib. 116]. 7 Αντεπίς 27. 22 αὐτὰρ ἐγὼ ὑμέων καὶ | ἄλλης μνήσομ' ἀοιδῆς 8 Diose, 33. 19 αὐτὰρ ἐγὼ ὑμέων καὶ | ἄλλης μνήσομ' ἀοιδῆς [contra Mus. 25. 7, and Hest. 29. 14].

Ruhnken (on Dem. 274) endeavoured to make the insertion of 78 absolute, but he is justly resisted by Ilgen on Aphr. 82. Variants on the point will be noticed at Aphr. 82, and in two slighter cases Herm; 289 άλλ' άγε μή πύματον τε και ύστατον ύπνον ιάνης (τε οια. At D ed. pr.), Aphr. 85 είδος τε μέγεθος τε και είματα συγαλόεντα (τε om. N). Outside the Hynns Ilgen l.e. quotes Γ 392 κάλλει τε στίλβων και είμασιν, ούδε κε φαίης and Theog. 66 μέλπουται πάντων τε νόμους και ήθεα κεδνά to which I may add Z 211 ταύτης τοι γενεής τε και αίματος εύχομαι είναι, where τε is omitted by H Cant. schol. Plat. Gorg. 449 A' etc., Vat., Ven., 13 A Mc, Z 478 & 65 βίην τ' άγαθον και Ίλίου Ιφι άνάσσειν, βίην άγαθον τε και many MSS. Λ 528 κείσ' Τππους τε και άρμ' Ιθύνυμεν, τε om. 'L' and the rest of this family; Ο 492 ήδ' ότινας μινύθη τε και ούκ εθέλησιν αμύνειν, τε om. I- w Vat.24 Ven. Τ 417 μόρσιμον έστι θεώ τε και άνερι Ιφι δαμήναι, τε οπ. L Lips. No Vat 100 22; Ω 574 ηρως αὐτομέδων ήδ' άλκιμος, for ήδ' many MSS, have Te Ral, Ral alone is found in Venus, No. Mos to Vates; Hes. Ορη. 222 ή δ' έπεται κλαίουσα πόλιν καὶ ήθεα λαών ' sic M 5 Vat. 2 V 2, al. πόλιν τε καί.

52. ως τε θεὰς ἀνέμιξε καταθνητοῖς ἀνθρώποις. The correction of Schafer, συνέμιξε, (contributed to Matthiae's edition 1805, pract. pp. vi, vii) is easy palaeographically, for to the examples Schäfer gave Demetrius' correction might have been added, Herm. 94 φὰς συνέσενε for φασίν ἔσενε; but it is hard to see why if the MSS, preserve συνέμιξε v. 50 and συνέμιξα v. 250 they should not have done so here. The probability is therefore somewhat in favour of ἀνέμιξε, for which in a metaphorical sense sufficient parallels may be found in the Lexx.

59—63 = θ 363, 45, Ξ 169, 172 v. 63 ἀμβροσίφ ἐσυῷ τό ρά οἱ τεθυωμένου ἡεν corresponds literally to Ξ 172 except that in the Hiad we have ἐδανῷ for ἐσυῷ. The distinction between ἐἀνός subst, and ἐἀνὸς adj., at which Ruhnken scoffed, is now firmly established; we have therefore the choice of making an unexampled synizesis of ἐᾶνῷ dissyll., αι (with Samuel Clarke, and not either Barnes αι Ruhnken, as it is wrongly stated in different editions) reading ἐδανῷ as in the Hiad; and the latter course is singularly recommended by the variant ἐσυῷ on Ξ 172 which is found in Athenaeus 688 E, schol, Ξ 346 and Pap. Mus. Brit. DCCXXXII (A. S. Hunt; Journ, of Phil. xxvi. p. 48). We are to suppose that ἐδανῷ, an ἄπαξ εἰρημένον, was

mistaken by an early but unmetrical scribe or reader for the more familiar epic forms.

62 άμβρότω οία θεούς έπενήνοθεν αίλυ δόντας

63 άμβροσίω έανώ το ρά οι τεθνωμένου δεν.

The theory of a double recension is no less dangerous than any other principle that is unsupported by direct MS, evidence: the lengths to which it can lead may be seen in Köchly's edition of Hesiod. As a provisional measure however it certainly tempts application in many cases, and is always preferable to the arbitrary and wasteful process of bracketing one line rather than another. Here of these two lines editors have inclined to cut out 63, on no other ground but that it is the second: Genical with much sense defends it. Similar pairs of lines of which either one or other is dispensable are, in this hymn 97 and 98, 136 and 136a, 274, 5 and 276, 7; Apollo 136-8 and 139, Dian. i. 4 and 6, 7, as previously noticed, and possibly Artem, ix, 8 and 9, Aphr. x, 4 and 4a, Herael, xv. 5 and 5a.

01 Αγχίσην δ' έρος είλεν έπος δέ μιν αντίου ηθόα-

Peppmuller Le. with unnecessary subtlety would read τάφος for δ' έρος in this place. Apart from the marked absence of graphical support offered by the tradition, and the asyndeton involved in the alteration, it is surely better that the impression made on Anchises should be immediate, Aphrodite had arranged her appearance with especial regard to avoid any over great respect (vv. 82, 83), and the hero's address 92—106 is almost as much epic compliment as Odysseus' to Nausicaa. His afterthoughts (185, 6) are not to be too literally taken.

113 sqq. Mr. Tyrrell Le. p. 48 remarks on the modernity of Aphrodite, who explains her knowledge of Anchises' language from her having had a Trojan boune. However difficulties of language are recognised in ancient literature: cf. B 804 Δ 437 Agamennon 1035.

136 οῦ σφιν ἀεικελίη νυὸς ἐσσομαι ἀλλ' εἰκυῖα 136α εἴ τοι ἀεικελίη γυνή ἔσσομαι ἡὲ καὶ οὐκί.

Cf. on v. 62 above. Both of these lines stand in all the MSS.; either makes acceptable sense, together they are incompatible, while neither seems derivable from the other. We have therefore a fair case for assuming a double recension, and the instance is parallel to Apoll. 136–8 and 139. Compare also Hes. Theog. 590 and 591, 639–41 and 642.

172 ἐσσαμένη δ' εὐ πάντα περὶ χροὶ δια θεάων ἔστη ἄρα κλισίη, εὐποιήτοιο μελάθρου κῦρε κάρη, κάλλος δὲ παρειάων ἀπέλαμπευ.

This passage and 266 sqq. are the two syntactical difficulties of this poem. Here the meaning was long obscured by the faulty tradition of the verb in 174; Demetrius' correction he was accepted down to Ruhnken, (on Dom. 189) who restored the obviously correct κύρε from M. Estienne invented πὰρ for ἄρα, and this was long believed to be the reading of one or more MSS. The local dative however needs no defence, and κλισίη is not 'bed' but 'hut.' She stood up in the hut and ber head touched the roof' is the sense. There remains the asyndeton of 173, and this difficulty is real. The facile alteration εὐποιήτου δὰ (due to Ruhnken la.) is unsatisfactory since it does not suggest an adequate motive for the corruption; μελάθρου seems intangible and is guaranteed by Dem. 189. On the whole the asyndeton may be excusable if we make a longer pause after κλισίη. The case will be somewhat similar to 267.

179. elev δή με τὸ πρώτον. Hermann would omit τό, and La Roche (hom. Studien p. 40) με, to avoid the 'Attic correption'—but as the commentators point out without reason. Contrariwise Artemis ix. 8 αὐτὰρ ἐγώ σε πρῶτα, M inserts τε before πρῶτα.

198 τῷ δὲ καὶ Λίνείας δνομ' ἔσσεται οῦνεκα μ' αἰνόν ἔσχεν ἄχος ἔνεκα βροτοῦ ἀνέρος ἔμπεσον εὐνῆ.

It is not surprising that commentators have doubted at ἔνεκα in 199, for if it be taken as a conjunction the poverty of expression is almost intolerable. At the same time no one will wish to substitute Gemoll's ὅτε τε, nor the attempts of his predecessors, ἵνα κεν (Barnes), ἔνεκα βροτοῦ ἀνέρος ἐμπεσον εὐνῆς ('that came upon me on account etc.', the too ingenious method of ligen, approved by Matthiae), ἔσχ' ἄχος οὕνεκ' ἄρα (Hermann 'certa emendatione, accepted by Franke), ὅτι ῥα (Abel). It has struck me that perhaps another asyndeton might be borne: 'his name shall be Aeneas for that a dreadful grief is come upon me—for a mortal man's sake ἔμπεσον εὖνῆ.' If this be thought too abrupt we must with Baumeister be content with the MS, reading.

224. ξῦσαί τ' ἀπὸ γῆρας ὁλοιόν. Το Ι 446 quoted by everyone since Barnes we may add Νόστοι fr. 6. 2 γῆρας ἀποξύσασ'.

252 νῶν δὲ δὴ οὐκέτι μοι στοναχήσεται έξονομῆναι τοῦτο μετ' ἀθανάτοισιν.

Martini's στόμα χείσεται, both picturesque and close to the MSS., has received fresh support by Mr. Tyrrell's advocacy (l.c. p. 33). Of the other suggestions Matthiae's τλήσεται is excluded by metre, as Tyrrell and Ludwich (Rhein, Mus. 1888 p. 566) remark, but Ludwich's own attempts στόμα λήξεται and στόμ' ἀλώσεται έξονομήναν are not convincing: Buttmann's ἀχήσεται, while admirably near to the MSS., introduces a doubtful form. Στόματ' ἐσσεται (Clarke), στόμα χήσεται, πείσεται, λήσεται (Ilgen), χήσεται (Buttmann, Franke), ήσεται (Agar), have pleased their authors.

254 έπει μάλα πολλου ἀάσθην σχέτλιου ούκ ονοτατον, ἀπεπλάγχθην δε νόοιο.

Martini's δυομαστόν has been accepted without question, owing doubtless to the familiarity of the phrase σὖκ ὁνομαστόν. The Homeric usage however confines itself to the phrase κακοίλιον οὖκ ὁνομαστὴν thrice repeated, where the meaning is literally that the ill-omened word 'Ιλιος is not to be pronounced. In Hes. Theog. 148 τρεῖς παῖδες μεγάλοι καὶ ὅβριμοι οὖκ ἐνομαστοί | Κόττος το Βρίαρεώς το Γύγης δ΄, the sense of literal 'naming' is the same: Is. 44. 7, εἶχε δὲ δῶρα | παντοῖ', οὖκ ἀνομαστά, 'countless.' The sense of 'unmentionable, horrible' does not occur till Apollonius iii. 801 πρὶν τάδο λωβήσετα καὶ οὖκ ὀνομαστὰ τελέσσαι.

Now δρότατα is plainly a clerical error for δροταστά; the omission or insertion of σ in these quasi-participles is universal, e.g. 123 ἄκτιστον for ἄκτιτον, Ηετπ. 80 θαυμαστά, θαυματά, Β 592 εδκτιτον, εδκτιστον είς. Όνοτάζω is a word which occurs only in the Hymn to Hermes 30 σύμβυλον ήδη μοι μέγ' δνήσιμον οὐκ ἀνοτάζω and in Hesiod Opp. 258 σκολιῶς ἀνοτάζων, therefore is appropriate in the vocabulary of such a document as this. I would therefore be content with οὐκ ὅνοταστόν ' not to be maile light of,' in the sense of the familiar ἔνθα κεν οὐκέτι ἔργον ἀνὴρ ὀνόσαιτο μετελθών and many similar phrases in the Πίαλ and Odyssey, and the participle ὀνοστά I 164. Aphrodite is not without a certain sense of the effect that her ἄτη will produce in Olympus.

It should be noticed also that ἀρομαστὰ is made somewhat less probable by the nearness of ἐξονομῆναι in 252. I see on examining the edition of Samuel Clarke (1729) that ἀραταστά is recommended, though not put in the text. I am glad of the coincidence. Clarke compares ε 379.

264 τήσι δ' άμ' ή ελάται ή δορύες υψικάρηνοι γεινομένησιν εφυσαν έπι χθονί βωτιανείρη, καλαί τηλεθάουσαι εν ούρεσιν υψηλοΐσιν έστασ' ήλίβατοι τεμένη δέ ε κικλήσκουσιν άθανάτων.

The arrangement and correction of these lines have given trouble to modern editors. Matthiae and Hermann cut out one or more, to avoid the asyndeton of 267; Gemoil with the same object inserted δ' after έν in 266. Franke however decided that all the lines were necessary to the description, and made a stop at ψηλοίσων. By this arrangement, which will probably commend itself to modern readers, the abruptness of v. 267 is to some extent excused by the parenthesis which opens there. 'Πλίβατοι 267 of trees is certainly an extension of Homeric usage, but is sufficiently warranted by Hes. Theog. 483 ἄντρφ ἐν ἡλιβάτφ, 675 πέτρας ἡλιβάτους στιβαρῆς ἐν χερσὶν ἔχοντες, Soul. Her. 421 ἡ ὅτε πέτρη [πεύκη ' Μ 3'] ἡλίβατος with Rzach's note. Not more violent is the use of δυσηλεγέες of frosts Opp. 506.

274. It cannot be denied that πρώτον in 278 together with πότικα following in 280 makes 274, 5 incompatible with 276, 7. It is evident that on the first occasion that Anchises sees the boy he is to acknowledge him, and therefore of the two presentations one must exclude the other. These considerations afford some ground for holding 274, 5 and 276, 7 alternatives, i.e. remains of different versions.

283 τῷ δὲ σὰ μυθεῖσθαι μεμισμένης ὡς σε κελεύω.
φασίν τοι νύμφης καλυκώπιδος ἔκγονον είναι κ.τ.λ.

By Matthiae's absurd conjecture φάσθαι, in 284, bolstered up by irrelevant quotations, a great deal of humour is lost. The necessary imperative is conveyed by μνθεῖσθαι 283: at 284 commences the statement which the here is instructed to make. The excellent Anchises, homms à honnes fortunes, cannot be supposed to remember his conquests, but with a delightful fatuity he does not disclaim his paternity: φασίν τοι νύμφης κπ.λ. The spirit is the same as in the familiar lines a 215 μήτηρ μέν τέ μέ φη σι τοῦ ἔμμεναι αὐτὰρ ἔγωγε | οὐκ υίδ', οὐ γάρ πώ τις ἐθν γύνον αὐτὸς ἀνέγνω, the merit of which was recognised by Aristophanes. Cf. also δ 387.

VII. DIONYSUS.

See Crosius, Philologus 1889 vol. 2 pp. 193-228.

41 οἱ δὲ ἰδάντες μὴ δ' ἥδη (-ειν κρ) τότ' ἔπειτα κυβερνήτην ἔκέλενον γῆ πελίαν

If we compare Apoll. 393 ημαθόην of all MSS, for what is generally accepted as original νῆα θοήν, we may suppose μη δ΄ ήδη here to represent ΝΗΔΗΔΗ, ΝΗΔΗΔΗ, i.e. νῆ' ήδη. The suggestion is Hermann's, the older editors down to Marthiae had taken μηδείδην seriously as a patronymic. Little is gained by Köchly's νῆα πάλιν or Gemoll's νηπιέμ.

55 θάρσει δίε κάτωρ τῷ ἐμῷ κεχαρισμένε θυμῶ.

Here I must confess to absolute impotence. Professor Ridgeway (Journ. of Philology 1888 p. 113) maintains κάτωρ and derives it. The conjectures are mere midsummer madness.—πάτωρ (quoted by Estienne in quibusdam editionibus), κράτωρ ap. Barnes, ἄκτωρ (Ilgen), ἐλατήρ (Wolf), ἔκτωρ and ἀκάτωρ (Baumeister: ἀκάτωρ from ἄκατος gives at least a sense); φίλε πάτερ (Κöchly) which mises the just wrath of Schulze, Quaest. Ερ. p. 386; βάρσει μηδέτι τάρβει (Gamoll), βάρσει Ιθύντωρ (Peppmüller, Philologus 1889, p. 22). The termination ωρ is used so sparingly in Greek to form agents, that it is useless to look for nouns derived from any stem such as κατ-, or ἐκάτ οι ἐκατόν, which are suggested by M.'s reading ἐκάτωρ.

On the other hand the word may possibly be a proper name, and the survival in M be a short form of such a mame as ἐκατήνωρ, Fick Personenaumen p. 107. In the version followed by Ovid and Hyginus the steersman is called Accetes.

XIX. PAN.

This poem of forty-nine lines has had the advantage of being thoroughly discussed by A. Ludwich, Rhein, Mus. 1887 pp. 547 sqq. and R. Peppmüller, Philologus 1889 vol. 2 p. 1 sqq. It may easily be imagined that the third comer has not much to glean. I pass by a certain number of alterations which possibly neither learned critic would press to-day, and attack the essential points.

9 ἄλλοτε μὲν ρείθροιστιν ἐφελιθμενος μαλακοῖστιν. The tradition is sound, certainly; we do not require ἐφεζόμενος (Baumeister) nor ἐφαλλόμενος (Ludwich), but it may be doubted if the sense 'attracted' applies. Surely a physical notion is more suited to the ungainly god; a semi-humorous term for floating—'hauled, towed,' appears more appropriate. This is suggested by A. Matthiae. It is doubtful if ρείθρον ever really means a bank.

14 τότε δ' εσπερος εκλαγεν οἰον ἄκρης εξανιών

Olor has puzzled the critics and produced a crop of alterations from Martini's exayer ofac to Ludwich's exhaver of unv or Suror. Hormann read olos, but that Pan has company is expressly stated v. 19. The key is given by Hes. Theog. 26 ποιμένες άγραυλοι, κάκ' έλέγχεα, γαστέρες οίου. This Peppmüller recognises, though he spoils his effect by the unfortunate alterations ότε δ' έσπερος ή κλάγεν οίον. Οίον = μόνον occurs Aesch. Agam. 130 σίον μή τις άγα θεοθέν κνεφάση where the scholiast glosses it μόνον μή; I 355 ἔνθά ποτ' οἰον ἔμιμινε as Eustathius takes it, and often in Apollonius, ii. 634, iii. 1109, iv. 652, 1077, 1316. Theorr. xxv. 199. Total for thre (as in 22, and cf. Ω 11) would improve the sense, which then is 'he often coursed over the hills and often chazed the beasts in the glades; and again would be sing, only of an evening coming back (up) from the chase. Pan being a sportsman waits till the day is over to begin his music. Pierson's correction άγρης for άκρης is generally accepted; cf. Theocr. i. 16 άπ' άγρας | τανίκα κεκμακόν άμπαθεται of Pan, xxv, 87 έκ βοτάνης άνιοντα of sheep, Apollonius ii. 938 άγρηθεν ότ' ούρανον είσαναβαίνη of Artemis, iii. 69 θήρης ékarubr of Jason.

18 θρήνον επεπροχέουσα χέει μελίγηρον ἀοιδήν.

The conjectures are very indecisive, for putting aside ἐπεπροιείσα χέει and ἐπεπροχέουσα ἴει as violent, Ilgen's ἀχέει, Ruhnken's Ιαχεί and Gemoll's ἡχέει are much of a muchness. The MS, reading is certainly hard

to swallow, but I have a secret suspicion that it is what the poet gave. Would a somewhat poor writer not find justification in phrases like χυτήν έπὶ γαῖαν έχευαν γ 258, χοήν χεόμην λ 26, χεέν πολυηχέα φωνήν τ 521, βοὺς δ΄ ἀπέδυνε βοείην χ 364, ἐς δ΄ ἀγορήν ἀγέροντ' Apollonius iv. 214, προρέειν καλλίρρουν δδωρ h. Apoll. 380?

20 φοιτώσαι πύκνα ποσσίν έπι κρήνη μελανύδρω

I heaitate to alter πύκνα into πύκα with Ludwich after Barnes (i.e. 551). Granted that the change is slight (cf. Quintus xii. 219 where πυκυά and πύκα are variants on πυκυά) the quantity of -κν- is too often short in the second syllable of the _ _ . to forbid us to allow it in a poem of the uncertain age of this hymn. (A. Theoer, xiv. 23 καὶ λύχνον ἄψας, xvi. 49 ἀπὸ χροιῶς κύκνον ἔγνω, Theognis 910 καὶ δάκνομαι ψυχήν, Anth. Pal. v. 133. 3 ὁ σοφὸς κύκνος: Quintus iv. 153 ὡς κύκνον ἔκτανε v. 374 οῖ οἱ τέκνα δηώσωνται; cf. also Aristophanes Clouds 384 and 406 πύκνότητα in anapaests, Knights 739 σαυτὸν δὲ λυχνοπώλαισι. Pseudophocyl. 158 εἶ δὲ τις οὐ δεδάηκε τέχνην.

22 δαίμων δ' ένθα καὶ ένθα χορών τοτὶ δ' ἐς μέσον ἔρπων πυκνὰ ποσὶν διέπει·

Köchly's Gopôn is too violent even for the awkward movements of Pan, and is justly rejected by Ludwich after Franke. Pan is now outside, on either side, of the ring, now inside it. The planal, to which Ludwich objects, surely contains no difficulty; we can as well say 'the dances' as 'the dance', compare Artemis xxvii, 15 with 18.

33 θάλε γὰρ πόθος ύγρὸς ἐπελθών.

Ruhnken first disturbed $\theta \hat{a}\lambda \epsilon$, which had satisfied the earlier readers, by turning it into $\lambda \hat{a}\theta \epsilon$, a conjecture which from its false air of graphical facility, has reigned in most editions since. Ilgen and Hermann kept the original, but the impulse once given produced $\delta \hat{a}\kappa \epsilon$, $\lambda \hat{a}\beta \epsilon$, $\kappa \hat{\epsilon}\lambda \epsilon$, and Ludwich and Peppmüller are at one over $\delta \lambda \epsilon$. $\Delta \hat{a}\theta \epsilon$ introduces a refinement foreign to the extremely simple psychology of Pan, and the other suggestions lack palaeographical probability: 'desire imperceptibly came upon him is hardly like Pan; 'the desire came upon him hot' is quite in character. For $\theta \hat{a}\lambda\lambda \epsilon i\nu$ in this sense cf. Soph Philodetes 259 and other tragic examples in the Lexx.

XXIII.-ZECS.

θέμιτι; corr. Barnes θέμιστι. The MS, reading as Gemoll observes is curious; it is quoted by schol Pind. Ol. xi. 28 as the reading in O 87, but the MSS, give it no support, nuless θέμιδε Vat. be considered as such (θέμιδος also in 'J' β 68). At T 4 and h. Arm viii. 4, there are no variants.

XXIV.—HESTIA.

 ἔρχεο τουδ΄ ἀνὰ οἶκου ἐπέρχεο θυμὸν ἔχουσα σῦν Διὶ μητιδευτο

Either θυμόν must be sacrificed (as Schneidewin with εὐμενέουσα, to support which one might bring Γ 411 πορσανέχουσα L_{100 10} Vat₂₇ γρ. Ven₁₄ for πορσανέουσα, Η 342 άμφις ἐοῦσα and ἔχουσα), or one must suppose a lacuna containing an epithet of θυμάν, (cf. Irem. 360, 1 Aphrod. 102, Dion. vii. 49), and to this I incline. The repetition ἔρχεο—ἐπέρχεο is singular, but perhaps forcible, cf. Soph. Electra, 850 κάγὰ τοῦδ Ἱστωρ ὑπερίστωρ. Ατ. Frogs, 369 τοῦτοις αὐδῶ καῦθις ἀπανδῶ, Anth. Pul. v. 161, 3 οίχομ, ἔρωτες, δλωλα διοίχομαι, and contrariwise Quintus ii. 314 ἀλλ' ἀναχάζεο τῆλε μόθου στυγεροῦ τε φόνοιο | χάζεο μή σε βάλοιμι κ.τ.λ.

XXVI.-Dionysus.

 δὸς δ'ήμας χαίροντας ἐς ώρας αὐτις ἰκέσθαι ἐκ δ'αὐθ ώράων εἰς τοὺς πολλοὺς ἐνιαυτούς.

These expressions which have troubled the commentators (Matthiae and Franke bracket 13) have probably a general significance and no reference to feasts or seasons, cf. Aristophanes Clouds 562, Thesm. 950, Progs 381 Theorem. 74. It was a popular formula conveying length of life or vague futurity.

XXIX -- HESTIA.

9 sqq. After proposing in the Oxford text a somewhat more alaborate arrangement, I have come round to Martini's transposition of v. 9 to after v. 11. Although this displacement is unmotived palaeographically, it seems necessary since the plural ναίετε, v. 9 can hardly follow the singular ἄγγελε, v. 8. A comma must be placed after είδότες, and θ', coming rather late, connects the whole sentence.

XXXII.-SELENE.

Roscher, Neue Jahrbücher, 1889, pp. 397 agq.

Μήτην ἀείδειν τανυσίπτερον ἔσπετε Μοῦσαι. 'Λείδειν and ἔσπετε are incompatible; of the two ἀείδειν certainly seems the sounder. Possibly the writer mistook the meaning of ἔσπετε, and thought it meant 'begin,' or 'follow.'

XXXIII - Dioscum.

 κύματα δ'έστόρεσαν λευκής άλὸς ἐν πελάγεσσιν ναύταις σήματα καλὰ πόνου σφίσιν:

The older editions, down to Franke inclusive, put a comma after ναύταις, and treated σήματα... σφίσιν as a clause by itself. Baumeister (after

D'Orville and Matthiae had suspected πόνου) was dissatisfied with the repetition of σφίσιν after ναύταις, and joined σήματα καλά with what precedes: σφίσιν then became corrupt, and in its place Baumeister proposed κρίσιν, Abel λύσιν, Tyrrell σχίσιν, and I σβέσιν. All these are evidently useless stopgaps, and failing some more convincing emendation of πονουσφισιν it seems probable we should go back to the old stopping, which may not have been intolerable to the poet.

T. W. ALLEN,

THE GREEKS AT PLATAIAL

For the future any discussion of the problems connected with the Battle of Plataiai must take into account Mr. Grundy's careful survey of the field. In the map that accompanies his monograph we have at last reached finality. The satisfaction of this supreme requirement is his best contribution to the subject. His application of strategical principles to the narrative of Herodotos is only partial; and his result is not clear, because he has tried to realize the apocryphal partions of the ancient account. It is only after stripping off the busk of romantic accretion that we can proceed to examine the details by the light of military principles. It is such preliminary work and such subsequent recasting of the narrative that is here attempted.

Mr. Grundy hits the truth when he suggests that Herodotos obtained his information about the operations from an intelligent, but not highly placed, officer. Further, Herodotos himself was not primarily a military historian. His narrative therefore treats merely subordinate and intermediate steps as final ends; and while events are thus viewed only from the outside their presentation is moulded by the epic cast of the writer's genius. Of perhaps still greater moment is his strong Athenian bias. In the recognition of these three factors,—the epic character of the parrative, ignorance of the true strategical issues of the situation on the part of his informant, and the contamination produced by the sympathy of Herodotos with, or his sole reliance upon, the Athenian tradition,-we hold the key to the entire account of the campaign of 479 B.C. Some of the details may have been derived from Thersander of Orchomenos, e.g. the Phokian episode. It is also possible that Herodotos incorporated in his history local stories of the battle. Specimens of these may perhaps be seen in the description of the charger of Masistics, and of the spoil taken from the Persian camp: the three stories which represent the Aiginetans in so poor a light? were

⁴ See the Rattle of Plataca, by G. B. Grandy; published among the Supplementary Papers of the Royal Geographical Scalety, 1894.

^{*} Op. sit. pp. 43 fol.

* I find from Holm's Grit. Hist. ii. 75 (E.T.)
that Delbrück 'explains the movements of both
armies on the basis of correct military principles.'
I have not seen Delbrück's book.

HS.-VOL XVIII.


^{*} iz. 16 fel.

[#] ig. 20.

^{*} in. 80 fol. cf. c. 83.

⁷ ix. 78 fol., Lampen of Aigina urges Pauaanias to maltreat the body of Mardonica: c. 30, Aiginetans buy golden spoil from Helets on pretence that it is brass: c. 85, pretended tomb of Aiginetans at Plataini.

perhaps also current at Plataiai. The contents of chaps. 71, 72, 76 probably come from a purely Spartan source. Not one of these supplements to the



Modern corriage read shown thus ____ Modern tracks connections with these used in ancient rines, thus _____ I. First position of the Greeks II Second position of the Greeks III Third position of Centre.

THE BATTLE-FIELD OF PLATALAL.
[Based on Mr. Grundy's Survey.]

Attic core of the narrative has any bearing upon the operations preceding the battle.

Relating the fate of Amountharetos, Aristodemos, Kalilkrates, etc. and the rescue of the concubine of Pharmdates.

The operations of the campaign resolve themselves into three strategic movements:—

- (1) The occupation of the lines on the slope of Mount Kithairon (cc. 19-24).
- (2) The advance to the Spring Gargaphia and the River Asopos (cc. 25-49).
 - (3) The retrograde movement to the 'Island' (cc. 50-70).

The key to these manoeuvres lies in the consideration of the roads running northwards across Mount Kithairon to the Boiotian capital. These roads and passes are clearly described by Mr. Grundy.¹

- (1) In the east there is the road running through the pass of Dryoskephalai, familiar to all who have travelled from Athens to Thebes by diligence. It enters the range under the walls of Eleutherai, and debouches upon the plain just to the east of the modern village of Kriekuki. The point at which it enters the plain marks the probable site of Erythrai.
- (2) The central road from Athens to Plataiai, with a branch to the right passing through Hysiai, the site of which, in the main, is occupied by Kriskáki.⁴
- (3) The western road and pass, from Megara to Plataiai.
- (4) Lastly, a road running from Plataiai to Thebes.⁵ This road probably, and the main Dryoskephalai road certainly, crossed the Asopos by a bridge.

On the eastern road lay the entrenched camp of the Persians, and the main body of their army, barring all advance northwards. The exact situation of the camp is a matter of no importance. It probably occupied the bend of the Asopos, lying on the north bank, quite close to the bridge, the retention of which was of the utmost moment to the Persians. Their cavalry must have lain mainly on the south bank. The disposition of the Persians was admirable, posted as they were behind a by no means contemptible river in a strongly entrenched camp, covering their communications with a well-provisioned base.

Mr. Grundy's description of the first position of the Greeks is probably quite correct. They advanced over Mount Kithairon, their objective being

t P. 5 fol. Cf. Lenke, North, Gr. H 334

^{*} But modern traffic now follows the loop to the left, which actually passes through & rick abi.

² See Grandy, pp. 6, 9.

^{*} Grandy, p. 15.

Mentioned in Thue, iii, 24, a passage to be discussed biter.

^{*} And is an improvement upon the generally received view, in which Hyalai is put at Krie-Fakt or E. of it, and Krythrai still further E. Grundy, p. 11 fol

Thebes. As their point of departure was Elensis, the allies must have traversed the easy Dryoskephalai pass. On finding the Persians confronting them they threw themselves in extended order across the Athens-Thebes road, thus covering their own communications with the Peloponnese and taking up a favourable position for defence. For as yet it was quite an open question whether Mardonios would not advance to the attack: the veriest tire could not have construed the Persian withdrawal from Attica as a confession of inferiority. The Greek right rested on the steep slopes of Mount Kithairen: the centre and left seam to have been thrown forward somewhat,—probably in order to take advantage of the wells and conveniences of the village of Erythrai.

The success of the Greeks in dealing with the Persian cavalry 2 was so pronounced that Pausanias was encouraged to make a change of position. The inaction of the hostile infantry also contributed to this resolution. Of greater influence than either of these reasons was the reflection that for the Greeks to remain passive was to play the Persian game. The masterly inactivity of Mardonios forced Pausanias to attempt a daring coup. It was at least better to die free men on a well-fought field than to survive the consciousness that the liberties of Greece had been betrayed by sitting still.*

The movement contemplated by the Greek commander involved two serious drawbacks. The hold upon the main road through the range of Kithairon was relinquished, and a descent was made into ground more practicable for the enemy's cavalry. Herodotos does not furnish any satisfactory answer to the inquiry as to how Pausanias justified his evacuation of the impregnable lines of Mount Kithairon. According to the historian, the change was suggested solely by convenience of ground, —the particular convenience not being revealed, with the exception of the more abundant water-supply, which was confessedly only one of several advantages. The ultimate design of Pausanias in descending from the heights must be given by modern conjecture.

What then was the second position of the Greek army?

If we read aright the intentions of Pausanias we can put our finger on the line. It involved a descent (ἐπικαταβῆναι), and a movement into the territory of Plataiai (ἐς τὴν Πλαταιίδα γῆν). It lay, therefore, N.W. of the first position. It was reached via the foot-hills of Mount Kithairon and the village of Hysiai (διά τῆς ὑπωρέης τοῦ Κιθαιρῶνος παρὰ Ὑσιάς). The goal of the advance lay consequently in the neighbourhood of the Asopos, as is clear from the subsequent history. Further than this, two points on the line

Le. 19: suppryferes & de Exemira. Le & Apa delicorro vijs Bouring de Epotoda.

^{*} ix. 22 fol.: death of Maxisties and repulse of the eavalry:

¹ ix. 25 : Ibali opi inicaraficat it Udaracia.

^{*} Here must be noticed the arrange, but in my opinion quite true, tale of Plutacch relative to the Athenian conspiracy frustrated by Aris-

teides (c. 13). I cannot follow Holm (Grk. Hist. ii. 118) is regarding it as 'altogether improbable.' On the contrary it is all of a piece with the conduct of the Athenians during the campaign.

ό τχ. 25 ; ό γάρ χώρος διραίνετο πολλή δών Ιπετηθεώτερος . . . τά το άλλα καὶ εδυδρότερος.

are expressly named, viz. the Spring Gargaphia and the réperor of the hero Androkrates.

Let us take first the Spring Gargaphia.

Among the low hills on the north of Mount Kithairon there are, according to Mr. Grundy's, two springs, and only two, that can put forward a claim to the ancient name. The area of the battle-field is marked by a distinct depression, which runs from N.E. to S.W. up the Krickith brook to the bottom of the village, and from that point N.W. to the head-waters of the most westerly tributary of the Asopos (stream A' in Mr. Grundy's map): there it joins the plain, which extends northwards from Plataiai. The two springs lie on the line of this depression. The traditional Gargaphia is the more westerly of the two, i.e. the modern Apotripi, which lies nearly on the verge of the plateau, about a quarter of a mile before the Krickiki-Pyrgos path enters the aforesaid plain. Measured upon Mr. Grundy's map, the distance of this spring from Plataiai is 12 stades. The other spring, or collection of springs, is found at some distance (on Mr. Grundy's map, 5 stades) east of Apotripi. Mr. Grundy follows Leake in giving the name Gargaphia to these last sources. They lie 14 stades from Plataiai.

What data do we get from Herodotos as to the position of the Spring

Gargaphia? He gives us the following items:-

- (1) It was 10 stades from the 'Island' (c. 51).
- (2) It was 20 states from the Heraion, which was 'in front of' Plataini (c. 52).
- (3) By implication we learn that it must have been about 10 stades from the stream called Molocis, the Argiopian Region, and the temple of Eleusinian Demeter (c. 57).

With regard to the identification of the 'Island,' it will probably be generally conceded that Mr. Grundy has made out his case, and satisfactorily established the locality to which this name was applied. More valuable, however, is his identification of the temple of Demeter. No one can doubt that its place is marked by the modern Church of St. Demetrios. Only with respect to the temple of Hera is hesitation unfortunately possible.

How do the springs above described square with the data extracted from

Herodotos?

(1) Measurement shows that the distance of the spring Apotripi from the 'Island,' as identified by Mr. Grundy, agrees more

P. 16. C. Leake, North, Gr. ii. 332 fol.

P. 16. Leake, North, Gr. ii. 332. Mr. tirnndy states that this spring is 16 stades com Platalah. Comparing this with the 12 stades of apotrips he writes, —'It is easy to imagine that a mistake of 4 states was made in a measurement of the distance by the cys alone; it is not so easy to suppose that the error amounted

to 8 states in a calculated distance of 20," Correcting the measurement as above the error comes to a choice between 6 and 8 stades,—an immaterial difference. He is symumbered also that the point to which the measurement is taken (the temple of Hera) is not yet established.

^{# 31, 271}

[.] P. 33.

closely with the statement of Herodotos than does that of his Gargaphia. At 10 stades from Apotripi we are in the centre of the Nesos; whereas, measuring from Leake's (and Mr. Grundy's) Gargaphia, we reach a point too far up the slope of Mount Kithairon, or else actually find ourselves outside the limits of the Nesos, in the direction of the town of Plataiai.

- (2) The uncertainty with respect to the situation of the Heraion renders an appeal to measurement here delusive. So far as it goes, the result seems to point to an exaggeration of the distance on the part of Herodotos.
- (3) Comparison of the interval separating the two springs from the Eleusinion is decisive against the claims of the well to which Leake and Mr. Grundy give the name of Gargaphia. Measuring from the Apotripi spring, 9½ stades bring us to the Chapel of St. Demetrios, 10 stades to the stream flowing along the S.E. side of the ridge on which that building stands.¹ On the other hand, measuring from Leake's Gargaphia, the Chapel and stream lie at a distance of only 4½ and 5 stades respectively.² Yet Mr. Grundy accepts the above-mentioned stream as the ancient Molocis and the scene of the final struggle.

We now turn to consider the position of the monument of the hero Androkrates.

Here we can supplement Herodotos in some slight degree from Thucy-dides. The 212 men who escaped from Plataiai during its investment in 428 BC, ran at first '6 or 7 stades along the road leading to Thebes, having on their right hand the herodo of Androkrates': subsequently they turned off to the right and fied in the direction of Mount Kithairon, towards Hysiai and Erythrai. We notice that whereas Herodotos speaks of a réperos, or enclosed domain. Thucydides calls it a howor, or monumental chapel. It must have been a building standing in the midst of a sacred enclosure, which was probably planted with trees. That this was indeed the case we learn from Plutarch, who describes the herodo of Androkrates as 'surrounded with a dense grove of shady trees.'

Few can have read the passage in Thucydides without having been struck by the apparent pointlessness of his remark as to the position of the

¹ Stream A5 on Mr. Grundy's map.

^{*} Yet Mr. Grandy writes (p. 23): "It will be seen on the map that the distance from the position of the Sparians near the spring which Leake (rightly, I think, as I have previously said) identifies with Gargaphia, accords closely with the distance gives by Herodorus."

Thine, iii. 24: οἱ Πλαναιῆς ἐχώρουν ἀθρόοι τὰν ἐι θήθαν ψέρουσαν ἀδὸν ἐν δεξεῷ ἔχοντες τὸ τοῦ ᾿Ανδροκράτους ἡρῷου, . . . καὶ ἐκὶ μὲν ἔξ ἢ

eurà avadiers el Maraufi the ent the Onshir Ludengar, étail descriébarres fessus the spès tò épot péseusus édès és Epúbau sal Trud sal aubéneres the épher diapréryongue és tas Abhras. Grundy (p. 10 fal.) quite accurately gives the route followed by the fugitives.

⁴ Pint. Arist. zi.; rò rov Ardpongarous hoffur. . Adoes runrier nel ovociar birdper reprezente.

monument in question. For if the heroon lay hard by the road, constituting a familiar landmark, it was surely needless to insist upon its relation to travellers advancing along that road in the direction of Thebes. A closer examination, however, removes this seeming pointlessness. In addition to the regular high road from Plataiai to Thebes (4), a man might cross the low hills in a N.E. direction 1 and so strike either the road that issued from the pass of Hysini (2), or the main road from Athens (1) issuing from the pass of Erythrai (Dryoskephalai). The remark of Thucydides, that the heroon stood on the right hand of the fugitives, thus turns out to possess considerable value. It fixes their point of exit from the town to the northern section of the enclosing lines, and the route of flight to a northerly direction, thus indirectly eliminating the possibility indicated above,-that the exit was made on the N.E. of the town and the line of flight continued towards the same point of the compass. The corollary from this is that the site of the monument should be sought between the line of the Plataiai-Thebes road and the line of the path that runs to the north-east; in other words, it is an entire mistake to imagine that the heroon lay quite close to the Plataiai-Thebes road, i.e. in the plain itself.

In addition to the passage from Thucydides, we are able to adduce one from Plutarch. It is true that, as history, Plutarch's account of the campaign is of small value. Nevertheless, the circumstance that Plutarch was a Boiotian, and the probability that he knew the ground, combine to give some importance to the few topographical details preserved in his Life of Aristeides. It is only by the adoption of a foregone conclusion that his testimony is brought into conflict with that of Thucydides, We refuse to subscribe to the verdict of Mr. Grundy 3 when he declares that one has to stretch the language of Plutarch until it cracks in order to reconcile his

topography with that of Thucydides."

In describing the movement of the allied army to its second position,

must refuse to asknowledge with Mr. Grandy, that 'it is evident that Thusydides understood the 'Hogor to be less than three-quarters of a mile from Plataen.' The unicome of this assumption is Mr. Grandy's hypothesis of a triple phase of the Greek second position. All that Thusydides says, is that the fleting Platzians ran about a mile along that read to Thorse which lay to the left, or west, of the monument; that they actually passed the monument is nowhere stated.

* P. 35 mot. An example of wrong method adopted by Mr. Grundy from Leaks, North, Ge, it 354, a passage which Mr. Grundy quotes with approval. Mr. Grundy makes much of Plutarch's failure to mention the seven. It will be seen that Plutarch is in the right: the situation of the seven is of no moment, as we might guess from the fact that not one of the Greek contingents over reached it.

In other words, taking the path shown by the Corinthians in their murch from the Heraion to the scene of action, as related in Herod. ix. 69: 5.5 vis drappy, and vis addards vis offerences from 100 vis less vis Adamptes. Such would not of course be the municipath from Platmal to Thebas, but it might well have been followed by the fugitives, whose objective was not Thebas, as it had the advantage of bringing them means the passes into Attics while avoiding the obviously dangerous route along the base of Kithniron.

The courts to telest from the purpose than to define exactly the preceding phrase the total to define exactly the preceding phrase the total to define exactly the preceding phrase the the state of the alternative path mentioned by me. It is ordinarily assumed that the fugitives passed the monument in question. For this opinion I can see so warmnt, and I

Plutarch writes as follows,- near Hysiai, at the foot of Kithairon, there is an ancient temple of Demeter and Kore, and there hard by was also the heroon of . Androkrates." The natural inference from this is that Pintarch imagined the Eleusinion and the heroon to have been fairly close together. Compare this with what Herodotos tells us about the enclosure of Androkrates 2,- and there they ranged themselves, nation by nation, close by the fountain Gargaphia and the sacred precinct of the hero Androkrates, partly among hills of no great elevation, and partly upon level ground.' What is there in this to support the double assumption on the part of Mr. Grundy a that Herodotes meant to give us the two actrones of the Greek line, and to indicate at the same time that the spring lay among the hills while the monument stood in the plain, i.e. on the left wing ! The conclusion to which both Herodotos and Plutarch point is that the heroon of Androkmtes and the Spring Gargaphia stood (within reasonable limits) in the same area. What this area was we have already ascertained for the spring. What it was for the heroon we have already deduced from the words of Thucydides. The two streams of evidence guide us to one and the same point for the site of heroon and Téperos. That site is marked by the modern Chapel of St. John crowning the height which rises immediately to the north of the Apotripi (Gargaphia) spring.5

What then do we conclude as to the second position of the Greeks? It occupied the depression which Mr. Grundy describes as running across the battle-field roughly from east to west. Here the allies had the advantage of a supply of water in the Apotripi (Gargaphia) spring,—the sources farther to the east would obviously also be in their hands; they were screened from the observation of the Persian main body; they were also protected from the cavalry as well as was possible anywhere off the actual slopes of Mount Kithairon. The Greek outposts would occupy the heights to the north of

³ Herod. ix. 25: ἀπικόμενος βὲ ἐτάσσοντο κατ' ἐθνεκ πλησίον τῆς τα ερήνης τῆς Γαργαφίης καὶ τοῦ τεμένεος τοῦ 'Αρδροκράτεος τοῦ ῆρωος διὰ ἔχθων τα οὸκ ὁψηλῶν καὶ ἀπέδου χωρίου. of Arch. vol. vi. 471).

^{*}P. 36 note: I think that the words of Rerodotas... can only mean that the winever was up the left of the Greek line, for the drides xapes can only be the plain between Platnes and the Thespian Asopas, on which, by the bye, according to Thucydides the relever must have stood.' Of p. 17: the repercy of the hero Androcrates, which Herodotus tells us was the other extremity of the line, i.e., on the left wing.' The same assumption is made by Stein (sete in Ice.) and Grote, (Hist. v. 19 note 2), but is rightly combated by Mr. Hunt (Amer. Journ.

^{*} The same conclusion seems to follow from Paus. ix. 4, 2, where the Tample of Elemainian Dameter, the prope of Leites and the Spring Gargaphia are apparently grouped together as contiguous to one another. We may note here that Mr. Grundy is altogether wrong in imagining (p. 34) the temple of Demeter here spoken of by Pansanias to be different from that mentioned by Herodotos in his account of the battle.

Taking into consideration what is told used the heroon by Plutarch in the passage already quoted. I see in the modern name Plutaral (=Plane tree), borne by the locality indicated, a traditional survival of the old Hellenio reperer. See Leake's map. The hors round the chapel have apparently disappeared, but the memory of the name romains.

⁸ D 16

The description of the position and its advantages, as given in Diod. xi. 30, 5 (fr. yap

the position, viz. the height on which the heroon stood, and the eminence lying to the east, between the heroon and the temple of Demeter.

The object aimed at by Pausanias in removing from Mount Kithairon is rightly stated by Mr. Grundy.1 The Greeks tried to effect a great turning movement by their left. They threw themselves upon the Plataiai-Thebes road, intending to force the passage of the Asopos and to cut the Persian line of communication. Mr. Grundy justly calls attention to the fact that the military capacity of Pausanius is universally underrated. For boldness of design, prudence in execution, and power of handling masses of men in the face of almost insuperable obstacles he deserves a high place in the list of Greek generals. Under the conditions of ancient warfare the undertaking was not as desperate as it would seem. In the absence of long-range weapons and arms of precision, it was perfectly feasible. Moreover the advantage in skill, discipline, and equipment was overwhelmingly in favour of the Greeks.5 The Persians might well have been driven castwards off their line of retreat. It was necessary, however, to take precautions against the Persian cavalry, which was massed on the Greek right flank, at a distance of at most three miles. A sort of echelon formation was therefore adopted, the Greek contingents being disposed obliquely from S.E. to N.W. across the roads leading from Plataini to Theber.

It is at this point that we begin to find the narrative of Herodotos interrupted and distorted by the national bias of his Athenian informants.

Here for the first time the historian directs our attention to the disposition of the Greek troops. He goes off at the word κατ'ξθνεα (c. 25) and introduces the quarrel between the Tegeans and the Athenians for the post of danger and honour on the wing (cc. 26-28 init.) The whole of the story must be excised, on the following grounds:—

(1) The left wing of the Greeks in the second position lay on iππάσιμος χώρος. It might consequently expect to suffer from the attacks of the hostile cavalry, as was actually the case (c. 40 πnd). How then reconcile the Tegean demand for station on the left wing with their previous reluctance (shared by the whole army) to support the Megariaus against the Persian cavalry in the first position? It is not sufficient to advert to the success already gained against the cavalry

is per raw Section realtopes benefit, in it considered in Associate termine the best person considered in apparentable, responsible to post of post and rais row rows as parelust, is clearly simply modelled upon that of Thermopylai, and cannot be pressed into service here.

river Nobel and the unrakes on its banka. Compare also the passage of the Granikos by Alexander.

¹ Pp. 22, 43.

The situation finds its counterpart in the battle of Blenheim. The Asopos did not constitute a more formidable obstacle than did the

³ Cf. Holm, Get. Hist. ii. 75 (E.T.): the Greeks were well-handled bodies of heavilyarmed infantry.

^{&#}x27;OK ix. 25 : 81' drider xuples; 81 : del eq. 'Asser'; 40 : 6 81 'Asser's 27200.

⁵ ir. 21.

- (c. 25) and to the confidence thereby inspired, for the service now demanded was much more than steadiness against cavalry.
- (2) There is no evidence to support the statement made, according to Herodotes, by the Tegeans, that post on a wing was their prerogative. Subsequently at any rate we find the Tegeans occupying precisely the station finally allotted to them on the field of Plataini, i.s. next to the Spartans themselves. This is the case in 418 B.C. at the battle of Mantineia, and in 394 B.C. at the battle of Corinth.²
- (3) How was it that the Corinthians, 5000 strong, did not raise objections if they were moved from the side of the Spartans, presumably a post of honour, in order to make room for the Tegeans?
- (4) The Tegean demand, if ever urged, must have been decided instantly by tactical considerations. A large compact body, like that of the Athenians (8000 in number), which was accompanied by the best light troops in the army (archers), was required on the wing, not the Tegean handful of 1500.
- (5) The story of Herodotos is irreconcilable with the words which occur in chap. 28,—'The place next to themselves was given by the Spartans to the Tegeans, on account of their courage and of the esteem in which they held them.' These words suggest that their actual place in the line was assigned to the Tegean hoplites in pursuance of some plan not given in Herodotos. The nature of the plan will clearly appear in the sequel.
- (6) The quarrel, if a genuine incident, must have occurred earlier than is stated by Herodotos. It must in fact have broken out at the moment of taking position on Mount Kithairon. For the evidence goes to show that there also the Tegeaus had not been posted on the wing.⁴

I Thue. v. 71.

² Xen. Hell. iv. 2, 19. And at that battle of Mantinela in which Epameinondas fell in 362 n.c. the Tegrans apparently stood next to the Thebans, i.e. the Isalers, in this case on the left wing. Cf. Diod. xv. 85, 2: Θυβαίοι δ΄ αύτοι μέν ένα τὸ εὐάνυμον κέραι ἐτάχδησαν, παραστάται ἔχειτες 'Αρκάδαι, τὸ ἐλ δεξιὸν παρέδωκαν 'Αργείοι κ.τ.λ. The point is that they stand shouldes to shoulder with the premier curps, whatever its position.

² iz. 28: xpoorxées dé aqu elhorro dordem al Temprifica vols Teyrétes en représ elveses sul aperifi.

In the second position the Magarises are third in the line, reckoning from the left, i.e. they stand next on the right of the Platziana and Athenians. This place appearently corresponds to that which they held in the lirat position: for there also they occupied the left centre (cf. iz. 21: Mayapier frace rays) rest of the centre (cf. iz. 21: Mayapier frace rays) rest, said appearance for rad xuples marries, said appearance placers rain x rad xuples marries, said appearance placers rains the left and left centre of the line). To this we ought to said the consideration that, if the Tegans had been us the wing in the first position, they would have urged that sa an argument here.

On these grounds we unhesitatingly reject the story of the quarrel. It is an Athenian invention designed to flatter Athens by means of a verdict put into the mouths of the best troops in Greece, at the expense of a contingent second to none in valour (c. 28).

In fact, the whole account of the marshalling of the Greek troops comes far too late in the narrative. Their arrangement in the line must have dated from the opening day of the campaign. With it disappears also the account of the marshalling of the Persian forces. There was no such formal parataxis as Herodotos depicts. The place of the account, which is closely modelled on the epic, is determined solely by artistic reasons, without reference to the logic of military practice. It is inserted precisely at this point because we have reached a crucial stage of the campaign: but the arrangement of the troops strictly belongs to an earlier moment, while the quarrel to which it is

represented as giving rise is a pure fiction.

Having thus adopted from his epic model a quite artificial scheme of events, how does Herodotos proceed to develop it ! Here we have the two armies ranged and described in battle array, but-nothing comes of it. Recourse is had to the sacrifices in order to explain the refusal of the combatants to finish the business, thus happily begun, in the true Homeric fashion," Herodotos is manifestly quite in the dark as to the real reason for their delay. His assertion of the only obstacle that would appeal to his hearers,—the persistent veto of heaven,-involves him in difficulties, as it directly contradicts the account given in chap. 41, which relates the conference of the Persian officers. For if Mardonios was so eager to fight," why had he not long ago given battle! It was surely not out of respect for the feelings of the Greek contingents fighting on the Persian side that he had conformed to the utterances of their soothsayers. Why should Mardonios summon his Staff only to insult it? The episode of the conference is inserted for no other purpose than that of enabling Herodotos to contrast dramatically, more suo, two antithetical solutions of the situation,—on the one hand decisive battle for good or ill, on the other the sound policy of waiting for disaffection and bribery to do their fatal work upon the national forces.

Next there follows the account of the midnight visit of Alexander of Macedon to the Athenian lines.⁵ This also is a story full of improbabilities, and without any claim to retention. How did Alexander escape recognition at the bridge-head held by the Persians? Or, if that is supposed to be no difficulty, how did his errand clude the notice of the Persian sentinels? If again these imagined him to be the bearer of despatches to the Greeks, where

impression of delay in the action.

The turn of expression in the concluding scateness (chap. 28) is designedly invidious,— Abscalars attractions after fixed to sipes free Aprasar. Who does not recognize the curl of the lip in this:

² Observe how skitfully the history of the various soothnayers (ix. 33-35 init.) is used in order to interrupt the angestive and to give the

<sup>λίχ. 37: Μαρδονίφ δὲ προθερισμείνε μάχης
δρχείν κόν δειτάδεκ δγίνετο τὰ Ιρά. Cf. chap,
Δ1: Μαρδόνωι παρεφμέκτες τῷ δόρη.</sup>

^{*} Partly also Herodotos dasign to give expression to his own apinton on the situation 2 ix 44 fol.

was the risk of which he makes so much? The reasons which he alleges to account for the Persian delay in attacking are very obviously put into his mouth by Herodotos himself in conformity with what he has already written in chaps. 36, 37. The assertion that the Persians found their commissariat breaking down is a manifest lie. The very emphatic and artistically well-managed revelation of his name on the part of Alexander was quite super-thous to Aristeides, who must have become familiar in Athens with the face, figure, and tones of the Macedonian king. Lastly, the whole point of the clandestine interview was to warn the Greeks of the intention of Mardonios to fight a decisive battle on the morrow. Yet, in spite of the alleged eagerness of the Persian general and the difficulties threatening his army, the following day passed without any serious attempt being made to justify the Macedonian's prognostications.

The excision of the nocturnal visit of Alexander necessarily involves also the abandonment of the disgraceful story contained in chaps, 46, 47. According to Herodotos, the near prospect of encounter with the Persians and Medes so alarmed Pausanias that he suggested to the Athenian leaders an interchange of position on the part of their respective divisions. The Athenians moved to the right, while the Spartans withdrew to the left in order to face the Boiotians and the other Greeks who fought in the ranks of the Great King. The exchange, however, was detected by the Boiotians, who at once informed Mardonios. The Persian troops were consequently transferred to the right of their line, so as to bring them once more in front of the Spartans. Pausanias then for the second time changed his position, and resumed his post on the right wing. Finally, the Persians returned to their old station, and the farce was brought to an end.

'No incident similar to this,' remarks Grote, will be found throughout the whole course of Lacedaemonian history.' He might safely have gone further and denied that any such incident ever did occur. From beginning to

end the story must be stigmatised as a slander.

(1) If the Spartans had contemplated the movement at all, for what had they delayed its execution? They could not have foreseen that they would receive timely warning of the approaching battle, nor yet that the Persian onset would be retarded long enough to enable the change in position to be made. It is evident that the proposition was only possible upon a very

1 ix. 45: 3ε Ελλήσων εξενείε ούτω έργου παράβολου έργουμαι ένδ προθυμίας.

⁹ ix. 45: δλίγων γώρ σφε δμερέων λείνεται words. How is this to be exceeded with the words of Astabans—ix. 41: *δ *είχων τὸ Θηβαίων, Ινθα σίτῶν τὸ σφι δσενητείχθαι πολλόν και χάρτην τοῦν ἐντοζογίων: † Cf. Rawlinson, iv. \$12 πολό 9: 'if is evident from their whole history that the commissariat of the Persians was excellently managed.'

On the consistent of his wisit to Athena as special envey from Mardonius, Herod. viii. 136. Alexander we there read had a compact of friendship (special) with Athena.

¹x. 45: νύν δι αι διδοκται τὰ μέν σφάγια διν χαίρειν, θρα ήμέρη δι διαφωσκούση συμβολύν κυιδεύθαι. Cf. chap. 42: δυήμηνε παραρτίευθαι τε τάστα και εθκρινέα παιδεύθαι &ς θρα ήμέρη τῆ διαδόση συμβαλώς δουμένης.

^{*} Hist. of Greece, v. 25.

general and decided feeling in its favour on the part of the Spartan hoplites; hence it cannot be set down to a sudden nervousness depriving Pausanias of self-command.

- (2) It was surely a strange preparation for the decisive struggle, fraught with such grave consequences for Greece, to march and countermarch the best regiments of the allied army in the face of the enemy.
- (3) What was the effect of the Spartan cowardice upon the mass of the Greek troops? The motive of the manoeuvre must, one thinks, have been as apparent to the rank and file of the contingents as to the Athenian hoplites.
- (4) How is it that we never subsequently hear a syllable of this compliment to Athenian arms?
- (5) The genesis of the story can be traced quite satisfactorily.

As the last of our long series of excisions we must abandon the incident narrated in c. 48. Mardonios sent a herald to the Greek lines with an absurd challenge, proposing that the Spartans and the Persians should fight on behalf of all. It is obvious that if the attempted change of post is cut out it must carry with it the challenge. It is modelled upon similar scenes in Homer; but it is also not uninfluenced by reminiscences of previous history.\(^1\) Apart from this, the narrative is intrinsically unsound; for how do the words 'puffed up by the empty victory'\(^2\) square with the statement that nothing more was attempted or achieved against the Greeks than the usual harassing attacks of the cavalry\(^1\) We expect some deed of arms to redeem the doughty resolves of chap. 41.

Now that the ground has been cleared of the excrescences due to Athenian light-hearted manipulation of history let us resume the interrupted story of the Greek movements.

We have surmised that the movement of the allies to the second position was based upon something more than the desire merely to obtain a better supply of water; for the abandonment of their main line of communication and the greater exposure to the Persian cavalry on the lower ground were attendant drawbacks too serious to be counterbalanced by the single advantage named by Herodotes. Pausanias had determined to make a dash, across the Asopos by the road which ran directly from Plataisi. The second Greek position represents the army in the act of carrying out this manocuvre, It is disposed obliquely across the field, the left wing leading upon the Asopos.

Cf. Hom. H. iii. 99 fol. Combat of champions was unsuccessfully used to decide the claims of Sparta and Argos to the Thyroutis, Herod. i. 82 (Time. v. 41).

ix 49: 4 55 repixagh; yerspieres and draugdels 40x09 view frace the Texas dri role "Eddgran. It it is argued that the cavalry

onest was designed to introduce the infautry attack, why did that attack not ensue in diecourse? Confessedly (seconding to Herodotes) the cavalry were more successful this day that ever before,

^{*} See Note A on the Asopos of Heredotes.

Why then was the offensive designed by the Spartan general not developed beyond this point; and why do we not find in Herodotos a

syllable in allusion either to the scheme itself or to its collapse?

The first difficulty is solved by reference to the position of Pausanias. The army under his command consisted practically of three brigades constituted respectively by the Spartans (with whom we must reckon the Tegeans), the Athenians (along with the Plataians), and lastly the general body of the allies. The loose structure of the Greek national levy made unanimity in sentiment and cohesion in action impossible beyond certain narrow limits. Hence the delay in accomplishing the passage of the river, a delay that ruined the scheme, and all but ruined the national cause.

The latter part of our question is answered by reference to the ignorance of the historian's informant, who was quite in the dark as to the strategic ideas of the Greek commander-in-chief.

Another cause also is at work. It must be remembered that the campaign was a national affair, and it was undoubtedly a point of national honour to present it in the most favourable light. By tacit general consent the battle never became the subject of discussion. An analogy may be found in the medism of the Delphic oracle, which yet, by a species of national self-deception, did not forfeit its claim to Hellenic respect, in spite of its failure in the hour of trial. So in the case before us, no Greek would have been so unpatriotic as to confess that dilatoriness and cowardice on the part of the national army had nearly proved fatal to Hellenic freedom.

We must also bear in mind that our knowledge comes almost entirely from the Athenians, and only from a certain section of them, so that we know scarcely anything of the views current outside Athens.² In spite of Athenian reticence, however, we clearly see that hesitation on the part of the Greek force, and more especially on the part of the Athenian contingent, which was in the van, enabled the Persians to divine the intentions of the Greek commander, and gave them time to perform a lateral movement in order to cover the Plataini-Thebes road. Their clouds of skirmishers then effectually prevented all approach to the Asopes, and the favourable moment was lost.⁸

This brings us to the origin of the story, already condemned, which is so discreditable to the Spartans.

The Athenians, being on the left extremity of the line, which rested on the Asopos, would cross the river at the head of the column. After crossing

lining the Asopos banks are regarded by the tradition as designed to entice the Greeka across the river (chap. 40: pexps pir 7ap res "Asserti érations of Baybapos, respectation of Eldérary battle, not the touches of a main versed in the actual experiences of the field.

¹ Cf. Holm, Gek. Hist. H. 60 (R.T.).

² Can wa, for example, believe that the Athenian version of the retirement of the centre to the Heraion (ix, 52) passed current among the states whose troops were implicated in that proving at 1

^{*} ir. 49 : loundarror 51 Ard roll 'Aranol. By a strange inversion the Persian skirmishers

they would wheel to the right, in order to check the Persian advance along the bank to hinder the passage. The Spartans, who were posted on the extreme right, formed the rear-guard of the column, and covered the crossing from the Persian cavalry, a most dangerous and responsible position, and one that explains why the valiant Tegeans were associated with the Spartan hoplites. When the whole Greek force had made good its footing on the far side of the Asopos, the Spartans would naturally form the left wing of the new line. It is on this reversal of position,—one suggested, but never actually realized,—that the Athenian misrepresentation is based.4 It contains this much of truth, that the brunt of the fighting, until the Spartan rear-guard effected its passage of the river, must have fallen upon the Athenians, who were required to sustain the whole weight of the Persian attack upon the head of the column.3 There was surely honour enough in that to have rendered superfluous the sorry attempt to cast shame upon the best troops in Greece, the more so as it was entirely due to the Athenians' own want of resolution that the Spartan valour was not put to the test contemplated by Pausanias.

The warp of the tissue of these fifty chapters is the green thread of Athenian jealousy of Sparta. It is a highly suggestive fact that we find both the Spartans and the Tegeans,—who shared the honour of the final victory,—more or less skilfully represented in Herodotos as inferior to the Athenian troops. And in each instance we have been forced to the conclusion that the episode is false and due to Athenian vanity. The cloven hoof is unmistakably displayed in the account of the events following the challenge feigned to have been thrown down by Mardonies. With what painful circumstantiality are we assured that it was to the Spartans, and the Spartans alone, that the thanks of the allies were due for the destruction of the Spring Gargaphia is as though to give point to the alleged reluctance of the Spartans to face Persian infantry by instancing this, probably equally fictitious, failure to stand against Persian cavalry. If these things were done in the green tree, what

1 1χ. 28: προσεχίαι δέ σφι είλοντο δοτάναι οἱ Σπαρτιβται τοὺε Τεγνήται κοὶ τιμῆς είνεκεν καὶ ἀρετῆε.

2 Possibly also the Persian change of position, from the left to the right wing, is a germine incident: the change might very probably be actually made in order to meet the threatened advance of the Greek left.

"This is the truth underlying the garbled account in Flutarch of the grambling on the part of the Athenians against Pausanias. They thought that Pausanias carried it with a partial and high hand in moring them up and down, like so many Helots, at his pleasure, to face the boldest of the enemy's troops. This surely alludes to the disposition of troops provious to the crossing of the river. Plutarch's sequel (the speech of Aristeides and consequent consent of the Athenians to shange their position)

is merely again the self-landatory Athanian tradition.

* Contrast the reiterated jubilation found in our Athenian sources over the victory at Marathon with the silence observed with regard to the brilliant schievement of the Spartana and Arkadians at Platniai.

2 Ix. 40 Four μès de marà την πρήτην Λακτδαιμότιοι τεταγμένοι μοῦνοι. Hore again the phrasing is used with set purpose.

"Here I may say that I see no sort of evidence for Mr. Grundy's laboured hypothesis of three 'developments' of the Greek second position. His theory leaves him with 100,000 mmu implication a single hill, out off from water, harassed by cavalry, and with morals at zero point. Surely this 'development' could have only in tragedy.

would have been done in the dry | Recall also the invidious expressions used with reference to Spartan duplicity, so different from the manly and straightforward, withal modest, character of the Athenians,1 and the reference to the by this time threadbare theme of Spartan cowardice, so glaringly in contrast with the calm steadfastness of conscious valour that glowed in the breast of the Athenian hoplite.2 Nav. the Spartans must be flouted even at the price of complimenting an almost equally odious people. Therefore is it recorded that the Tegeans charged the Persian rampart of shields before that the Spartans advanced a foot 3; far be it from the Athenians to see any other city deprived of its meed of honour for the sake of other than-themselves! Lastly, what prominence is given to the Athenian share in the assault on the fortified camp.4 Well might this be so, else were the hoplites of Athens like to have been but sleeping partners in that day's achievements. Here as so often, the Lakedaimonians were baffled by the combination of barricades and stout defence. Not until the invincible amalgam of Athenian valour and resolution (aperi) και λιπαρίη) was applied could any impression be made on the fortifications. Into the breach there rushed, not the Spartans, -alas for that national defect of ponderosity, -but the Tegenns.

With the end of chap. 49 there comes a change in the nature of the Greek operations,—a change from offensive to defensive tactics. The allied army, having lost the opportunity of turning the Persian position, is reduced to its old attitude of covering the approaches to the Peloponnese, and of waiting for Mardonios to take the initiative.

The real objective of the movement of the Greeks to the 'Island' was the recovery of their line of communication, upon which they had then but precarious hold. They were, it is true, not driven entirely off it, for, as Mr. Grundy points out, the Plataiai-Megara pass (3) still remained in their hands. Nevertheless, according to Mr. Grundy, the character of the most westerly pass is such as to render it impossible to supply satisfactorily the wants of one hundred thousand men through this channel alone. That the occupation of the eastern passes by the Persian advanced posts had begun to tell upon the Greek forces may readily be believed, but Herodotos himself represents the determination to fall back as due primarily to want of water, in consequence of the failure of the Spartans to protect Gargaphia.

ix. 54; ra danedamenter operhears in Alda specificus sal Sada depórtus. For Athenian mock modesty, see chap. 46 and.

¹x. δδ: 'Αθηναίοι δε ταχθέστες βίσης τὰ Εμπάλικ ἡ Λακεδαιμόνιοι οἱ μέν γὰρ τῶν το ἔχθων ἀντείχωντο καὶ τῆς ἐπωρέρε τοῦ διθαιρώνου, ροδεόμενοι τὴν Ἱκνον, 'Αθηναίοι ἐξ κάτω τραφθίντει ἐς τὸ πεδίου.

^{12. 62:} προεξαναστάρτες πρότεροι al Τεγνήται Ιχώρουν ές τοὺς Βαρβάρους.

^{*} ix 70: Ter pèr yèp àrhaur et Abyreios, of E habrauro nal radah «dése elzor rur daxebaposter Care obs ériarapéres reixogaxéeis, às

dé syn af 'Adminio sposhidor tédos de ápetil re sal desaply ésélhyese 'Adminio rod rélyeon n.c.d.

^{*} This 'ball-dog obstinany' is precisely the quality usually attributed to the Spartana. At any rate Thurydides recognizes this,—v. 73: xperious rate udgas sal Sedaleus ra pateur routeras.

See Note B for the chronology of the events proceeding the battle of Platsial.

P. 32.

^{1 (}x. 50 : are red re boaros orepnybelage ein: Orparific.

This repetition of the water difficulty we should be inclined to reject here again, at any rate as furnishing the ground of the retirement. For, wherever we place Gargaphia, the army had still the other spring at its command; and Herodotos admits that at the foot of Mount Kithairon, ten stades or so in the rear of the position, water was abundant.\(^1\) There was also the water supply of the town of Plataiai itself.\(^2\) For surely the Greeks ought not to be imagined as cut off from Plataiai and the base of the hills, and hopelessly surrounded by the Persian horsemen. There cannot have been any grave difficulty in supplying the needs of the troops in line on the Spring Gargaphia,\(^3\) as the country between that position and the mountain is by no means difficult. The stress laid upon the deficiency of water, if not due to the character of the historian's informant, has its origin in the desire to bring in the Spartans as ultimately responsible for a retrograde movement primarily caused by the Athenians themselves.

The main features of this last act of the drama, as given by the Athenian tradition, are as follows.

The council of generals determined to execute a night movement to the rear, the so-called 'Island' being given as the rendezvous of the contingents. It was further resolved that, on the same night, half the army should be detached eastwards to Mount Kithairon, in order to extricate the commissariat train blocked up in the pass. When the appointed hour arrived the centre fell back, -not to the 'Island,' i.e. 10 stades, but 20 stades, finally taking post at the Heraion, which lay 'in front of' Plataiai. Next, the Spartans were ordered to retire; but the irrational obstinacy of the Lochagos Amompharetos, who construed the movement as a flight, detained the Spartan contingent all night. Meantime the Athenians, suspecting the Spartans of a desire to play them false, remained in position on the left awniting definite instructions. As day dawned, Pausanias at last abandoned his recalcitrant captain to his fate, and set his troops in motion 'along the line of the hills.' The Athenians also retired, by way of the plain. After marching 10 stades Pausanias halted for the Pitanate regiment under Amompharetos on the stream called Moloeis, near a temple of Eleusinian Demeter, in the district called Argiopian. Simultaneously with the appearance of Amompharetos the Persian cavalry swooped down upon the Spartans and Tegeans, to be followed soon by the Persian infantry.

Such is the narrative of Herodotos, deceptive in its simplicity and apparent straightforwardness. Closer examination reveals in it the features with which we have become familiar. On the one hand Herodotos fails to appreciate the significance of the various movements of the forces, on the

¹ ix. h1: Το τούτου δά του χώρου έβουλούσωντα μεταναστήναι (κε. thu "Inland"), Γνά καί βδατ: Τχωύι χράσθαι άφθόνφ.

² Assuming that the town had other sources of supply than the aprings commanded by the

For what other service engaged the activi-H.S.—VOL. XVIII.

ties of the Helots and light troops in attendance on the hoplites? They were apparently of not the slightest use against the cavalry. We may remark here, by the way, that no one can take seriously their numbers as given by Herodoros.

^{*} Az. 50-57.

other he has incorporated all that national vanity, with the double object of

glorifying Athens and disparaging Sparta, had invented.

Up to this point in the story the central brigade of the allies has escaped Athenian calamny; its share in events is shadowy, but not actually disgraceful. Its turn has at last come. Although the troops of the centre had borne the heat and burden of the day that proved so disastrous to Spartan prestige, yet now, under the cloak of night, they flee in headlong haste, eager only to secure themselves against the dreaded cavalry. Mark, however, the point wherein the narrative halts. In spite of their anxiety to put themselves beyond the reach of the Persian horsemen, the contingents of the centre do not seek shelter in Plataini itself nor on the rocky slopes of Mount Kithairon (which ultimately became their refuge 1), nor yet on the 'Island,'—a position admittedly outside the sphere of cavalry operations,2—but they take up their station, apparently in good order, 'in front of the temple, which was itself in front of the town."

There are several possible sites for the Heraion.* The most probable one stands within the circuit of the existing enceinte of Platniai, just to the east of the akropolis. The question of the site is of far greater moment than is the identification of the 'Island,' which was in fact never reached by any of the Greek force at all. Its importance lies in this, that, knowing the exact site of the temple, we should be able to decide what amount of credence should attach to the Athenian account of the conduct of the troops composing the centre.

That account can hardly be accepted as it stands. It will be observed that the suggested site of the Heraion lies at no great distance from the tract of ground which is convincingly identified by Mr. Grandy as the Island. The Heraion may well, therefore have been actually the position which the central brigade was instructed to occupy. Its proximity to the town is an important feature: it was surely of some moment for the Greeks to retain possession of Platsini, which was a fortified place commanding the entrance of the pass to Megara. In order to carry out the project of Pausanias it was essential to dispose the various brigades in such a way

When cut to pieces by the Theban cavalry, in. 69.

³ ix, 61: de robrar 8h rox xupor (m. the 'Inland') éffancebourro peraragripus Tra., al luxdes apéax phospolaro, Zuvey sarefté éderas.

^{*} IX 52: of hi he harmfore share, before the liver sphe the Harmfore share, peliperes hi investment in the Harmfore share, peliperes hi investment in the harmfore the repetition focuses property were always designed to give the impression of paniostricken retreat. Associate and his real to Believ forparenthiners a.r. h. Apparently the town of Pistalal is not approached more marry than is indicated by the place of the temple. Of course only a small fraction of the centre could have been accommodated within the lown: the point is that so far

as we can see not a man betaken himself thither.

* See the American Journ. of Arab. vol. vi.
(1890) p. 469.

^{*}Yot the identification of the 'Ichmi' is generally made the touchstone of theories of Plataian topography. This misconception of the comparative value of the two points is strikingly exemplified by Mr. Grundy, who finds it possible to discuss the operations without reference to the site of the Herzien, other than its incidental mention in a sentence or two on p. 17.

⁶ About eight stades, or one mile, on Mr. Grundy's map.

is. 52; Agoryou uphe the Mautaches ubber ... iul th' Apaion. to be upd the udule but the Mautaches,

that they might support one another. The new post of the quandam centre, near the Hernion under the walls of Plataiai, was well chosen in this respect, to check any attempt on the part of the Persian cavalry to creep along the side of the mountain and endanger the operation in which the Spartans were about to engage.

That such was the intended function of the Greek centre appears from its behaviour during the conflict. Herodotos tells us I that the Greek right was already pushing the enemy off the field when news was brought (ayyex-Aeras) to the centre at the Heraion that the fight had begun, and that Pausanias was gaining the victory.' The words of Herodotos are hero significant,-not in respect of any inference that may be supposed to be deducible therefrom as to the site of the temple, but as indicating that Pausanias deliberately detached a member of his force for this special service, and also that he knew exactly whither to send his messenger. Here again Herodotos has missed the real import of the fact. The message of Pausanias was nothing less than an urgent summons for an advance. The sudden development of the Persian attack caused a rapid modification of the combinations of the Greek general; and, failing support from the 'Island' (upon which the Athenians ought long before to have taken up their position), a mossage was despatched to the centre, then lying uselessly at Platnial, to harry it up in reinforcement. It is in the highest degree worthy of notice that the centre in response at once splits up into two sections. Corinthians and their companions marched off through the hills, while the Megarians and the Philasians with their comrades proceeded by way of the plain. Now, in the second position, the Corinthians stood alongside of the hoplites of Tegen and Sparia: the Megarians were ranged shoulder to shoulder with the Plataians and the Athenians. It is pretty clear from this that the two sections of the centre 2 hastened to join their respective wings,in accordance with the orders transmitted from the communiter-in-chief; it was no pell-mell scramble to be in at a battle already decided without them.

With regard to the centre of the Greek line all is intelligible and free from complications. In opposition to the received view I maintain that it is almost entirely in connection with the left wing, i.e. the Athenians, that difficulties arise. The Athenians were evidently hard put to it to render an

¹κ. 60: ἐν δὲ τοῦτφ τῷ γυσκένψ φόβφ ἀγγέλλεται τοῦσι ἄλλαισι "Ελλησι ταῖσι πεταγμένρισι περί τὸ 'Ηραῖον καὶ ἀπηγενιμένουν τῆς μάχης, ὅτι μάχη το γέγους καὶ πικῷεν κὶ μετὰ Παυσανίκο κ.τ.λ.

And, again, these sections correspond in strength to the wing. The right wing (Lake-datmonlans and Tegorns)=11,500. The left wing (Athenius and Plataiana)=8,600. The united contingents of the senter annaboved 18,600. If we take the expression in ix. 62 : el hapi Meyapéas re sai #Anarious to gave the two extremes of that section, and thus to include the contingents standing between those of

Philons and Megara, we shall find that it numbered 7,800 man. The remainder of the centre was 11,300 strong; the numerical strongth of the central sections thus bearing an appropriate relation to the strength of the respective wings. The two sections also contain a nearly oqual number of contingents. I think that the mention of the Philanane is really meant to indicate the point of cleavage of the centre, as above suggested.

³ As it is represented in ix, 69 r of δi acodcurrer raws obliga κόσμος ruxθeres κ.τ.λ. Lower down, the Thibans capy the Megarians ένειγομένου υὐδένα κόσμος.

explanation of their action during the retirement to the 'Island.' It is in vain that with malice prepense meaningless prominence is given to their own march through the plain, while the Spartans fell back through the hills.1 Meaningless, for this reason; given the position and the objective point of the wings, no other route than that which is so invidiously described by Herodotos is possible. The map furnishes the unanswerable proof of the disingenuousness of the narrative. The historian tries to fasten upon the centre the imputation of deliberate betrayal of the wings; 2 but what of the Athenian disobelience to orders? For the Athenians also never reached the 'Island.' Could anything be more transparently false than the reason assigned by the Athenians themselves for their breach of discipline, - knowing that it was the Spartan temper to say one thing and do another, they remained quiet at their post ' 12 Although Pausanias had issued the order for the troops to fall back, an order which he knew had already been obeyed by the centre, one which he had a right to believe was likewise respected by the left wing, we are asked to allow that it was possible for him to remain in position unsupported, for no other reason apparently than to delude the Athenians at the cost of his own destruction and the ruin of Greece, The Sporton king appears in the Athenian tradition as a simple furceur. Amid all the contradictions in which the narrative of the campaign abounds no sentence is so preposterous; none exhibits in a more baleful aspect the inherent vice of the Athenians. The lie is inserted in order to conceal their own failure to gain the rendezvous appointed by the council of generals, a council in the deliberations of which Aristeides the Just had a voice. It was necessary in 479 a.c., and still is necessary, to ask how it came about that the right wing found itself without supports when the attack opened against it.

The root of the distorted version of the retirement of the army to its third position is the malicious persistence of the Athenians in depicting the movement as a flight instigated by the Spartans. Hence they were at pains to minimize their own share in it, oblivious of the fact that in avoiding this feigned Scylla they fall into the more terrible Charybdis of confessed

disloyalty and insubordination.

The desperate efforts of the Athenians to represent their conduct as magnanimous would be amusing were it not that their tradition has won its way to credence as sober history. The bonour of the victory belonged solely to the Tegeans and the Spartans. It was a bitter pill to swallow, but Hellas could not be befooled on so patent a fact; all know that the Athenian hoplites had not contributed a single blow to the overthrow of the Persian infantry in

¹ ix. 56: 6 Παυσανίην . . . άπθην διά τῶν κολανών τοὺι λυιποὺν πάνταν . . . "Αθηναίοι δέ τοχθέντει ξίσαν τὰ ξωπαλιν ἡ Δαυσδαμένου. ψί μέν γὰρ πῶν τι δχθων ἀντιίχοντο καὶ τῆν ὑπαρέψε τοῦ Κιθαιρώνου, φοβιέμεναι τῆν Ίππαν, "Αθηναίοι δι κάτω τραφθέντει ἐν τὸ πεδίον.

[&]quot; IX. 52: Fredita depoterts of wallof dranhadrones, is also the xipow is the surveylers she from frontes n.t. A. Of the expressions used

iu the lictitious missage from Pausanias, ix. 60.

1 ix. 6t; 'Αθηναίοι δε δνοίευν ναιάδε' είχου άπρόμαι σφέσε αύτουν ίνα δνάχθησαν, ένιστάμενη τὰ Απανδαιμονίων φρονήπατα ών δλλα φρονεόντων καὶ δλλα λεγόντων. Δε δε έκινήθη τὸ υπραπόντεδος, ένεμκαν αφέων Ιαπέα δφάμενδε τα εί πορούνοθαι έπεχειρέσειν οί Συαρπήται, είτε καὶ τὸ παράσαν μὰ διανοσύνται άπαλλάσσουδαι, έπείρεσθαί το Παυνανίης τὸ χρεὸν είη ποιένε.

the decisive struggle. The efforts of the Athenians were perforce confined to accounting for the damaging fact and turning it to the national honour. The Theban attack at the head of the second Persian column came in here very opportunely to prevent their carrying aid to the Spartans, who were beset in spite of their pusillanimons concern to be secure. What, however, is the value of the text of the Spartan message which bulks so largely in the narrative? There is an evident anxiety to magnify the Athenian arms on this day: yot their victory over the Thebans is not so decisive as to drive their cavalry from the field.

From what I have written, my conception of the plan adopted in the council of generals is easily gathered. The Greek force was instructed to retire by brigades,-the centre to the Heraion, covering Plataiai and the 'Island,' the Athenians to the 'Island' itself. These two divisions were designed to support the crucial element of the entire movement, viz. the Spartan advance to the relief of the convoys beset in Mount Kithairon. To the right wing, composed as it was of the flower of the army, this difficult and dangerous task was appropriately committed. In the new position, the old central brigade would form the extreme left, under the shelter afforded by the Heraion and the fortifications of the town: on the other hand, the troops of the new centre, being nearest to the Spartans, might anticipate heavy calls upon their alacrity and courage, so that they were judiciously composed of Athenians. As in the second position, so in the third Pausanias made the hest possible distribution of his forces. The Spartans themselves were designed from the first to advance straight from their old position, near the Spring Gargaphia, to the pass. The locality in which the final encounter took place proves this, for it lies off the line that must have been followed by troops falling back directly upon the 'Island,'

What, then, caused the break-down of this scheme? To this question Herodotos has a ready answer. The obstinacy of the Spartan captain who refused to withdraw from his post was the prime cause of the collapse of the plan. His ill-timed punctiliousness broke the Greek force into its component brigades, which at the moment of contact with the enemy found themselves sundered by no inconsiderable intervals. The different units had all but lost touch of one another when the Persian squadrons held the Spartan division fast for the attack of their supporting column.

¹ iz. 67 : Βοιωτοί 'Αθηναίσιου εμαχέσαντα χρόνου έτε σεχνών, οί για μυδίζουται τών Βηβαίων, ούται νέχον προθυμένη εύκ όλεγην μαχόμεροί το καί ούο έθελοκακέστους, ούτω Δυτιτ τρηχόσιοι αύτών οί πρώτοι καί δριστοι ένθαϊτα Επικον όν' Αθηναίων. Herodoton has taken cure

in a previous chapter (ix. 40 cod) to prepare for this by magnifying the courage of the Thebana in leading the cavalry charges. Whose the Athenians occoperate in the assault on the fore (ix. 70) sires by laxuely bylevro recognizing and xelect (x1 rollers).

Which cuts to pieces the Megarians and Philasians on their march to the scane of action, iz, 69.

^{*} ix. 50 i of των Έλληνων στρατηγοί . . . συνκλοχθήσαν . . . σαρά Παυσανίην κ.τ.λ.

The story about Amompharetos is perhaps one of the most difficult points in the narrative of the operations preceding the battle. We may,—and this is the least satisfactory course,—accept the story, and compare the attitude of Amompharetos with the refusal of the polemarchs Hipponoidas and Aristokles to execute a factical movement at the battle of Mantineia on the orders of king Agis.¹ Or has Herodotos here incorporated a regimental tradition of the Pitanates, one derived from his Pitanate friend Archias ¹? I profer to account for the origin of the story in the following manner.

The Spartans did not evacuate their position without taking the precautions demanded by the situation. Amompharetes and his Loches were detached to occupy the crest of the ridge which concealed the Spartan lines: on the ridge stood the monument of Androkrates. The object of this was twofold,-to observe the Persian cavalry, which would soon resume its daily task of keeping in touch with the Greeks, and to retain as long as possible the semblance of the Greeks being in position.2 Amompharetos stuck to his post to the last minute that it was prudent to do so, and then rejoined the main body at a walk's; the honour of a Spartan would not have permitted a less leisurely pace. The main body had come to a halt for him and his news a little over a mile in advance. His arrival just in time, with the report that the Persians were moving, enabled the Spartans to change front and to form for action in a favourable position on the slopes at the head of the stream Molocis and the Argiopian region. Amompharetos is painted by Herodotos as an obstinate fool, the rival of his commanding officer in On the contrary he was an officer conspicuous even among Spartans for intropidity, one whose tried valour gained for him the perilous but honourable task of screening the retirement of the main body. undeserved was the prize he won for bravery in the presence of the enemy," a prize which the Spartan purchased only with his life. Possibly there is this amount of truth in the story of his refusal to retire, that he may have been prominent at the council in urging the rejection of the combination which Pausanias tried to effect. The parenthetical remark of Herodotos, that

* ix. 57 : Δυαλαβόντα τον λόχον να δέλα ήγε Βέδην πρός το άλλο στίφος.

I Thue, w. 71. But there the charge had already begun, and the movement may wall have been impracticable. The fact that a court martial condemned the two communican to banishment proves nothing.

² For Archias see Herod, iii, 55. We need not enter here upon the voxed question of the Pianuate regiment, the existence of which is denied by Thuc. i. 20,

^{*} So Herodotes (ix. 58 (ast.) correctly distinguishes between the report brought to Mardonies by his scouting cavairy (as drifters roles "EAApput droughout ord rivers) and the avidence of his own syes (all is the Kaper lephon). The former refers to the discovery by the cavalry of the true state of the case, notithatanding the presence of the Greek output

on the hill; the latter indicates that by the time Mardonies made his inspection the rearguard had withdrawn, and the heights upon which the Greek sentinels had been for some days visible were deserted (cf. freel adjust table applicates applicate).

^{&#}x27; Ibid. το δε άπελβου όσον το δένα στάδια άνθματα του 'Αμομφαράτου λύχου, στρὶ ποταμέν Μολόεντα Ιδρύμενου 'Αργιόπιδε το χώρων καλεδιμενον, τὰ καὶ Δήμητρου Έλευσικής» Ιμόν δυται. ... καὶ οῖ το ἀμφὶ τὸν 'Αμομφάρετου παρογίσευτό σφι, καὶ ἡ Ιπτου ἡ τῶν Βαρβάρων προσεπέντα κάσα.

^{*} ix. 35 : 6 66 (m. Paumnien) parrépenso nal ad preripen nucleur éneiros.

⁷ ix. 71.

Amompharetos had not been present at that council, is scarcely credible in itself and has the air of a makeshift to get round what the historian himself felt to be an improbability.

The retirement of the various divisions of the army cannot have been attempted simultaneously. It was an operation of much delicacy for an army of nearly 100,000 to fall back over hilly ground in the dark, especially if we accept an pied de la lettre the account of the demoralisation produced in the Greek force by the incessant attacks of the cavalry. Not until the centre was on the march did Pausanias give the word to his own brigade,* The retirement was evidently intended to take place by divisions. It was timed to begin at the second night-watch, i.e. about midnight. The sum total of the retiring centre, according to Herodotos, was about 39,000 men. battle was fought in the month of July-August; when day begins to break between half-past four and five. A simple calculation from these data brings us to the conclusion that the manocuvre could not have been executed within the time allowed. The Athenian division, deliberately or not, made the mistake of not marching first; they were consequently delayed by the chumsiness and unwieldiness of the centre, and the Spartans themselves were surprised by daylight as they advanced towards Mount Kithairen.

The failure of the scheme must be traced to the tactical unskilfulness of the Greek commanders. In the battles of the pre-Alexandrine age in Greece nothing is more striking than the absence of tactics, and this in spite of the brilliant success attending the combinations of the few tacticians who passed meteor-like across the horizon of Hellas. In 479 B.C. it is almost too early to speak of tactics in connection with Greek armies: their movements are still somewhat haphazard and capricious. Pausanias set his officers a task beyond their powers. They had succeeded in the advance from the first to the second position; but in the retrograde movement, with all its complications of direction and its nice adjustment of the divisions to the work of mutual support in the offensive designed by the Spartan general, the commanders of the contingents utterly failed. The army was split up into separate bodies.

¹ ir. 53: εθάτραζέ το δρίων το τοικόμονου, δτο

[&]quot;The following also occurs to me,—that Athenian wit gave this turn to the facts in order to axhibit a quasi-comic reductio ad absording of the beasted Spartan principle as faid down by Demaratos, Herod. vii. 104: "Law forbilds them to flee in battle, whatever the number of their foca, and requires them to stand firm and either to conquer or to dis." The Athenians amed have been as warry of hearing this as the Spartans themselves were of hearing about Marathon (Thue, 1, 73).

Recent Greek history affords an instructive

^{4 (}x. 58) Παυσανίη: δε δρίων σφέαι άναλλασσομένους δε τοῦ στρετοτέδου παρήγηνέλε καί

veir. Annehamorlami.

ix. 51; dredo rie rourde f beurfon podanh, is he ph ibilare al Ofpan Hopensteiner and orders despression rapides out of leafre.

ix. 56: robs 86 free draspirautrors ands turrobe has naturally flare.

It is instructive to unite that it is precisely when in conflict with foreign troops that taction and strategy are exhibited by the Greek generals, in the earlier period of Greek history. For the whole principle governing such contests was quite other than that governing the intertribal wars. Home the lattles of Marathon, Salamis, and Platsial stand agars in interest in this respect. It is a difference that is not explicable merely by reference to our fuller knowledge of the details of the operations.

but the rare steadiness of the men retrieved the blunders of their leaders. Plataiai also was a 'soldiers' battle,'-one of the finest ever won by the Dorian spear.' 1

W. J. WOODHOUSE.

NOTE A.

On the Application of the Name Assym in Herodoton

Mr. Grandy (p. 18 fed.) finds in the use of the name Asopos the 'real difficulty' in the account of the operations at Plataial, and suggests that its solution lies in the assumption that Herodotos used the name in two senses :-

- (1) The main stream of the Asopos, called by Leake the Thespian Asopos.
- (2) The stream that takes its rise in the Apotripi spring (stream A1 in Mr. Grundy's map : al Leake, North. Gr. 333).

He bases his opinion upon the following arguments:-

- (1) The Greek second position was defined by the Spring Gargaphia and the monument of Androkrates, which lay in the plain "less than three-quarters of a mile from Plataca.' Yet, at the end of chap. 39, in speaking of the same position, Herodoton uses the words obres als the raxbleres bel to 'Aauso berparenedeborra.
- (2) The expression just quoted is followed in the very next sentence (chap. 31) by the words raphear, rudoussus ross Eddapeas eleat de Adarmifet, na abrol dal ros Acurde TOP TROTT MOSTOL

From this, Mr. Grundy concludes that the reference in the first passage is to the tributary A'. and that the addition of the words row radry Morra, "not evidently referring directly to the Azopus at the end of chapter 80, but to the words is HARRADEL, leaves no reasonable doubt that the stream here mentioned is the main Asopua,"

In chap. 40 (pages pie yap row 'Assesso derhisar al BapBapes a.r. A.) the reference is again to

the main or Thuspian Asopos.

Reading further (p. 28), we find that this hypothesis of a twofold signification of the name has apparently been prepared in order to surmount the difficulty presented by the statement in chap 51, that the 'Island' lay 10 stades 'from the Asopos and Gargaphia' (4 56 dorr ext re-Ασωτού και της κρήτης της Γαργαφίης, έπ' ή έστρατακεδεύουτο τότε, δέπα σταδίωε άπέχουσα).

We must altogether reject Mr. Grundy's suggestion. The name Asopos is applied by Herodoros consistently to the main stream, and to it only. If Mr. Grundy is right in taking Leake to task (p. 45) for calling the large Kristicki stream the Asopos, it is somewhat strange to find that he himself applies the name to the insignificant brook A' on the ground that it can be

seen from the walls of Plataia, while the main river is invisible (p. 26).

It is in the highest degree improbable that two distinct senses of the word should have been so closely combined as in the two consecutive sentences quoted from chaps, 30, 31. In se far as Mr. Grundy's hypothesis rests upon the locality to be sasigned to the monument of Audrokestes, it has already been refuted. It is also partly the autcome of a loo great rigidity in the translation of the phrase (a) vo 'Acuzo. Mr. Grandy is concerned to show that the army was literally untride the brook (p. 21). The preposition is used in its technical military sense, which would not conflict even with the ordinary acceptation of the situation of the heroon. (Cf. chap. 38 vor. 3' ir) vo Acure Mapdorie assurbanivos... (blove which does not mean literally on the banks.) There is no mystery in the addition of the words she raing beare to the name Asopes in the second passage. They murely indicate the change of position to another portion of the river. It would surely have been strange to remark simply that the Persians also advanced to the Asopos, seeing that they had been encamped on that river since the commonousent of the operations (cf. chap. 19: fusfer to be two Enchapses in the 'Acassis' experiences). The words mean little more than 'to this precise point.' Even admitting them to have some special signification, it would enroly follow from Mr. Grandy's confession that they refer to the words is Macrasians (p. 19), that Herodotes meant thereby the stream A', which takes its ries in the direction of Platsiai.

When we reach chap. 40, Mr. Grundy decides, on what criteria I know not, that the Asopos there mentioned, is 'certainly the main or Thospian Asopos.' This, taken in conjunction with the rest of his topography, necessitates the adoption of a theory as to three 'developmenta' of the second Grock position (p. 19). It would surely have been simpler to keep to the first hypothesis, that the Asopos upon which the Greeks lay was the stream A', then to pile up this new hypothesis.

in order after all to bring the Greeks to the main elream.

There remains the passage relative to the situation of the 'Island.' If we take the Assection which the 10 stades are measured to be the main river, then the given co-ordinates (10 stades from Gargaphia, and 10 stades from Asopea) bring us to Leake's 'Island,' a position which Mr. Grundy has shown to be impossible (p. 23 fel.). Yelf if the Spring Gargaphia is rightly identified with the Appercia, it becomes obvious y impossible to argue that Herolotos measured from the stream A', as his starting-point in that are could only be obther the source or the mount of the stream. The source is impossible as it coincides with the oping. The mouth is equally impossible as that is on the line of the Thespian. Asopes, which line is out of the quantion, as already remarked. I enggest that s' (=20) has dropped out before the soil. We should read had fore and Asome Samuel Samuel Could be staded to be true of Asome Samuel Samuel Could be staded from the Thespian Asopea. The truct of ground identified as the 'Island by Mr. Grundy lies almost exactly 20 stades from the Thespian Asopea.

The latest utterances of Mr. Grundy (Chessical Review, April 1803, p. 161), in answer to Mr. France, simply re-affirm his views, with the additional conjecture that in the application of the name Asspos to the stream A' Herodotes has preserved the local custom of the Plataisne!

NOTE B.

On the Chronology of the Operations at Plateins,

The views advanced in the preceding pages necessarily involve the rejection or the modification of the chronological items embedded in the narrative of Herodotes.

Herodates does not tell us how long the Greeks remained in their first position, on the breast of Mount Kitharon. We are informed, however, that the two armies had been caramped opposite to such other already eight days before Mardonias was advised to close the pass through which the Greeks received their supplies (ix. 39). The pass was actually closed at nightfull of the sums thry. The expression of Herodotos is ambiguous : it is not clear what is the point of departure involved in the words the par 34 opt derivarquerous for every freeze exec. Are the eight days to be counted from the marshalling of the troops in the second position? Such everes to be the generally accepted view, but it has always appeared to me somewhat of a marvel that historians should credit this reflection upon the intelligence of the Persian general. If Herodotos really meant that the Greeks had been eight days in the second position before the pass was blocked, I should see in the statement but one more instance of the working of national autipathy. The Greeks esmot allow the invaders to have possessed ordinary common sense. Obvious as was the stroke of blocking the main artery of the Greek communications, the tradition puts it to the credit of Throgenidas, a renegade Theban it is true, but still a Greek (ix. 38 fol.). Mardonies, to my mind, was more than a match for his opponents in point of military skill, and an caplanation more in accordance with the probabilities of the case must be sought. The words quoted hear reference to and date from the first day that the two armios found themselves face to face in the first position. The pass was closed as soon as the evacuation of the lines on Mount Kithairen threw it open to attack. The Greeks abandoned their first position within the week.

In proceedy the same way must we interpret the words in chap. 41: is to desire exercises in the same are interpreted in the same of the same of the same of

operations, and does not restrict us to the second position. The slaves days in this case also are reckonsel from the opening of the campaign. Whether this was indeed the intention of Herodotos must be left undecided.

The next note of time is given in the important words at the opening of chap. 40: 'after this the armies walled two more days' (acrà δε τοῦτο το έργος δτέρας δόο ξαέρας διέτροξας, εὐδέτερος δουλόμετοι κάχει δρξω). What are the two termini involved in this expression is With regard to the event from which the reckoning is made no doubt is possible: it is, as Herodotos says, the closing of the pass. When we ask to what conspicuous event in the development of the drama the two days' interval brings us, the roply is vague and unsatisfactory. For they are followed by the resolution of Mardonics to end this idio delay; and yet two days more intervens before his purpose is accidentally accomplished. As it stands, the sentence is meaningless. It becomes intelligible only upon the view already developed.

The eleventh day is devoted to the committation of his Staff by Mardonios (ix. 41). Alexander's visit to the Greek outposts takes place at midnight (ix. 44). On the twelfth day occur the challenge of Mardonios, and the cavalry attacks which culminate in the less of the Spring Gargaphia; the Greek generals determine to fall back upon the 'Island' (ix. 45 fol.). During the night the army evacuates the second position (ix. 52 fal.). In the early morning of the thirteenth

day the final battle is fought (In 56 fol.).

Now we have already seen that we must out not as firstitions items the consultation, the visit, the challenge, and perhaps also the loss of the spring,—that is to say, the whole of the matter alletted to the eleventh and twelfth days, with the exception of the deliberation of the Greek generals. The evacuation of the second position and the final struggle must therefore be antelested by two days, and be assigned to the night of the tenth day and the merning of the eleventh day respectively. In other words, the event to which the reckening is made in the sentence quoted from chap. 40 ("after this the armics waited two more days") is the final battle steel, which took place two days after the closing of the pass of Dryoskephalai.

The story, as given by Herodotes, impossified requires a somewhat protracted stay in the second position on the part of the Grocks. It was also clearly impossible, from their very insture, that the interpolated episodes of the consultation, the challenge, etc. should immediately follow the adoption of that position. Herodotos has consequently duplicated the interval believes the clearing of the pass and the final tattle. He may purhaps be sequitted of the mistake already pointed out, by which a further addition of eight days is under to the time spent in the

second position.

My idea is that when their offensive failed the Greeks at once ratired, i.e. at midnight of the tenth day, reckoning from their first appearance on the northern slopes of Mount Kithniren. They were not more than three days in the second position.

Hence my disry of the operations is an follows :-

Greeks take up First Position. 21 3 Attacks by Persian Cavalry. 4 Death of Masistico. Ġī 0 [Evacuation of First Position probably on night of this day.] Greeks in Second Position. [Pass cheed on night of this day.] it Continued Skirmishing. Flataful-Thebas road blocked by Persians. 10 Meeting of Grock Generals. [Retirement to 'Islami' partially effected on night of this day.] 11 Pinal Battle. 12-20 Berizl of Dead. Collection of Spail. Communication, 21 Greeks march on Thebea.

The usual schome gives in addition :-

(I) An unknown number of days in the first position.

Eight days in second position before the closing of the pass.
 Two days of purposeless waiting after the closing of the pass.

(4) Two days devoted to Persian Conneil, the Challenge, and blocking of the spring.

The result of the usual scheme is that the battle was fought on the thirteenth day after the occupation of the second position, and Thebes is reached on the twenty-third day after the same event. If the same generous measure is used in meting out the time spent in the first position, the Greeks must have been four or five weeks on the Asopes. Could a force of one hundred thousand men have kept the field for that length of time in the fifth century not. The case is very different from that of a blockade, to which am side has an absolute superiority. Leatly, how explain on the ordinary theory the arrival of the Mantinoians and Elema too late to take part in the battle (iz. 77). An explanation cannot be found in the closing of the passes, as one at least remained open to the end: nor, if such had been the reason, would the leaders of these emitingents have been banished for failure to arrive in time. On the view here presented, ten days covered the whole series of operations previous to the final catastrophs; and the two Pelepounesian contingents may well have found that events before Plataial entstripped their progress to the seat of war.

W. J. W.



Vio. 1.—Trenn and Pluttes Ufrom a column of the Hally

EXCAVATIONS OF THE BRITISH SCHOOL AT MELOS.

THE HALL OF THE MYSTAE.

[PLATES I.—III]

THE Hall of the Mystae is a Roman building on the western slope of the ancient town of Melos. The principal object and result of the excavation begun by Mr. D. Mackenzie and myself in April and extended by Mr. Cecil Smith in Mny 1896, was to put on record its fine mosaic pavement. We were fortunate in being able to call to our aid a skilful and indefatigable draughtsman. Mr. Charles Clark, architect to the School, joined us in Melos as soon as he could be spared from the Athens excavations, and worked upon the mosaic for several weeks in the full heat and glare of a Mediterranean summer. Of the illustrations, fruits of his patient labour, which this paper serves to introduce, Plate I represents the two figured panels on the scale of 1:25, and is a very faithful rendering of their general effect; while Plate II. gives part of the finest panel on the scale of 1:5, and shows the method of execution in detail; it is reproduced from one of a series of rubbings' coloured cube by cube upon the spot, which are practically full-size facsimiles of all the principal figures. The spirited figure of the cock (Plate III.), supplied by

another rubbing, gives a good idea of the life-like force of the design. For the restoration attempted in the key-plan (Fig. 4) we are jointly responsible.

The mosaic seems to date from the first half of the third century.

The site is marked H on a sketch-plan of the ancient town which accompanies Mr. Cecil Smith's account of our work in Melos (J. H. S. xvi. p. 348). Mr. Cecil Smith has there described the mosaic (p. 354); he has since published two inscriptions which we found there and inferred from them that the place belonged to a Society of Dionysiac Mystae (J. H. S. xvii, p. 14).

Previous History of the Site.

This conclusion is confirmed by the fact that other inscriptions naming the Mystae have been found at the same spot. An Athenian magazine of the year 1862 contains the following among other archaeological news: 'In Melos in the ground called Tpemivela near the ancient theatre in the course of an excavation made by private persons there was lately found a mosaic pavement said to be about 40 m. in length, a wall of squared stones with a door in it and various marble sculptures bearing inscriptions, apparently of Roman date." After describing them the report goes on the excavation is being made with the knowledge and indeed under the supervision of the local authorities." How little this meant is implied by the words which follow, we hope that the objects found may not be dispersed, as has happened on other occasions." Finally it is suggested that an ephor should be sent from Athens. From enquiries made on the spot, it appears that there was no official excavation; the Government contented itself with stopping the enterprise of the 'private persons' and securing the marbles for the Athens Museum, where they now are. They consist of a bust of Aurelia Euposia (Fig. 8) set up & 76 loio aυτής έργω by certain Περιβώμιοι (Cavyadias' Catalogue 424), the head of a young man bound with a fillet (Catalogue 459), and two columns, the ends of which have been sawn off for convenience of transport. On one of these columns is incised a figure of Athene, on the other that of the Good Fortune of Melos, and in each ease there is inscribed a prayer that the Goddess may be propitions to Alexander, founder of the Holy Mystan (κτίστη είερῶν μυστῶν). They are fully described and published in a valuable article by Wolters on 'Melische Kultstatuen' (Ath. Mitth. xv. 1890, p. 246). The figure of the Tyche of Melos has acquired a certain importance in the history of act since Furtwangler used its testimony in support of his restoration of the Melian Aphrodite. It is reproduced in Fig. 1.

^{**}Mersop, vol. ii. p. 274. Copied theree into the Arch Austiger, 1861, p. 234, and Bullettine, 1862, p. 86. See aspecially the artisls by Wolters, Ath Mitth. vv. 1890, p. 246, to which I refer below.

² The Inscription is published on p. 16 of the

last volume (svii) of this Journal. The early notices mention a headlass bust and secheads. The second of these may have been the head which is now fitted to the bust.

Meisterwerke, p. 624. English edition, p. 381.

The description of the site as ἐν τῷ θέσει Τρεμινθία πρὸς τῷ ἐκεῖ ἀρχαίφ θεάτρῷ is accurate in the sense that the hill-side called Tramithia and the theatre are in the same part of the island; but they lie ten minutes walk




Fig. 2.-View room the East Exp.

apart on different sides of the central acropolis-ridge. The identity of that site with ours, which is in Tramithia but not near to the theatre, is put

We have usually followed Ehrenberg's map (Leipzig, 1889) in spalling the name Tramythia, but Tramithia is as near to the local pronuncia-

tion. The form Transfia suggests a derivation from voimeor Tipuress. Steph. Byz. mentions a place called Transfer (v.L. Transfer) in

beyond a doubt by our discovery of columns of the same diameter and material as those in the Athens Museum and by the local story that parts of such columns had been sawn off and sent to Athens with other marbles from this site. An idea of the lie of the ground may be gained from Mr. Clark's sketches, figs 2 and 3, and from the key-plan on the opposite page. That part of the site which was first pointed out to us as containing a mosaic was a small field just south of a mule-path which leads from the villages on the heights to the Tramithia landing-place, Like most other fields on those highly cultivated hill-sides it is a terrace bounded by higher and lower terraces. each supported by a massive retaining wall locally called τράφος (for τάφρος). In this case there was a rising traphos to the east and a descending traphos to the south; the other sides of the rectangle were formed by the mule-road which gradually descends from the higher level of the terrace on the east to the lower level of that on the south, curving round our field and cutting off its north-west corner. The course of the road-wall and of the terrace-wall to the east is shown by the dotted lines W W on the key-plan; it was only under them that we found the mosaic in first-rate preservation. The field has a downward slope from east to west, and at the lower end the pavement had been obliterated by cultivation; further east, where there was some depth of soil to protect it. considerable injury had been caused by the recklessness of the excavators of 1861. It was then that a great part of the fish-panel was destroyed. They dug as far as the eastern terrace-wall, and seem then to have worked down from the upper field and to have penetrated as far as the door in the east wall of the Roman building; but the τράφος between the two terraces happened to be the boundary between two properties, and that fact preserved it inviolate and with it the whole panel of the vines which lay below. This belt of unknown ground had weighed on the consciences of local treasure-hunters ever since. We heard of at least two attempts to explore it. In one case the adventurers tunnelled under the road, breaking through the north wall of the Roman building, and worked along its inner face as far as the corner-column A which is still in situ. They dared not go further, fearing that the mass of stones overhead would fall in on them, and retired by the way they had come, but not before they had found a marble head. This head, which was sold to the Athens Archaeological Society in 1884 and passed with their collections into the National Museum, has since proved to belong to the statue of a hierophant which we found lying on the mosaic in 1896 (Fig. 6).

Cyprus and derives the name and the reply of retrove repumber, he Tépus repuldous sakouar. The name would be formed like that of Papraës in Affin = Papraes from planes. The form refuser is further attented by Nicard. That, \$44 regulous rise ratembia sagrain.

The Malian 's who Tounded seems parallel to

island. For place-names in Graces derived from trees see Tozer, Highlands of Turkey, it. p. 107. Sibthorp (Florus Oraccas Prodremus, it. p. 256) and Fiedler (Leise, i. p. 529) say that Pistachia Terebinthus grows abundantly in the Grack Islands. Both give the modern Grack name as responsible. Mr. Bickford Smith gives responsy as the Grana form.

The Building.

We demolished the eastern terrace-wall, cleared the remains of mosaic in the lower field, and found that we had two panels and part of a third. Later Mr. Cecil Smith pulled down the wall on the north and uncovered a long strip of mosaic, which not only proved the existence of a fourth panel, but also preserved just so much of the geometric design of a fifth as enabled us to complete it and to determine the dimensions of the whole.


The building was a long hall running east and west, 8:32 m, wide and at least 23 m. long (27 ft. 4 in. × 75 ft.). The east and north walls are in great part preserved; the south wall has almost disappeared, but enough remains to justify us in restoring it on the analogy of the north; the west end is wholly destroyed. The tessellated pavement did not occupy the whole width of the hall; along either side ran a stylohate 1:50 m, broad, raised 0:27 m. (10½ inches) above the floor, supporting a row of unfluted marble columns. Of the marble slabs of the stylobate only one survives; it is under the single base which remains in position; but the dwarf walls which carried the stylobate are preserved, 14 cm, high. As for the columns, A is in place and the position of the two adjoining columns is indicated by blocks which once supported the marble slabs under their bases; they give 3:32 m. (10 ft. 10 in.) as the intercolumniation.

The exact length of the hall was not determined; this might possibly have been done by digging for the foundations of the north-west angle from the field beyond the road; but there was great risk of injuring some valuable olive-trees. We dug down at the only possible place, where there happened to be a gap in the olive-grove, and found the outer face of the north wall (at F in key-plan) under the roadway, some five feet below the level of the mesaic. This part of the wall probably dated from Hellenistic times and originally rose above ground, for it was better built than the upper part, and along its foot there was an accumulation of pottery ranging from third-century Greek to Roman. The evidence is slight, but one is inclined to infer that the Hall of the Mystae stands on the site of a Greek building, using its walls as foundations; in that case the earlier floor-level may be some feet below the mosnic. Beyond the point where we suppose the west wall to have stood the ground falls away; had the building extended further in that direction it would have required very massive substructures; but of these no trace remains. It can hardly therefore have been longer even by one intercolumniation than we have shown it in the key-plan. On the other hand the remains of the mosaic prove that it cannot have been shorter, The restoration of seven columns on each side may be regarded as fairly certain.

We were also unable to dig as far as we wished to the east. Once beyond the shelter of the thick terrace-wall we found that the whole area in the upper field had been ransacked and filled in with stones. We cleared part of the little chamber at the north-east angle and worked some feet beyond the large door in the east wall, but there were no mesaics. As the débris was eight feet deep and difficult to handle we did not feel justified in

going further for the sake of completing our plan.

It is probable that the principal entrance was at the west end, and the east doorway led from the body of the hall into a chancel-like extension, an above opening out of the relection. Just each an inner sanctuary may be seen in the plan of the Baccheion, a building much like ours in date and character, excavated by Dr. Dorpfeld between the Pnyx and the Arcopagus. The internal arrangements of the hall are in agreement with the view that this was its principal end. Of the five mosaic panels the western is the



Pto. 3.-VIEW FROM THE WEST END.

simplest, the eastern the most elaborate. Close to this doorway in the southeast angle stood a square structure (D in key-plan), obviously of importance, for the outer border of the mosaic was compressed and cut short to leave room for it; it must have been a small shrine or altar.² In a niche on the opposite side (C on key-plan) stood in all probability the statue of a priest to be discussed later, which we found fallen on the pavement. Before giving up the idea of exploring the supposed adylum we sank a pit 8 m. east of the mosaic, and found fragments of a wall covered with red stucco, its floor-level being

¹ Ath. Mitth. 12. p. 161. Taf. iv.

In position and perhaps in form it resembled the 'home-alters' of Pompail Cf.

Overbook, Pompell, p. 268, Presuhu, Die Neuerten Ausgrubungen, i. Taf. iv., vi Taf. ii.

about the same as that of the mosaic. Somewhat further east we must suppose an ancient terrace-wall; for it was at a much higher level, though only 20 m. further away, that we found the basis (Fig. 6) dedicated to Dionysos Trieterikos. The circumstances under which it was found are described in J. H. S. vol. xvii. p. 14. We dug round the spot, but found only some walls of Roman date, a flagged court, in the middle of which the basis stood, and a cobbled path leading towards the mosaic. It is very probable that these buildings were in some way connected with the Hall of the Mystae.

Before passing to the mosaics it may be noted that the walls of the Hall were covered with a thick coat of plaster. In demolishing the traphos we came upon a quantity of plaster including many fragments of mouldings.

The Parement.


The space between the stylobates is filled by the mosaic pavement 5:35 m. (17½ ft.) wide, and as restored 22:22 m. (nearly 73 ft.) in length. The length that is preserved is 19:20 m. (63 ft.). The whole design is framed in an unusually broad triple border, 1:38 m. (4 ft. 4 in.) wide. The width of the panels is 2:67 m., just double that of the border and half that of the whole pavement.

There are five panels; the following measurements do not include the guilloche border, which is 17 cm. wide, but are taken up to its edge;

L	Vines, birds, gazelle and hare .		3·28 × 2·67 m.
II.	Fish and fisherman		2.67 × 2.67
Ш.	Geometric	-	648 × 267
IV.	Probably a figure-subject, destroyed		3.07×2.67
	Geometrie, as restored		3·28 × 2·67

It will be seen on reference to the key-plan that the places of the columns correspond broadly though not exactly with the divisions between the panels. Panel III. is twice as long as I., which again is the same length as V. The preservation of these proportions, as of those between the breadth of the panel and the border, shows how carefully the mosaic was designed for the building.

The detailed execution and technique of the Meles mosaic are admirably exhibited in the large scale drawings (Plates L, H, and HL). Glass tesserae are freely used in the birds, beasts, and fishes; all these figures are carried out with a skill that must have been the result of long experience. The glass tesserae are much smaller than the marble tesserae; the latter are usually square or nearly so at the top, while the former are of all shapes, and seem to have been chipped off from a slab of glass as they were required. They are mostly blues and greens. Mr. Henry Powell, who is an expert in modern glass-mosaic, has been so kind as to point out that these glass tesserae seem to have been translucent; some of them retain their transluc-



A-COLDAN SERVICE B-PROPERS. C-NORE, D-SHREET OF AUTOR.

ence, others have lost it owing to the action of weather. The colouring matter in the blue tesserae is cobalt, in the blue-green, copper, in the other shades of green, iron. It is difficult to say when the practice of adding arsenic or tin to make the tesserae opaque first came into use. Besides glass and marble a local material, the lustrous black obsidian, is used with great effect, especially in the long geometrical panel.

The Panel of the Vines.

The panel of the vines is the most elaborate and the best preserved (Plate I.). Mr. Clark has been wonderfully successful in reproducing its originality, its grace of design, and its rich harmonious colouring. The subject is unusual; it must have been chosen for the place of honour in the Hall as one especially appropriate to the society of Mystae and their patrongod. This special local significance may help to explain the unconventional character of the composition, its freedom and want of symmetry; it is like the work of a man who has put aside his pattern-book and is feeling his way towards a fresh design. The elements which he had to group together were familiar; the animals grapes and leaves are the work of a practised hand; but in the stiff lines and abrupt curves of the branches there is the irresolution, the hesitating touch, of an experiment. Strangest of all is the want of balance in the disposition of the birds and beasts among the foliage. The whole south-east corner is given up to grapes and leaves and tendrils with no living thing among them. The contrast must have been all the more conspicuous before the pedestal (B in key-plan) was thrust into this end of the panel; it cuts so rudely into the design that there can be no doubt of its being a later insertion. We may perhaps connect the different treatment of the south-east quarter of the panel with the shrine or altar which stood close by in the south-east angle, and suppose that even in his glowing picture of the fruitful earth, blessed with a luxuriant crop that leaves enough and to spare for bird and beast as well as man, the artist has found means to suggest the reverence due to the god and He shows us the wild creatures gleaning, but hints that the boldest of them spares the clusters that ripen in the shadow of the god's altar. The explanation may seem fanciful; at any rate it is not unlike the fancy of the man who wrote µovor µn voor, Give them water and they will steim, among the fish of the adjoining panel.

I have claimed for the panel of vines a good deal of originality. Among published drawings of mosaics one looks in vain for any that closely resembles it. But its general scheme, the decoration of a rectangular panel by means of tree-like forms springing from the corners, was by no means a new one. It may be traced back to the fashion of filling the spandrils of a square panel containing a round medallion—spaces such as in our fish-panel are occupied by masks—with branches issuing from a stem or vase set diagonally in each corner; and this fashion, which appears several times at

Pompeii, was doubtless borrowed from the favourite vase-and-foliage border, of which our scroll-border with its vase at each angle is a good, though late

and elaborate, example.

The nearest parallels to our design are furnished by some vine-moraics which have come to light in North Africa. They seem to mark an earlier stage of development; the vines spring formally and symmetrically from vases placed in the angles; they are not allowed to cover the whole field, but orm a broad frame to a central picture-panel. It is as if their derivation from the scroll-border were still remembered. On the other hand the birds among the branches and the Capids busied in gathering grapes show that the frame is in process of acquiring an independent pictorial importance. In a mosaic from the Arsenal at Sousse (Hadrumetum) just published by M. Gauckler (Rev. Arch. 1897, Pl. ix. p. 8 ff.) the central picture representing the Triumph of Dionysos is surrounded by a comparatively narrow frame of interlacing vines. In a magnificent design which is the principal glory of the House of the Laberii at Uthina (published by the same writer in Monuments Piot, Vol. iii. Pl. xx.-xxiii.) the vines have encroached much further, and the central picture has become subordinate to the animated vintage-scene. A third design of the same type, found in the baths at Kourba, forms part of the rich collection in the Bardo at Tunis. In each case the African vine-mosaics contain a central picture representing Dionysos; the omission of this feature, as well as of the angle-vases and of the Cupids gathering grapes, is in keeping with the greater simplicity of the Melian panel. That the general idea of the design was commoner than the few instances which I have collected would imply, is made probable by its wide distribution in early Christian times, when the imagery of the vine, beloved in Jewish poetry and Christian teaching, was reproduced in every branch of art. The vintage-mosaic on the ceiling of the ambulatory of Santa Costanza at Rome, a church built about the middle of the fourth century, is a good instance of a perfectly pagan design adopted for the sake of its associations.1 The amorini who are plucking the grapes, leading wains and treading the wine-press, were doubtless felt to be incongruous in a church; they do not appear in the later vine-mosaics. Rather the Christian significance of the design is set beyond doubt by some such inscription as that of a mosaic-paved apse at Ancona in which every leaf has the form of a cross-Vinea facta est dilecta in cornum in loco uberi.2

It is in keeping with the relatively late date of the Hall of the Mystae that the panel of the vines finds its closest parallel in the pavement of a Christian basilica. The same symbolism is Dionysiac in the one case, Christian in the other. The design is essentially the same, and it is difficult to believe that the interval of time between the two can be much more than

De Rossi, Musaici cristiani, xvii., xviii, A coloured paper cast and a coloured drawing by Zeri are exhibited in the South Kennington Museum.

A variant from the Vulgate of Isalah v. t. Bull. crist. 1879. Tal. iz., z. Krauz, Gesch, der christl. Kunst, i. p. 298.

a century. The pavement which so closely resembles ours is that of the church at Orléansville in Algeria; an inscription which forms part of the mosaic shows that the building was begun in 324 and completed before 340,1

It is commonly said that in the early Christian centuries the use of mosaic pavements diminished, and mosaic work was almost confined to walls and ceilings. Of late years however a surprising number of Christian mosaic pavements have been discovered in Syria and Palestine. Several of them have the spreading vine pattern. The best known instance is the pavement of a church discovered by Renan's expedition at Kabr-Hiram near Tyre and afterwards transported to the Louvre.2 The general design recalls the African mosaics published by Gauckler; four vines spring from vases placed in the corners of an oblong panel; their branches however are quite formally arranged so as to encircle a series of medallions placed in rows of five across the design. An inscription fixes the date of the pavement according to Renan's interpretation at 575 A.D., in the reign of Justin II. De Rossi ascribed the vine-panel on the ground of its style to the fourth century, but later discoveries seem to confirm Renan's conclusion. particular two mosaics of this type have been found at Jerusalem, one on the Mount of Olives in 1871, the other outside the Danmsons gate in 1894. Both bear Armenian inscriptions; the former can be dated with comparative certainty to the middle of the sixth century; while the latter, as Mr. A. S. Murray has pointed out, though retaining much of the refinement of classical work, may well belong to the vigorous art of the age of Justinian. A simpler mosaic from Medaba in Moah (Pal. Fund Quarterly, 1895, p. 207) resembles the older type in having a single medallion containing a head as the centre towards which the diagonally placed trees converge.

Our Melian vine-panel seems to be a link, geographical as well as chronological, between the two main groups of similar designs; these from North Africa, which are at their best in the second and third centuries, and those of Palestine which seem to date from the fifth and sixth of our cra. In Africa as elsewhere there has been a tendency to place the decline of mosaic-work too early; a study of the mosaics from Carthage in the British Museum shows that good work was done there long after the time of the Antonines, and the same view is maintained by M. de la Blanchère (Collections du Musée Alaoni, 1890, p. 17 ff.) in publishing the spirited groups of race-borses from Hadrimetum which he assigns to the fourth century. There is a rich field for investigation alike in Africa

^{*} Rev. Arch. 1v. (1847), Pl. 78, p. 641. Traces of a fish-panel were found in the same church. This juxtaposition of earth and sea, conventional in pre-Christian mesale, and retained perhaps because to the Christian the fish as well as the vine had a mystic meaning, is seen in other early backless of North Africa. e.g. at Tipusa, Mélangus d'Arch. et d'Hist, torn. six., and at Sartoi, Mélangus O. B. de Easté, p. 227.

^{*} Renny Mission de la Phinicie, 12. 1111.

Photograph in Quarterly Statement of Palestine Fund, 1894, p. 261. Cf. Mr. A. S. Murray's note, 45, 1895, p. 126.

[&]quot;To the fourth century too the British Museum authorities ascribe the Carthage pavement of the Months. Its decorative design of syrvess-like trees growing in research converging towards the centre is a very beautiful develop-

and in Palestine, and for the present it would be premature to do more than indicate the general relationship of the two groups of designs. It must be remembered that they are not likely to have been the exclusive property of mosaic-workers, who often borrowed and adapted the ideas of wall-painters and modellers in plaster.\(^1\) Mr. Cecil Smith has already hinted at the possible influence of similar textile patterns in comparing the Melos vine-panel to some of the older Persian carpets.\(^1\) The tree with birds in its branches, springing sometimes from a kantharos-like pot, sometimes from a mound of earth; is a favourite subject in woven stuffs and embroideries in Persia, India and even China.

The birds are for the most part conventional, always excepting the cock (Pl. III.). The gazelle (Pl. II.) was perhaps intended to represent the wild goat of the Cyclades, which still survives on Anti-mile; but the figure which the \$\psi n\pho\theta\theta represent the wild goat of the Cyclades, which still survives on Anti-mile; but the figure which the \$\psi n\pho\theta\theta representation of the North-African influence which we have already had reason to suspect. It may be compared with a reclining gazelle which is represented eating grapes from a basket on the Sousse Arsenal mosaic. The crouching hare of our panel finds a parallel in the same part of Africa.

The Panel of Fish (Plate I.)-

To the picture of fruitful earth succeeds one representing the harvest of the sea. It is less elaborate than some of the fish-mosaics in the Naples Museum which seem to present a side-view of a tank or a section taken through the sea, with the surface marked by a line near the top of the picture and fish swimming to and fro in the green water: and less ambitious than the great floors representing the Triumph of Neptune and Amphitrite which have been found in the provinces. In Roman Africa pavements representing fishing scenes were often the appropriate ornament of an impluvium. The inherent qualities of glass-mosaic are so well adapted to depict the gleaming scales and iridescent colouring of fish that the subject became increasingly popular.

Just as in the preceding panel the principal figures are placed upon the north side of the hall, so here the position of the fisherman and the motto over his head presuppose that the spectator stands on that side. But this also is a decorative composition, not a realistic picture, and is meant to be intelligible from whatever point of view it is seen. The throng of darting

of late classical architecture. Texter and Pullan, Pl. xxxiv.


* Do la Blanchiro, Music Absoud, p. 25,

ment of the older tree-patterns. Archaeologic, xxxviii. Pl. (x.-xiii. It was originally planned for a dome rather than a floor. Cf. Garrucol. Arte cristians, iv. Tav. 255.

The estiling-mession in the side-chapels of S. George at Salonica imitate not only the painted coffers but also the cornice-mouldings

^{*} Compare a tile-work design of vines, grapes and birds from 'the south gate of the Top-Maidan, Teheran, 17th cent, reproduced in the Cross Gallery of the South Kenaington Museum

fish follows the circular frame in an endless wheeling movement, for which a fixed centre is supplied by the absurdly disproportionate figure of the little fisherman perched in their midst.1 Owing to the injuries done to the panel by previous excavators no part of the boat remains; Mr. Clark has restored it on the analogy of many similar mesaics, making the boat nearly as disproportionate to the man as he is to the fish. One could imagine him fishing from a rock like three fishermen figured on a silver patern from the coast of The boat on Plate I. Algeria 2; but this would be unusual in a mosaic. is sketched in from the fish-panel at Sousse, a picture which furnishes a vivial illustration of a passage in Aelian describing the four methods of fishing: δικτυεία or netting, κόντωσις or spearing, κυρτεία or catching by means of the xupry (Latin nassa), a basket-trap like our "weels" and "oel-bucks," and ayrearpela or angling with hook and line. Of the four methods Aclian considered line-fishing the most sportsmanlike; and trapping the least worthy of a free man. The Sousse mosaic when it was complete had a boat in each corner; in one the fisherman is striking a fish with a trident, in another he is about to cast a net, in a third he holds a cord to which three bottle-shaped basket-traps are attached; the fourth corner, in which dykiotpeia was doubtless represented, has been destroyed. The fisherman on the Melian panel holds a rope, the loose end of which passes under his left arm, but we have no means of deciding what was at the end of it. Like other boatmen from Charon upon the lekythoi onwards he wears the chiton exomis.



Fro. 5.

The words μόνον μή ὕδωρ picked out in black tesserae on the white ground above the fisherman's head (Fig. 5) have been happily explained by Dr. Sandys, who compares them with Martial's Epigram I. xxxv.

Artis Phidiacae toreuma clarum, Pisces adspicis; adde aquam, matabunt.

The ides of link awimming is a circle is used with equal effect, as Mr. Coeff Smith points out, on a series of red-rigured plates from South Italy, among the latest examples of Grasco-Italian pointed pottery, which were probably intended to be used as fish-plates at table.

Brit. Mus. Fass Calad. F. 259 ft.

³ Found between Tipses and Cherchel. Dullitis Archild, de la Concilé des Transas Historiques, 1893, Pl. x.

Aalian, N.A. 11i. 48. M. Gauckier does not mention the passage. I am in many ways indicated to his full and interesting essays on the meanies from Serson (Ees. Arch. 1807, (2), μp. 3-22; Habing-seems Pl. 11.) and Ondra (Meanwarts Piol. 11. pp. 177-229; Habing-seems, p. 198). In Plato's Sophiat the art of Sahing is resolved into Ιρκόθηρική, προδαντία, and άκναλονονική.

Martial is describing a chased silver bowl, an old piece of Greek plate; when it was filled, the fish with which the interior was decorated appeared to swim, just as the ships painted in certain black-figured kylikes floated when they were filled with wine.

In compressing some such epigram into three words the artist has made the point a little obscure. His self-praise was certainly justified during our excavations by the expert criticisms of local fishermen. They readily recognised and named most of the fish, and were never tired of admiring the life-like play of light and colour on the scales. One detail baffled them as well as ourselves—the globular object with a stender neck to the right of the fisherman. It looks like nothing so much as a gourd-shaped glass bottle, three parts full of dark-blue liquid, the upper part being empty and transparent; but this does not correspond with any known kind of fishing-appliance; neither a $\kappa \dot{\nu} \rho \nu \eta$ nor a gourd-float would be transparent; so we are constrained to suppose that it represents some marine creature. The name $\kappa \dot{\nu} \nu a$ (classical $\kappa \dot{\nu} \nu a$, a bearded mussel) was proposed and rejected.

The Geometric Panels and Border.

The two geometric panels are typical specimens of Roman provincial mosaic. They are not original compositions like the two preceding panels, but stock designs. In skeleton, as is shown on the key-plan (Fig. 4), they are based on different systems of intersecting octagons, such as any one experimenting with regular geometric design must inevitably discover. In the case of the long panel the intersecting sides of the octagons bisect one another, and divide each octagon into a square and four hexagons. The next step is to subdivide each hexagon into a square and four rhomboids. By this device the original octagonal planning is effectually masked, and a cross-like form made up of eight rhomboids becomes the predominant feature of the design. In this form the pattern appears at Pompeii; it is increasingly common in the provinces during the second and third centuries.

The design of the western panel, where the octagons intersect at their angles, is at no time so common as the other, and is hardly found before the third century. Almost the only building, besides the Hall of the Mystae, where these two patterns occur together, is the somewhat late British villa

of Weldon in Northamptonshire.1

The character of the border is a further evidence of late date. The swastika-like wheel-pattern is very common in the later floors of Britain, Ganl, and Germany. The florid scrolls of the vase-and-foliage border find parallels in Christian rather than classical mosaic; and the proportion (1:4) of the width of the border to that of the whole mosaic is characteristic of corridor-payements in the third and fourth centuries A.D.²

^{*} Lysons, Rol. Brit. Rom. I., Pt. ii., Pt. vit. Pl. 41. The latter own hardly be earlier than * E.g. at Silchester, Archaeologia, iv. p. 241. the 4th century.

und at Hallestnassus, Newton, Hist. Discoverice,

The Sculpture and Inscriptions.

The clue to the identification of the building had already been given by the basis dedicated to Dionysos Trieterikos (Fig. 7 below) when in demolishing the great traphos we came upon a headless statue which proved to be a portrait-herm of a hierophant. Marcus Marius Trophimus, set up by the Mystac (Fig. 6). One of our workmen had previously told us of a head



FIG. 6.—STATES OF HIEROPEANT. Height 1 80 m.

which he had found in the same part of the building, and his description of its beard and wreath enabled as upon our return to identify it with an unpublished head which is thus described in Cavvadias' Catalogue of the Athens Museum; '329. Portrait-head of a man wearing a wreath, with a short beard and moustache and carly hair; small life-size; work of Roman times. Found in Melos, and bought by the Archaeological Society in 1884. Eye-brows and pupils indicated. End of nose broken. Parian marble?

Mr. Cecil Smith has since taken a east from the neck of the head in Athens, and tried it upon the herm in Melos; the two were found to join accurately at the back of the neck; in front the surfaces had been chipped and did not meet, but the identification was quite satisfactory. The marble of both head and body is singularly white even for Parian.

The statue represents—or will, when head and body are united—a middle-aged man with broad face, full cheeks, curly hair, and chipped beard. The wreath on his head is of ivy and flowers, a wreath such as Dionysos often wears. He is dressed in a chiton which is girt up above the knee with a deep fold falling over and concealing the girdle, a nebris confined by a broad belt and passing over the left shoulder, and a mantle. Part of the mantle is brought forward and thrown over the right fore-arm, so as to provide the starting-point of a passelle to support the right hand; the stump of it is seen on the drapery below the breaks in the arm. The right hand was found, and when it is readjusted the arm will be complete but for some of the fingers; there is evidence that the hand held a curved vase, phiale or kantharos. No part of the left arm, which is broken above the elbow, was discovered. It was sharply bent, and the hand was raised nearly to shoulder level and probably held some heavy attribute such as a thyrsos, to judge from the stump of a cross-support which projects from the upper arm.

In accordance with a custom of ancient and more especially Oriental religion the priest is here represented in the character of the god. There are several much-restored copies of a statue which represented Dionysos as wearing a girt-up chiton, a nebris confined by a belt, a mantle, and long hunting-boots. The figure is usually restored as holding a kantharos in the right hand, and a thyrsos in the outstretched left; the left arm rests on the head of an archaic idol. The type was known in the Cyclades; it appears on a late Greek silver coin of Andres (B. M. Catalogue, Crete and Aegean Islands p. 86, No. 2, Plate XX. 10). The obverse is 'Head of young Dionysos r., his hair long and wreathed with ivy, like that of our statue; reverse 'ANAP ION youthful male figure (Dionysos) l., wearing short chiton; his r. is extended down above a tripod, his left is placed on the top of thyrsos (?) '; I have examined the coin itself and thought that I recognised a nebris passing over the shoulder. There was a famous temple of Dionysos in Andros; containing a fountain which ran wine at the festival called Ocobaiora; the figure on the coin probably reproduces the temple-statue. It recalls Callistrates' description of a bronze Dionysos by Praxiteles, which were an ivy-wreath and a nebris and held a thyrses in the left hand. The Deepdene statue is decidedly Praxitelean,3 and may be directly related to the type which was worshipped in Andres and was adopted, as the attire and attitude of the Hierophant prove, by the Legol Mooras of Melos.

Change, Vol. IV. Pl. 695, Figs. 1614, 1615. The former, at Decydone, = Michaelie, Ancient Muralles in Grent Britain, p. 280. For other instances of the type, see Rosslier, Muth. Lec., p. 1133 (Dionyses in Art, by Thrimer). A

pardalis sometimes takes the place of the indicate in our figure the arriar has compromised; the hosts are cloves, but the mask is a panther's.

* Cf. Puriwingler, Mosterpiece, p. 323, 5.

The lower part of the figure consists of a plain shaft, on which the inscription is cut, and a larger base meant to fit into a pavement. The back and sides of this base are for the most part left rough, which accords with the supposition that the herm stood in the niche (C in key-plan) near which it was found. In front the smoothly dressed surface shows where the base met the marble stylobate. Three akanthos leaves spring from the pavement-level and clothe the foot of the shaft.




FIG. 7. - MARBLE BARRS.

The inscription, which in the forms of its careful deep-cut lettering resembles that on the Dionysos Trieterikos basis (Fig.7), cannot be much later than the end of the second century; on the other hand the coarse and ugly workmanship of the hierophant and the mouldings on the basis make it difficult to date either of them as early as Hadrian's time. Both may be older than the Hall of the Mystae; at any rate the niche looks as if it had been built to accommodate the herm.

A later group of inscriptions, in which Γ and W are used for Σ and Ω , consists of the prayers to Athene and the Fortune of Melos incised on two columns of the Hall, and the dedication on the bust of Anrelia Euposia (Fig. 8). To these we may perhaps add the inscription on the mosaic (Fig. 5 above), which seems to have had W in the last word. The poor style of the bust, in particular the clumsy lines of its rectangular pedestal, and the rudeness of the sculpturings on the columns mark a further style of degradation; they may belong to the early part of the third century, when the names Aurelius and Aurelia were very common. The phrase $\ell v \tau \tilde{\varphi}$ $\ell \delta \ell \varphi$ $\alpha \tilde{\nu} \tau \tilde{\eta} \tilde{\varphi}$ $\ell \gamma \varphi \tilde{\nu}$ implies that the Hall or some part of it had been built or restored at the expense of this Aurelia Euposia. We have already seen reason, on grounds of style, to assign the mosaic to the first part of the third century. It may have formed part of the $\ell \gamma \gamma \sigma \tilde{\nu}$ in question. Alexander, who on the column-inscriptions is called $\kappa \tau \ell \sigma \tau \eta v$ of the Mystae (Fig. 1), must have carned this honorary title by some similar benefaction; it is not necessary to suppose

that he was the original founder of the Society. His appeals to the favour of Athene and Tyche, the guardian-goddesses who appear on the Roman coinage of the island, suggest that the cult of Dionysos Trieterikos had been newly introduced and might arouse the jealousy of the older divinities; and the fact that these appeals were incised in a prominent position on columns of the Hall may mean that he was responsible for the building.

With regard to the style and date of the three heads found upon our site (Cavvadias, Catalogue, 329, 424, 459) Mr. Crowfoot, who has made a special study of portrait-sculpture, writes to me from Athens as follows:—



FIG. 8.—BUST OF AURELIA EUPORIA.

'These heads all seem to belong to the same period, the early decades of the third century A.D. The close-cut hair of the boy is similar to that

Fortuns, which was at Romo when Pliny wrote. The people of Antioch were doubtless following an established fashion when they set up a statue of the Fortune of their city early in the 3rd century. See Wolters' article in Ath. Millh. xv. For the Melian type of Tyche bearing the infant Plutus, cf. the status at Thebes, Paus ix 16, 1;

The worship of Atheno, as the very archaic character of the xonnon on soin and column-relief shows, was much older than that of the Tycha of Melos. But the latter patriotic cult may have been established as early as the 4th century n.c., by the remaint of the old population whom Lysander sent back. Cf. the Tyche made by Praxiteics for Megars, and his Bons.

worn by Alexander Severus and his successors, and the short curls of the hierophant to those of the emperors at the beginning of the century. The coiffure of Aurelia may be related to some of the fashions which prevailed in Rome during the second quarter of the same century, or may be a modification of an earlier fashion, set perhaps by Julia Domma. (It would obviously be rash to say that the Melian bulies were always successful in copying the short-lived fashions of the capital.) Such a date suits the style perfectly. The bust of Aurelia is the rudest, but all three are as good as most contemporary Athenian works. The surface is polished and the eyebrows not raised but incised; in both points this is a contrast with the treatment usual at Athens about the middle of this century, of which we have a dated example in the Kosmete, No. 388 (Archanship of Kasianos, 236 or 245 A.D. Cf. Dumont, Sur l'Ephébic attique, I. p. 247). The Melian works are at least successful in portraying distinct characters, and are interesting, therefore, for the light which they throw upon "certain people of importance in their day." The sour face of the hierophant is hardly more attractive than the lady's expression of obstinate bigotry; combined they are sure evidence of the psychological atmosphere of the third century, and differ strikingly from the air of blost refinement which is dominant among the Antonines.'

To the inscriptions already published may be added a mason's mark

DIA

cut on the top of a column-drum at the S.E. angle.

The Society of Mystac.

Associations of worshippers of particular deities had been common in Greece since the fourth century B.C. under the name of δργεῶνες, θιασῶται, or ἐρανισταί.¹ The Mystae of Dionysos Trieterikos may be compared with a number of other Dionysiac societies, calling themselves of Μύσται, which flourished especially in Asia Minor and Thrace during the second and third centuries A.D. We find them at Smyrna (with a cult of Dionysos Βρεισεύς), Ephesus (cult of Demeter and Dionysos Φλέως), Teos (Dionysos Σητάνειες), Magnesia on the Macander, Seleucia in Cilicia (D. 'Αρχίβακχος), in Western Thrace (D. Βότρυς), and at Apollonia on the Black Sea. They had much in common with the associations called of Βάκχοι and τὸ Βακχείον, which existed in the period at Athens, Megara, Cuidos, Cyzicos, Perinthos, Thasos, and Tomi. Our knowledge of both groups of societies is derived from inscriptions, of which the most important is one found at Athens which contains the statutes of the Iobacchi and the minutes of one of their meetings.¹ This curious document gives the most minute information about the

from Fourart's Associations etligiouses.

The inscriptions relating to these and other associations among the Greeke have been collected by Erich Zhilarth, Lies grischische Percessures, Leipsic 1896. The facts which follow are drawn in the main from this work and

² Published by S. Wide, Ath. Mitch. 1894, p. 257, and by E. Maass, with fuller commentary, Orphone, p. 18.

constitution and procedure of a Bacchic society, the election of members, entrance-fees and subscriptions, the duties of the officers, the meetings at which the members drank wine in the Society's banqueting hall, and the strict rules which were found necessary for the preservation of order.

The Mystae of Melos honoured their hierophant with a portrait-statue. About the same time, early in the third century, τὸ ἰερώτατον νέον Βάκχιον of Thasos paid a similar compliment to their hierophant. We also hear of a hierophant in connection with the Mystae of Ephesus and of Magnesia. The fact that at Cyzicos the names of the hierophant and the μυστάρχης, followed by those of the Mystae, appear in a list of public officers, shows that there at any rate they occupied a prominent position. The officers and many of the members of these societies were persons of good birth and standing. In many cases women were admitted to membership and to office. The βάκχοι of Tomi are called Πασοῦς ἱερὸς θίασος, apparently after their foundress. There is nothing unlikely in the assumption that the rich lady whose ἔργον is mentioned on her bust (Fig. 8) was a member or even an officer of the Melian Mystae

The inscription on that bust raises a new point of some interest; it reveals the existence within the society of a body called οἱ περιβώμιοι. We might suppose that these were members who had attained a higher stage of initiation, privileged perhaps to take part in some sacrifice or choric dance weel βωμόν. But the inscriptions which give so full an account of the organisation of these societies say nothing of such a subdivision. On the other hand we find constant mention of a throng of functionaries, who bear a great variety of names. The Iobacchi had six officials, the Mystae of Magnesia five. The Boundain, a Bacchie society of Pergamon, had an άρχιβούκολος, a secretary, two singing-masters, three Sileni and a choragos.1 The height of extravagance is reached by the Mystae of Apollonia on the Black Sea, whose eight officers bear names suggestive of the cult of Zagreus and of the Tricteric festival that was celebrated on Parnassus and Cithaeron and in Crete. The Mystae of Dionysos Trieterikos in Melos may also have had their λικναφόρος and κρατηρίαρχος, their άρχιβασσάρα and κισταφόρος. By of περιβώμιοι we should probably understand the whole body of officers. This interpretation may help to explain the only passage where the word occurs in classical literature. Juvenal (ii. 16) describes a man of infamous life, evidently a well-known character, under the name of Peribomius. There is a scholion, Peribonius: nomen archigalli. If the person referred to was a priest of Cybele, and if, as our inscription suggests, περιβώμιος was a general title for the functionaries attached to Asiatic cults, the name chosen by the satirist conveys just the discreet hint which might be expected.

The discovery of the hall in which the Mystae held their meetings is an

The twelve priests mentioned as conducting a Dionysiae festival in Patmos, in a passage quoted by Maass, Orpheus, p. 52, from the Acts of John, were probably the officers of an asso-

clation of aderes or Sdaxes. This description by a hostile writer shows us a Bacchie society at its worst, just as the rules of the Iobacchishow one at its best.

important addition to our knowledge of these associations. Such halls are mentioned in inscriptions under the names olkia, olkor, or iepov. Its resemblance in general plan to the Hall of the Iobacchi at Athens (p. 65, note 1) confirms the view already expressed as to the similar character of the societies

of μύσται and βάκχοι.

The building remained in use for a considerable time, so long that in several places the mosaic became worn; instead of being repaired or renewed it was roughly patched with bits of marble wall-lining. Judging from the fact that on Roman provincial sites it is not uncommon to find traces of three or more tessellated pavements one above another, we may estimate the probable life-time of such a floor at from 100 to 150 years. There is no reason to suppose that the building was ever converted to other uses; had that been the case the statue of the hierophant would not have remained unmolested in its niche, still less have been left in fragments on the floor, It looks as if in the course of the fourth century the meeting-place of the Mystae was first neglected, then deserted, lastly stripped of its marble fittings. The removal of the stylobate slabs which formed its secket would naturally occasion the fall of the statue; it was pushed on to the pavement and lay there, broken by careless hands; but not mutilated by the spite of fanatics as were the torses discovered in the Three Churches excavation (J. H. S. xvii. p. 131). Later the collapse of the roof buried it in fallen plaster, Last of all the construction upon the rains of a broad cultivation-terrace preserved to our own day both the statue and the finest part of the pavement.

The head and body of the hierophant are still separated. It is to be hoped that the authorities of the Athans Museum will not neglect the opportunity of securing the body, which remains at Melos in the warehouse of the proprietor of the site. By so doing they will double the value of the head which they already possess and add to their collection a new type of

the highest interest.

I have to thank Mr. Duncan Mackenzie, my colleague in the excavation, for a number of valuable suggestions.

R. C. Bosanquet,

A SUMMER IN PHRYGIA: II.

[PLATES IV., V.]

THE PHRYGO-LYDIAN FRONTIER.

AFTER exploring the north side of the Lyces valley, and before proceeding down the right bank of the Macander towards Ortakche (see Part I. init.), we spent a short time in the Phrygo-Lydian borderland, seeking for some evidence to clear up the uncertainties attaching to the situation of Sala, Tralla, Actos, Kallatebos, and Apollonos-Hieron. (See Plate IV.)

In discussing this district, I enjoy the advantage of having before me the work of three provious explorers, Prot. Ramsay, Prof. Radet, and the late Dr. Karl Buresch. I have been careful to quote the opinions of these critics, though I must sometimes differ from them, because it is convenient for the reader to have before him all the views that are, or have been, held in regard to each town. Amid a few differences, I find myself in general agreement with Prof. Ramsay and Dr. Buresch. In the development of their views from the earliest to the latest stage there is, happily, a stendy approximation towards the same results :; and yet, by a strange accident, this approximation was quite unconscious, for Dr. Buresch knew only Prof. Ramsay's earliest views, while Prof. Ramsay in his latest work had only a very imperfect knowledge of Dr. Buresch's earliest opinions." I regret that I am obliged to differ more widely from the results reached by M. Radet, and, as some readers might put a wrong construction on such expressions of dissent, I would here record my appreciation of the value of his fresh and suggestive work. When a subject is in process of growth, every suggestion and every fresh point of view are valuable, and it is only by due consideration and open criticism of all proposed combinations that we can cherish the hope of ultimately reaching, or approximating to, the truth,

SALA.—Starting from a point opposite Tripolis, we proposed to keep along the left bank of the Macander towards Tchindere keui, and then cross

¹ The obligations expressed to Prof. Ramssy in Part I. have to be repeated here.

² This is the more striking when we consider that Prof. Ramany had explored only the fringes of this district.

^{*}We may take as an example the case of Mysotimolos. Buresch at first rejected Rameay's view in the strongest terms, but recently he him

came to regard it as 'and richtigem Wege' (Merzeber, p. 108 = Ann Leption, p. 201): only he would place the town never Blaundos, while Ramany in the meantime has also found reason to bring it nearer Blaundos (CB, vol. it.). Again, in regard to Apollones Hieron their earliest views differed greatly, while they are now (as we shall see) practically agreed.

over to Geune. A few minutes ride brought us opposite the hot springs (Ridja), mentioned by Arundel 1 and Hamilton,3 which are built over in the conventional Turkish style, and used as a hamman (bath). In half an hour more we came to another very hot spring (likewise on the right bank), which has formed around itself a rocky incrustation, over which the water flows down into the river. About this point we entered the great gorge in the Mossyna mountains, through which the Macander forces its way smid picturesque scenery into the low-lying valley of the Lycos, and we travelled up and down its steep sides for nearly two hours to Dere kemis (850 ft. above the Lycos valley), and thence for two hours more to Tchindere keui (1100 ft. higher), near which we copied inser. 14. On the opposite side of the canon. almost on the same level as Tchindere keni, lies the large village Genne, a governmental centre, and seat of a mudur. Our chief object at Goune was to find and examine the extensive ruins seen by Hamilton east of the village, between it and the Macander. 'While crossing this flat country,' he says (II, 371), 'my attention was arrested by several square blocks of stone in the fields on the right; and on proceeding to examine them I found myself on the site of an ancient city. The ground and walls between the enclosures contained many similar blocks, some of which were still in situ, others were pedestals, but without inscriptions, while broken pottery and tiles lay scattered about in all directions. The most remarkable feature was what may be called a street of tombs, extending in a north by east direction from the town. All of them had been much injured, but the foundations of many were still perfect. The whole area of the city had been ploughed over, but the remains of walls of houses and other buildings were everywhere visible. . . . A little to the south-west of the tombs were the foundations of a small building, with several broken columns five or six feet high still in situ. . . . The rains extended on both sides of the road, and were in places much overgrown with vegetation . . . The Turks call them Kepeiik . . . Arrived at Genne, we naturally expected to have no difficulty in finding a guide to show us these mins, which were so conspicuous in 1837; but no one in the village seemed to know anything about them. This extraordinary fact is confirmed by the experience of the late Dr. Buresch, who visited Genne some years ago but failed, notwithstanding the assistance of the 'courteous mader,' to discover any one who knew anything whatsoever about the existence of Hamilton's city. Unable in the poor state of his health to undertake the task of searching for a site which was unknown to the natives, he naturally concluded, that 'like numberless other ancient towns, it had vanished from the face of the earth." Such, however, is not the case. When we set out

¹ Resembles L. p. 526.

³ The Seven Churches, p. 227.

⁴ Not Dede kani, as in CB. L. p. 104.

At Genne I heard of the previous visit of an archaeologist whom I inferred to be Dr. Burneth, but unfortunately I had not seen his Reinhericht, which appeared in Rev. dev Kgl. Sucha. Ges. d. Wiss., 1894, p. 88-123, and has been reprinted

in the full account of his researches, Aus Lydies, spigraphisch-prographesche Kresefriichte hinter-tasses sun Karl Buresch (published just as this [mpst was going to press). I have added references to the latter.

^{*} Aber ich glaube sernichern zu stätzfen, dans sie wis ungzählte endre som Erdboden serschwanden ich, p. 108 (= Aus Lydien, p. 205).

in despair to search for the ruins, we found that they were not unknown to some of the peasants in the fields, and though nothing would induce them to leave their work and show us the spot, we ultimately discovered the site. just where Hamilton placed it, on the level plateau fully three miles cast of Genne. The rains have become much more rainous since Hamilton's visit. The stones have been thrown into ignominious heaps to make room for vineyards and cornfields, or used to build huts and outhouses; yet a few blocks still remain in situ, and the foundations of a large rectangular building (with portions of one or two courses of stones) are still visible. The 'street of tombs' has entirely disappeared, but some fragments of columns and innumerable squared blocks extending over a large area on both sides of the road attest a city of considerable size. Not a single inscription is to be seen; Hamilton found none when the ruins were more numerous and better preserved, and our search of two hours resulted in nothing but the discovery of the 'Constantinian' monogram within a circle, neatly carved in relief on the end of a large rectangular block.

Without excavation we cannot hope for documentary evidence to fix the name of this city.\(^1\) But the choice is small: it must be either Sala or Tralla. Now Sala was the more important of the two, and these ruins are by far the most imposing of the midentified ruins which exist in this district. Moreover, as Prof. Ramsay points out (CB. i. p. 179). Sala, like Blaundos, is assigned to Phrygia by Ptolemy (v. 2, 27) and by numismatists, to Lydia by the Notition: hence both towns must be looked for in the same direction, and no site west of the road (or on the road) from Tripolis to Sardia could possibly be assigned to Phrygia. These considerations lead us to adopt the opinion of Prof. Ramsay (Ls.) and Dr. Buresch \(^2\) that the site is to be identified with Sala. The perfectly defenceless character of the site, which may be compared with Bria (see Part I. p. 415), suits the view expressed in CB. p. 179 that it was a Pergamenian foundation established as a counterpoise to the Seleucid city Blaundos.\(^3\) Prof. Radet places Tralla here, as Prof. Ramsay did in his first essay; Sala he puts far away at Göbek (En Phrygia, pp. 107-109).

AETOS *.—'Αετός, a place of importance in the Middle Ages, is mentioned by Nicetas in his account of the march of Frederick Barbarossa (1190 A.D.) from Philadelpheia to Laodiceia by way of Tripolis, and also in the Natitiae where it is conjoined in one bishopric with Apollones-Hieron. Tomaschek has acutely pointed out that the modern village Aidos 7 on the upper waters

Some evidence might be found if all the blocks could be turned over and examined: but our efforts were nurrewarded.

In Anterracht three Redesting bin ich . . . pennigt in ihr Sala zu erkennen (Reiseb, p. 108 := Aus Lyd. p. 205).

^{*} The Epirote name MOΛΟΞΟΣ occurs on its coins (ep. Part I. p. 408). Hamilton could find no traces of fortification (II. p. 87).

Cp. Hist. Geog. p. 124, CB, 1, pp. 194,
 497, etc.

Nic. Chon. p. 539 ed. Bonn. δελ τοῦ 'Asταῦ χάρου λεγομένου πορέυθέντει, which mount that Preducick marched through its territory (not uccessarily through the town).

^{*} Not. X, 232 and XIII, 92, ed. Parthey and Plader.

Tomaschek, Zur hist. Topoge, von Klein feien im Mitteleder, p. 08. He falls into error, however, when he says der antike Name von 'Aerès war 'AwéAlaror lepèr (Not. up.),' misunderstanding the meaning of free. Aldos is

of the Kogamis, two hours WSW, of Geune, retains the ancient name. The old site however is, as usual, at some distance from the modern village. About two miles lower down the Aidos Dere, on its right bank, there rises a conical hill which the natives call Assar, isolated on all sides except the north, where it is joined by a low ramp to the ridge which bounds the Dere. On the hill there are distinct traces of ancient life: we saw a few blocks of stone lying about near the foot of the slope (including one or two marbles), the remains of a flight of steps leading up the SW, side, the foundations of a small Byzantine chapel on the summit, and small fragments of tiles and pottery strewn about over the hill-side. Amongst these fragments I picked up a few painted pieces which Mr. Cecil Smith has been good enough to examine: mest of them may be late, but one fragment showing a series of concentric circles on a light-red background, a pattern so common on Cyprian ware, is (he says) genuine Greek work and may go back as far as the fifth or sixth century n.c.¹

A glance at the annexed map (Pl. IV.) shows that Assor is a point of strategical importance, commanding not only the road from the Kayster Valley by Kirk Tchinar Devrent to Sala (Geune) and the East, but also, to a certain extent, the path along Karindjaly Dere which Frederick Barbarossa followed in his march from the plain of Philadelpheia to Tripolis, avoiding the direct route through the pass Devrent (or Derbent) Boghaz. His army was attacked after leaving Philadelpheia, and by making this détour round by Actos he

avoided all necessity of fighting his way through the pass,

A different identification of Actos is proposed by Dr. Buresch. He would place it beside Kirk Tchinar Devrent ('Devrent of the forty planetrees"), a village at the entrance to the pass, where there is an old site called Devrent Kalessi* similar to Assar: and he also suggests that Kallatebos (Herod. vii. 31, see below) may be placed there. He argues that in the two days' march from Philadelpheia to Tripolis Actos was probably the intermediate station. Now, apart from the fort at Devrent, it seems impossible to find a site which will suit the dates of the march; and this situation 'possesses the characteristic (a very important one for our identification) which Herodotus attributes to the position of Kallatebos, viz. παριέναι πάσα ἀνάγκη ylurrat: that is, as the Persian marching from the Macander plain to the Hermos valley in 481 B.C. must necessarily pass the fort of Devrent, so the Crusaders in 1190 A.D. could not avoid passing it. 6 But in estimating this theory we must bear in mind that his exploration was incomplete: he did not visit the site at Assar or observe that Aldos retains the ancient name. Of Kallatebos we shall speak presently; but the preceding exposition has shown that Frederick could and did avoid passing the fort at Devrent

matos)

new carruptly pronounced Atdas. Tomasshink's identification of Actos with Aides is accepted both by Prof. Ramesy and by Prof. Radet.

¹ So far, of course, as one may judge from a small fragment.

² So called in Kiepert's map, but, I think, not rightly (though I am not sure of the sorrest

We followed this route in going from Aidos to Baharlar: it is an easy road.

^{*} Or Asser.

hale nach der Mainndecachene.

^{*} Reisebernate, p. 111 (= Ann Lychien, p. 207).

TRALLA.—But we can approve everything else that Dr. Buresch says about Devrent Kalessi. The hill (which is not very large but somewhat steep) is situated a quarter of an hour W. of Kirk Tchinar Devrent. Lying as it does at the point where the great road through the Kogamis valley emerges from the long narrow pass and crosses the road leading from south-east Lydia into the Kayster valley and thence to Ephesos, it is obviously of 'extraordinary strategical importance.' 'It would be strange' (as he says) 'if this important point had remained unoccupied...; it might be said that Nature had expressly formed it to bear a castle and set it as a sentinel in this important place. Remains of late fortifications and foundations of houses on the not very roomy 'summit, fragments of pottery and tiles acattered in rich profusion over the summit and slopes, a sarcophagus accidentally uncovered on the S.E. slope, and finally the Roman and Byzantine coins found here, show that right into the Middle Ages men have lived and watched here (p. 110 = Aus Lydien, p. 207).

What name, then, is to be assigned to this site? I think we must identify it with Tralla, following Prof. Ramsay's first suggestion (in CB. p. 180). He rightly says that 'the very name would suggest its origin in a settlement of Thracian mercenaries, who under the name of Tralleis or Traleis. served under the Pergamenian kings along with Mysian, Paphlagonian, and other troops . . . and Tralla perhaps lay near the Derbent-Boghaz, commanding the important road from the Hermos to the Lycos valley. In later passages (e.g. pp. 200 a. 2, 580 f., 688) he inclines to identify Tralla with Actos (which also occurs as a Thracian name, Niceph. Bryen, p. 149), taking Actos as the name given by the Thracian Tralleis to their own town, while Tralla was the name used by others (CB. ii. p. 580, a. 5). But the fact that Tralla and Actos are both mentioned in Not. x. 228,

232, and Not. xiii. 88, 93 seems conclusive against this view.

An important confirmation of our identification is to be found in the Peutinger Table, which places Tralia at a point where a road from Philadelpheia forks, one branch going to Peltai and Apameia, the other to Laodiceia. It is represented thus:—



¹ My note says, 's time space on the top."

We may add (1) traces of steps up one side (2) quite near the foot remains of building in much better style than those on the summit. The cometeries of the village contain a very few old stones.

⁸ Tpakers Incohr. Perg. no. 18: Heaych, s.v. Tpakkers (up. Tomaschek Die alten Throbos h. n. 44).

[•] His map (vol. I.) rightly indicates Tralla annualists in the Devrent Boghas (in accordanos with the view expressed on p. 180).

Prof. Ramsay, following a hint of M. Radet's, has shown that there are two reads mixed up here, Philadelpheia-Tralla-Peltai-Apameia, and Philadelpheia-Tralla-Tripolis atc., which in reality aniacide in part (viz as far as Tralla). Now Devrent Kalessi is just about 25 Roman miles from Philadelpheia, and the situation therefore suits excellently his proposed restoration, Philadelpheia xxv Tralla xxviii Atyokhorion, etc. (CB. ii. p. 580). In spite of the jumbling, the Table still rightly indicates the fact that at Tralla there is a parting of the ways, one going to Laodiceia, the other to Peltai and Apameia.

The road from the Kayster valley joined the Kogamis valley road at Tralla (beside Kirk Tchinar Devrent). In the upper part of the Kadi keui Deressi remains of the pavement of this road are still visible, and in an old cemetery hidden amongst trees, 25 minutes southeast of Kadi keui (which is about four miles from Devrent keti), I copied the following milestone, which makes Tripolis the coput viac. The stone is unfortunately in very bad condition.

There is a milestone of Jovian at Apameia (C.I.L. III. Suppl. 7034), otherwise we might restore [Iiil]iano.

At the bottom of the left-hand side there is a fragment of a Greek inser, engraved the reverse way in small characters, which seems to refer to a different emperor (? Gratian).

The form Tripoli is curious.

KALLATEROS.—From Aidos we crossed over the hills to Baharlar, a village in the Kogamis z valley south-east of Inc Giol, and recopied there the

^{&#}x27;He ingeniously explains Stourage uses Latin corruption of 's xepics 'Areas through the form s-cor-atu. The reading is not certain, as may be seen from the photographic representation

⁽Vienna, 1888).

So on a coin (CB, p. 196 m. 3); Cogumns in Pliny.

inscription in which M. Radet believed he had found documentary evidence for the situation of Kallatebos (Herod. vii. 31).

In the epigraphic copy I have tried to represent the inscription exactly as it is on the stone. The shaded part is a hole cut in the marble, which has destroyed the important portion of the text. As I have already said, the present state of this stone is remarkable: some letters have partially, others wholly disappeared, and yet the polished surface remains intact. I have therefore not used the shading which is generally employed to indicate breaks in the stone, except where there are actual breaks.



"Ετ ους . . . της Καίσαρος
νί]κ[ης μη(νός) Π]ανήμου δ΄, οἱ κάτο]ικ[οι ἐν . .]λβοις ἐτείμησαν
Θ[ευδαν ἢ Θ]εοδώρου Θεόφι[λδ ο]ν ἤ[ρωα τὸν] ἐαυτών εὐεργέ[τη]ν ἀρε[τῆς] ἔνεκεν καὶ εὐνοία]ς τῆ[ς εἰς] ἐαυτούς, ἄ[νδρα
ἀ]γο[θόν], ὑμεῖν στο[ι]ὰς [καὶ βουλευ]τήριον καὶ εἰς ἀπο[δοχεῖον
10 ὑ]δραγώγιον ἐκ [τ]ο[ῦ ὅρους ἀπεργασάμενον.]

Notes.—I. 1, My impression was that the left edge of the stone was not broken. Buresch says that before the k the whole | [probably part of N]

Radet, B.C.H. 1891, p. 373 ff.; ep. CB, 1
 (Aux. Lyd. p. 298) restores the first three lines.
 p. 199 f. Burosch, Reisedericht, p. 112 f.
 Athenaeum, Oct. 23, 1897, p. 566.

is preserved hart um Bruchrande: if so, the edge must have got rubbed down, and I have arranged the restoration on this supposition. L. 2, probably M, as Buresch says, the M being spread out. L. 4-5, the restoration of the name seems doubtful. L. 7, ἄνδρα suits the traces [the F is squarely cut] but the introduction of the second person in ὑμεῖν is very odd. L. 8, there is space for a latter between O and A: στοιᾶς occurs C.I.G. 2483. L. 9.

perhaps arodoxecor, i.e. 'reservoir' (= \$\$\delta\delta\delta\text{ytop of \$C.I.G. \$454}).

The restoration of 7-10 is, of course, not certain: but the crucial line is 3. M. Radet wishes to make the name of the karousia Kallataboi for better Kallataba], assimilating it to Kallatebos, the town which Xerxes passed on his march between the Macander and Sardeis. Unfortunately, M. Radet's restoration is quite impossible. The number of letters lost between IK and ABOIE cannot be more than six, allowing for at least one narrow letter 1: seven occur in an equal space in L B, but there the letters are slightly smaller. oi ka[το] κ[οι οί ἐν Καλλατ] άβοις οι οί Κάρες οἱ ἐν Καλλατάβοις (which is in itself most unlikely and does not suit the letters) are therefore both impossible, even if of be omitted. It was audacious to say that 'Kallataboi, being given by epigraphy,' ought to be preferred to Herodotus' form Kallatebos (B.C.H. Lc. p. 376)! Another suggestion is that of Prof. Ramsay in CB, ti. p. 573 µ. 5. He has come across a reference to 'Αρδαβαῦ ἐν τῆ κατὰ τὴν Φρυγίαν Μυσία," which he thinks 'may very well indicate the Mysian country that lay south and south-east from Philadelpheia on the Phrygian frontier (ii. p. 573); and he suggests of ka[το]ικ[οι έν *ApolaBors as a possible regtoration of our inscription. This is, however, alightly too long : and moreover the termination is most probably-\Bois, an objection which would also apply to the late Dr. Buresch's κά[το]ικ[οι οί έρ] "Aβοις, giving a name "Aβa, which is a possible form (cp. Steph. Byz. s.v.). We must reluctantly conclude that the name of the karoikia is lost beyond recovery.

As to the provenance of the inscription, Dr. Buresch says that all accounts assigned it to an old site N.E. of Baharlar on the other side of the Kogamis, stretching from the foot of the hills nearly down to the river and with its N.W. edge not far from Bahadyr keui. I received the same account; and the spot whence it is said to have been taken (beside an old cemetery beyond the river) was shown me by a villager who was present at the ceremony. The ruins at this site are extensive but characterless. Now

But I that not think they extended nearly so far as Bahadyr keni,

This nearly agrees with Barrech '4 sem frequenche lake MTH) oder zur Noth 4 Buchstaben som Durchschräftsbrack und 2 schmale (d. h. l.) rerocklungen Laben. My views were formed at Saharlar before I knew of his paper

[&]quot;Allowing for two narrow letters (like I or P) and considering that the letters are not always of quits the same breadth, nor equally spaced; I said in Allormouse that 'the spacannot contain above seven letters'; but the

shire statement is more exact,

³ Enseblus, Hist. Eccl. v. 16 (referrises to Montanua).

I made a noise to the effect that the letter before B is apparently A, although it might possibly have been A toomidaring the way in which parts of letters have disappeared.

though we cannot restore Kallataßa in this inscription, can we suppose that these ruins represent Kallatebos, considering that after the foundation of Philadelpheia the older waxes dwindled into a mere sarousia! That it did so dwindle is most probable, and the site is not unsuitable, though one rather nearer Ine Giöl would be preferable. It is at least certain that Kallatebos was near Inc Giol. What Herodotus says is, that in marching from Kydrara [Hierapolia] to Sardis it was absolutely necessary for the Persian army to cross the Macander and pass by the city of Kaliatebos, SiaBhyai Top Malayδρων ποταμόν πάσα άνάγκη γίνεται καὶ Ιέναι παρά Καλλάτηβον πόλιν, έν τή ανόρες δημινεργοί μέλι έκ μυρίκης τε καί πυρού ποιεύσι, i.e. there was only one possible road, the road which goes through the Devrent Boghaz and along the river-valley, passing by Ine Giol and Ala Sheher (Philadelpheia). And Hamilton observed that the tamarisk does not grow in the mountain passes, but occurs in great abundance in the valley of the Cogamus, near Aineh Ghieul' (ii. p. 374). The old site opposite Baharlar, therefore, may very well represent Kallatebes, for the plain round Inc Giol would in any case be part of its territory; but it is possible that the site of the city was nearer Ine Giöl and has completely disappeared.1

Apollonos-hieron or Apollonieron has evidently been found by Dr. Buresch, who places it at an old site 2½ kilometres E.S.E. of Bôs Alan. This confirms Prof. Ramsay's suggestion (CB. i. p. 194 f.) that it should be looked for at or near Bulladan, which is the important town of the district and a governmental centre (seat of a kaimmakum). I agree with Dr. Buresch that Bulladan is a purely modern foundation; but to it have passed the heritage of Apollonieron and the name as well, for Bulladan or Bullandann is not a Turkish word, and Prof. Ramsay is clearly right in saying that it 'retains the ancient name Apollonieron, just as Abulliont in Mysia retains the old name Apollonia.' M. Radet places Apollonos Hieron at Erziler, north of Aidos.

THE LYCOS BRIDGE.

On our way eastwards, we may be permitted to stop again for a moment in the Lycos valley to note an interesting discovery made by my friend M. Weber of Smyrna, who desires me to publish it here. Last autumm M. Weber found the ruins of the bridge which carried the road from Laodiceia to Hierapolis over the Lycos. This bridge was evidently a solid structure built

Herod, 's words, which simply state the fact that the sale seculable read was that on which Kallet lay. The Bakarlar site is, therefore, not a whit more 'maningaughth' than Inc Giol or any other point on the read.

We cannot therefore approve Buresch's idea (quoted above, under Actea) that Kallat, might be placed at Devrent Kalessi. Speaking of the site near Baharlar, he sakes Kannot man near cluss diese für üle Stelle iles herneletekene Kaλλάτηβοι, der unumgänglichen Wegestation, unsprechen? Teutes ist, dass men janer Stätte schon seelt aber ole Inv Gjöl die Eigenschaftes eines als 'snampangick' gekommeriehntes Punktes suspreches ktousts (p. 117 – Anc. Lyd. 212). This entirely misses the point of

For the loss of the a, see CB, p. 195 note 1. Compare also Bulawoodin or Bulawoodin, the modern name of Polybôtos. The sense to which a modern town may be said to represent an ancient one is clearly defined in Hist Grey, p. 83.

of fine large blocks, with three arches, of which the central one is still complete. It is situated about half a kilometre to the north of the point where the river Asopos now joins the Lycos, the ground between it and the present course of the river being now an impassable marsh. The discovery is important as showing that the Lycos has here changed its course considerably.

COLOSSAE.

Two inscriptions of Colossae have to be added to the small list we already possess. The first is a dedication to Hadrian by a tribunus militum.

25. In a field near the ruins.

 ΑΥΤΟΚΡΑ
 Αὐτοκρά

 ΤΟΡΙΚΑΙΣΑ
 τορι Καίσα

 "ΙΤΡΑΙΑΝΩΑ
 ρ]ι Τραιανῷ [Α

 ΔΡΙΑΝΩΣΕ
 δριανῷ Σε

 "ΜΛΣΤΩΘΛΥΙΙΙΙ Βαστῷ 'Ολ[υμ σίῳ Δ Μα

 ΠΙΩ ΛΜΑ
 πίῳ Δ Μα

 ΚΕΔΩΝΧΕΙΙ κεδῶν χ[ει λίαρχο[ς.

26. In another field.

'Αγαθή Τύχη.
πυγμαχίης τόδ' ἄεθλου έγω Κάστωρ άπεδέγμην
νεικήσας σθεναραίς παλαμ[α]ίς ἄξυστος ἄμωμος·
οὐδὲ γὰρ ἤν θέμις ἄλλω ἀδελφειῶ Πολυδ[εύ]κους
χεῖρας ἀνασχ[εμ]έναι πυγμῆς χάρ[μ'] ἀν[τι]πάλοιο.
ἀθλοθέτ[ης] δ' έμὲ παῖς [(name) κρείττον ἔνειμε ?

L 4, XAPNAN- .|ΠΑΛΟΙΟ. Nothing seemed to have been engraved after ΠΑΙΣ.

In the inser, published by Waddington, no. 1693b, from a copy by M. Renan, read in l. 1 [.... ἀνέθηκεν τὴ]ν θεὰν Τόχην τῆι πατρίδι. Cp., for instance, an inser, of Antioch, Sterrett, E.J. no. 97.

ANAVA-SANAOS.

Three inscriptions of Sanaos, which had to be omitted in Pt. I. on account of the strict limitations of space imposed, are added here.

27. On a large architrave block, in the cemetery below Sarikavak.

Διοδώρου καὶ Καλλιστράτου τῶυ Καλλιστράτου ὁ τόπος.

The two sons are the same who are mentioned as having taken part with their father Kallistratos, son of Diodoros, in presenting a βουλευτήριου to Sanaos (M. Weber in Ath. Mitth. 1893, p. 207 = CB. no. 83).

28. Used to cover a kuyu in the watercourse of the fountain: dug up and replaced for a consideration.

THE TAYTAIC COPOICT PORES

THE SEN DIEICINT FOR TONOILAY PHO

BEOYBTOYATION PONION TO POCE THE

BHACYBHICTRACKHOMOYCE OCEN

THE ATAYCMACOPPENHENIHM

THE ANTOYATANICKAIH I'N H

AY TOYA & PIATIPOKEKHALEY

MENIALEHCINCLACTICE TEPONKH

ACYCLENTAICCOPOIC TAYTAICBELI

ICTON PICKON & TENTAKICKINIA

Εν τ ες τ γ ταύταις σοροίς προκε κηδευ μένοι είσιν πρόγονοι Αύρ. Μο υσέου β΄ τοῦ 'Απολλωνίου, προσεπικ ηδευθήσετε δὲ κὴ ὁ Μουσέος ἐν 5 τῆ κατὰ δυσμάς (σ)ορῷ, ἐν ἢ καὶ ἡ μήτηρ αὐτοῦ 'Αταλίς καὶ ἡ γυνὴ αὐτοῦ 'Αφφία προκεκηδευμέ[ν]αι είσιν εἰ δὲ τις ἔτερου κηδεῦσι ἐν ταῖς σοροῖς ταύταις, θησι ἰς τὸν φίσκον δην. πεντακισχίλια.

L. 8 'Aφφίa, more usually 'Aπφίa. On the name, which is probably a Lallname (a by-form of Appa), see Kretschmer Einleitung in d. Gesch. d. Griech. Spr. p. 347. On κή for κal see CB. II. no. 678, p. 742.

29. At Appa (Yokaru), near a well: small lettering.

OYNOMAMENKANONEPM
IACENBADEKEITAICYNTATI
AFAMETHOINANDPODEMA
AICTAKAITPOOIMOYTOYY
IOYOYAENIDEESECTINAN
AOTPILICOMATIEICENMINEITICDEATTEIBHCEIHAM
AOTITTPAEIBHCEITTPOCTMINOY
KA

The first two lines are very rude attempts at hexameters.

THE PLAIN EAST OF L. ANAVA.

The plain east of Lake Anava, now called Taz Kiri, was probably Apameian territory, and it does not seem to have contained any town. There are however considerable remains, including many large blocks of stone and a

Ramsay's reading, UB. 11. p. 525, no. 357, where M. Paris read +le[Ba]aris (B.C.H. 1884, p. 351).

The letters have upices, and in L 2 the stone has favor.

[&]quot; Op. is vir Aurenour, J.H.S. 1887, p. 393.

^{*} Compare locator at Eumeneia, and to Prof.

few unimportant inscriptions, at Basmaktchi (where a weekly market is held): and although they are mostly to be found in the cemeteries and have probably been largely carried from Sanaos, it is quite possible that there was a village here.\(^1\) A small settlement existed at Basmaktchi Yaila, a refugee village high up on Yan Dagh, three hours from Basmaktchi, on the path to Buldur. I copied there the following inscription which is engraved on an enormous block (now broken into two pieces) forming part of a heroon, the foundations of which have been uncovered by the peasants.

30. In the epigraphic text the two pieces are placed together,

EAYTOKALTHEYNASKITATAKATECKEYACENT ETEICZEMHNOC TIPO TOYOYAENIMENTOICES SINZONFERINCETALMZTATHNTEAEYTHN TOYEYK AEOYZANYZAITHNCOPONI KAIETTEICZTENKEINIC OMAETTEIOTOYTO TOAMACACYTEY OYNOCFENHCETAL TOTOKPICKONTONAYTOK PATOPONITPOC 10. TEIMOXTENTAKICXEIAIOICTOYTONAETO

Εὐκλής τοῦ Καλλικλέους Ι τ]ου βωμου καὶ] τὴν σ[ο]ρον καὶ τὰ περὶ τὸν βωμον ζῶν ἐαυτῷ καὶ τῷ γυναικὶ Τάτα κατεσκεύασεν ἔτει σ[ξ]γ', μηνὸς πρώτου σύδενὶ μέντοι γε ο ἔ]ξὸν γενήσεται μετὰ τὴν τελευτὴν τοῦ Κιὐκλέους ἀνῦξαι τὴν σορὸν καὶ ἐπεισενενκεῖν σῶμα, ἐπεὶ ὁ τοῦτο τολμ[ή]σας ὑπεύθυνος γενήσεται ἰς τὰν φίσκον τῶν αὐτοκρατόρων προσ10 τείμφ δην. πεντακισχειλίοις τούτων δὲ τὸ ἀντίγραφον ἀπετέθη ἰς τὰ ἀρχεῖα:

ANTIFPASOMATTE TECHIETAAPXEIA

The date is 178-9 A.D. Eukles and his wife Tata evidently belong to a tamily of Maximianopolis, whose stemms is traced in CB. I. p. 333. The Record Office is probably that of Apameia, unless Maximianopolis possessed one. Basmaktchi Yaila was probably an outlying settlement of the great Imperial Estate near the southern and western end of Lake Askania. Beside the village there are some rock-cut sarcophagi.

¹ That the name Zerośroku (Hierocles) which M. Radet places at Basmaktchi (map in En Phrygis) is a corrupt form of 'Assersanio'szku,

as Kuricorulus is of Διονυσούνολιε, was shown long ago by Prof. Rainsay.

31. Of another inscription on a cornice piece, now forming the lintel of the mosque door, I could make out little more than [τον βωμ]ον σύν τοῖς ἐφεστῶσι κείσσιν καὶ . . .

SIBLIA

The Siblianol are placed by Prof. Ramsay in the marshy Maeander valley which stretches south from Ak Dagh and forms a corner of the great plain of Peltai. He thinks they possessed no proper πόλις but retained the old village organisation, having three centres (κόμαι), one at Vicus (Tchandir Tchiftlik), one at Boz-eyuk, and one at Khoma on the slope of Ak Dagh (CB. i. p. 222 ff.). Yet the coinage shows that at least 'in the early third century the tribe must have become more closely organised... and selected one of these villages as a πόλις or city centre (p. 225). The change seems to have occurred earlier: for the following fragmentary inscription, which can hardly be later than the early second century, mentions the Record Office of Siblia. This inscription, which is the only epigraphic evidence we have for the name, is built into the platform of the Railway Station at Evjiler * (close to the site of Lampe); it has been cut on all sides.

32.

TANKATA OE COALETEPOI

DAMHCELY THEN AN ION

ATTO ELECTIC TO LEPOT

ICXELATO LA COLLECTA

(OLCELE KNOIC MOYHER

OTOHOONY THEY BY NOCE

KINDY NOKALTO TPODHA

VOC. TPOCTELA OVAC

[οὐδενὸς ἄλλου ἔχοντος ἔξουσ]ίαν καταθέσθαι ἔτερο[ν πτώμα· εἶ δέ τις τ]ολμήσει ὑπενάντιὸν τ[ι ποιῆσαι ἡ ἄλλο τι πράξει], ἀποτείσει ἐς τὸ ἰερώτ[ατον τα-

others and formed a sort of centre.

Yet it may be hald that this fact is not inconsistent with the want of a real whis; for though the relation of the villages in a superwake is an unsolved problem, we must inferthat one when was more important than the


It has been earried from one of the villages in the plain, no great distance. See the map in CB, vol. i.

μείον 'Αττικάς δ]ισχειλίας τούτου ἀν[τίγραφ5 ον ἀπετέθη ἐς τὰ] Σιβλιανῶν ἀρχεῖα, ἔτο[υς διακοσιοστοῦ ' κὲ] δεκάτου μη(νος) ε΄, ς΄ · ἔστα[ι δὲ οὐδενὶ
εξουσία .] . . . εἰ [μ]ὴ τέκνοις μου ἡ ἐγγ[όνοις, εἰ δὲ
τις ἔτερος ἀνύξει τοῦτ]ο τὸ ἡ[ρ]ῷον, ὑπεύθυνος ἔ[σται τῷ
ταῦ νόμου] κινδύνφ καὶ τῷ προδηλ[ουμένῳ
10

For the use of Attic drachmae in this district, see Part I. No. 15. In the troublous Byzantine times Khoma with its strong fortress (kald) became the great centre. On a hot August morning I started up the mountain to examine the kale and reached it after an ascent of fully an hour and a half,—alone, my attendants having fainted by the way! It is a bare, isolated rock, standing out from the mountain-side in solitary grandeur, about 2,000 feet above the village. There is little to be seen now except part of a late wall on the narrow summit and a cistern (hammam) lower down on the further side (which is not visible from the top, but was reported to me after I had climbed down again).

LAMPE.

33. In the village of Evjiler.



Another kuls was reported further to S.E. (nearer Dinkr-Apamels).

³ See CB, p. 227 f., 347 etc.

IOHPMONTINAOP////
NAIOHCEIEICTOI
EPMTATONTAMEI
ONONOMATITIOC:////
20 //IOYAMAPIAAICXEIAI
ATTENTAKOCIA

τό ήρφον τινα θεξίναι, θήσει είς τό ίερώτατον ταμείον δνόματε πίρ)οσ[τεί 20 μ]ου δηνάρια δισχείλια πεντακόσια.

On the right-hand side is $\Theta Y(\rho a)$, for which see CB. II. p. 395, no. 280.

The date is 214-15 A.D., which suits well the use of Aurelia as prainomen.

34. Ibid. IT-IOYA-TIB-AFAGYP-COC Π. Ἰοῦλ(τος) Τιβ(έρτος) *Αγάθυρσος.

APOLLONIA-SOZOPOLIS.

A visit which I paid to Apollonia resulted in the discovery of some new inscriptions and the improvement of some already published.² I failed, however, to find the important inscription given by Prof. Sterrett, W.E. no. 548.

35. On a large rectangular block now used as a fountain-trough, in the vineyards below Ulu-Borlu. A large cross was afterwards cut on the stone where the breaks are shown. The block had to be displaced before the inscription could be read, and it was no easy matter to move it.

ΑΥΤΟ///ΡΑΤΟΡΑ
ΚΑΙΣΑ///Α-Μ-ΑΥΡΗ
ΑΝΙΣΕ///ΙΠΟΝ
ΣΕΒΑ////ΤΟΝ ΥΙ
5 ΟΝΑΥ///,ΟΚΡΑΤΟ
ΡΟΣΚΑΙΣΑΡΟΣΛ
ΣΕΠΤΙΜΙΟΣΣΕΥ
ΟΥΗΡΟΥΠ-ΡΤΙΝΑ
ΚΟΣΣΕΒΗΒΟΥΛΗ
10 ΚΑΙΟΔΗΜΟΣ
ΑΠΟΛΛΩΝΙΑΤΩΝ

Αὐτο[κ]ράτορα
Καίσα[ρ]α Μ. Αὐρή(λιου)
'Αν[τωνεί]νου
Σεβα[σ]τον, νίδ ον Αὐ[τ]υκράτορος Καίσαρος Λ.
Σεπτιμιο[υ] Σευσυήρου Π[ε]ρτίνακος Σεβ(αστοῦ) ή βουλή
10 καὶ ὁ δήμος
'Απολλωνιατῶν

AYKIRNOPAKRN Aukiwa Opakra Koaranan o Koawaa o

¹ The kepps is slightly blurred on the stone, but it means quite certain.

^{*} Inser. of Apollonia C. I. G. 3069 ff. ; Le Bas-

Waid 1192 ff.; Sterretz, W.R. 517-554; S.C.H. evil. pp. 255-50.

Lt. 11-13. The title used by the people of Apollonia in the second and following centuries in inscriptions; and on coins; creates some difficulty.3 The name Apollouis, and the existence of Thracian colonists would seem to point to a Pergamenian foundation. But, as Prof. Ramsay points out to me, an inscription published by Sterrett (W.E, no 589), recording the erection of an άγαλμ[α Θεού] Νεικάτορος κατά κέλευσα του Δ[τος] by a priest of Zens Enjrydamenos), seems to show that Apollonia was a foundation of Seleucus Nikator. The Thracians, then, may have been settled in the city at a later time, for we have already found (Part I no. 10) that the Attalidae 'actually introduced into Selencial foundations bodies of new citizens likely to be faithful to themselves.' It would appear from an early inscription, no. 40 (below), that the two classes of colonists maintained (for some time at least) a separate existence in reality as well as in name, for there a bequest is made eis εὐωχίων ἐν τ[ŷ] πῦλ[ε]ι Θρακῶν ὡν [ἀν ἔ]ιη δικαί[ω]s. The use of the term colopol is not easy to understand: was it adopted in a spirit of rivalry with the Augustan Roloveias, such as Antioch, Lystra, etc., in place of the usual term κάτοικοι, which was by this time synonymous with κώμη ?

36. In the wall of the Kishla.

///APIENENOEΔΙΕΥΡΥΔΑΜΝ//// ...κεχ]αρισμένος ΔΙ Εὐρυδαμηνίφ εὐχήν.

The form Δi occurs also in an unpublished inscription at a village between Apia and Aizanoi Δi Βρουτώντι εὐχήν, and in an inscription at

Karadilli (see Khelidonia-Diniae).

The cult of ZEYΣ EYPYΔAMHNOΣ is mentioned in two other inscriptions of this district, (1) at Böyük Kabadja (Sterr. W.E. 589), where we should restore lepric Δειός Εὐ[ρυδαμηνοῦ] and (2) in an inscription of Gendj Ali published from Ramsay's copy in Rev. Arch. 1888, ii. p. 223 (=Uhron. d'Or. 1883-90, p. 500), where a monument is erected by a priest of Zeòς Εὐρυδαμηνὸς and his wife πρώτανλος Διὸς Οὐρυδαμηνοῦ. Πρώτανλος, 'chief flute player,' first flute,' implies that music and dancing formed part of the religious ceremonial; on this subject, see CB, ii. p. 359. Εὐρυ-δαμηνὸς is doubtless a Hellenized form of a native name. We may compare Εὐρυ-βάλινδος, a name of Dionysos (Hesych. s.v.), where βαλινδος is certainly the same word as Phryg. βαλήν 'king,' which occurs in Thrace as a name of Dionysos (B άλιν,' τὸν

* Cp. Wadd. on 1195; C. F. Hill, B. M. Cata.

logue of Lyon etc., p. cir.

K.J. 97 als.

* Possibly Odpočensohe is not an angraver's error but a form really nearer the original

A. C.I.G. 2989 etc.; Sterrett no. 517 : Hist, Geog. p. 172.

³ From Antonium Pius to Gallieum (Hand, Hist. Num.).

As Prof. G. Himschfeld thought (Gree. Gel. Aug. 1888, p. 592): so Rammay, Had. Geog., p. 400, who shows that having specie means Augine and Specie (as given in an inner. St. 172).

* Op., for example, Sterr. W. E. no. 852.

Shr. bala. 'power,' balis 'powerful': cp. Tunmechek, Dis alten Thruker li. p. 41, (in Situangeber, Wien. Ainel 1854), where this is given as one of several explanations of the name 'Berker alter Bakdet' which 'soll Dioagnos being Thrulen gracium haben EM.' Onisford's alition of Et Mag., however, gives neither Bakles nor Bakdet, but only Baker (without any variant), which is clearly the same as Phryg. Sakhe.

Διόνυσου, Θράκες, Etym. May. ed. Gaisford) and in Bithynia, which is Thracian (Strabo 541), as an epithet of Zeus, Δil Βαληφ (Ath. Mitth. 1894, p. 373). Εύρυ- was taken by Fick¹ as the Greek adjective, in which case Εύρυ-βάλινδος would be equivalent to Εύρυ-μέδων, Εύρυ-άναξ (-άνασσα).

37. By the side of a field below Ulu-Borlu: letters rather broadly cut.

```
[ yepovala]
                                   erei\mu]\eta\sigma\epsilon\nu\Delta[\eta-
           /// IXENAI///
                                   μήτρι?]ου 'Ολυ[μ-
           ///ONOAY/ ////
                                   mixlov, lepéa Pio-
        ///OYIEPEAPC ///
                                   μη]ς γενόμενο[ν,
        ///ETENOMENO///
                               ς πρ]εσβεύσαντα
      ///ESBEYSANTA
5
                                   πΙρός του Σεβασ-
     ///POSTONSEBAS////
     ///ONAIZA OPEANK///
                                   Top die Sopeau Klai
     ///OPANOMHEANTA///
                                   άγ Ιορανομήσαντα
     ///FYMNASIAPXIAN ////
                                   καί] γυμνασιαρχίαν
   /// VEXANTAKATA ////
10
                                10 τελ έσαντα κατά
     ///AOHKHNOAYMTI///
                                   δι]αθήκην 'Ολυμπ[ί-
    1///OYLAMATOYANE////
                                   γ ου [Δ]άμα τοῦ ἀνε[ψ-
    ///OYA////MTPQEKA////
                                   ι]ού λ[α]μπρώς καί
    /////OAOEQEKAIT/////
                                   φιλ Ιοδόξως, και πίασ-
15 ///ZAPETHZENEKE///////
                                15 η ς αρετής ένεκε[ν.
```

The last phrase και πάσης όρετης ξυεκεν is co-ordinate with the participles. D[emetri]os is honoured for his public spirit in undertaking these munera and 'for his merits generally.'

The mention of a priesthood of Rome shows that this inscription belongs to the early times of the Empire (see CB. nos. 199, 302, 345, and p. 365 on this cultus at Eumeneia and Apameia). The main function of the Gymnasiarch in Roman times was to superintend the distribution of oil and help to provide it: 'nothing could better illustrate the deterioration in moral fibre of the Graeco-Asiatic cities than the transformation of the director of education into the purveyor of oil' (CB. ii. p. 443-4, where the office is described).

The person honoured in this inser, belonged to one of the most powerful families of Apollonia. The following genealogy can be traced from Sterr, no. 518 (better in Wadd, 1195a.*) and our next inscription:—

¹ Die griech, getterheimenen in Bemen, Beiträge xx. p. 100.

Wald a reading 'Aroll 'Arolleries to

^{&#}x27;Ohiganizau reli "Apressere is the correct one: in L 4 1 read TATIA (complete).



38. In the Kale wall, upside down :

'Αλ]έ[ξαν]όρος 'Ολυμπίχου τοῦ ΤΟλυμπίχου Απολλώνιου τὸ]ν ἐαυτοῦ θείον κα[1] πενθερόν. B.

'Αλέξανδρος 'Ολυ(μ)πίχου τοῦ 'Ολυμπίχου την & <την> έαυτοῦ πευθεράν.

39. Of the following inscription two different examples exist, one in the Kale wall (=Sterr, 530) and another in the wall of a house at the opposite end of the town. In both cases the lettering is rude,

AVPEYTYXIIL

AYPEYTYXHEKALIIII

> Αύρ, Εὐτύγης καὶ Πατρίκιος νίοὶ 'Αλεξάνδρου ἐπίκλην Α. ΥΚΥΕ πολιτε(υσμένου) φυλής Βενέτων εποιήσαμεν μυήμης (χάριν).

The words φυλή Βενέτων mean perhaps the 'Blue Faction,' not a tribe called by the Thrako-Hlyrian name Béveros, though the latter would be quite suitable. W. M. R. informs me that he copied the second stone in 1888 and read APYKYE, marking the P as very doubtful.

40. The copy which I made of the badly defaced inscription published by Sterrett (no. 539) helps us to complete II. 10-20.

	WETTLEKE
	YAZAENTOBKAIM
	KAIPETEIENOKAI
-	AYTOE E E DOMHN DIATON DHMOE
5.	ONTPAMMATONIA
	OE CEPIE AKAIAYTHN
	OAHNTOMNHMEI
	CATIT - AAAAATPI
10	QTONA" ALL OH
-	DOM E THEE
	AYTHERPOEDAOY
	EIZTEANAN 'INTOY
- 1	MI EIN AIEYA
(3)	XVANENT, TOA-1
	GPAKONON IH
	AIKAIOE GIATON
	AHM OEIDNANET PA
	YAENTATKAIMKAI
20.	PETEI

The style of this inscription is early. The monument was erected in the year $\rho \mu \gamma'$, 143, but the era is doubtful. In Studia Biblica IV, p. 54, Prof. Ramsay suggests that the Galatian era may be 189 s.c., the era of 'freedom,' which would give 47 s.c. as the date of our inscription. L. 9, the third letter seemed not to be Y; AAAO is doubtful. L. 11, after the first E there is room for two letters. L. 16, 'The Thracians who are entitled to it,' implying a specified number or body; evidently the Thracians were still distinct from the Lycians (see on no. 35). After ΩN there is room for two or three letters. L. 17, I have a note to the effect that the letter after $\Delta 1 N$ AI is apparently 0.

41. In the wall of the Greek church, on two blocks: restored wrongly by Prof. Sterrett (Nos. 520, 521), who did not observe that they are parts of the same inscription.

AHMO MIMINING EN MEATIN HI MIME NO ΔΡΟΥΓΥ NAIKAΔΕΔΗ MHTPIOITOΥ MENEΛΑ ΟΥΑΡΕΤΗ ΣΕΝΕΚΕΝ ΚΑΙΣΩΦΙΜΙΤΟΥ ΝΗΣ

ό] δήμος [ἐτίμησ]εν
Μελτίν[ην 'Αλε]ξ[ά]νδρου, γυναϊκα δὲ Δημητρίου τοῦ Μενελά5 ου, ἀρετής ἔνεκεν
καὶ σωφ[ροσ]ύνης.

The first block contains also Sterr. 519, the second, 522. From these inscriptions we get the stemmo,

Menelsos Denotron = Maltino, d. of Alexander Menclass = Tatifal, d. of [Aristo flunches (no. 522).

42. In the wall of a house:

Αρτεμίδωρο[ε] | Διομήδους [τέ] κυφι ίδίω μν[ή] μης χάριν, κα[ί] | Πάντανδρος [Αρτεμιδώρου.

43. A fragment in another wall; small letters.



We can see in 1. 2 Γάιον Κ[λαύδιον]; in 1. 4 έτ[ών] πέντε καὶ δ[έκα]; in 1. 7 iππείς δε 'Pω[μαΐοι]; in 1. 9 έκ των Ι]δίων κατ[εσκεύασαν]. I subjain corrections to Sterr. 529 and 532.

- 44. In No. 529 Prof. Sterrett's restored reading of Il, 1-9 is confirmed by the stone (which is complete from beginning to end), except 1, 6, where we should read arakoyýgavíta. Il. 10-14 I read ér awagur ebroig, bija to sai του νεανίαν | πάσης άρετης τελειότατον έσχηκέναι | ζήλου. Γοι ζήλου ΜΜ., Legrand and Chamonard read πόλιν (B.C.H. 1893, p. 258.)⁸
- 45. The beginning of No. 532, where Prof. Sterrett has 'A[θην]as Neuropopou, must be corrected. My copy, which was made by means of a glass, reads

ΤΠΑΣΝΕΙΚΗΦΟΡΟΥ ΠΡΕΣ λεγεών]ος τ[ρ]ιακο[στής] Ο[ύλ-πίας Νεικηφόρου.

This confirms a suggestion made by Dr. Brandis in Hermes, 1896, p. 164.

and I read it with a glass from the top of the wall opposite.

TAIES/ANETI, etc.

^{111. 3-4} in Sterrest are wrongly spaced. Read Terffor Aports Hadyon, your lien & Mo readou.

My mpy has in 1 8 FONENAELA THTOY; but red is necessary, whether actually on the stone or not. The inscription lies on its side at the very top of the Kale wall.

In B.C.H. no. 36, 1. 6-7, road Acarprian-Marofodleses, and in I. D APTEMIAOS. In no. 35, L 8, I seemed to see

THE EASTERN HIGHWAY,

In the last chapter of CB, vol. ii., the anthor gives some notes on the trade-route to the East, reserving a fuller discussion in view of further exploration. I spent the best part of a month in traversing the country from Apameia (Dinér) to Tchai (where Phrygia Parcreios begins), and from Tchai to Tyriaion and the south-east corner of Phrygia. The results, at least for the former half of the journey, are more meagre than we could have wished; but this is hardly surprising, just because this district was the great artery of communication between east and west, and was therefore exposed more than others to the destructive inroads of successive invaders. Especially is this true of the country at the head of Sultan Dagh and along its eastern slope.

ROADS FROM METROPOLIS TO SYNNADA.—The Campus Metropolitanus has been so often ransacked that little new was to be expected there. I copied, however, an interesting fragment of a Latin inscription which seems to mention a village Polynta, but meanwhile I reserve it pending a re-examination of another stone which would appear to bear a companion inscription.

But there is one controverted question on which a thorough exploration should have something to say, I mean the line of the Roman road between the Campus Metropolitanus and the plain of Synnada, along which the huge monolithic columns of Dokimian marble were carried to the coast.3 The modern waggen-road from Synnada crosses the hills by way of Uzun Bunar, joining the Eastern Highway at the lower village (mahalla 'quarter') of Karadilli. In 1881 Prof. Ramsay decided that this must have been the line of the Roman road.3 In 1888, however, he discovered another road passing Baljik-Hissar (or Baghtehe-Hissar), beside which it 'crosses a lofty ridge by a finely engineered path, the cuttings and curves of which can still be observed," and then wends its way over the hills to Ginik and Metropolis. Though he was prevented by circumstances, which the archaeological traveller can appreciate, from exploring this route completely, he was convinced by the evidence of engineering skill that this was the line of a Roman road, and in 1891 he discovered the Termini (No. 693) by the side of this road, opposite the village Yiprak (see CB. ii. p. 751 ff.). His final suggestion is that there were two roads, a trade-route, and a horse-road " to carry at least the lighter trade" (CB. II. p. 752-3). M. Radet has recently adopted the former view, dismissing the latter route (which he has never examined)

¹ waisch rat 650s respectas Annos roll ent rids end ridses.

deutschüt öberkopelare et Esplane, Strabo,

j. 663.

2 Strabo, p. 577, nivert parchides perchies . . .

with the words 'un effroyable chaos de rampes, de gorges et de précipices '; but this does not settle the question, for scientific method does not accept as proved a theory that refuses to take account of negative evidence.

The maps of this district are very inadequate, and though I cannot guarantee the absolute accuracy of the one which I give (Plate V.), I claim that it is nearer the truth than any of the others. Let us briefly describe the routes. (1) The road by Uzun Bunar naturally passes by Atli Hissar, and enters the hills a very short distance to the south of the village Tchoban Kaya, (1 hr. 20 min. from Bedesh). After a short ascent of 350 feet, it goes along the level summit for fully an hour, and then descends 250 feet into an ora. Traversing this ora, we come to undulating ground, and descending by the very slightest of gradients pass Uzun Bunar 1 hr. 35 min. from the point at which we entered the hills, and reach the edge of the Karadilli plain in about half an hour more. Here we are only from 150 to 200 feet lower than the Synnada plain, and the whole road is so easy that we are hardly aware that we are crossing hills at all. At Kara-dilli we join the Eastern Highway (to Metropolis).

(2) There is another road to Metropolis which diverges from the former below Atli Hissar and enters a long glen in the hills, appropriately called Uzun Dere ('the long valley'), running in a SW, direction. Fifty minutes after leaving Atli Hissar, we pass Alaka (which lies above us on the left) and travel down the dere for an hour until we come to a point at which it bends round to the left. Just at this point it is joined by the road which crosses the hills vid Baljik-Hissar. Starting again, we reach in twenty minutes the foot of a Bel (a low broad ridge with hills rising on both sides), whose summit lies 400 feet above us: and after crossing it we make an easy descent of forty-five minutes to the brow of the hills looking down on Ginik, where stands the boundary-stone already mentioned. From here there is a long easy descent of an hour or so to Ginik (Euphorbion). This road also is remarkably easy for a hill-path: the only climbing we have to do is in getting over the Bel.

¹ En Phrygis (1895), p. 123,

^{*} From this point the village is perhaps about an hour distant. Usun Bunns seems to be M. Radet's Foxtaine (see his route-map); but if so, it does not seem to be correctly placed, as the above description shows. Cf. Ramsay, Ch. p. 752 s. 4.

³ Here is the itineyary from Paljik-Himar to this point. It will show the erronecusness of M Rader's description. [It will be noted that this route cannot pass Alaka.] At the village the ancroid read 4,700 ft. The road winds by a line curve cound the Kabl and than over the ridge.

^{9.33} A.M. Leave the Kall.

^{9.42 ...} Brow of the ridge (5,200 ft.). Reach the summit (5,300) at

^{9.49 ..} Begin to descend towards the broad ravino, opposite the mouth of

which lies Ath Hissar. The descent is rather steep towards the (not, which is reached (4,800) at

^{10.5 ,.} Green the ravine at its extreme limit, and begin the ascent even the next ridge, reaching the top (5,200) at

^{10.32 ,,} Thence an easy duscent, reaching the (oot (5,100) at

^{10,52 ..} Ascend again till

^{11.5 , (}summit 5,850). Thence a winding, mutulating path, and a final descent to the Unia Deve, which is reached at

^{11.25 ...} Level is 5,290. Here we join the Alaka-Ginik road. At 11.5 we were still passing fields belonging to Baljik-Hissar.

Now, though we can testify to the very clear traces of cuttings and curves on the Baljik-Hissar road, we are obliged to conclude that no Roman or other engineer making a road for heavy traffic from Synnada to Metropolis could choose this route: and this conclusion I am sure Prof. Ramsay would at once have reached had he been able to examine the whole line of the road. It is not conceivable that an engineer would select this line for a waggon-road in preference to the easy route via Atli Hissar and Alaka, so clearly marked out by nature, if he wished to cross the hills to Metropolis in this direction. What then is the explanation of this engineered road ! Baljik-Hissar is an old site.1 Its inhabitants are called Overapidas in the metrical inser. set up by the township, δόγματι κοινώ βουλής και δήμου, in honour of Demetrius, the Asiarch (Ramsay, Bev. Arch. 1888, p 220). Thynnaros is a local hero of Synnada, mentioned on its coins," and Thymnaridai is obviously the poetical equivalent of Symauleis 2; Mat is to say, the settlement at Baljik-Hissar was a village in the territory of Symada, which had many subject κώμαι. The lists of the Ξένοι Τεκμόρειοι give us the names of several of them, e.g. Kandroukome, Konmalettos, etc., and prove that the full designation of their inhabitants was Συνναδείς οἰκοῦντες ἐν Κανδρουκώμη, ἐν Κουμα-Aérro, etc. The raison d'être of the road might, therefore, be found in the existence of this village and its need for a direct road to the plain of Metropolis on the one side and to Synnada on the other." This, however, does not seem to constitute a sufficient reason for such a carefully made road; and doubtless Prof. Ramsay has given the true explanation when he suggests that this was the direct horse-road from Dokimion and Synnada to Metropolis, made by the Romans to carry the lighter trade.

The line of the great Roman road, then, is limited to two possible routes, that by Alaka and that by Uzun Bunar. Which are we to accept? On consideration, I think we must regard it as certain that, while there always existed a road viá Alaka, (used at least as a horse-road), the road by which the great blocks of Dokimian marble were transported took the line by Uzun Bunar, joining the Eastern Highway at Kara-dilli. The mutilated milestone discovered by MM. Radet and Ouvré at Atli Hissar (B.C.H. 1896, p. 115, En

On the rounded till above the village, round which the road runs, a very few traces of the old settlement remain. The matires call is the "Castle" (Kall). The highest point of the kall is 375 ft. above the village.

^{*} Drexler, Nun. Zft. 1889 p. 177; Imboof-Blumer, Grisch. Micros. in Abbandl. d. Boyer. Apad. d. Wiss. (I. Ch.) 1890 p. 748.

³ So it is rightly explained by Ramsay in Hist. Geog. p. 36 note.

^{*} It may be MELISSA (see below).

a Storr. W.E. no. 388, 20 and 376, 38, 42, atc. See G. Hirschfold, Gitt. Golchrie Auszigen 1888, followed by Ramsay H. G. p. 409. We cannot at all accept M. Radet's explanation that co done [de Symmole] a appellant Thyomera

of qu'il honorait le herre l'agrentifie comme épongeme (p. 122). Il have since come access au excellent parallel in a metrical inscription of Temenothyra, where the inhabitants of that city are called Temerica, i.e. descendants of the here Temenos (mentioned on their coins), as the late Dr. limes is rightly explains it, quoting possepidas as a parallel (Aus Lydies, p. 184)).

^{*} The road is still used by the villagers of Baijik-Hissas in going to Tchul Ova (Comp. Metropol.). At some future time the boundary-stone mentioned in CB. ii. p. 752 will be discovered to give us a fixed point, but the peasants will have to re-discover it first. Only one man some to have seen it: he guided us to the spot,—but it could not be found!

Phrygie p. 124) supplies no decisive evidence, for it would suit either route; but the Uzun Bunar route is easier than the other and only very slightly longer. On this view, the Roman road will pass near Ginik, beside which M. Radet and Prof. Ramsay agree in placing Euphorbion; and this is probably all that is meant by the Peutinger Table's route,

A Synnade Inforbio i mil. xxxvii

Enforbio Ab sufarbio

Ab amea mil. xxxvi

Apanese
Ciboton,

when we remember that in the Table the distances are reckoned from city to city, and the cities often lay a little apart from the direct line of road.² In order, apparently, to conform to the appearance of the Table, M. Radet makes his road climb up among the hills on the north side of the Kara-dilli Ova and high above the Kiz-Kapan pass to Ginik and thence to Metropolis. Can any one who has seen the country between Ginik and Karadilli believe that there is the slightest probability that the road followed such a line? The distances in the Table are, of course, quite wrong. Synnada xxiiii (or xxv) Euphorbion xxvii (or xxviii) Apameia would be nearer the truth.

Khelidonia-Diniae.—On our view of the roads, there are two other important points, viz. Kara-dilli (lower village) and Atli Hissar. At the former there are considerable remains, including a carefully defaced inser. of about ten lines, of which I could decipher little more than . . . και 'Αγαπα άδελφη αὐτοῦ , while in the upper village there are the two inscriptions published by F. Sarre, Arch.-Kpig, Milth. 1896, p. 31, Nos. 7 and 8. No. 7 is inscribed on an altar-stone, bearing reliefs on the top and four sides, and reads Καρποφίδρος μισ θωτης 'Ηλίω και Δι εὐχήν.* To this site should probably be assigned also CB, II. No. 707 a and b. There seems little doubt that we should place here Χελιδώνια, mentioned by Strabo (p. 663), on the trade-route between Metropolis and Holmoi, and identify with it the town Diniae which Manlius passed on his march between Metropolis and Synnada (Liv. xxxviii, c. 15). After emerging from the Kiz-Kapan pass, the road naturally converges on Kara-dilli and then turns away towards the hills.

SIRDOUNDA.—The other important point is Atli Hissar. The neighbourhood of this village is the best situation for an ancient city in the whole district of Synnada (after Synnada itself). Lying in the plain at the point

¹ The I perhaps belongs only to the word PHEVILA written across this route.

Whence it follows that 'the sum of separate distances is decidedly greater than the whole ength of the tend, 'J.H.S. 1887 p. 468, where the principle is stated.

^{*} They are much worn, but one is the head of as ox.

For the form Δi see no. 38 above. In Sarre no. 5 φπρλ in exceedingly common in such Byzantina inscriptions: read also at [K₂ with a twirt].

So identified by Ramany, Hist, Geog. pp. 142 and 171 and Radet, Map in En Parppir (where it is placed at Kura-dills).

where the roads from Metropolis converge, surrounded by fertile lands and supplied with water, it might naturally be expected to correspond to an important ancient site; and we find as a fact that the remains here are more considerable than any other unidentified ruins anywhere near. Now there is an independent city belonging to the country around Synnada which has not been plausibly located, viz. Sibidounda. It struck coins at least from the time of M. Aurelius to that of Gordian, and is given as a bishopric of Phrygia Salutaris under the metropolis Synnada by the Notitiae, where the name occurs under forms which are only slight variations of the one form Sibindos or Sibindon, as the following Table shows:—2

Not. VII.	Later editions of Not. VII			Not ed. De	Not	Not, IIL
	Not IX.	Not. VIII.	Not, Bazilii	Boor,	Lanuis	and X.
1.84×800	1e8istoo	Zeerddon	Lifterdoü	Timle Son	Libirdas	2wpire.

That the city belongs to the district around Synnada is clearly shown by the order of names in the Notitiae which is as follows:—

4. Tpace 7. Ormus [De Boor] 10. Phytoia (= Bendos*) 18. Lysias 5. Prynnessos 8. Sibindon (-os) 11. Hierapolis 14. Augustopolis 6. Mercs* 9. Polyboros 12. Excarpis 15. Brounss.

Now if this list be compared with that of Hierocles, we find that corresponding to Sibidounda is the corrupt name Δεβαλικία, which is given after Augustopolis [Κλήρος 'Oplogs and Κλήρος Πολιτικής, Hist. Geog. p. 178; CB. p. 635] and before Lysias, Synnada, Prymnessos, etc. This fact was pointed out by M. Radet (En Phryg. p. 115) and is accepted by Prof. Ramsay, who explains the corruption as due to a copyist's error, Σ passing into Δ and Δ into Λ. I would suggest, then, that Atli Hissar with its fine situation and numerous remains is far the most suitable site for a city of the importance of Sibidounda; and this situation suits perfectly the order of Hierocles when we recognise, to use Prof. Ramsay's words, that Lysias was in Oman Ova [see below] and that thus the three cities were closely connected by a line of road (CB. p. 753). This identification would accord excellently with the Termini

Excepting the corruption Zureddov (a for B).
Not. Burthii [=Not. i. in Parthay-Pinder] and Not. Lecuis edited by Gelzer (Georg. Cyperii Descriptio Ord. Ross.)
Do Boar's Not. in Zft.

f. Kirchengesch, zii. p. 324.

The intrusion of Meros is probably to be explained by the circumstance that it was formerly subject to Prynnesses (see Parl L. 19. 424).

^{*} Boudels and Phytein are perhaps other forms of the name Bendes Vetus* (H, 6), p. 143). This is clearly right.

Inscriptions are published by Hamsey, B.C.H. 1883, p. 299, by MM Legrand and Changement, R.C.H. 1893, p. 289-90, and by MM. Radet and Ouvré, B.C.H. 1896, p. 109 f.

[&]quot;We might compare, for example, Hieroches' order Singulandos, Laodifecia Katakekaumene, Tyrinion; or Hemonadeia, Histra (Hieroc), Larando (Karuman), Deris (Guddissin). A protest must be made against the exaggrated stress that is often faid on the precise order of names in Hierocles (or the Notit). We have a good specimen in M. Radet's reasoning about KNipos.

(CB. No. 693 and p. 751; see above), if the name Sibidomada (in any form) is mentioned there, but the stone is so badly worn that the central letters of the name will never be read with any certainty.\(^1\) Prof. Ramsay himself suggests Baljik Hissar or Bedesh, where M. Radet determines an ancient site, as suitable for Sibidounda (p. 753); but the former we have seen to be a village subject to Symada, not an independent city; whence it follows à fortiori that Bedesh was a κόμη too.\(^2\) Our localization at Atli Hissar, on the direct lines of communication with Pisidia, suits also the fact that the coins of the city show a Pisidian type, the goddess Helena between the Dioskouroi,\(^2\) and are similar in fabric to Pisidian coins.\(^4\) It is probable that, if the lists of the Xenoi Tekmoretoi were complete, we should find mention of Sibidounda, considering how largely the district round Symada figures there.

According to this identification of Sibidoumda, the village MELISSA, on or near one of the roads from Synnada to Metropolis, where Alcibiades was killed and buried and where Hadrian erected a statue to his memory in Parian marble, must be placed at Bedesh or at Baljik Hissar. The only evidence is Athenaeus xiii., c. 34, 'and we too saw the tomb of Alcibiades at Melissa, on our journey from Synnada to Metropolis's; and it is obvious that these words do not fix the precise situation. It is probable that they were travelling by the direct horse-road, but even if they were taking the waggon-road, and the tomb of the famous Athenian were some little distance off it, at Baljik Hissar, they would certainly turn aside to visit it and then continue their journey. In either case they would have seen it 'on their journey from Synnada to Metropolis's

Opient, Kanpor Hoderient, Arbuduela, Applar, Mirada (Hier. 677, 3-7). Synnada is fixed. A town 'Oriné' is placed at Tchukurdja in a mountainons district (on evidence for a criticism of which it is sufficient to refer to CB. ii. pp. 835, 687, etc.), whence it follows that KASp. Holer. 'le Domaine Urbain' designates the neighbouring plain Kutchak Sitchanli Ova-Le classement du Synerdème ceigo qu'on y place non seulement Kanp, Hoa, vonte encore l'évêché qui lui fuit mite dans le catalogue AsBahorla [= Sibiliounda] . . que as place tout maturellement à Kavadirek, dans l'angle oriental du Kutchuk-Sitehanly-Ova. Lyrias, qui vient ensuite, tombe a Efel-bred [Effe Sultan]. The topography of Asla Minor would soon be settled, if such Tensoning were admitted !

I summined the stone on two occasions, one is certain (the first letter is not so rounded as the c above and may be a mis-cut for s); os is also certain. There are rounding of a letter below u (in the line above), which on the first examination I teak for a bailty-formed r, but the second time it seemed to be the tail of an a. There is room for other four letters, for the space between the and enor is greater than

Prof. Ramsay's copy shows. sinfinurs jos seems quite probable.

Which agrees with the insignificant character of the rules there.

⁸ OB, p. 755 NOTE 1: Imboof-Blumer, Monn. greeq. p. 345; Brisen in Lykien ate, ii. p. 168 ff. (rollefs): G. F. Hill, B.M. Catal, of Lyric, Fample, and Pixid, p. 1vli.

* For example, coise of Arisesse, Andeda, etc. A cursory gluone at Hierocles' list of towns in Pamphylia might lead the reader to think that Sibidounda is really to be found there under the form Zirōassōa. But if he takes the trouble to compare the Notities, he will see that Zirōassōa corresponds to Zarōides, Zarōides, or Karōides, i.e. Andeda.

* Here is the whole passage: ... αποθατών έπηθεδόθη έν Μελίσση κώμη τῆς Φρυγίας έπιθαωλευθείν ὑπὸ Φαρναβάζου. «Τόσμεν δέ καὶ ἡμεῖς τὸ ἐν Μελίσση τοῦ 'Αλευβιάδου μεῆμα, ἐκ Συτάδων εἰκ Μητρόπολεν ἀφικνούμενον ἐν ῷ καν ἔνος θόστα: Βοῦν, διακελευσαμένου τοῦνο τοῦ πάντα ἀρίανου 'Αδυιακοῦ Βασιλέων 'bs καὶ ἀνέστησεν ἐκὶ τῷ μνήματε Παρίου λίθου κίκόνα τὸν 'Αλευβιάδην.

* May there but he something more than a more coincidence in the occurrence of the name

Lystas.—Everything that is known about Lysias, which was probably a Seleucid I foundation, will be found in UB, ii. p. 754 f. The name is there assigned to the city whose ruins are seen on a mound between Oinan and Aresh.' In support of this localisation Prof. Ramsay quotes a passage from the Acta S. Abereii, where it is said that one day while engaged in his apostolic labours in the Pentapolis, Avircius found himself athirst and without water on a lofty mountain, δπερ έστιν άντικρύ τῆς πόλεως Αυσίας; whereπρου, κλίνας τὰ γόνατα προσηύξατο καὶ ἀνέβλυσεν πηγή καθαρού νάματος. και πάντες οι διψώντες εξ αύτου έκορέσθησαν. ο δε τόπος εξ έκείνου του καιρού Γοννκλισία ἐπεκλήθη. The sacred fountain and 'Place of Kneebending," as Prof Ramsay says, are evidently on the mountains bounding the Pentapolis on the east, and south of the Sandykly hills, which lie over against Symmula (p. 755). It seemed well worth while to make a search for this fountain. We crossed the mountains twice, from Karghyn to Baljik-Hissar and from Yiprak to Karghyn, without discovering anything. But at Karghyn and afterwards at several other villages we heard of a fine bunar in the mountains S.E. of the village Mingile (Mingine, wrongly, in Kiepert's map), called Giaour Oluk, i.e. Giaour spout. This unique name promised well, and we set out on a journey of three hours up Gumular Dagh to examine it. Arrived at the spot, we found a copious spring surrounded by the ruins of what had been a square building, as we judged from the foundations, for hardly any of the numerous squared blocks remain in their original position, though a few have been roughly thrown together again to enable the water to flow through the stone spout into two rectangular troughs. It is probable that both the spout (which has given its name to the bunar and to the yaila around) and the troughs are ancient work, and that we have here a genuine old fountain,-a fact recognised by the traditional Turkish name Giaour Oluk, Its position is marked approximately in the map

Ralfik-Hisser 'Homey Chatle' at a site which, as we have seen, may be Milarga ! The saggestion (which secured to me independently) was made in Wist, Geog. p. 86 n I do not, howover, mean that the Greak name was translated by the Turks, M. Hadet asserts (En Phryg. 123) that rion went plus frequent, dans l'ononastique de l'Anatolie, que es remplacement du terms gree ancies pur un mot ture affrant was signification identique (La Lydis etc. p 80 n. 2): but he shows no proof. There is some doubt as to whother the real name is Baljik or Haghtche ('gurden') Hissar [or Asser]. From the rude pronunciation of the peasants which runs the words together, it is impossible to decide. If you sak them which is the correct form, they answer 'The two are one '! Oue of the Hodjas assured me that the former was more correct, but they do not seem really to know. W. M. R. was corrected for saying Baljik and assured that linghtche was the real name.

The name Lysias is connected with Seloucid history: Lysius, a general of Seloucus Nikator in 216 a.c. (Polyson, iv. 9, 5), may have been the founder of the city.

³ Op. also J.H.S. 1887, p. 497.

² See CR. ch. writ, p. 714; Church is R.E. p. 436 u., 'At the source of a stream among the mountains between Synnada and Hisropolis was a place called Gouyklisia—a.c. where the sarly rite yerdraw which was held. This remote place was charly a secret meeting-place; and after the meetings had accord, and the archaic term was no longer understood, a foolish legend grew up to explain the name; see Expension 1889, p. 262.'

^{*} The name uself is sufficient proof, for it states in se many words that this is a 'non-Turkish fountain': compare, for example, trianso Orea, the name of the rains of Trajanopolis. The Turkish number 1(AA which is scratched on one of the fallen blocks is a more

(Plate V.). Now if it be remembered that the whole space between the Pentapolis and Oinan Ova is occupied by Gumular Dagh and its spurs, it is clear that this situation corresponds very well with the description 'over against Lysias.' I have not the slightest doubt, therefore, that Gianar Oluk represents Γονικλισία, and that we have found an important confirmation of the site of Lysias in Oinan Ova.

One or two inscriptions of Lysias may be added.

46. At Oman-

///MIONKAIEAPOEAOYAI////

'Α]μιον Καίσαρος δούλ[η-

Relief

Relief

τὸ ήρφον Διαδουμένω τ]φ ἰδίφ ἀνδρὶ Καίσαρος δούλω]

47. Ibid: carved on a rectangular block.



+ 'Υπέρ εὐχής του χωρίου.

48. Ibid. Fragment of a sepulchral stele; on pediment, relief of eagle standing with outstretched wings.

έαυτῷ καὶ τῷ συμβίω μνήμε χάριν Σώστρατος.

At Karadja Oren in the S. corner of Oinan Ova there is a fragment of a similar stele with...[\(\mu\)]\(\tau\)]\(\tau\)[\(\alpha\)]\(\epsilon\)[\(\alpha\)]

Kinnaborion.—After traversing Oman Ova, the Eastern Highway crosses a ridge which bounds the own on the north and enters the great plain called Karamyk Ova, the lower part of which has been transformed by centuries of neglect into one enormous marsh, extending from below Geneli well on to Karamyk. In this large plain, which runs right up to the edge of Phrygia Parareios, there is room for several cities; but only two can be certainly assigned to it, Kinnaborion and Holmoi, Kinnaborion is discussed in J. H. S., 1887, p. 495 (No. lx). It is first mentioned in the Tekmorian Lists of the third century: by 451 A.D. it had been raised to a bishopric, a rank

recent graphia: I was it again on a transless at Utob Ryuk, in the valley of the Tembrogius. It means 1871 4.18.

¹ Korandepalrur, Sterrett W. R. no. 300, 33

and 46 (= J.H.S. 1883, p. 23 ff.); KerenSopeés, m. 374, 2 and 45, no. 378, 5 and 9; KerenSopéres, no. 366, 32.

which it holds also in the earlier Notitiae (dating from on 700), where it is placed under Synnada.\(^1\) In accordance with these indications, Prof. Ramsay rightly assigned Kinnaborion to the lower side of Karamyk Ova (CB. ii. p. 748 and Map, J. H. S. Le.\(^2\) The exact site lies in front of the village Armudli, where there is a low mound which clearly conceals ancient ruins, and beside it a T\(^1\) To be\(^2\) built of old blocks. Neither here nor in the village did we find any inscriptions, but a mile or two further on, where the marsh runs up to the mountain side, we discovered a Latin inscription cut on the face of the rocks. As ill-luck will have it, it is now almost entirely obliterated, but it seems to contain the name C. Carist[anius Fronto], and in the meantime I reserve it, pending a re-examination.

The omission of Kinnabarian in Hierocles' list is to be explained by the fact that it was for a time conjoined in one hishopric with Lysias (ὁ Αυσιάδος

ήτοι Κινναβορίου).

The name Κινναβόριον is connected by Kretschmer* with the Lycian personal name χῆταbora, Κινδάβυρις (Reisen in Lyk, i. 82): for the assimilation he compares Τρεβεινατῶν and Τρεβένδαι, and we may add 'Opoavveús, the ethnic of 'Oρόανδα in B.C.H. iv. (1880), p. 401 (= Loewy, Inethr. gricch. Bild., no. 305) and in an inscription of 208/206 в.c. from Egypt (Class. Rev. 1898, p. 275 ff.). This seems probable: a similar relation between place name and personal name is seen in Κίδραμος—Κιδραμούας (No. 66), Tottaion—Tottes, etc.

Holmot.—The villages of Karamyk and Ak-kharim both contain a certain number of remains, but they have probably been all carried. An ancient site, however, undoubtedly existed beside Karadja-Ören ('Blackish Ruins'), the most important of the villages in Karamyk Ova at the present time. At a short distance east of the village the natives still point out an old site (eski öven), part of which is occupied by a deserted cemetery, while the village itself is full of remains of all kinds built into the mosque, Titrle, fountains, and walls. Inscriptions unfortunately are almost non-existent; the demand for good building stone has doubtless caused the destruction of many within comparatively recent times. Only two fragments were found; one has been published in Heberdey and Wilhelm's Reisen in Külkisis p. 163 (No. 272); the other is possibly a fragment of an honorary inscription.

49. ////ICKAICW///

κτίστη]ς και σω[τηρ της πόλεως?

vin Equatopino Not. vii. 170, iz. 358; 6 Konafapino viii. 448; 5 Konafapino Not. Equit. 389 (cd. Gelson); 5 Konafapino Not. The Bose.

A site 'perhaps near Genell' is proposed in J.H.S., but the few remains that the village contains have probably been carried.

⁴ For the significance of this fact cp. above, Part I, Vol. xvil. p. 400.

^{*} Binlettung in d. Gesch d. Griech. Spr. p.

^{307.} He wrongly calls it Koraskops, not observing the occurrence of the city name in the Notition.

^{*} Cp. Kinnaborian (above).

^{*}The basement of the fine mesque-minures is composed entirely of old blocks re-faced: a small 'door-stone' may be seen built in near the top.

It seems clear that this site is to be identified with Holmoi mentioned by Strabo (p. 663) on the eastern trade-route ἐπὶ τὴν ἀρχὴν τῆς Παρωρείου. The name may be a descriptive epithet, like Trapezopolis, and not the Grecized form of a native name, and ὅλμος would indeed be a neat description of the site of Karadja-Ören, as one sees it coming from Tchai. In CB. ii. p. 748-9, Bazar-Agatch, two miles N.E. from Karadja-Ören, is taken as the site of Holmoi, but the remains there are inconsiderable—some squared blocks, Byzantine pillars, and a few fragments of ornamental work—and I came to the conclusion that an ancient site could hardly be placed there.

PHRYGIA PAROREIOS.1

For the definition of Phrygia Paroreios, a district so clearly marked off by nature, see *Hist, Geog.* pp. 139-M0. It may be roughly described as a long plain running N.W. to S.E. between the parallel ranges of Sultan Dagh and Emir Dagh, as far as Ilghin (Tyriaion), where it is bounded by the hilly country which stretches between these two ranges (see the Map, Pl. IV.).

IULIA-IPSOS.—See J.H.S. 1887, p. 420 (cp. Hist. Geog. p. 434). Amongst the critics Tchai and Ishakli (Sakli) dispute the claim to the heritage of Julia-Ipsos. The actual site will probably never be found, for most of the remains have been used up by the Seljuks for the fine buildings whose ruins are still to be seen at Tchai and more especially at Ishakli. But it seems to me that the probability is all in favour of a site quite near to the latter.2 Both Tchai and Ishakli are market towns, but Ishakli is the more important of the two, and it is the governmental centre (a mudurlik). Tchai appears to have been selected as a site in post-Roman times on account of the copious supply of good water which comes down from the mountain beside the village, but is not to be found anywhere else in the neighbourhood.4 Moreover, it is a most striking and important circumstance that the modern governmental arrangements in this district repeat the ancient facts. Not only is the boundary between the vilayets of Broussa and Konia the same as the ancient boundary between Salutaris and Pisidia (see Ramsay, J. H. S. Le.; op Cuinet, Turquie d'Asic), but the centres of government are now Ak Sheher (corresponding to Philomelion), Bulawôdin (corresponding to Polybôtos) and Ishakli (likewise in all probability corresponding to Julia-Ipsos). Lastly, the most important remains, both ancient and Seljuk, are at Ishakli. A fragmentary inscr. has

⁸ Some inact. from the north side of Parousios (along Emir Dagh) are published by Hogarth, J.H.S. 1890, p. 158 ff.

J.H.S. 1890, p. 158 ff.

The site at Kandja-cren, however, was probably the chief quarry for the buildings at Tchal.

The Peat. Tab. gives no help, as one of its two numbers is wrong.

^{*}The water in the plain is not good for drinking and there is no other copious stream

flowing down from the Sultan Dagh nearer than Deresinek, a village lying up a glen far off the road.

A Synnada, Premussas (Kara Hissar,) and others might be added.


Amongst these is a large building of Byzantine work. At Tchai, spart from the Seljuk ruins, there are only some Byzantine blocks in fountains, etc.

been published by Mr. Hogarth J. H. S. 1890, p. 161 (No. 7). I have two to add, the first copied at Ishakli, the second at Yaka Sinek, a village about three miles to the North-West. These arguments seem to show distinctly that the importance of Ishakli at the present day is not a new fact, but only a continuation of the conditions which existed in Graeco-Roman and Seljuk times,

 Ishakli: a square alab with large cross carved across the field, and on the upper margin,

| ////ΑΠΟΛΦΑΝΟΥΠΑΠΑ/////// | 'Απολ(ο)φάνου(ς) Παπά . . .

51. Yaka Sinek: doorstone with inser, on either side,



Ζήνων καὶ 'Αππᾶς καὶ 'Γατεί[ς] 'Αλεξάνδρφ τῷ ἰδίᾳ ἀδελφ[ῷ μνημεῖον ἐποίησ[αν μνήμης χάριν χ[αῖρε?

The metrical part is hardly worth the trouble of an attempt at restoration,

Ι. 1. Εὐη]θής τις ἀνὴρ 'Αλέ[ξαν]δρος ἐνθάδε κεῖ[ται. ζ]ῆσεν (ἐν) εὐτυχίᾳ [κὲ] ἔβα ἵνα γ' ἔ[λδετα θυμός: [?] (Λ. Souter). εὕτε δ]ἐ μοῖρα πικρὰ [ζωῆς νιν ἀφήρ]πασεν αἰφνως πότμ]ον ἄφευκτον . . . ἐστιν ἀνά[γκη

PHILOMELION. While passing through Ak Sheher, I made a copy of an epigram published in C.I.G. 3982 from a very fragmentary copy of Hamilton's

Huser, of Philom and vicinity, C.I.O. 3982 155 and perhaps 168-4; Ramssy in Kulm's Z/t. ft.; Let Has-Wadd. 1704-5; Sterrett E.J. No. f. veryl. Sprachf. viii. p. 391 (Phrygian);

and repeated in an improved form by Kaibel (Epigr. Graces e lapid. conlecta, No. 248), who noticed that it is modelled on Anthol. Pal. vii. 164. The stone is much worn and the letters are very faint. If I had not recognized from L 5 that the inser, was already published, a closer examination might possibly have furnished a complete restoration of ll. 9-10.

52

Αίθαλος Έλάτηι τῆι ἐαυτοῦ γυναικὶ φιλοστοργίας καὶ μνήμης αἰωνίου χάριν.

5 Α. Φράζε, γύναι, γενεὴν ὅνομα χθόνα, πῶς δὲ θανοῦσα ἢλθες δειλαία δύσγαμος εἰς 'Αίδαν, ὅππως οἱ παράγοντες ἀναγνώωστν ὁδεῖται τὴν σὴ[ν λυ]προ[τά]την δύσμορον ἡλικίην.

Β. Εἰμὶ μέν [οὐκ ἀγενής ?], γενεῆ δέ μο(ν) ἐστι Θνάτειρα (-ας !) 10 αὐνο[μα μοι δ' Ἑλάτην οὶ]φίλοι<>έθεντο τροφ[ῆε]ς.

Α. Σήμα δὲ [τίς τό]δ' [ἔχωσε]ν; Β. [Εμ]ὸς πόσις ὁ πρὶν ἄθικτα ἡμετέρης λύσασ<ας> ἄμματα παρθενίης.
 ὥλεσε δ' οὐ το[κ]ετός με λυγ[ρ]ός, Μοῖραι δὲ ῥοπῆ μοι εἰς νόσον εἰς πένθη<ι> καὶ μόρον ἡντίασαν.

15 Β. Ἡ καὶ ἀπαις : Α. Οὐ, ξείνει λέλο(ί)πα γὰρ ἐν νεότητι τ[ρι]σσοὺς ἀρτιγενείς παίδας ἐν ὀρφανίη.

Β. Εἰεν ἐν ὀλβίστηι πολιῆι τριχί. Α. Καὶ σόν, ἀδεῖτα, εὕδιον εὐθύνοι πάντα Τύχη βίστον.—
 "Οστις ἐμεῦ στήλλαν βαλέει λίθον οὐκ ἀδικηθείς, οὐτος τὰν αὐτὰν μοῖραν ἐμοὶ λαχέτω<...>.

Lt. 8-10.

THNEHMOITPOTATHNAYEMOPONHAIKIHN EIMIMEN ANNIMINING FELLE HAEMOESTI BYATEIPA OYNG MAN ANNIMINING OPINOUN BOENTOTPOPUES

- L. 13. POΠΗΜΟΙ: POΠΙΜΟΙ Hamilton.—The epigraphic copy of 1. 10 seems to show that this line was made a haxameter; such irregularities sometimes occur in these epigrams. On λόγρος, see A. Souter in Class. Rev., 1896, p. 420, and 1897, p. 31. The composer retains the Ionic dialect of his model, and adds a little Doric in the imprecatory formula!
- 53. Geurness keui: ornamented stelle with standing bird in the tri-

Hoberdey-Wilhelm, Reisen p. 163, mo. 271. In C. f. G. 3884; = Wadd, 1704) Hamilton's copy of R. 7-41 is correct and is wrongly altered by the editors. The inser, was apparently not com-

53 bis. Gedil keui: a fragment of a Christian inscription.



[... ε τις ..] ... χ]είρα π[ρασοί]σει έσται αὐ(τῷ) π[ρό]ς τὸν θεόν.

On the contraction av cp. no. 88 below.

Gisza.—In the Tekmorian Lists we find the ethnic Γισζηρός οτ Γιζηρός (Sterr. W.E. 366, 19 and 75), giving a village name Gisza or Giza, which is clearly the Carian γίσσα 'stene.' The following inscription, which lies in a street of Ak Sheher, proves that it was a village subject to Philomelion.

54.



. Δούδης Μενάνδρου
Γεσζεανή ζώσα έαντη
καὶ Ἡνράνη Παπά τοῦ Μενάν]δρου Γεσζεανῷ ἀνεψιῷ
δ ίδίφ καὶ Μενάν[δρφ
Μη]νοφίλου [καὶ
'Α]σκληπιάδη . . .

55. AZARA or EZARA, another subject κώμη, mentioned in the same lists (Sterr. 382, 5 and 366, 28) retains its name as Azari keni (Hist. Geogr. p. 411, see Map). I copied there the following rudely engraved inscription.

AOYTWEMMINEMENTERP

ώς] ἔπρεπευ μερόπε[σ]σιυ
καὶ ἐπὶ τύμβου ἔτευξε δάμαρτι σο[ρό]υ τε κάσεσσι,
Λαοδίκη τῆς κύδος ἀνὰ χθόνα πᾶσαν ἰκάνει
καὶ οξ πάντ' ἐτέλεσσαν ὅσα θυητοῖσιυ ἔοικε(ν)
τύμβου τ' ἔστη[σεν

The T after Tougon has been accidentally omitted in the epigraphic text

(the YM being too widely spaced).

Before we discuss the district south-east of Philomelion, a few words must be said about its geographical character. As the traveller leaves Philomelion, his eye wamters over what seems to be (and; roughly speaking, is) an enormous plain stretching in front of him for many weary miles. But this great expanse of country is not one dead level. The plain proper extends only a little beyond the Ilan Yusuf Tchai, the river which rises behind the village Kara-Agha and falls into the Ak Sheher Lake; and on the side of Sultan Dagh it is broken by a succession of low mountain-spurs, between which numerous rivulets run down to join the main stream. Beyond this river the ground slopes gently up to an undulating plateau, diversified by low sand hills above Arkut Khan and extending as far as Ilghin and the hilly country which bounds the Balki Deressi on the East. This plateau is drained by the Balki stream and the river that rises at Doghan Assar and flows past Arkut Khan into the Ilghin Lake." From Philomelian to Iconium two roads are available. One takes the route by Arkut Khan and Ilghin, coinciding with the Eastern Highway as far as Laodiceia Katakekaumene, where it turns southwards and crosses the mountains to Iconium.3 This is the line of the The other crosses the plain in a south-easterly modern waggon-road. direction to Balki-keni, whence it turns southwards to Tchigal and then eastwards over the mountains to Konia. This road passes Hadrianopolis and Kaballa (below).

Pisa and Selinda.—Botween Philomelian and Kara Agha we discovered two new sites. (1) The first of these is Pisa, which retains its name to the present day. It was situated beside the village Bissa in the plain under the shadow of the mountain, less than half-an-hour (about a mile and a quarter) from Aghait, the Byzantine Gaita (Cinn. p. 42, infra). The village contains numerous remains, but many of the marbles have been destroyed to build a new mosque: the process of destruction was going on when we visited the village. This town has to be distinguished from another Pissa, likewise retaining its name, situated on the hills on the north side of the valley of

So called, at least in its lower course, from a Circassian village on its banks.

I susprind particularly at different places about the course of these streams and all accounts agreed in saying that the Doghau Assar stream flows past Arkut Khan into Hghis Lake, while the Ayaslar-Urus-Yeutin (miscalled Kendil) stream falls into Balki Derssai's little to &

of lights. We exposed the latter about threequarters of an bout after leaving lights. There is no stream from Doghan Assar joining the Han Yusuf Tchni at Kotchach (so far so I hyard or could see).

There is also a hill-path from Kunderaz, described by Hogarth, i.e. p. 153 f.

Apollonia Pisidiae, and mentioned in the wars of Alexius Comnenus (Nicetas, p. 549, see CB. i. p. 186-7). The ancient name of our town is attested by the following inscription, recording the presentation of a statue of Sept. Severus.

56.

Αὐτοκράτορα Καίσαρα Λούκιον Σεπτίμιον Σεουῆρον Περτίνακα Σεβαστόν, γῆς καὶ θαλ[άσση]ς καὶ πάσης τῆς οἰκουμέ[νης] δεσπότην, Φίλαιος Μαρίωνος Εὐμένη τῷ Πεισεανῶ[ν] δήμῷ παρ' ἐαυτοῦ ἀνέστησεν.

Εὐμένη in I. 6 for Εὐμένη(s); cp. Έρμογένη, correction to Sterrett No. 169 (below); it is less likely to be a corrupt form of the genitive, and it can hardly be the adjective, agreeing with Σεονήρον. The form of the ethnic Πεισεανοί supplies a parallel to (T)ογεανῶν proposed in No. 20, I. 7.

- (2) Selinda has left its name to the modern village Selind, which lies further along Sultan Dagh to the south-east. In the cemetery of the village there are some old stones (Phrygian doorstones' and other sepulchral slabs bearing traces of inscriptions, architrave fragments, pillars, etc.). Judging from the reports of the natives as to the provenance of the two inscriptions given below, we shall place the ancient site a short distance up the hill side behind the village of Ellesler, which lies on the lower slopes of the mountain, about a mile SSW, of Selind. Here therefore we have another example of the common rule that the modern site is generally some little distance from the ancient one. The site is fixed by the following inscription.
 - 57. Lying by a house beside the mezarlik of Ellesler.



Ασκληπιάδην 'Ιέρωνος ὁ Σειλινδέων δήμος έτ] (μησεν.

^{&#}x27;They were turned up by a villager while ploughing his field behind the villager the place was shown us by this man's brother.

The township is also mentioned in an inscription now at the village Eregiz or Regiz (pronounced Ereiz or Reiz) in the plain below Bissa (=Sterrett, Epigr. Journ. No. 163), where a tombstone is erected by a busband to his wife, the daughter of Menemaches, son of Charidemos of Selinda. It is possible that this village Seilinda or Selinda is the Silindo-kome mentioned in the Acta S. Theodori Sykcotas, see Hist. Geog. p. 246. But more probably two Phrygian villages bore this name, one in the Paroreios, another in the territory of Juliopolis (compare Silandos in the Katake-kaumene). Both Pisa and Selinda are called merely $\delta \hat{\eta} \mu o_S$ in the inscriptions. It is probable that both were dependent townships, subject to Hadrianopolis, in the same way as a considerable town like Orkistos was subject to Nakoleia until A.D. 331, or Takina, &c., to Apameia (CB: p. 296).

58, Ibid. A small sepulchral stele:

AYPHATAAMMIAHE HANAPOYONHEINA KAIETIKHTOMIH MHEXAPIN Αύρηλία 'Αμμία Μεκάνδρου 'Ονησίμ[φ καὶ 'Επικτήτφ μνήμης χάριν.

The stones have all been carried away from the site, but the village of Ellesler contains nothing: it is probably of more recent foundation than the other which retains the old name.

Thymbrion—Hadrianopolis Seraste—These cities are discussed by Prof. Ramsay in J.H.S. 1887, p. 491, and Hist. Geog. p. 140. According to Xenophon's Itinerary, Thymbrion was situated midway between Kaystron Pedion (probably Ipsos), and Tyriaion (probably near Kölitolu Yails in Xenophon's time), 10 parasangs or nearly 35 statute miles from either town. This points to a situation in the neighbourhood of Kotchash. The Fount of Midas (Yassaghan or Yassian Bunar, midway between Ishakli and Philomelion) was apparently in the territory of Thymbrion, and Prof. Ramsay is clearly right in thinking that Thymbrion was the great city of the plain until the foundation of Philomelion by the Pergamenian (or Seleucid) kings. The last mention of Thymbrion occurs in Pliny N.H., v. 95, where the Tymbriani are in the conventus of Philomelion. We are therefore led to infer that 'the city was refounded by Hadrian under the name Hadrianopolis' (J.H.S., l.c.). Hadrianopolis, which comes between Tyriaion and Philomelion in Hierocles' list, is mentioned in

Anatolian pronumiation tends to convert g between two vowels into a g sound and finally to let it drop altogether; ep. Tahigil, now pronounced Tchiyll (below). Regiz is a different village from Egrigion, which is quite close to Ak Shaher.

The correct reading is CEAIN LEWC.

The surrection Silinda-kenne, there maggested in a feetnote in place of Silindicaneuss, is proved to be right by comperison of the Greek original, published by Joannes Theophili

In his Mequela 'Ayiokoyica

^{*} J.H.S. Le., Ath. Mitth. 1889, p. 180-1;

Χατι, είπαι. 1, 2.1 Έντενδεν (fram Kayatron Todion) εξελαόνει σταθμούν δύο, παρασάγγας δέακ, είε Θύμβριαν, τόλιν είπουμένην. Ένταύδα Το παρά την άδον κρήνης η Μίδου καλουμένη του Φρυγών Βασιλέων έφ ή λέγεται Μίδας τον Σάτυρου θηρεύσας σένα εκράσας αυτάν. Έντευθεν εξελαόνει σταθμούν δύο, παρασέγγας δέακ, είς Τυριάκιον πόλιν οίκουμένην.

an inscription now at Kara Agha, (Sterr. E.J. 160), which, however, does not fix the site : for it is obvious that the inscriptions of the village, which are all built into the mosque and engraved on the same rough reddish sandstone blocks, have been carried, and there are no other remains in the village. A passage in Cinnamus, p. 42, describing the operations of Manuel I. against the Turks in 1145, gives us some help. The Turks after a defeat at Philomelion retired to a place called in Turkish 'Ανδραχμάν, whereupon Manuel started in pursuit, πόλιν τε Αδριανούπολιν ύπερβάς (διαβαίνει γάρ και ές αύτην Αυκαονίαν το δνομα τούτο) εν τινι χώρο Γάιτα όνομα την παρεμβολην έποιήσατο, i.e. crossing into the territory of Hadrianopolis (which includes the whole southern part of Paroreios), he encamped at Gaita, which is still called Agha-it.2 An examination of all the villages in this plain led me to the conclusion that Hadrianopolis should be placed beside Kotchash, where there are numerous remains built pell-mell into the Türbe-mosque or lying beside it (see Sterrett, E.J. Nov. 165-173, and below No. 59). In that case the river Karmeios mentioned on its coins (Ramsay in Athen. Mitth., 1889, p. 76) will be the Han Yusuf Tchai.

The importance of the ancient city has passed in some degree to the mudurlik Doghan Assar, situated on the slope of Sultan Dagh (like the majority of the villages in this district), and a site at or near the village has been suggested for Hadrianopolis (J.H.S. and Hist, Geog. U. ec.); but Doghan Assar lies away in a corner, off the line of the direct road to Iconium, and does not suit the conditions nearly so well as Kotchash. It was probably a xóyny subject to Hadrianopolis, like Gaïta, Pisa, and Selinda.

To Hadrianopolis belong the inscriptions of Kotchash (Sterrett Nos. 165-173) and Kara Agha (156-161), Tchetme (162), and Doghan Assar (174 and Sarre, A.E. Mitth. xix. p. 37). Some improvements on the published copies

may be given here:

No. 156, Il. 3 and 5 are corrected in Hist. Geog. p. 178

No. 157, l. 4 read [ζ]ών: space for only one letter.

No. 158, I. 3 BACIAICH is clear.

No. 159, I. I ABACKAN//UL, i.e. 'ABGORANTOS.

No. 160, 1 4 restore τ[ŷ ibiq]: the H is under Δ and the C under N.

No. 162, L I read της Maribos, and Τειμολάφ (as required):

No. 166 apparently reads Αυρήλιος Σούσ[ου], Αυξάνων, Θόω[ν]* Ταπεί [μν]ήμης χάρω.

No. 168, l. 4 [H]awlov, and in 5 // /ΕΙω, i.e. [6]elφ (with angular +),

since it cannot be [v]eral

No. 169. The stone is rough both above and below the engraved part, which shows that nothing more was inscribed. Έρμογένη is the nomin, case like Εὐμένη in No. 56 (above).

¹ The lettering is poor and late.

² 'Agha-lit, Herryapossage' Tomaschek p. letter. The last three words are under the 103. Gaits is also the name of a village man relief.

Nimea, H.O. p. 201.

No. 170, L 1 AMT, which gives 'Αμπέρως.

No. 174. My copy begins υζ////ΑΙΝ († αινι) and continuesκ κνουμ μανει δοκε [apparently].....[αττ]ιαδ ειτου.

59. Kotchash, in the mosque.

AYPEYCTAGIC

IMENOC

AYP>KYPEIAMENEKAEWC

THEAYTOYCYNBIW

MNHMHCENEKEN

Αύρ. Εὐστάθις Ίμενος Αύρ. Κυρεία Μενέκλεως τῆ ἐαυτοῦ συνβίω μνήμης ἔνεκεν.

For the form Εὐστάθις (=Εὐστάθιος) ep. Πατρίκις and 'Ηράκλις (No. 91) and CB, ii. No. 264, where reference is made to J. H. Wright, Harvard Class.

Stud, 1895, p. 59 f.

"Iμαν (gen. Tμενος), with prothetic ε like Τσκύμνος for Σκύμνος, εtc., is one of a group of names (so common in the Pisidian inscriptions) derived from the name of the god Manes-Men. The frequent occurrence of this group and of other native names in Paroreios and the vicinity is a significant indication of the vitality of the native civilisation. Τμαν occurs also in No. 63 (cp. 54), Hogarth Le. No. 19; Μάνης in 65, Hogarth 9, 20, 21; Μανίς Sterrett 162 (see above); Μανία, Hogarth 17 and 20; Μανοσᾶς Hog. 16. Similar names are 'Ασία in 73, 'Ασεύς in 83 (Chr.).

60. Yendin keni.

Παπάς Παπίλω νίω . . .

In another fragment occurs the name Kôvæv (see No. 85).

61. Doghan Assar, a fragment in the mosque.

TYMBWETICT////
HAHNANYCIOYYI
EOCAYTOYEZET
EWNMNHM////ECTHC

τύμβφ έπι στήλην 'Ανυσίου υίέος αὐτοῦ ἔ[ξ] έτέων μνήμ[ην 1] ἔστησ[ε-

BALKI DERR and KABALLA.—One inscription of Balki keui, and some from other villages on the road between it and Konia, are published by F. Sarre, A.E. Mitth. xix. (1896), p. 35 f. I traversed the road from lighin by Balki to Tchigil and copied the following inscriptions.

[&]quot; So Epar for Nar, sto.

62. Getchid keni (in the Dece, 2 hrs. 5 min. from lightn): in the mosque,

MEIPOCNADITHEAY

FYNAIKIFAYKYTATH

KEAYTOZONKOP

ONONANECTHCEN

Μεϊρος Νάδι τῆ ἐαυ(τοῦ)
γυναικὶ γλυκυτάτη
κὲ ἐαυτῷ ζῶν κὲ φρονῶν ἀνέστησεν.


Nas, Na (No. 65), 'Evas' belong to the class of Lallnamen which appear in all languages and of which Kretschmer, Einleitung, p. 234 ff., has collected numerous examples. This class of name is very common in Isaaria (Heberdey-Wilhelm, Reisen p. 123) and Pisidia.

63. Balki keui (7 hr. from former), in the bridge.

AYPMENNE ACIME EN OG THE AYT DY CHIMBI W FA KYTATHAOY AAKAITWYW AYPHIENTICH HILLINGEN Αύρ. Μεννέσες τη έαντοῦ σ[υ]υβίφ γλ[υ-κυτάτη Δούδα καὶ τῷ ὑῷ Αὐρ. "[μ]ενι μυ[ήμης χά]ριν ἐποίησε]ν.

The name Aup. Merréas "Ineros occurs twice in Sterr. W.E. 373 (30 and 39).

64. Tchigil (Ashagha); poor lettering.



*
Δύρηλία Δόδα κὲ 'Ορεστίνα τῷ ἰδίῳ ἀνδρὶ ποθινοτάτῳ
Μ[ο]ὑᾳ ὶ ἀνέστησα[ν] μνήμης χάριν.

Δόδα also in Sterr. E.J. 202. Δόδα, Δούδης, Δούδας are all by-forms of DADA: see Kretschmer, op. cit. p. 337.

¹ Cp. CB. uo. 91, p. 209, where Er4 rg yermal is rightly read, Rev. Univ. Mill. 1896, p. 302.

65. Tchigil (Yokaru), 20 min. East; mar the mosque.

AYPNAMANOYT WANAPITTATIAM ANOYIWAAAN CTHEENMAHAHC KAPIN Αύρ. Να Μάνου τφ ἀνδρὶ Παπφ Μἀνου [Δ]ώδα (? στ Ἰώδα?) ἀνέστησευ μ - χ .

66. Ibid. on a pillar.

ATTAAOC EAYTWKA THEYNAIKIK Hidden TWYIWZW NWNAANII PINETIOIH "Ατταλος
ἐαυτῷ κα[]
τῆ γυναικὶ κ[αὶ
τῷ υἰῷ ζῶ[ν καὶ φρανῶν μνή[μης χάριν ἐποίη[σεν.

Besides these there is another fragment and an inscription on a tall bonow; the latter was so faint and worn that I failed to make an intelligible copy.

These inscriptions and the numerous remains at Tchigii and Balki, which were said to have come from a site called Bel Ören on the casy hill-road between Balki and Tchigil, attest an old settlement of considerable importance. Prof. Ramsay would place at Tchigil the town Kaballa, birth-place of Constantine V. Copronymos, an important fortress on the road between Hadrianopolis and Iconium, the Caballu-come of the Peut Table's false road Laudicia Catacecapmene xxiii Caball xxxii Sabatra. The important passage for the topography is Cianam. p. 42 ff. already quoted in part In 908 it was held by a certain Andronicus and is described as δχυρόν τι φρούριον, οὐ πάνυ τι μήκοθεν τοῦ Τκονίου διακείμενον (Zon. xvi. 14). Dr. Tomaschek gives some additional references: in 822 Choireas held φρούριον τοῦ Ανατολικοῦ ἡ Καβάλα (Theoph. Cont. p. 72); ἐν τῷ Καβάλα λεγομένῳ ἄστει (Vita Euthym, ed. De Boor, c. xi. 8: ep. xiii. 29).*

I think that an examination of the passage in Cinnamus shows clearly that Kaballa was situated much nearer to Konia than Tchigil. Here is the course of events. After a defeat near Galta, the Sultan Masut fled to Iconium; but not desiring to be shut up in the city, he divided his army into three detachments, leaving one to guard the capital, placing the second on a steep behind the city and the third (with himself at its head) êv ceşuş relying on the strength of the mountain which stretches between Iconium and the fortress Kaballa. Manual now reached Kaballa and a battle ensued (on the right of the city). Part of the Sultan's army was routed and fled, pursued by the Romans. Meanwhile the remainder of the Roman army was attacked by an ambush reinforced by the guard left in Iconium (who sallied out, taking courage from the fact that Manuel was being carried by

The ordinary road keeps along the Dere.

^{*} Hist. Gong. p. 359.


Mich. Glyksa p. 528.

^{*} Tomaschek, op. cit. p. 103.

the ardour of pursuit far from Iconium) and by the detachment posted on the steep behind the city (τῆς πόλ. ὁπίσω). On the return of the pursuers, the Romans succeeded in repelling the attack when night came down. In the morning Manuel 'set out thence and encamped before Iconium' i: but he gave up the idea of besieging it and after burning τὰς πρὸ τῆς πόλεως οἰκοδομὰς he began to retire again towards Lake Pasgousa (p. 58, i.e. Lake Karalis, Beysbeher Giöl). Meantime the Sultan was reinforced by troops from beyond Iconium and hastened to attack the Roman army at the difficult pass Tchivrili-tehemani ('the sinnous declivity,' Tomaschek, p. 101) . . .

This account shows clearly that Tchivrili-tehemani is the pass a few miles west of Iconium, beyond which the road to Vaaada and Lake Karalis diverges from the Iconium-Hadrianopolis road, and not the pass just east of Tchigil. It is equally clear that Kaballa is quite near Iconium, as Zonaras says (xvi. 14). Dr. Sarre (p. 35) would place it at Kavak keni, where there are remains (especially many fragments of Byzantine sculpture). I have not traversed this part of the road and therefore cannot offer an opinion about the site, but the situation suits the conditions. Whether the Gleichlaut der Worte Kavak mit Kaballa is more than an accident is doubtful, for Kavak ('poplar') is a common village name: but it is quite possible that the Turks in taking over the old name gave it a form which had a meaning in their own language.

Trataion.—Some inscriptions of Tyrinion and the district between it and Laodiceia Katakekaumene have been published by Mr. Hogarth in J.H.S. l.c. p. 162 ff.³ There has recently been a great destruction of marbles to obtain good stones for the new government buildings at Ilghin, but I succeeded in adding a number of inscriptions to the small list already known. Individually they may not always be very interesting, but in the mass they are not unimportant, and I give many of them in cursive only rather than omit them altogether. The first will interest philologists.



Cp. Nicetas, p. 72, ed. Bonu

a of dependence to hear factors theretoe, p. 40.

PfiBender (quart xinos overpósodos eleses ess e.e.d., p. 47.

⁴ Cp. Hist. Geog. p. 859 note t.

^{*} In no. 13, 1 2 cm. 1 read FAIOY; no. 14, the epigraphic text is correct. One inser, of Tyrialon in Heberday-Wilhelm, Reises, p. 162, no. 270.

For a discussion of the Phrygian inscriptions reference may be made to Ramsay in Kuhn's Zft.f. veryl. Sprachf., N.F. viii. pp. 381-410 (where all the inscriptions are collected): notes by Fick in Bezzenberger's Beiträge z. Kunde d. indg. Sprachen, xiv. (1889), p. 50 f., and Ramsay, ibid. p. 308 ff.; A. Torp, Zu den phryg. Inschr. aus röm, Zeit (Kristiania, 1894) and Zum Phrygischen (Ibid. 1896).

Ll. 2, 6. Ξευνη or Ξευνα, a fem. name, occurs several times in N.W. Phrygin: at Nacolcia (Ramsay, &c. Nos. xv., xvi), at Apia and in upper

Tembrogios valley (unpublished),

L. 3, parkar iar cotacs . . . 'the monument which . . . set up.'

68. Malimud Assar, in the cemetery : letters rather faint.

IOCCEMOY///NOYN/ ANEIKACEY///ADAKET TITTETIKMENOCATTI EADEITOY VAC. ιος σεμου[ν κ]νουμανει κα[κ]ευ[ν] αδακε[τ τιττετικμένος αττιεαδ ειτου.

κακευν: cp. κακεν, B.C.H. 1893, p. 289 (cp. B.C.H. 1896, p. 111).
αττιεαδ: so in C.I.G. 3986 (near Ilghin) according to Sestzen's copywhile Hamilton's has ΑΠΙCΑΔ: ατιαδ. Hogarth, No. 3: αστιαν, Ramsay, No. xiv., -ττιαδ, No. xi., -ιαδ according to my copy of Sterr. E.J. 174.

69. Arkut Khan;

COYCOYAPE////
AIAFYNAIKI
MNHMHC
XAPINПAPE////
AY*OYKAI
7 WNEAV
TW

Σούσου 'Αρελία γυναικὶ
μνήμης
χάριν παρ' έαυ[τ]οῦ καὶ
ζῶν ἐαυτῶ.

Σούσου occurs frequently in this neighbourhood, Sterr. E.J. 156 (better in Hist. Geog. p. 178 m.) and 166, Hogarth Le. Nos. 17, 25, 27. On the name, which is perhaps another Lallname, see Kretschmer, op. cit. p. 352.

TOPAEOC etc., the host letter being slightly blursed in the inside. In E.C.H. 1896 Le. MM. Radet and Ouvré collect a few of those previously published, in ignorance, apparently, of the articles quoted above.

Except the two fragments added by Storr. E.J. 174 (see above) and 186; three schied by Flogarth i.e nos. 1-5; and one by MM. Legrand and Chamonard, B.C.H. 1893, p. 239 (better in B.C.H. 1896, p. 111); a copy of this inscription which I made in 1896 reads ΔΔΔΚΕ

70. Eldesh, in a cometery :

KOCTION KALICH BOC OLE BNACE I BH LICTON COLLINE COLLINE CALICH EA. CALICH EA. CALICH Κοσμίων κυρίου Kulσαρ]ος οὐέρνας είρηνάρχης ΔιΙ Μεγιστφ εὐχήν.

It seems somewhat strange to find the Eirenarchate held by an Imperial verna. Was be connected with an Imperial Estate? The Eirenarchate is discussed by Prof. O. Hirschfeld, Berl. Akad, Sitzungder, 1891, p. 868 ff.; cp. CB, i. p. 68. The relations between the Eirenarch (with his gens d'armes, διωγμίται), the Paraphylakes (heads of the village police, see above No. 14), and the Στρατηγός έπὶ τῆς χώρας cannot as yet be definitely determined; but it seems probable that the Eirenarch (who was responsible to the municipal authorities) was charged with the maintenance of public order in the city and its territory as a whole, and was therefore the superior of the local paraphylakes.

71. Ilghin: in large cometery.

BATAKHCMAI PATEIT HMHTPIMNHMHCE NEKEN Βατάκης Μαιφάτει τη μητρὶ μυήμης ξνεκεν.

Bατάκης or Βαττάκης was the name of a family which held the priesthood of the Great Mother of the Gods at Pessinus, at the time of the campaign of Cn. Manlins (Polyb. xxii. 20, 5 παραγίγνονται Γάλλοι παρὰ "Αττιδος καὶ Μαρίος (Polyb. xxii. 20, 5 παραγίγνονται Γάλλοι παρὰ "Αττιδος καὶ

Barrasov) and in the time of Marius (Plut, Vita Marii, v. 17).

Maidareis is an interesting name. The masc form occurs as the name of a Galatian slave [but Phrygian by race] in an inser, at Delphi, Marcaras το γένος Γαλάταν (Wescher-Foucart, Inser. rec. a Delphes, No. 189) and at Tokat in Pontus Galaticus (C.I.G. 4184, better Ath. Mitth. xiv. p. 316) along with Zapanros (gen.) for which Dr. J. H. Mordtmann aptly quotes Hesych. The first element of the name is seen also Zaphtis · "Артерия, Первал. in Mai-βουζάνης (Cataonia, B.C.H. 1883 p. 130), as is clear from Μιθροβουζάνης, the name of the Cappadocian general at the battle of the Granicus (Diod. Sic. xvii. 21: ep. xxxi, 22); also in Masôáray at Cos (Paton-Hicks, No. 10h 73, and No. 44 = B.C.H. v. p. 225), and perhaps also in Markings at Cibyra (B.C.H. ii. p. 595) and Malevoy at Myrina (B.C.H. vii. p. 211). Just as Ζαραήτος goes back to Ζαρήτις, and Μιθροβουζάνης to Mithras, so the Mas- group is derived from the goddess Ma ('the mother,' as every child knows i), worshipped especially at Comana (Capp.) but also in Rhodes, probably in Cos, and in other parts of the Asiatic mainland.

72. Ibid.

Τατείς Κιδραμούη άνδρι | μνήνης ένεκεν.

Kιδραμούας is related to the city-name Κίδραμος, as Attes to Attenda Tottes (Tatas) to Tottaion (Tataion), and many others quoted in Hist. Geog. p. 241. The name occurs in Pamphylia (Κιδραμύας, Κυδραμώας, Lanckor, Nos. 98, 65), in Pisidia (Κιδραμᾶς C.I.G. 4366ω), and the Phrygo-Pisidian frontier (Κιδραμᾶς-Κιδραμᾶς Sterr. E.J. 39, 1, 30 and 46, 1, 13, Κιδρομᾶς CB. 127, p. 310 improving Sterr. 45). Cp. Kretschmer, Einleitung, p. 333.

73. Ilghin: now lying beside the new Depôt.

'Αχιλλεύς | 'Αχιλλεί | ἀνεψιώ | μνήμης | χάριν σύν | γυναικί 'Ασία.

'Aoia and 'Aorès (No. 83) are interesting old names: they are clearly connected with the old divine names ACEIC, the title of the native Laodiceian deity, which was perhaps of Syrian origin (see *UB*. i. p. 83), and 'Aoia, which remained as an epithet of Athene in Colchis and at Las in Laconia (Paus, iii, 24, 7).

- 74. Ibid. Μενεκράτης 'Αππία | θυγατρί | μνήμης | χάριν.
- Tighin: large cometery.
 Δίδυμος | 'Ακυλείνη θ(υγατρὶ ἀνέ[σ]τ[η]σεν μν[ή]μης χάριν.
- Ilghin: in a tcheshme.
 Αξλία Μάξιμα καὶ Λύρή(λιος) Νί[κ]ων ἐαυτοῖς [μ]νήμης χάριν.
- Ilghin: in another toheshme.
 Εὐχάρι[σ]τος Εὐ|φροσύνη γυναικὶ | καὶ ἐαυτῷ ζῶντι | μνήμης χάριν.
- 78. Tchaüshji keui (head of Ilghin lake): 'door-stone' with pediment ornamented with floral designs.

'Αρχέλασς Τατεί τη γυναικί ίδια φιλοστοργίας ένεκεν.

79. Mahmud Assar: in the Mosque,

This inscription may be Christian. For the date [']wa' expressed by letters alone without \$\tilde{\epsilon}\text{rovs}, see CB. ii. p. 479, no. 350 and no. 645.

80. Mahmud Assar: below the inscription is a relief representing two women, the left holding a hammer (?).

Αύρ. Σελευκία καὶ Α[1]λιος καὶ Δέκμος τῷ | ίδίψ πατρὶ γλυκυτά(τφ) μ.χ.

81. Eldesh: in cemetery.

'Αππάς Τατεί [τ] ξι είδία | γυναικί μ. έ.

In this village there are other two defaced inscriptions.

82. Ibid.: in large letters.

MHCTONANATOAHKO!!!

κομίης του Ανατοληκο[ν]

CHRISTIAN INSCRIPTIONS.

83. Ilghin: beside the Depôt

Έλία Βασίλισσα θυγατήρ Είλάιρου πρεσβυ(τέρου) [τ]οῦ 'Ασέως |[σ]ου τῷ ὑἰῷ μου Πα|[τ]ρικίου ἀψέστησα]υ τῷ γλυκ[υ] τάτῷ μου ἀ[υδρί Πα]τιρικ[ίου μ.χ.].

Basilissa at Hadrianopolis, Sterr. 168 (see supra); Hilam in Sterr. 163 (read Αλλάρα, cp. αίαυτῷ for ἐαυτῷ); cu 'Ασευς. No 59 (above).

84 Ibid.



 $\Lambda + \Omega$

+ Αυρύλιος 'Ανένκλητος
κέ Μῖρος ὑειῦ Θεοδούλου ἀδ΄ νεστήσαμεν τῆ μητρὶ
Πριειντος τὴν
(σ)τήλην ταὐτην μνήμη(ς)
χάριν.

In 11 8, 9 the stone has E twice for C. TPIEIYTOC seems to be another Phrygian or native name.

85. Ilghin: in a mosque.

+ Αὐρίλιο(ς) | Κόνων ἀψέστησεν | μνήμην τοῦ | τέκυου αὐτοῦ Παύλου,

The name Κόνων was common among the Christians: cp. on No. 60, and Hogarth No. 18. Παθλος also in a fragmentary inser. at Tchanshji keni, Παυλείνος at Hadrianopolis (Sterr. 160): while 'Ιωάννης occurs in No. 90.

86. Highin: in large cemetery,

+ Αυρήλιος | Μάξιμος | ἀν(έ)στησ|ε τοῦ είδιου τέκνου Ερμογένου | μ.χ.

87. Ibid., in large letters.

. . δίξου, Κύριε, τῶς ἐχθρ[ὖς . .

88. Tchaüshji Keui.

Ματρώνης τόδε σήμα επισκάπου δε θυγατρός Μυησιθέου, τον πάντες ετείμων,
ως γὰρ ἔοικεν ἐστήλλην δ΄ ἐστησεν πόσις καὶ φῖλτατα τέκυα αὐ(τ)οῦ 'Αρελλιανὸς τἢ ἰδία γυνεκὶ
καὶ αὐ(τοῦ) τέκυα 'Αμμία καὶ 'Ερμιανὸς τἢ ἰδία μητρὶ
ἀνέστησαν μνήμης ἔνεκεν.

89. Malimud Assar.

TYNBOCEIC[[8c AEWNHAKA OMNEUNTAONO MATA PAA AEZANAPOC KEAMIHEAIA KONHCHEENE THEAMENTOS THEAMENTOS THEAMENTOS THEAMENTOS THEAMENTOS THEAMENTOS THEAMENTOS + Τύνβος είσπουδέων μακάρω]ν οἰν τὰ ὁνοματα Φλ. Αδ λέξανδρος κὰ 'Αμίης διακονήσης, ἀνεστήσαμεν τό(ν) τίτ[λ]ον μνή-10 μης χάρινκὰ Μείνου +

LI 1-3 Prof. Ramsay acutely detected είςπουδέων (i.e. σπουδαίων) μακάρων.

Le 11 perhaps Mes[p]ov.

90. Tekke keni, 1 hr. E of Mahmud Assar.

Αὐριλία Θέκλα ἀνέστησα τοῦ έμο ο τέκνου 'Ιω άνου μνήμης χάρ(α):

91. Eldesh:

'Ευθάδε κατάκιτε 'Ηρώκλις κε Πατρίκις | κε Η[ο]λύκαρπος | πρεσβύτεροι | μ.χ.

92. Arkut Khan.



We have now reviewed the country along the great commercial highway of the Roman period from Apameia to the south-east corner of Phrygia. For five containes or more, a commant stream of traffic passed along this road, and flourishing cities with numerous subject villages were to be found on it at Here then, if anywhere in the interior, we should expect to short intervals. find that the Graeco-Roman civilisation struck its roots wide and deep, absorbing and transforming the old native half-Oriental civilisation. Yet nothing is clearer than its failure to make any lasting impression. The Phrygian language lived on, and the native spirit retained its vitality and ultimately prevailed. In the plain of Metropolis the native population, the Euphorbeni,3 maintained its existence side by side with the Greek city. Lysins was planted amongst the Omiatai: now only a low mound marks its site, while the Qiniatai have left their name to the village Oinan and the plain around. The Roman city Julia flourished and died, and the old name Ipsos reasserted In the plain of Philomelion the villages Azara, Pisa, Selinda live on as Azari, Bissa, Selind. In the remaining part of Paroreios we have found numerous indications of the persistence of the native element. Tyriaion clearly retained its native character, with a mere veneer of Greek civilisation. till the establishment of Christianity. The Hellenization of the interior (apart from the great cities) as a whole was due to the spread of Christianity; but the Helleniam is brought was of a pithless, stagmant type, which was too

^{*} Ca CB. H. to 756-L.

easily absorbed and assimilated when the great wave of Orientalism overapread the land with the Turkish invasion.

J. G. C. ANDERSON.

March, 1898.

NOTE ON KABALLA AND TCHIVEHA-TCHEMANI (p. 121).

Prof. Ramsay has sent me the following communication: —"It is very probable that you are right in placing Tribrillizemani, etc. nearer Iconium than I have done. I hesitated long between your view and the one I have taken: and at last it seemed to me that here, as in other cases, the Byzantine accounts exaggerate Manuel's progress and speak as if he had gone further than he really did. The literal interpretation of the Greek words is with you; but I am not sure that we can take them literally. Similarly, historians speak of Loulon as near Tarsus, though it is nearly seventy miles distant." It is, of course, true that no stress can be laid on a more phrass like of sure re another red Troolee (Zen. xvi. 14), which may (in a Byzantine historian) be perfectly vague, or on a mere solltary statement that a certain event took place; but if we discredit a detailed account such as Cinnamus gives, do we not thereby ruise a very large question?

Note on the Mark

The map of Phrygia Paroreios (Pl. IV.) is based on Dr. Richard Kiepert's map attached to Dr. Sarre's book "Raise in Kleinasien," but I have introduced several alterations and additions based on my own observations and compass readings. The small inset map follows Prof. H. Kiepert's map in Dr. Buresch's Aus Lydles, etc., with a few alterations and some additions. Plate V. is based on Prof. Kiepert's large-scale map of Westliches Kleis Asien, but numerous alterations are made from my readings and observations (while in one or two points Prof. Railet's maps in En Phrygie have been laid under contribution).

THE GAME OF MORRA.

The Imperial Ottoman Museum has recently acquired a very valuable and interesting gold ring (Fig. 1) which was found in 1894 or 1895 in a tomb at Lampsacus. The Museum authorities subsequently undertook further excavations in the necropolis of which this tomb formed part, and it is a matter for great regret that no detailed report of the results was drawn up; we are therefore forced to content ourselves with the somewhat meagre information given by the late Baltazzi-Bey to M. Salomon Remach, according to which the necropolis yielded fragments of red-figured pottery and specimens of silver autonomous coins of Lampsacus. Both these details are of importance in fixing the date of the ring; for on the one band silver coins of this class



Fig. 1.—Gold Ring in Imperial Offician Muneum. (Twice octual nize.)

belong almost exclusively to the fourth century, and on the other, the manufacture of painted vases was not continued after that date. When we add that the evidence of coins and inscriptions proves that this was the most flourishing period in the history of Lampsacus, we have strong a priori reason for assigning the ring to this century, while a consideration of the style of the intaglio may help us to fix the date within narrower limits.

The ring has been already published by M. Salomon Reinach,3 who thus

¹ Beom Archibigique, 1895, ii. p. 363 = Chroniques d'Orient, ii. p. 471.

^a For columns B.M. Catalogue of Grack Cries, Mysic, Pl. six. For inscriptions, B.C.H. ax, p. 553 (Proxents of Epidaurus).

H.S.-VOL. XVIII.

[&]quot;Had sincetype in the Rowse Arch. (Inc. vii.). Enlarged design in the Chroniques of Ordent, which gives a very inadequate idea of the delicate execution of the design. The drawing in the text is by Mr. P. Anderson, from an in-

describes the subject—Seated draped Venus, holding in her hand a long wand with which she is threatening a Capid who stands facing her.' As a matter of fact Capid is holding the wand quite as much as Venus, and Venus is not threatening her son; she has extended two fingers of the right hand, the first and the middle finger, as if she were counting, from which we may conclude that she is playing a game well known to every traveller in Italy, the game of morra—(il ginoco della morra). Venus lifts two fingers; Capid replies by a recognised move and flings forward his clenched fist. Additional proof is furnished by the wand, which each party clasps with the left hand. The game of morra is played with the right hand and at such a rapid pace that it would be impossible to count the moves if the attention of the players were distracted by any movement of the left hand, which is therefore ruled



Fig. 2. (From R. F. Attic bydris in Daialynski Collection.)

out of the game. Nowadays this is achieved by putting it behind the back, but in Greece, as vase paintings show, it was done by making the players hold a wand. There is however this difference between the vase paintings and the integlio, that in the former each player holds one end of the wand, and in the latter they both hold it by the same end. In order to facilitate comparison between the two methods of holding it we furnish (Fig. 2) a drawing of the scene depicted on a red-figured Attic hydria in the Dzialynski collection—the earliest known representation of the subject.

pression given to me by M. Mylones. My thanks are due to H. E. Hamity-Bey for kind permission to study the original. The dimensions of the benefits of 25 mm. × 21 mm.

¹ To Panofka is due the credit of baving been the first to recognize that this scarm depicts the game of morra. He detected it on a Grasco-Italian hydria in Munich, No. 806 (Bilder aut.)

I only know one ancient monument which represents the game of morra played as it is played in the present day, with the left hand behind the back. This is a large bronze (Fig. 3) in the British Museum.\ It is said to have been found at Foggia in 1869. In any case it is Italian, and not Greek work, and of comparatively recent date, being very similar in style to the large bronze Cupids found at Pompeii. It represents Eros standing holding up his left hand with an animated gesture, while the right is concealed behind his back. It may be presumed that this statue formed part of a group which represented Eres playing at morra with his mother, or more probably with his friend Ganymede. He plays three, raising the thumb, index and second



Pro. 3.—BRONER FIGURE PROM FOGGIA. (Bertink Manouma)

fingers. From this we see that the game of morra was played in Italy in antiquity as it is to-day. It was only in Greek countries that it was played with the wand.

Lober, Pl. z. 6), and on the Dzialynski hydria (Arch. Zent. 1848, pp. 246, 7), published for the first time by Otto Jahn (Annuli, 1866, Per. Pagg, U). Both vame have been frequently figured, the latest publication being by Schreiber Anderson, Atlas of Class. Ant., Pl. Ixix. 7 and 10, with a bibliography of the subject. Heydemann found and published another representation on a map from Ruvo (Naples Messam), No. 2574 (Arch. Zeitung 1891, FL 56, 1), but it is doubtful whether the game is depicted on a Berlin hydris, No. 1953 (Jahn, Justiff, 1866, Twe, at app. V and p. 328).

1 No. 826. Hi. 2 ft. 61 in. Acquired from

Piot, Unpublished.

The Lampsacus ring is a masterpiece of fourth-century goldsmith's work; nothing but actual study of the original can enable us to realise the absolute perfection of technique displayed in rendering the folds of Aphrodite's chiton; but some idea of it may be gathered from a comparison with the intaglie of another gold ring now in the British Museum, which represents Aphrodite amusing Eros with a bird (Fig. 4). The type of Aphrodite is the same, costume and chair are identical, but the execution of the design wants the exquisite finish of the earlier work and proves that it must be assigned to a later date. This difference of date is confirmed by a comparison of the different types employed for Eros. In the one design he is a youth with great strong quivering wings meant for use, in the other a mere cupid decorated with a pair of useless winglets.



Fig. 4.—Gold Ring in British Museum (Twice setml slee.)

The composition of the design of our ring is no whit inferior to the rendering of it. If we study those vase paintings which represent this subject, we see that the adversaries are of equal size and are seated facing one another, each holding the wand by one hand; but our engraver has varied the design so as to make it fit better into the space at his disposal. Approdite sits and Eros stands before her; thus the artist obtains an apright design better suited to the narrow field of a seal than the horizontal one required for a vase painting. The design is so admirably suited for the decoration of a mirror case that it is there perhaps that we may most reasonably expect to find it some day.

PAUL F. PERDRIZET.

Unpublished. Acquired at the sale of Lord Vermon's antiquities, 1885 (Arch. Ausriger, 1886, p. 128).

NOTE ON SOME ATTIC STELAL

I SHOULD like to call attention to an attitude in some of the Attic stelai which has attraced little, if any, notice, while its meaning, so far as I know, has met with no consideration.

The best example of the attitude is to be found in the beautiful Plate XXIV. of Mr. Percy Gardner's 'Sculptured Tombs of Hellas' (Conze, Pl. LXXVIII). Mr. Gardner describes the sitting figure as 'a lady stretching out both hands towards a matron who stands before her,' certainly an inadequate description of a peculiar attitude. Conze, in his great work 'Die Attischen Grabreliefs,' says that the standing figure with the left hand takes held of the right arm of the sitter on the under side (unterfasst). But this seems to me to miss the point. It is not the right arm but the right wrist of the sitter that is laid hold of. 'The forefingers of the standing figure are extended along the forearm and the thumb is raised at the wrist, so that the sitter's right hand lies softly in a sort of couch. From an artistic point of view the attitude is a remarkable one, being unlike that of any of the other best known stelai.

In the nine parts of Conze's work I have found but one other example of the same attitude (Part I., Pl. XLIII., fig. 150), and in it there is a slight modification, viz. that, while the left hand of the standing figure still lays hold of the right wrist of the sitter, the fingers of the latter twine softly round the standing figure's left wrist, from the under side, so that the two hands are linked together closely at the wrist, just below the bracelet which lies on the forearm.

In the almost unique example of a 'Dying Woman' treated in a realistic manner (Gardner, fig. 66), we have the same looking of the hands together at the wrist, but with this difference from the previous illustration (Conze, fig. 150), that the fainting lady extends her right hand, which is received by the standing figure's right hand at the wrist. The latter lady is described by Mr. Gardner as the 'Mother whose extended arms signify sympathy and grief,' the peculiar attitude being entirely overlooked.

In Conze, Part I., Plate XXVI, there is a beautiful relief of a sitting lady between whose knees a naked boy presses forward with loving eagerness. Conze says, 'She embraces him with both hands' But this is a weak description of a beautiful attitude. Her right hand lies tenderly under his left wrist or forearm, her fingers being extended to his elbow, a change of position from that of our former illustrations. But from the relation of the

figures to each other any other arrangement would have been impossible. We have however the same soft, gentle touch as in the former cases.

Other two variations complete the list of illustrations which I have

been able to find in Conze.

In Part VIII., Plate CXCVIII. an old man with his right hand clasps the right hand of a girl (in the usual manner of the δεξίωσις), but Conze fails to observe that the left hand of the old man is laid on the right verist and forearm of the girl, his flugers appearing below, clearly a mark of the closest attachment.

The same attitude is found in Conze, Part I., Pl. XCVIII. 'Corallion' clasps the right hand of 'Agathon' with her right in the usual manuer, while her left lies under his right wrist and forearm. This is noted by Conze.

Here again this action shows an affectionate tenderness.

Last of all in the beautiful mural bas-relief of Naples (P. Gardner, Pl. XXIX., 'Orpheus, Eurydice, and Hermes') we have a fine example of the attitude in its most expressive form. Here it is Hermes, the Psychagogos, that lays his hand most tenderly on the right wrist of Eurydice, twining it round in what seems to us a forced action, as by this gentle touch he performs his sad duty of leading again to the Shades the newly-lost wife. The mournfulness of the scene is heightened by the position of Orpheus and Eurydice towards each other. Turning to him with her last fond gaze she places her left hand softly on his shoulder (another mark of loving regard), while Orpheus gently lays the fingers of his right hand on the left wrist of Eurydice. The pathos and beauty of this bas-relief and of the one in the Louvre have long attracted the admiration of all beholders, but my special point has been overlooked.

Now, have we any allusions in Greek literature to the significance of these rarely found illustrations, specially in connection with the right wrist? Doubtless scholars will discover others, but I find in Homer two very distinct references. In a most tender passage (Od. XVIII. 258), Penelope tells Eurymachus that, when Odysseus left for Troy, whence he might not return, as the Trojans were great warriors, he bade her an affectionate farewell and

δεξιτερήν έπι καρπώ έλων έμε χείρα προσηύδα.

This seems exactly to describe the attitude and its pathetic significance.

Another passage (Il. XXIV. 671) also throws light on the subject.

Achilles, yielding to the commands of the gods, and conquering his implacable hate, agrees to give up the dead body of Hector on the prayer of the aged Priam, and

"Ως ἄρα φωνήσας ἐπὶ καρπῷ χεῖρα γέρουτος ἔλλαβε δεξιτερήν, μήπως δείσει' ἐνὶ θυμῷ.

In his note on this passage Mr. Leaf says that this attitude is a mark of kindness. But it surely indicates a deeper and stronger feeling, a desire to give courage and confidence (as Homer says) to the aged king amid the dangers to which he was exposed in the camp of his enemies. Coming from

the resentful Achilles it has a deep significance. The two passages taken together show that the attitude was used on occasions of intense emotion or of deep passion. Carl Sittl (Die Gebärden der Griechen und Römer) mentions the attitude in p. 314, note 2, and on p. 315, note 6, but does not attach any special meaning to it. With regard to the hand on the shoulder (two figures each with the hand on the shoulder of the other), he says that the position somehow, yet still clearly, indicates affection. In art, however, he connects it with a late period, but it must be borne in mind that we find it in the Orpheus and Eurydice bas-relief, which is generally ascribed to the end of the fifth or at the latest to the beginning of the fourth century.

The aspect of the Greeks and Romans towards the wrist seems worthy of careful examination. While we speak of kissing the hand, Homer says λαβῶν κύσε χεῖρ' ἐπὶ καρπῷ (Od. XXIV. 398), doubtless the right wrist in connection with δεξίωσις. From the more delicate skin and the more sensitive touch of the wrist, one would feel inclined to say that the ancients

showed a finer appreciation of the motive.

Then, further, while our young men and maidens dance hand in hand, Homer, in his picture on the shield of Achilles, represents them as dancing ἐπὶ καρπῷ χεῖρας ἔχουτες.

JOHN FORBES WHITE.

BOREAS AND OREITHYIA ON A LATE ATTIC VASE.

PLATE VL

THE vase which is the subject of the present paper was acquired a few years ago in Italy for the Ashmolean Museum. The find spot was given as Capua

The vase is a bell-krater, in height 201 in. (m 523) in diameter 101 in. (m 498). There is a wreath above, and a line of maeander pattern beneath the figures. The sides of the vase have a decoration of unusual richness. An elaborate pattern of palmettes rises to the handles, the roots of which are surrounded by the se-called egg-moulding (Eierstab). The reverse type is one of the conventional groups usual in this class of vases. Three youths, their long hair bound with wreaths (white), and wrapped in himatia, are standing together in a building which is indicated by a column rising in the midst. In the back-ground are hung up two square frames (dedications?); two tall curved leaves like notes of interrogation rise from the ground. One of the youths, to r., holds a patera; another, to L, holds a strigil; the third is wrapped wholly in his cloak. In the field to I is a flower.

The interest of the vase resides wholly in the painting of the obverse, which I take to be a new and probably unique representation of the carrying off of Oreithyia by Boreas. Boreas, who is represented as a dignified bearded man, clad in Phrygian cap, chiton with sleeves, chlamys and boots, is seizing by hair and right arm Oreithyia, who has flung herself violently on the ground, and raises her hands beseechingly to a richly draped matronly figure who is seated on a rock (hair in kerchief, under- and over-garment). An Eros, in a curious attitude, as if he were also perched on a rock rather than floating, rises beside the seated matron, holding some white object (wreath or tillet !) in both hands. Behind the matron stands a female figure, her hair bound with a sphendone, holding in her left hand the end of her well. Behind Boreas, his horse advances to r. The drawing is very good for the period, which I take to be not very late in the fourth century. White colour is used for the face, arms and feet of the standing woman, the border of the cap of Boreas, and the mane of the horse, as well as for ornaments and accessories. Plate VI is from a very faithful drawing, made by Mr. F. Anderson.

That the vase is Attic will probably not be disputed. The subject in itself points clearly to Athens. The elaborate devices under the handles, which are



KRATER IN ASHMOLEAN MUSEUM (RRYERSK),

almost identical with those on an Attic vase of earlier style from Gela, recently acquired by the Ashmolean Museum, indicate the same origin. Vases of this class are in the Berlin Catalogue (Nos. 2641-8) and in the British Museum Catalogue (vol. iv) assigned to Athens.

Representations of the carrying off of Oreithyia by Boreas are by no means rare in Greek vase-painting. They are especially common on Attic vases of the fifth century. Sometimes the scheme is one of flight and pursuit: sometimes the girl is represented in the arms of her suitor. On the chest of Cypselus Boreas has the serpent legs of Typhon; on a red-figured vase the is double-headed like Janus; Oreithyia like Thetis is often seized in the presence of her companions, who hasten away to tell the tale. The most important vase of this class is at Munich. It is a fine red-figured vase. Boreas winged (EORAS) has seized Oreithyia (SRE(OVIA), who stretches out her hands towards Herse (SPSE) who follows the pair with arms outstretched as if to aid: Pandrosos, Aglanros, and a third young woman not named, fly in terror to Cecrops and Erechthens to tell them what has happened. A very similar vase at Barlin is published by Gerbard, where the same figures

⁴ Ann. d. Inst. 32 (1860), 11. L.M.

O. Jahn's Catalogue, No. 37d. ef. Welcker, Berlin Catalogue of Vascs, No. 2165.
Alts Denkmaler, ili. p. 144.

Brush n. Kumpan. Vasenh Pl. 26-29 cl.

reappear, though only the names of Boreas and Oreithyia are given; and where again Herse seems disposed to attempt a rescue. On one red-figured vase Athena is present, and is by no means out of place, since according to one version of the myth Oreithyia was carried off while engaged as a canephoros in her service. But according to more generally received accounts she was surprised while picking flowers by the Hissus, or filling a vessel at Callirhoe, or carried off from the rocks of the Areiopagus.

A distinctive representation dating from the fourth century is found in the well-known akroterion of Delos. Here, Boreas, winged, clad only in drapery which falls behind the shoulders, and in boots, raises aloft Oreithyia, whom he has seized in the presence of two of her sisters or friends. At the feet of captor and captive, a small horse springs to the right. This horse, or mare, is taken by Miss Harrison to represent a transformation of Oreithyia, whom she thinks to have been, in origin, a sea-nymph, and so to have possessed, like Thetis and the Old Man of the Sea, the power of assuming

various shapes.

In Roscher's Lexikon, under Borcas, p. 811, citation is made of a vase whereon a young man, wearing a Phrygian cap, bears away, in a quadriga, a struggling girl. This vase was published originally by Welcker, who took it for an abnormal representation of the carrying off of Oreithyia, and the writer in the Lexikon (Rapp) accepts the attribution. But it cannot be upheld; Stephani observes that all save the horses is modern painting, and the figures in the chariot have neither a genuine appearance, nor any likeness to Boreas and his bride. Probably, the real subject of the vase, which is of the Panathenaic class, is a victorious racing chariot.

Passing from other representations of the wooing of Boreas to our vase, we are struck by the many points in which it varies from the accepted version. To begin with, Boreas is not winged. The pattern on his cap and the scales on his sleeves serve to mark his northern origin, and his affinity to Scythians and Amazons. He wears tall hunting boots closely like those in the Delian group. The horse which accompanies him seems clearly meant to bear away the captive, and does not lend itself readily to the view of Miss Harrison above quoted, that it belongs rather to Oreithyia than to her suitor.

Of the three figures on the left of the picture one is and onbtedly Eros, and one must almost certainly be taken for Aphrodite. But it is possible to hesitate whether Aphrodite is the seated or the standing figure. We have, indeed, here, an interesting problem. Three views deserve con-

sideration :-

(1) That the standing figure is Aphrodite, the scated figure a relative of Oreithyia.

(2) That the standing figure is Aphrodite, the seated figure an impersonation of locality.

(3) That the standing figure is Peitho, the seated figure Aphrodite.

^{&#}x27; See Furtwangier's restoration in Arch.
Zeitung, 40, 389, Roscher's Lexiben, p. 318, Miss.
Harrison, Mythology and Monuments, p. lxxvii.

The presence of the horse is a certainty

I Alto Denkontier, v. pl. 21.

Boreas, p. 11.

We must consider these possible interpretations in turn; and first, the view that the seated lady is related to Orcithyia.

The name of the wife of Erschtheus, Praxithea, is recorded, but according to all accounts, she was not present at the scene of abduction. We may, perhaps, suppose that the idea of separation from home has introduced the

mother into the scene as the representative of home.

Greek vase paintings of all ages have, as every one knows, a strong tendency to fall under definite schemes, and the presence of a mother at a scene of abduction certainly adds a touch of pathos. Instances of the addition in vase-paintings of persons whose presence is rather ideal than actual are very common. We may cite, on black-figured vases, the father and mother of the Cercopes witnessing the capture of their sons, and Peleus and Neoptolemus present at the arming of Achilles2; on red-figured vases, Timandra present at the abduction of Helen, on the vase of Hieron; Apollo present at the duel of Achilles and Hector,3 and Cheiron present at the surprise of Thetis. Such instances might be multiplied, but it is unnecessary. Perhaps it is more to the point to observe that Demeter is sometimes, on vases, present at the seizing of Persephone, although, according to the received legend, she was absent at the time, and unaware, for a while, what had happened. It is true that the majority of archaeologists, from Millingen to Overbeck, have seen, in the vase paintings mentioned, not the first violent abduction of Cora, but her more peaceful annual departure to the world of shades; but this interpretation is doubtful, and even if it be adopted, Demeter should scarcely be present. An objection to the identification of our seated lady as Praxithea is that she is perfectly quiet and self-contained, evidently in no wise disturbed by the terror and the appeal of the girl.

Of one of the sisters or companions of Oreithyia we can scarcely think. Herse, daughter of Cecrops, is, as we have seen, present at the deed on some early vases, and even tries to interfere. But our scated lady can scarcely be Herse, nor can she be Athena, since none of the characteristic features of

Athena appear.

A second interpretation is to find in the seated lady some personification of locality, perhaps Callirhoe, present, as Eleusis is sometimes present at the sending out of Triptolemus. The rock-seat would, certainly, very well suit this interpretation. On late vases, and especially in Pompeian paintings, such personifications are frequent in mythological scenes. And they take an interest in what is going forward, expressing sympathy by attitude and gesture. But they do not usually take an actual part in the action. It is difficult to think that Oreithyia could appeal for protection to Callirhoe, or any impersonation of locality.

The third interpretation remains, that the seated lady may be Aphrodite, and the standing figure behind her Peitho. In favour of this view is the

Ashmulan Fans, PL 8.

Beydemann, Gricch, Vermbilder, vi. L.

^{*} Gerhard, Auseri Vanene, 202.

Overback, Kunstmpthol. pl. xvil., 28, 28a, cf. taxt, p. 597.

position of Eros, close to the scated figure. But an argument against it may be drawn from the attitude of Oreithyia, who is evidently appealing with vehemence to the scated figure. Approdite, if present, would be invisibly

present; and an appeal to her would scarcely be in place.

Since there he such serious objections to all interpretations which most readily occur, I am greatly disposed to adopt one which is more far-fetched, and has, as far as I know, no support from ancient writers, but yet has something in its favour. Can the seated figure be Gaia! Gaia was, in a sense, the mother of Erichthonius, who is scarcely to be distinguished from Erechthous, and appears in vases at his birth. She is closely connected with the early dynasty of Attica. The figure on our vase, in its dignity, would stand well for Gaia. Her rock-seat is appropriate. And Gaia, knowing the future well, might probably regard with complaisance a deed of violence of which the results were so auspicious to the Athenians, who more than once during the Persian wars had cause to rejoice that Boreas was their son-in-law. On the other hand, it would be very natural for Oreithyia to make appeal to her ancestress, Gaia, if she were present.

I am quite alive to the dangers of giving far fetched or fanciful interpretations of vase scenes, which in ninety-nine cases out of a bundred fall into classes and schemes. But, occasionally, a vase of unusual character makes its appearance, in interpreting which one is at liberty to assume more originality and more definite purpose in the painter. Our vase seems to me to belong to this small class. In any case, whatever the true interpretation of the picture before us may be, it is certainly a rare and important repre-

sentation of an interesting Attic myth.

PERCY GARDNER

A HEAD IN THE POSSESSION OF PHILIP NELSON, ESQ., M.B.

[PLATE XI.]

The head reproduced upon Pl. XL has recently been acquired by Philip Nelson, Esq., M.B., and we are indebted to him both for his courteons permission to publish the head and for the photographs, taken by himself, from which our illustration is derived. The head is of Parian marble, and is clearly of Greek workmanship; it is also evidently derived from an original of the very highest artistic merit. It is in excellent preservation, except that the end of the nose and a part of the lips on the right side have been restored.

Dr. Nelson has kindly supplied me with the following information as to the history of the head and as to its dimensions and present condition. It was acquired by him in Bath at the sale of the collection of the late Captain Maignac, who inherited it from his father-in-law, an artist named Walton, a contemporary of the painter Barker of Bath, 1769–1847. This Walton in all probability brought the head from Italy, where he is known to have travelled and collected pictures, &c.; but there seems to be no more exact record as to its origin. The head seems to have remained practically unknown to archaeologists until its acquisition by Dr. Nelson, who, appreciating its importance, sent photographs to the British Museum in July, 1897. In addition to the photographs now reproduced, he offers to have a mould made and casts prepared, if there is sufficient demand.

The left side shows the bend of the neck and the beginning of the shoulder; on the right side this is broken away; the cleavage marks on the under surface show head and body to have been in one piece. Dr. Nelson also sends me the following dimensions:—

Length of nose			Between inner angles of eyes without
, eye with lashr, omal	ke .	81	lashr, casal 28 mm.
without	-	27	Aperiare of eye 11
in month			Ala to als of pow 39 ,,
Height of forebond	-211	47: 11	Als of new to angle of mouth 92 ,,
Length of car	-	63	Now to trp of chin 68 at
Width of our	1000	81	Length of face
Tip to als of nosn			Width of face at zygoma 107
n medge of lower lip	977	37 11	Inner corner of eye to thin 107 "
Upper to lower edge of lips	100	20 11	15 .11 15 11 hair 60 11

³ Dr. Nelson's address is 14, Princes Read, Liverpool, I feel no doubt that his offer will be widely accepted.

Dr. Nelson also observes the resemblance of this head to the works attributed by Professor Furtwangler to Cresilas, and suggests that we should recognise in it the Doryphorus recorded by Pliny among the works of that master; this is an identification we must now consider.

The head, which appears to represent a youthful athlete, is not an exact replica of any known type, but it has an obvious affinity with the series that has been grouped together and discussed by Professor Furtwängler in his Masterpices of tireck Sculpture under the name of Cresilas. And, if we were to accept this grouping and identification without discussion, all that would now be needful would be to describe the new head, and to record that another example—perhaps the most beautiful and characteristic of all—has now been added to the series.³ But the subject is so complicated and difficult that even those who have followed and accepted Professor Furtwängler's brilliant arguments will not be sorry to reconsider the evidence on which they are based; while there are probably others who are still unconvinced, and will be glad to investigate an alternative theory.

The head which shows the closest resemblance to that reproduced on Pl. XI. is the well-known Amazon of the Capitoline type. Now the relation of this Amazon to the other well-known statues of Amazons has always been a puzzle. Our views upon this matter depend to a great extent upon the amount of weight we assign to the tradition recorded by Pliny, that four' of the most celebrated artists of antiquity made statues of Amazons in competition for Ephesus, and that when the relative merit was decided by the votes of the competitors themselves, Polyclitus was placed first, Phidias second, Cresilas third, and Phradmon fourth. In the various attempts that have been made to fit this story to the various statues of Amazons that are extant, there is practically only one point on which all authorities are agreed; this is that one of the types, which represents the Amazon as leaning her left elbow on a pillar, and resting her right hand on her head (Furtwangler, op. cit. Pl. VIII.), is to be attributed to Polyclitus. One may feel inclined to discredit the rest of the story as a mere fabrication to glorify the Argive school; but we know from Lucian, the most trustworthy and intelligent art-critic of antiquity, that there was an Amazon by Phidias. and a wounded Amazon by Cresilas is mentioned elsewhere by Pliny. Professor Furtwängler says that Pliny's statement 'should rather be considered as confirmed by the fact that copies of precisely four statues of standing Amazons still exist, which on the one hand are clearly to be

4 Furtwangler, Masterpieces, Fig. 54 (Eng., edition).

Pliny's confusion in making Cresilas' nationality, Cydon, into a fifth, does not affect the value of the evidence; it simply shows his was

copying unintelligently.

¹ This is a matter on which I speak with the more confidence, as I understand from Dr. Nelson that Prof. Furtwangler has expressed the same opinion.

^{*} This new head shows a poculiarity in the elearly marked line bordering the synlids, which occurs elsewhere, e.g. on the head of the Mattel Amazon. It is there claimed by Portwingler, ep. cit. p. 134, n. 2, as a point of style, not of "branze technique," as is commonly sup-

posed. But surely, if so, the style is that of the copyist, not of the original. It can hardly be disputed that the line originates in the brunze casing of the inserted eye-sockets.

referred to four different artists, and, on the other, are evidently closely connected by identical measurements, by a general similarity of conception and dress, and by their belonging to the same period of art.' Even if we grant - what is by no means beyond dispute - Professor Furtwangler's distinction of the four types and his assignment of all of them to the same period, we are faced here by a coincidence which is at least improbable, Any one who is acquainted with the history of the monuments of Greek sculpture, with the strange freaks of fortune that have led to one being lost and another preserved, and with the utter disproportion of what is now in our museums to what once enriched the shrines of Greece, will appreciate how unlikely it is that such a set of works should be preserved to us in its entirety. And, moreover, the assumption that all these Ephesian Amazons were represented as standing, not on horseback, and that they were identical in size, rests on no better evidence than the assumption that they were all wounded. The story of the competition itself is probably not taken seriously by any one; but if we give it up, what is left to be deduced from Pliny's story except that there were four statues of Amazons at Ephesus? There is no proof that they were either contemporary, similar in pose, or identical in size. It follows that there can be no compulsion for us to assign these four given types of Amazons to just the four masters mentioned by Pliny. Of course it is perfectly open to an archaeologist to prove, upon purely stylistic grounds, that any one of these types does belong to any one of the four masters; and in the case of the Polyclitan type, there is a general agreement, based upon adequate evidence for comparison. But, in the case of the others the evidence is slighter, and under the circumstances there is no necessity to assume that any particular one of the types goes back to one of the four sculptors mentioned by Pliny, though of course there is a probability that the work of some other beside Polyclitus may be preserved.

It is desirable to keep before us these conditions as to identification, because, if we admit that the Capitoline type and the Matter type must be by Cresilas and by Phidias respectively, the room for argument and conjecture is very closely circumscribed, though probably some authorities would be inclined to reverse the attribution, and to go back to the old view that the Capitoline type must be assigned to Phidias. But if we do not admit that these two masters necessarily made these two statues, the field for comparison is widened. Now the attribution of one of these statues to Phidias, though it has been maintained in either case, has never been proved to conviction. To Cresilas Prof. Furtwangler has made a most brilliant attempt

to affiliate the Capitoline type.

The monumental evidence from which his argument starts is the status of Pericles made by Cresilas, of which we most probably possess some copies. These copies differ a good deal among themselves; and while there is enough in common to all of them to give us some notion of the style of Cresilas, there is also a good deal of variation, especially in technical details, which may be due to the copyist rather than to the original artist. Now if we look at the general conception and style of the head, apart from such technical details, and compare it with that of the Capitoline Amazon, or the similar head on the Mattei Amazon, I venture, for my part, to think that there is a difference far more essential than any points of resemblance that can be traced. The treatment of the hair is decidedly different, so far as one can compare a male head with a female; and, even if this difference be due to the copyists, its evidence must tall against rather than for the identification; and there is a considerable difference also in the shape of the eyes. That the eyes differ considerably in the various copies of the Pericles is an indication in itself; for the extraordinarily definite and clear-out eyelids that we see in the Amazon and in Dr. Nelson's head could hardly have given rise to such variations. A comparison with the Pericles does not then compel us to attribute the wounded Amazon to Cresilas. Prof. Furtwangler argues indeed with great persuasiveness from Pliny's description of Cresilus' Amazon as wounded that the Capitoline type must be his. But the Polyclitan type is wounded too, though there is no record of it in literature, and though the motive of the wound is not worked out with equal skill. The fact is that we have do deal with a succession of probabilities, rather than with any definite proof, and so the question may at least be regarded as open enough to invite further discussion.

In the case of the Amazons we meet with a phenomenon which is repeated with remarkable exactness in another case, and whatever explanation we accept in the one instance we shall probably be justified in applying to the other instance also. And curiously enough we have to deal in both cases with a group of works of which the most characteristic is universally recognised as belonging to Polyclitus. The other group comprises the statues which show us, in several variations, representations of a Diadumenus.2 In the case of the Diadumenus we have not, it is true, any tale of a competition by several well known. sculptors, as in the case of the Amazona; but we have a Diadumenus by Phidias mentioned, and so we have, in the two cases, the same two sculptors recorded as responsible for the most famous examples. And we find, as we should naturally have expected, that in the case of the Diadumenus as of the Amazon, modern authorities have recognised one type as decidedly Polyclitan, while another has been identified, though with less consensus of opinion, as derived from Phidias3 There is however, another complication introduced in the case of several copies of even the Polyclitan Diadumenus; for they show a strange contrast with the copies of the Polyclitan Doryphorus. Furtwangler, fully recognising this contrast, attributes the difference to a change of style on the part of the sculptor, the Doryphorus being an earlier work of purely Argive character, while the Diadumenus represents the work of his later years, under Attic influence which may well have been conveyed

⁴ The Mattei Amazon, it will be remembered, has lost its head, which has been replaced by one properly belonging to the Capitoline type.

This coincidence is seculiarly interesting, when we remember Dr. Neison's suggestion that his head represents the Doryphurus of Crosiles.

while the two must characteristic athletic statues of Polyclitus were the Diadumenus and a Doryphorus.

Furtwingler regards the Farness Diadunrenus as Phidian, following Gerhard and Betticher.

through the channel of Cresilas. The only alternative is to recognise in the much mutilated head of the Vaison Diadumenus the most authentic copy of the work of Polyclitus himself, and to see in the more perfect and much softer work of such heads as those at Dresden and Cassel a modification introduced by an Attic copyist. Such a modification, of a quite Praxitelean character, must be recognised in the terra-cotta statuette from Smyrna published in the Hellenic Journal for 1885, Pl. LXI., unless indeed we regard this Praxitelean modification as the work of a modern rather than an ancient copyist. whichever explanation we adopt as to the Dresden and Cassel heads-to which must be added another recently acquired by the British Museum, and the new Diadumenus from Delos-we must see in them a modification of Argive severity under the influence of the softer Attic style, whether that influence was exerted upon Polyclitus himself in his later years or only upon

the copyists who reproduced his work.

Now if we turn to the Amazons again and remember that the explanation which applies in the one case must in all probability apply to the precisely similar phenomenon in the other case also, we may with great probability infer that here also we see the modification, under Attic influence, of the severer Argive type which is most characteristic of Polyclitus, at least in his younger years. If this explanation of the relation of the softer and the severer type be accepted for both cases alike, it will follow that we cannot while attributing the severer type in both cases to Polyclitus assign the softer type to Cresilas or to his influence. For Cresilas was the contemporary of Pericles and of Phidias, and belonged to an older generation than Polychitus. It is not indeed impossible that the artistic activity of the two may have overhapped to some extent. But it seems more natural to suppose that what is generally recognised as the characteristic Polychian type is the original, and that the other softer-one is almost inclined to say sentimental-type is a later modification; and any such relation implies that we must not attribute the second type to Cresilas, but rather to some pupil or follower of Polyclitus who had fallen more or less under Attic influence. If, merely for the sake of clearness, and without any notion of introducing useless conjecture, we wish to bring any names into the matter, such a work as this is what we should expect from a sculptor like Naucydes or the younger Polyclitus; or, if we take the Amazon into consideration, we might well attribute the new head which so closely resembles it to Phradmon, who appears to have been another artist of the same school, and then identify the Capitoline Amazon as derived also from Phradmon, the fourth of the sculptors quoted by Pliny for the Ephesian Amazona. This, however, is a conjecture which might be upset by the discovery of new evidence as to Phradmon's style; and, in any case, we know so little about Phradmon that we cannot speak of him with any confidence. But it certainly seems to me that, if we are to assign both the Amazon and Dr. Nelson's new and beautiful head of an athlete to any particular sculptor, Phradmon's name suggests the right associations.

There is a whole series of later Polyclitan works, among them such wellknown examples as the Idolino at Florence and the Westmacott athlete in H.S .- VOL. XVIII.

146 A HEAD IN THE POSSESSION OF PHILIP NELSON, ESQ., M.B.

the British Museum; and it is among these, though far above most of them in artistic merit, that the head we are now considering finds its natural place. This head is certainly the work of a sculptor who was a pupil of Polyclitus, but who introduced an Attic grace and power of expression into his master's severer style. Viewed in this light, the new head is not only a great acquisition in itself, but it also supplies us with the earliest and finest example of a series already recognised and widely represented in the museums of Europe.

The object of the present publication is to make accessible to archaeologists, in an adequate reproduction, a head of very great beauty and interest. Before its exact place in the history of sculpture can be established, there is need of a far more lengthy and elaborate discussion than the mere suggestions that are given above. They will serve, however, to indicate the direction in which its affinities are to be sought, and to open a discussion in

which others besides myself will doubtless take part.

ERNEST GARDNER.

PYLOS AND SPHACTERIA.

[PLATES VIL-X.]

Ix my first article on Pylos and Sphacteria 1 I made the rash promise that in an early number of this Journal I would support my theories by documentary evidence. It is with shame that I realise that this is now two years ago. Various circumstances have delayed me. I have been unable to visit Greece again myself, and the friends who were kind enough to do the work for me were constantly banked by the storminess of the place. Not only was it often impossible to set up a camera οπότε πνεύμα έκ πόντου είη, but even to reach Sphacteria at all. Of the Pylian boatmen, as I know from my own experience, it cannot be said that άφειδής ο κατάπλους καθέστηκε. It is only as a patchwork of the results of three different expeditions that I am now in a position to publish a plan of the makator count and a fairly complete collection of photographs. In the present article my business will be to act as showman to this series; I have little new to add, and, happily, no fresh opponent to meet. My collaborators have, I think, on practically every point on which they have expressed an opinion, given their support to my views." The British School at Athens has been good enough to send down a representative on two separate occasions. Plate VII. Fig. 3, Plate VIII. Fig. 4 and Plate IX. Fig. 6 are from photographs taken by Mr. R. C. Bosanquet, who is publishing some of his own observations at the end of this article. The plan of the παλαιον έρυμα-Fig. 10-was made by Mr. J. W. Crowfoot, and I shall be able in dealing with it to quote in extenso from his notes. The bulk of the photographs, Plate VII. Figs. 1 and 2, Plate VIII. Fig. 5, Plate IX. Fig. 7. Plate X. Figs. 8 and 9 and Fig. 11, were taken jointly by an old Glasgow pupil of mine, Mr. A. Lindsay, now Scholar of University College, Oxford, and his father, Prof. Lindsay, of the Free Church College, Glasgow. 1 cannot be grateful enough for the zeal with which all these scholars have thrown themselves into the details of this intricate question, and the kindness with which they have placed their results at my disposal,

The illustrations naturally bring out many of the points which formed the subject of my controversy with Mr. G. B. Grundy. To Mr. Grundy's last.

¹ J.H.S. vol. xvi. pt. 1. p. 55.

Mr. Lindsay's one exception is noticed p. 151.
Mr. Bosanquet thinks Thucydides nover visited the spot. For the extent to which I attach importance to this point, see C.R., Feb. 1897, p. 9.
* The bibliography of the subject is as

follows:—
(a) Athenaeum, April 11, 1896;

Paper and before the Hellenic Society by G. B. Grundy. Criticism by R. M. Burrowa.

⁽b) J. H.S. vol. xvi. pt. I., April 1896. Articles by G. B. Grundy and R. M. Burrowa

⁽c) Classical Review, Nov. 1896. Criticism by G. B. Grundy.

⁽at) Classical Review, Feb. 1897. Answered by R. M. Burrows.

⁽c) Classical Review, April 1897. Further criticism by G. B. Grundy.

⁽f) Classical Ession, Dec. 1897; Further criticism by G. B. Grandy.

A lucid, and to me very gratifying, summary of my position is contained in vol. v. of Mr. France's Passancies, pp. 608-613. (Addendam to vol. iii.)

words in this controversy I do not mean to reply in detail. The argument would largely resolve itself into the question not whether he is right or I, but whether in our mutual criticisms we have misrepresented each other. This is an unfruitful subject, and it is better to leave readers who are sufficiently interested to judge for themselves. They have all the data before them.\(^1\) I can only say that if I have misrepresented Mr. Grundy in any point

I am extremely sorry for it.

Let us turn to the illustrations, and begin with Plate VIII. Fig. 4, the general view of Pylos. It is taken from Sphacteria, which is just seen in the immediate foreground. The prominent position in the foreground is occupied by the Sikia Channel. Behind it is Pylos and the Sand Bar. The western of the two existing outlets is seen on the extreme right; one which is now blocked up, further to the left. On the extreme left are the rocks where Brasidas tried to land. On the summit of Pylos are the remains of the Venetian Castle, with the Bay of Boidia Koilia and the circular spit of sand enclosing it to the right. On the further side of Boidia Koilia can be seen rather dimly Hagio Nikolo and the mainland to the north. On the horizon to the left is the Island of Prote,9 Plate VIII. Fig. 5, gives in detail the land side of the rough ground on the left of Fig. 4. If instead of this photograph I had chosen for publication another of Mr. Lindsay's, taken nearer the water's edge. I could have shown still more indubitably the impossibility of beaching ships at this point. I wished however to call attention to the curious groove formation of the rock, noticed by Mr. Lindsay, which can be seen slanting from the centre of the photograph to the right foreground. It looks as if the rock was at some time or another roughly cut so as to form a groove for a wall. I should not imagine however that this was done at the time of Demosthenes' occupation. It may be remembered that I noticed traces of Messenian and possibly Athenian work a little further inland, and Mr. Lindsay's remarks point to a Venetian date for the groove. He says The width of the groove varies from two to five feet. It runs just within the rough rocks, usually about two yards outside the smooth ground. It begins at the south-west corner and runs for about 170 yands, at one place at a distance of about 70 yards from the sea. At its northern extremity it is joined by the remains of a wall running inland. This wall is not at all like any of the others of early date, and, so far as one can judge from its scanty remains, is Venetian work.'

Mr. Lindsay also reminds me of an interesting point about the rough ground where Brasidas tried to land. The jagged rocks near the water's edge lie detached, one behind the other, and between them there is standing ground. When Demosthenes and his men came outside their proper line of defence they could stand $\pi n \rho'$ $\alpha \hat{\nu} \tau \hat{\eta}$ $\rho \alpha \chi (q, 0)$ with their feet in the water,

They may compare for instance J. H. S. vol. avi. p. 47 line 8 with itsel, p. 42 line 29, C.R. Feb. 1897 p. 9 note 8 and C.R. April 1897 p. 162 bottom of first column and top of second.

[&]quot; Thue, iv. 13, 3,

Feb. 1897 p. 4 and C.R. April 1897 p. 157

^{*} It is pensible that this groove was seen by Bory de St. Vincent (*Edition*, p. 147).

^{*} J.H.S. xvi. pt. L p. 64

^{*} Thur. lv. 2, 2 and 3. 10, 4.

and yet have ready-made walls to give them cover. It is little wonder that they won the shield of Brasidas.1

The only other points to notice in Fig. 5 are the fine view of the Venetian Castle in the background to the right, and the glimpse of Prote to its left.

Brasidus' rocks naturally suggest the exact position of Demosthenes' southern line of defence. Fig. 4 shows clearly enough that it would never have done for Demosthenes to leave outside his line of defences so much good level ground as Mr. Grundy's wall BB would make him do.2 My point however has been not merely that the southern wall-marked G.G. in my original plan 3-must have been built as close to the edge as possible, and turned inland only where Brasidas' rocks compelled it, but that a short crosswall-marked I in the plan-must have been built from north to south at the south-east corner. Here it was that, according to my theory, Demosthenes beached his ships and here where the Spartans meant to make their attack with siege engines when they had failed on the south-west. I pointed out that I myself had walked without difficulty into Pylos this way, and that the Spartans would have done the same if there had been no wall to stop them. I suggested too that to the east of this wall, of the direct north to south line, there must have been then, as now, a slope where men could beach ships and use siege engines.4 The documentary evidence is interesting. If we had only Fig. + to judge from, a view taken from the south, it would be difficult to believe that the rise in the ground at the south-east corner was so gradual. Mr. Grundy's heart, hardened against me by his survey, might become harder still. 'I do not know, of course, he says, what Mr. Burrows means by " never approaching the perpendicular." I see that at this south end of the east cliff, the summit of the cliff rises to a vertical height of 60 feet above its eastern foot, which is only at a horizontal distance of 81 feet from that summit. This slope moreover is not continuous, but in part much steeper than that implied by these general measurements; in fact, if I recollect aright, the lower part is perpendicular chiff, with a slope from the top of the cliff to the 60 feet level. Anyone who realises what this really means in nature will understand that Mr. Burrows' remark is highly misleading. Mr. Burrows then proceeds to talk of survey defeating it own object if it supersedes observation How can survey supersede observation when it is itself nothing else save the record of observation aided by instruments of accuracy?*

I must ask Mr. Grundy to look at Plate VII. Fig. 1. It is this same slope taken in profile from the east, from the sand-bar itself. The ground running down from left to right in the background is of course part of the north slope of Sphacteria, the Sikia Channel lying unseen between.

¹ Thue, iv. 12, 1.

See J.H.S. vel. avi. pt. f. pl. II. and C.H. Feb. 1897 p. 3.

³ J.H.S. vol. xvi. pt. L. p. 57. I shall often for

clearness sake refer to the lottering of this plan.

* J. H. S. vol. xvi. p. 64 and C. E. Feb. 1897.

pp. 2, 3. See too Mr. Homnquet's notes, infra.

B. C. E. April 1897 p. 156.

Demosthenes' would, I imagine, follow the same line as the Venetian wall, a tower of which we see to the right. Comment is needless.

As for the slope to the east of the wall, it is clear that it is older than the alluvial deposit of the immediate foreground, and probable that it is of different formation. There would be ample room on the slope itself for the operations involved in my theory, even if the sand-bar had not yet begun to form to the east of it.¹

While we are near the Sikia Channel it may be worth while considering from a new point of view the question of the blocking of the channels.² I have not laid sufficient stress on the wild improbability of the blocking ever having actually taken place under any circumstances and in any position. When the Athenians arrived and found no anchorage, they sailed north-west to Prote. Even if the Spartans could have thought it possible that they should abandon Demosthenes without an effort, without even an attempt to land stores and reinforcements, the direction in which they sailed and the nearness of their anchorage would have made them hesitate in forming any such idea. Are we to believe that when the Athenians sailed away the channels were blocked, but that when they came back the next morning the passage was clear? We may allow a good deal for the stupidity of the Spartans, but are we to believe that they went through the difficult and claborate operation of mooring light ships across channels exposed to wind and current, and that then, just as they had proved

on the north. Mr. Grandy (C.R. Dec. 1897, p. 848) should contrast Thus. iv. 9, 2, 11, 2 and 23, 2, with iv. 13, 1. See also C.R. Feb. 1897, p. 4, col. 2, on the sand the highest religer.

* Prote was near enough for it to be quite clear if a fleet were making for it, even if the actual anchoring could not be seen.

I have argued-C.R. Feb. 1897, p. 4-that the sand most have drifted to the S.E. corner before what we may call the West Centre of the Sand-Ras filled up, and that the present state of the two emission confirms this view. Mr. Grundy-C.R. April, 1597, p. 157-zusweru that they are artificial. It would be more strictly accurate to say that they are weak points in the sand-ber, artificially turned into regular openings. Mr. Grandy himself gives this reason why they are where they are. It is because if made close under the cliffs they would become choked by the sand forming on the inner side of the Sikis Channel. This is what has actually happened, he proceeds to say, with the emissary marked on Plate VIII., Fig. 4, as running half way through the sandhank near the South-East corner of Pyles. His arguments are surely all for me. The causes which operate now may have operated then. None the less the movements of currents are us insecure basis for argument, and I am glad that my theory can, if necessary, dispense with it. See J. H. S. Vol. 2vi. Pt. I, p 159.

It is scarcely necessary to remark that the wall attacked by the Pelopocusaiana after the armistics was not wall I at all, but that which the land army had from the very first attacked

² C.R. April, 1897, p. 158, cp. C.R. Feb. 1897, pp. 5 and 9. Though still feeling that the arguments against Mr. Grundy's revised theory are overwhelming, I grant that I spoke too strongly when I said he had not one argument for it. He has pointed out that the land forces would thus have been kept in touch with Sphaeimia. See, however, J.H.S. Vol. xvi. pp. 74, 75. Sphaeteria was safe so long as the Atlantians could not unchor.

It might also be argued that the time they sould have had at their disposal for doing this was limited. For some part of the day immediately preceding the arrival of the Athenian fleet they were still attempting to affect a landing on the S.W. (Thue, iv. 13, 1). For this they would not only need all their ships, but also a free passage through the Sikis Channel. Besides it is evidently part of a different policy.

the value of their policy by baffling the enemy's fleet, they promptly set to work in what remained of the same evening to loose their cables and beach their ships? Men do not build elaborate fortifications and then throw them down on the same day that they have repulsed an attack.

It is, after this, hardly necessary to point out again that Thucydides' words are not only not in favour of the blocking ever having taken place,

but directly against it.1

In regard to the fortifications on the north side of Pylos there is less to be said. Plate VII., Fig. 3, is the Cyclopean wall or tower behind Plate IX., Fig. 6. This, which I conjecture to be Demosthenes' line of defence, was marked L on my original plan; to the Cyclopean wall I gave no special lettering. In regard to these two photographs I have nothing to add to my original remarks, except that Mr. Bosanquet agrees that "L may well be rough fifth century work." Plate IX., Fig. 7, however, which is wall L taken from a distance, brings out a point which I had overlooked when arguing as to the strength of the position it occupied. Mr. Grundy questioned the defensibility of this wall because it lay on a slope and the lower portion of it would therefore be exposed to enfilleding. I answered the argument without disputing its main premise, that the enemy would overlook the lower part of the wall. I forgot that immediately in front of the upper part there is a deep fall of the ground. Mr. Lindsay has brought this clearly out in his photograph. An enemy would not be at an advantage over any section of the defenders of the wall."

In regard to the a priors question as to whether, apart from any consideration of the wall, Mr. Grundy's line of defence or mine is the more probable, I have only to quote some remarks of Mr. Lindsay's. He does not agree with everything that I have said on the subject. He could see not that there was any possibility of landing on the north shore of Pylos behind Mr. Grundy's wall AA. He does agree, however, that south of AA much ground would have to be defended, or at least guarded. His conclusion is: 'The line of LL therefore gives a much stronger and shorter line of defence. The line of AA is very easy to approach and has no such natural advantages.'

We now turn to Sphacteria. The first point to notice is Figure 10, the plan of the παλαιὸν ἔρυμα made this spring by Mr. J. W. Crowfoot. He writes to me that it was made with a prismatic compass and measuring tape only, but that each of the walls was measured separately and with care. The contouring on the other hand was done by eye, and is quite rough.

Thuc. IV. 18, 3. See C. E. Feb. 1897, p. 9.

³ J.H.S. Vol. 2vi. pp. 87, 68. See, however, Mr. Bossaquet's notes, infra.

^{*} C.R. Nov. 1896, p. 373. * C.R. Feb 1897, p. 5.

It is only at this fall of the ground that there are the number of stones of Cyclopsussize that can be seen in Fig 6.

^{*} J. H.S. Vol. xvi. Plate II., op. ibid. p. 65.

Mr. Crow(cot sends me a note to say that he thinks he has rather underrated the hillys on the north-west corner of the wall round the summit. This agrees with my own remonstrances of the subject. See my original plan, J.H.S. vol. zvi. pt. L. p. 57. On this point, and in regard to the position of the S. wall of the Hollow (p. 155), I have thought except to leave the plan as Mr. Crowfoot made it.

In regard to this plan Mr. Crowfoot writes as follows :-

The walls which compose the fort are in some parts difficult to trace; in others there is no regular line now visible; these I have marked on the plan with dotted lines. The island has probably never been much more




Fig. 19.—Pean of the stands (populon Schauteria. By J. W. Crowfoot.

Of the Walls marked III me estate traces were seen.

Where there are dotted lines - - - there is new no regular line of wall.

The other parts of the Fort are drawn as at present standing.

inhabited than at present, and the stones forming the walls have not been carried away: except at one point on the western side they can be seen covering the slopes beneath the fort. I saw none which had been shaped or faced either on the ground or in the remaining courses, which were often set

in rough lines. Only in one place, near the north end, could I find both sides of the wall: it measured 2 metres. Of the four bastions, only the most southerly is at all difficult to trace; behind this and behind the western bastion I could follow the line of the connecting wall, which was not, so far as I could see, "bonded" with the walls of the bastion. But when so few courses remain, it would not be safe to lay much weight upon this fact,

Descending into the hollow I found the northern wall fairly easily, and measured it for more than 37 metres: its breadth in the middle is 3 metres. I am inclined to think that a line may have run at right angles to it, connecting it for some distance at least with the northern point of the upper fort, but there are no distinct traces of this. About the southern wall of the hollow I cannot speak so confidently. The ground was covered with such a thick growth of brushwood, etc., that though I saw several lines of stones, I could not be sure of the exact position of the wall, but I have no doubt that it lies approximately where I have marked it.

Those who have visited the spot will see at once the importance of the Hollow. The upper fort is, except at the southern end, a mass of rock without an inch of soil anywhere upon it and the incline everywhere is considerable. The Hollow is much more attractive; it is sheltered more or less on all sides, and there is, as I found to my cost, sufficient soil to support a very sturdy underwood. But unless the summit of the hill was defended, the

hollow would have been exposed to an attack from above.

One question remains at present undiscussed. The fort was ancient in the time of Thucydides: what then can have been its original purpose? The walls of Giannitza (v. Peruice, Athen. Mittheil. 1894, p. 359) prove that the sub-Mycemacan folk of Messene were driven to higher points than those usually chosen by their predecessors, but the fort at Sphakteria can hardly have ever been the Akropolis of a flourishing community. It is more likely, one may conjecture, to have been a nest of pirates, who would have found plenty of spoil in the rich lands north and south of Pylos (v. Thucyd. i. 5)."

We may now illustrate the plan by the photographs. The walls round the summit of Mount Elias—marked BB on my original plan—are represented by Plate VII Fig. 2 and Plate X. Fig. 8. In regard to them I have little to add. 1 More than one of us who have worked at Pylos and Sphacteria will be glad that our dragoman, Charles Papadopoulos, is immortalized in Fig. 2. He was with Mr. Grundy and Mr. Lindsay, as well as with me. Speaking for myself I can bear witness that nothing could have been more enthusiastic, devoted, and capable than the way in which he threw himself into the spirit of my work. I know too that it was not a little owing to his knowledge of the ground that Mr. Lindsay and his father were able to take such apposite photographs. Plate X. Fig. 9, for instance, represents the South Wall of the Hollow—marked D in my original plan—and it is particularly fortunate that Mr. Lindsay was able to photograph it. So hidden is it by brushwood that

^{1 850} J.H.S. vol xvi. pp. 58, 59; also Mr. Bouanquet's mites, safen,

Mr. Crowfoot could not discover it. As it was, a thick tangle had to be cut away before the camera could be got into position, and this was finally effected at so near a distance that the size of the stones is altogether out of

proportion to those in the other photographs.

Mr. Lindsay, on seeing Mr. Crowfoot's plan, writes to me as follows:

'I think you are quite right in saying that the conjectural position of the southern wall on Mr. Crowfoot's plan is too far north. The wall is just where the hollow begins to slope down into the gorge. It was very hard to see owing to the dense growth of bush all round it, but the condition of the greater part of it was much like that of the north wall of the Hollow, I managed to get under the bushes at several points and made out the line of the wall. It only differed from the north wall in the fact that only a single row of stones was standing in most places and not so many stones were lying round. Where the Hollow slopes down into the gorge the rock goes sheer down on the west side a little way, say about 10 feet at first. This



FIG. 11.-SPHACTERIA. WALL CO.

height gradually gets less as we move further east and when it is about 8 feet high we begin to find wall D built against it on the outside. The bit we have photographed is situated at this point, built against a low line of rock. Where the rock stops the wall goes on over the level ground, at the east side of the top of the gorge, just in front of the south end of the Hollow.

Our next photograph is Fig. 11, the north wall of the Hollow, marked CC on my original plan. Mr. Crowfoot writes to me that it appears to be at a curious angle, but that he was struck by the fact at the time, and cannot have exaggerated it by more than a foot or two, if at all. I can quite believe that the angle is exact. Of that part of CC which connects with the appear

¹ Mr. Bosampast did not see it, because he left his search for it to the end, when the weather because unfavourable.

fort, I thought I found traces, but grant that they were not so certain as the

other parts of the fort.1

The only point that remains to be discussed is the last struggle round the Fort. All there is left for me to do is to quote Mr. Bosanquet and Mr. Lindsay. Mr. Bosanquet writes: 'Your theory of the surprise' held good when read over on the spot.' Mr. Lindsay confirms my views on two essential points. The Messenians could not have surprised the Spartans except from the south-east, because any movements to the north-east must laye been detected. 'Standing behind wall BB,' he says, and looking north-west, I could see every foot of ground right down to the sea. It would be absolutely impossible for any one to pass from the west to the north without being seen by the defenders of wall BB.' But not only was it impossible for the Messenians to enter the hollow from the north, but it was possible for them to do so from the south-east. 'The gorge,' he says, ' is quite climbable. The chief difficulty would be the dense growth of bushes and trees.' In regard to the way by which the foot of the gorge was reached, Mr. Lindsay is inclined to believe with Mr. Tozer that a path may have existed along the foot of the cliff. 'We sailed close along the cliff,' he says, 'several times. It is sheer at the top, but slopes more towards the foot. There is still a continuous line of bush from a gap in the cliffs north of the Panagia landing right to the foot of the gorge. Where there is bush there is some foothold. There is only one place which would be difficult to pass now, and that from the look of the rocks has changed recently. In fact the boatmen said the rocks had been shattered there by lightning."

With this quotation I bring my argument to an end. The need for constant reference to previous articles in this journal and elsewhere will probably irritate the reader. I must plead that the only alternative was to repeat much that is easily accessible and to run to excessive length. The time has not yet come to go over the ground again and give anything that should purport to be a final account of the whole matter. To do so at this stage would not have advanced knowledge, nor indeed have been courteous to my critics. I hope that before long I shall feel at liberty to banish polemics to footnotes and describe in direct narrative form what in my opinion actually took place in the affair of Pylos and Sphacteria.

RONALD M. BURROWS.

NOTES BY MR. R. C. BOSANQUET.

The Wall on Pylos.

PROFESSOR BURROWS quoted Blonet's opinion that this wall was modern, but ought in fairness to himself to have mentioned that one member at least of the expedition to the Morea held it to be ancient. 'Ce mur cyclopéen,'

¹ For my argument that the Sparing must have held wall CC as well as wall BB, see J. H.S. vol. xvl. pt. 1, pp. 60, 61.

^{*} J.H.S. vol. svi. pt. 1, pp. 81, 62; C.K. Feb. 1897, p. 2. Cp. C.K. April 1897, pp. 156, 156.

says Bory de St. Vincent, 'est évidemment ce qui reste de plus antique dans tout le cauton, et cependant on a affecté d'y voir une bâtisse moderne saus importance,' an allusion to the scepticism of the architectural section.\(^1\)

A careful examination of this wall satisfied me that it contains no squared stones, no stones with mortar adhering to them, and no tiles, such as would probably be found in a wall hastily constructed for defence in recent times. The fact that it is built of undressed stones is the explanation of its survival. No one takes such stones to build with when he can get blocks ready squared a few yards away. The supply of more attractive material on Koryphasion is not yet exhausted, although an enormous quantity has been carried off to build the modern town at the south end of the bay. Bory saw the process of destruction going on in 1829. Vischer in the fifties remarks that the ruins are being used as a quarry and verschwinden immer mehr.2 Many of the walls marked on Bory's plan (of which, thanks to Professor Burrows' foresight, I had a photograph with me upon the site) have been demolished, but the wall of unhewn stones still stands, eight feet thick, its top level with the ground on the west and rising from four to nine foot above. that on the mist. The 'tower' behind it is fully ten feet high (Plate VII., Fig. 3).

Sphaeteria.

Gell speaks of Sphacteria 'famous for the defeat and capture of the Spartans in the Peloponnesian War, and yet exhibiting the westiges of walls which may have served as their last refuge,' This is his only remark on the subject, and he gives us no clue as to what he saw or heard.

Leake paid a hasty visit about the same time (1805) as Gell, 'Of the fort, he says, 'of loose and rude construction, on the summit, it is not to be expected that any remains should now exist; but there are some rains of a signal-tower of a later age on the same site." This tower probably stood not as Professor Burrows conjectured (J.H.S. xvi. p. 63) at the S.E. angle of the Greek fort, but on the foundations of the best preserved of the western towers, in and around which I noticed a quantity of tiles. There were none olsewhere in the line of wall, and their abundance at this point is explained if a mediaeval building of stone and tiles at one time stood here. It was probably a signal-tower, as Leake inferred, intended to warn the garrison of Palaeokastro of vessels making for the southern entrance to the harbour. The παλαιόν έρνμα was no doubt occupied as a look-out station in Hellenistic and Roman times; near the walls I picked up bits of Greek black-glazed ware. and part of a common 'pseudo-Arretine' plate. If the tower stood as late as the fighting on Sphacteria in 1825, its squared stones may have been requisitioned for the Greek batteries. The Turks too may have used them in

J.H.S. xvl. 66. Cl. Exped. de Morée, Architecture i. p. 4, and Bory do St. Vincent, Ethatian p. 154, at p. 63 and his plan, Pl. 1v.

¹ Vischer, Erinnerungen u. Englenete qua

Arischenhamil (1857), p. 488.

^{*} Sir W. Gell, Journey in the Morca, p. 5.
* Leake, Provole in the Morea 1, p. 408.

1827. Had it survived until 1829 the members of the French expedition, who looked in vain for Greek remains on the island, would probably have mentioned it.

However, not only the mediacval tiles, but the rude blocks of the Greek foundations were left, and in 1865 Captain Mansell marked them as

Cyclopean Ruins on the Admiralty Chart.

In 1888 Schliemann came here in quest of Homeric remains, and employed men, as I learned on the spot, to clear away the debris which obscured the line of the western wall.¹ His brief report attracted little or no attention.

In 1895 Professor Burrows independently discovered these walls, and was the first to discover those across the hollow. His observations have

since been verified by Messrs, Lindsay, Mr. Crowfoot, and myself.

As to the early date of the little fort there can be no question. It was perhaps a stronghold to which the fishermen and shepherds living round the bay retired upon the approach of pirates. In recent centuries the bay was a favourite resort of the Corsaira.

The Question of the Sand-bar.

My visit to Pylos in November 1896 chanced to coincide with the exceptionally heavy rains which caused disastrous floods in many parts of Greece. At Athens the Ilissus rose as it had not done since the spate recorded in Dodwell's drawing, destroyed houses and gardens, and inumlated the Piraeus. Owing to wind and rain it was hardly possible to use my camera, but I was able to watch the process of lagoon-formation under the most favourable circumstances-a privilege for which, I afterwards paid a heavy penalty in the form of fever-and to verify the theory independently put forward by Mr. Grundy in these pages, and by Dr. Philippson in his study of the Peloponnese. On the morning before the heaviest rainfall the Jalova brook was barely a foot deep when I crossed it near its mouth. In the evening after some hours of min it was a swollen torrent, discoloured with the sandy soil of the plain and quite unfordable. The main stream was certainly emptying itself into the bay, not into the lagoon. There was a gale blowing from the south, and much of the solid matter brought down by the flood must have been added to the sand-bank which separates the lagoon on the north from the bay. Two days later, when I again rode to Old Pylos round the shores of the bay, the trunks of several trees had been thrown up on the south slope of the sandbank, and the wash of the sea was fast covering them with sand and shingle. Within the lagoon a similar process had been at work. The water was much discoloured and had risen to the level of the sea outside. Evidently the soil brought down by the streams which discharge into the lagoon is deposited on the bottom, tending to fill it up, while the soil

¹ Alth. Millh. sis. 132

² Randolph, Present State of the Moree (1686), p. 25.

brought down by the Jalova and other streams flowing into the bay is deposited on the bottom in calm weather, but goes to increase the sand-bank whenever the wind is from the south or west. Before the partial obstruction of the Sikia Channel the flow of the sea from the west must have tended to keep open a passage through the sand-bar at its western end. But I see no reason to suppose that the slope, which undoubtedly exists to-day at the south-east angle of Koryphasion, did not exist two thousand years ago. Professor Burrows' view, that this was the place where Demosthenes drew up his ships and where the Spartans proposed to use their $\mu\eta\chi\alpha\nu al$, seemed to me both possible and reasonable; and I spent some time on this part of the ground.

May it not have been here, near the present well, that the Athenian sailors διαμώμενοι τον κάχληκα ἐνὶ τῷ θαλάσση ἔπινον οἰον εἰκὸς ὕδωρ?

Maps.

A useful bibliography relating to Pylos and Sphaeteria will be found in Mr. Frazer's Pausanias. It seems worth while to add a note on the maps of the area under discussion.

J. Leaks (1805). Travels in the Moren L PL iv., 1830. A rough sketch-map.

II. Stanhope and Allason (1814),

Cf. J. S. Stanhope, Topography of Platons, etc., p. 27, 1835.

Perhaps never published. Guil, who names Allason, Gell, and Hobbouse, as authorities for his map of Plataes, would probably have used Allason's work, had it been accessible, for his very inaccurate map of Pylos and Sphacteria, but does not profess to have done so. See J. R. Guil, Cartes relatives at la geographie de Hecodote, Thucgelide, etc., 1824, Fl. 26, 47, 63.

III Capt. W. H. Smyth, R.N., Bay of Navaria (Admiralty), 1820, and later revisions. [Hence Bursian, Geogr. von. Gricchenland ii. Tal. V. 1872.]

IV. The same. Two maps in Arnold, Thucydides ii., 1832.

V. Bory de St. Vincent (1829) Exped. Scient. de Marée, Atlas, Pl. iv., 1835.
[Hence Curtius, Peloponnesse ii, Taf. viii., 1852.]

VI. Blonot (1829) Kapéd. Scient. de Mores, Architecture i. Pl. v. vii., 1832. Unimportant map of Pylos, plan of Palacokantro, plan and section of Nestor's cave, detail of Hellemin wall, plan and elevation of Hellemic pier.

VII. Capt. A. L. Mausell, R. N., Boy of Navores (Admirally), 1855.

VIII. G. B. Grundy (1895) Journal of Hellenic Studies zvi. Pl. ii., iii., 1896.

Bory de St. Vincent's map will always be of value as recording walls and ancient remains, some of which have since disappeared. For topographical and historical purposes Mr. Grundy's admirable survey has superseded all others. Since it is certain to be largely copied, I feel sure that he will pardon me for pointing out some triffing errors of nomenclature, due for the most part to the recent Admiralty map, which is not so safe a guide as it should be.

J.H.S. xvi. Pl. III. Lykos (cf. p. 5 'The alluvisi plain of Lykos'), should be Levko (Λευκό). Gadaro Point should be Gaidaro. In both cases the

right spelling is given in the Admiralty map of 1820. Tortori rocks Gk. τούρτουρι. Pylos Island, a map-maker's name for the rock south of Sphacteria, is not known locally. Cf. B. de St. V.'s protest, Relation, p. 48. Marathonisi: the real name is Chelonaki, 'tortoise,' which appears under the form Kilonaki in the map made by Smyth for Arnold. Smyth's Admiralty map gives Marathonisi or Kuloneski, and these names have passed into all the later maps and into the text of the Expedition to the Morea Possibly the island was once called Marathonisi, but the name has long been obsolete. Kuloneski is suspiciously like an engraver's misreading of Smyth's Kilonaki. Enquiry at Pylos failed to elicit anything but Chelonaki, with a possible variant Chelonitza. Finlay gives the right spelling in his account of the Battle of Navarino,

The elders of Pylos also demied that the name Boidio-Kilia had anything to do with the cave. Leake is the first and perhaps the only authority for the statement that the cave gave its name to the harbour. In the same year (1805) Gell saw the cave 'which some Frank has taught the two or three Greeks who ever heard of Nestor to believe was the stall where he kept his cows.' Both Blouet and Bory in 1829 speak of the cave as bearing the name of Nestor. It is possible that Leake or his informant was mistaken. A last century writer mentions that part of the harbour of Zea (Keos) was called 'le cul de bouf.'

R. C. BOSANQUET.

[I am grateful to Mr. Bosanquet for more than one reference, including that of Bory de St. Vincent's Rélation, which I had read, but overlooked at the time of writing. Vischer, it should be added, saw the Tower behind L (Erinnerungen, p. 435) and considered it Cyclopean. In reference to Boidia Koilia, it may be worth while to point out that the connection of the name with Thucydides' Βουφράς (J.H.S. vol. xvi., pt. i., p. 10) is as old as the French Expedition, where it appears in the Recherches Géographiques of M. Boblaye (1836, p. 114).

To Mr. Bosanquet's list of Maps I would add an interesting plan of Modon and Navarin, published in Venice, 1572 (Brit. Mus. Cat. S 132 (41)). It is based, I think, on local knowledge, gained, perhaps, immediately after the battle of Lepanto. The lagoon is treated as an inner harbour with a narrow entrance. Sphacteria (the name is not given) lies in front of the outer harbour, through not quite in the right position. Prote (Prodano) is placed rather too near. 'Navarino,' without the qualification of 'Vecchio,' is the name given to our Pylos. New Navarin was either not yet built when the information on which the map is based was procured, or was not firmly established enough to be given a name of its own by the Venetians. It was built at any rate by the end of 1572.

RONALD M. BURBOWS,]

RICHARD CLAY AND SCHO, LIMITED, LONDON AND DUNGLY,

COIN-TYPES OF SOME KILIKIAN CITTES

[PLATES XII., XIII.].

AIGEAL.

1. # 32-AVTOKPATOPA I, TPA[IANON KAI . . .] r.

Head of the Emperor, laureate, to right.

Rev. AIFEAION !. EKKAH[EIA ?] r., EMP (145) ! in field. Goddess in double chiton scated to left, patera in her right hand, the left resting on the chair. In the exergue is the emblem of the town, a goat lying to left.

Dr. H. Weber, London.

Pl. XII. No. 1.

The era of the city begins in the autumn of 47 R.C. Hence this coin, which is struck in high relief, dates from the second year of the reign of Trajan (autumn 98-99 A.D.). The head is not a likeness. The inscription on the reverse identifies the goddess represented with the $(E \times \lambda \eta \sigma)^a$ of the Aigeaians, a personification which has not hitherto, as far as I know, occurred on coins.

 Æ 26.—MAP. 10 V. ΦΙΛΙΠΠΟΝ ΕΠΙ. ΚΕC. Bust of the Caesar, laureate, to right, wearing cuirass and draped.

Rev. EY. III. BE. MA. AIF I., EWN NE r., BQC I. in the field. Tyche scated to left, wearing a turreted crown and veil. In her right, a small temple represented in profile, with a statue under the arch of the façade and an eagle on the pediment. At the feet of the goddess a goat lying to left, its head reverted.

Coll. Giel in St. Petersburg.

Pl. XII. No. 2.

EPI . KEC . stands for émiquiéstator Kalsapa, EV . TI . GE . MA for elyspile mestên deoplia Makelona.

ANAZARBOS.

3. Æ 21.—AYTO. KAI ØE, YI. AOMI r., TIANOE CE. FEP. L. Head of the Emperor, laureate, to right; behind it a star.

Cf. Grind. Minutes, p. 142, 422 (Salonings).
H.S.—VOL. XVII).

Bev. ΚΑΙΣΑΡΕΩΝ (πρός) L. ΑΝΑΖΡΑΒΩ (sic) r., ETO | YE B | P in two lines in the field. Elpis as goddess of the city stands to left, wearing turreted crown double chiton, and cloak. In the right hand, which is raised, she holds a flower, and in the left, which is lowered, a fold of her robe.

Inv. Waddington, No. 4111, Pl. IX. 26. Pl. XII. No. 3. Cf. the erroneous description of this specimen in V. Langlois, Revus Num. 1854, p. 9, 3, Pl. I. 2, and A. de Longpérier's correction, los, cit. p. 137.

A similar piece with the date 1P published by Babelon in the Annuaire de la Soc, de Num. vii. 1883, p. 25, Pl. II. 6 apparently also bears Elpis as the type of the reverse; instead of $[\phi \wedge AY] \circ \Sigma$ we should probably read $[\Theta E \cdot Y] \circ \Sigma$.

Elpis again appears as goddess of the city, wearing a turreted crown, on coins of Alexandria in Egypt.¹

4. Æ 23.—AYT, KAI. NEP. TPAIANO . . . Head of the Emperor, laurente, to right.

Rev. KAICAPEON r., A ANAZAPB[Ω] L. Bust of Zeus(!) to right, laureste and draped, in the background the Acropolis rock, crowned by two buildings, one on right, one on left. Between them, above the bust, the date $\lceil \epsilon T \rceil \rceil \propto KP$ (126).

Berlin Museum.

Pl. XII. No. 4.

A similar representation is seen on a coin with the portrait of Claudius. The only era of Anazarbos begins in the autumn of 19 s.c. Thus the date 126 corresponds to the year beginning autumn 107 and emling autumn 108 a.b.

AUGUSTA.

Æ 26.—AVTOKP. KAI. NEPYI (είκ.) r. ΤΡΑΙΑΝΟΣ
 ΣΕ. ΓΕΡ. ΔΑ. J. Head of the Emperor, laureate, to right.

Rev. AYΓΟΥΣΤΑΝώΝ r., ΕΤΟΥΣ ωΠ (86) l. Bust of youthful Dionysos wreathed with ivy to right, on the breast robe or nebris, over the left shoulder thyrsos. Behind, kantharos.

My collection.

Similarly in Cat. Greppo No. 1093, with erroneous description, and Babelon, Annuaire de la Soc. de Num. vii. Pl. II. 10 with the date II (?). This date is inadmissible for the reason that Trajan did not assume the title 'Dacicus' until the end of 102. As the era of Augusta begins in the autumn of 20 A.D., the year 86 runs from autumn 105 to 106.

Pools, Alexandria, 19. VIII, 1820.

Movin processes, p. 349, 10, Ft. F. 20.

LAMOS.

6. Æ 28.—AY. K. NO. AI. L. OYAAEPIANOC r. Bust of the Emperor with radiate crown, cuirass and drapery, to right.

Bev. AAM. MHTP. Tl., HC AAMω (τιδος) r. Apollo standing to left, with chlamys on his back and quiver on the right shoulder. In the left hand be holds a bow, and in the right, which is hanging down, a branch.

My collection.

Pl. XII. No. 5.

Hitherto only two coins of Lamos, bearing likenesses of Severus and Caracalla, have been published. The town lay on the river Lamos, somewhat to the east of Elainsa Sebaste.

MALLOS.

Ba. Æ 37.—AVTO. KAIC. MAPK. Off . . . Bust of Macrinus with laurel wreath, entrass and clock to right.

Rev. MAA. IEP. TOY | ΘΕΟΥ ΑΜΦΙΛΟΧΟΥ, in the field I.

 ϵT ., r. $\overset{\Delta\Pi}{\epsilon}$ (year 284). Tyche seated to l. with turreted crown and veil. In her right hand are ears of corn (?), the left rests on the rock. At the feet of the goddess are two river gods swimming one to left, the other to right.

Num. Chronicle 1897, Proceedings p. 6, where the date is given ARC.

This is the first dated coin of Mallos. The era of the city may be the same as that of Mopsuestia, which begins in the autumn of 68 B.C., or it may be the one beginning a year later. The date 284 would thus correspond either to the year 217 (i.e. autumn of 216), the first year of Macrinus' reign, or (counting from 67 B.C.) to the autumn of 217 to 218.

The mention of the Hieron of the deified Amphiloches, the founder of Mallos, also occurs here for the first time on coins. This sanctuary was the seat of an oracle, famed till late Roman times, which Alexander the Great, on his march to Issos, distinguished by offering sacrifice. Amphiloches as here and seer is represented on various other coins of Mallos as well as on a coin of Tarsos (v. No. 53).

The two river-gods doubtless denote the two arms into which the Pyramos divides from Mallos to its mouth.

Mouv. America de l'Inst. Archéol. II. p. 849, Pl. E.

Moberday and Wilhalm, Reises in Kilikian, Wisn, 1896, p. 47f.

³ Imbout, Mallet, Annuaire de la Est. Fr. de

Nemdemintique, 1883, p. 95-98 and 126.

^{*} Loc. ed. p. 118, 59; 119, 62 and 63; 120, 66 and Pl. VI, 59, 40 and 40.

² Loc. cit. p. 94. Heberdey and Wilhelm, Review in Killiston, Winn, 1896, p. 9.

66. Æ 35.—AYT . . . MAPK, OTTEA. ATA AOVMENT-

AN ON | CE. Bust of Dischumeniams to left, draped:

Rem. M[AA.1]EP. HOA. | SEOV AMOIAOXOV. Youthfal Amphiloches unde, wearing boots, standing to left, with a branch in his right hand, and in left, drapery and sceptre. At his feet in

front is a boar to left. In the field l. [$\in T$.], τ . $\bigcap_{\Gamma} (284)$.

Löbbecke.

Cf. Inv. Waddington, No. 4369, with MIAIHPHOA (?) OFOY etc., ET . AII . (the robe is described as a snake).

The numeral sign (in the date appears to have been missed in the striking, either from some damage to the die or from carelessness on the part of the die-cutter. I have no suggestion to make for the completion of HOA, which in Löbbecke's specimen takes the place of TOY on the previous coin. If Δ stands for Λ, πόλις would be a possible reading.

SELINUS TRAIANOPOLIS.

The earliest known coinage of Selinus is that with the portrait of Queen Iotape.4 With Trajan begins the coinage bearing portrait-heads of the emperors.2

> 7. Æ 32.—AVTO.KALMAP, r., AVPH. below, ANT.... L. Bust of the youthful Caracalla r., laureate and draped.

> Rev. TPAIANO T. MONEITAN CENI. THE IEP L. AC T. Youthful god standing to front, with long hair, chiton and girdle, and a cloak hanging over his back. In the right hand, stretched out sideways, is a patera, and the left, mised, rests on a sceptre, on the top of which there seems to be a bird sitting to left.

My collection.

B. A 20.-AV. KAI, M. AV. CE. L. AMETANAPOC T. Bust of the Emperor to right, laureate, and wearing a cloak,

Rev. TPAIANO, CEAIN L. OV. THE IEPA L. C in exergue. The same god to front, with paters and sceptre. On the right, at his feet, is a bird sitting to right, with head turned round and flapping wings.

My collection.

Pl. XII. No. 7.

Coins of the same type with portraits of Caracalla (7) and Philip are described by Boutkowski (who identifies the god wrongly, once as an Amazon and again as Diana.") and also by Babelon in Inv. Waddington No. 4486, Pl. XI. 15, with the portrait of Macrimus. The type on the reverse undoubtedly

¹ Grisch, Mausen, p. 100, 580; Löbbecke, Zuitmby, f. Num. 2vil. p. 17, Pl. H. 8.

^{*} Inv. Waddington, No. 1485.

Serrare's Bull, de Num. 1895, p. 3.

represents Apollo, and seems to be a replica of the Sidetic god with the raven.

Soloi Pompeiopolis.

9. Æ 24.—Aegis with winger gorgoneion in the middle

Border of dots. Edge sloping.

Rev. ZOAEON, below. Goldess with turreted crown riding on a bull which gallops to right and which she holds by the horns. In the field L, above E. r. N or K.

Gr. 8, 30.

My collection,—Cf. V. Langlois and A. de Longpérier, Roene num. 1854, p. 23 and 142. Pl. IV. 27.

 At 25.—The same, I., above 2 and behind the riding goddess an eagle standing to left, head reverted.

Brit. Museum. T. Combe, Pl. X. 17. Pl. XII. No. 9.

 Æ 26.—Similar, L. above A. in front of the riding goddess an owl sitting to right.

Gr. 14, 51.

A. Löbbecke.

Pl. XII. No. 8.

A design similar to the 'rider' type of these coins may be seen on the silver coins of King Stasioikos. One of these a stater (gr. 11. 10) in my collection, is represented in Pl. XII. No. 10. It is usual to interpret this Kyprian goddess as Aphrodite or Astarte, and undoubtedly the riding goddess of Soloi (who is identified as goddess of the city by her turreted crown) should be interpreted in the same way, and not as the Greek Europa.

To these coins of the period of the Seleucidae correspond half-pieces of

the same date:

12. Æ 20.—Head of Athena to right. Border of dots. Edge

sloping.

Rev. SOAEON r. Bearded Dionysos with bull's horns, standing to front in a long chiton, kantharos in his right hand, the left on a thyrsos. In the field L 🛱 and 🙀. Border of dots.

Gr. 6, 40,

My collection.

Pl. XII. No. 11.

Copenhagen, Ramus i. p. 271, 1 described as Bacchus simply: Munich, Mionnet iii. 611, 344 as Zous.

J. C. Avan. Chemiolo, 1897, Pl. IX, 6; Zeitschr. f. Num. z. (1888), Pl. L. 2-4.

⁵ De Laynes, Num. Oppr. Pt. V. 1 and 2; Stephant Compts rends, 1866, p. 101; Siz. Series Oppr. p. 348, ff. but Babelon, Role

Acherococies, p. culvi. and lav. Waddington, No. 4840, discribes the riding goddies as Artenus.

De Longpérier fon stt. Cabelon Inv. Wad dington, No. 4501.

Cambridge, Leake, Num. Hell. p. 123 called Bacchus in pointed cap' and with two different monograms.

Berlin, on L. M and I.

The Bull-Bacchus, who, according to Inv. Waddington, No. 4524, seems to occur also on a bronze with Gordian, is a rare type on coins, and has

hitherto been known only from coins of Skepsis.1

After the restoration of the ancient Soloi by the Kilikian amigrants who returned from Armenia, the city took the name Pompeiopolis, and a new era began in autumn 66 B.C.2 The reading 'Solopolis' on coins given by Khall and Allier is founded on an error, that is to say, on arbitrary restoration of the initial letters of imperfectly preserved inscriptions.

On the other hand it appears from the following rare and rudely executed copper coins, which were probably struck while the city was being rebuilt, that its name was at first, but only for a short time, Hourgiot or Hournia,

> 13. Æ 22.—Head of Pompeius to right; behind AN. Border of dota

> Rev. HOMIHIANON in a straight line r. Nike moving to right, with wreath and palm-branch; in the field r. O | A | N. L. W Gr. 7, 37.

My collection.

14. Æ 23.—Similar; in the field r. A, NH, A (?).

Gr. 8, 65, My collection.

Pl. XII, No. 12.

These coins show the usual types of Pompeiopolis, but the name of the inhabitants takes the form Hourniavol.

During the empire, down to the middle of the 2nd Century, Pompeiopolis appears to have coined very little. But afterwards, the year 229 (autumn 163-4) is marked by a numerous and peculiar coinage, which includes, besides Concordia coins of the two emperors, Marcus and Lucius, a series of coins without portraits of the emperors. Of the latter kind I bring together the following:

15. Æ 26.—FN, HOM I, THIOC r. Head of Pompeius to

right.

Rev. HOMPHIODO T. AEITON OKC I. Tyche scated to I. with turreted crown and veil, a swimming river-god at her feet. The chair is ornamented with a sphinx.

Paris. Mionnet III, 612, 354. Pl. XII, No. 14. Milan. Mus. Sunclements, II. p. 1, Pl. XIII., 1,

16. Æ 21.—Head of Pompeius to right.

Rev. HOMITHIOTO | ACITON and in the field r. OKC. Bearded figure standing.

Griech, Minuse, p. 104 ff, Pl. VIII, 8-9.

Mountain granges, p. 382; Zeitschr. f. Num. 1 (1883), p. 200 f.

Berlin, v. Prokesch-Osten, Complex vendus de la Soc. fr. de Num. vi. 1875, p. 245, 41.

17. Æ 18.-OKC L. Nike with wreath and palm-branch

moving to left.

Rev. MOM[HHIO] L. MONEITON r. Bearded figure standing to left, the upper part of the body nude, the right hand raised, the left at the side.

Rollin and Feuardent.

Pl. XII. No. 13.

18. Æ 33.—Zeus Nikepheros seated on throne to left, his left

hand raised and resting on sceptre.

Rev. HOMITHIOTO 1: ACITON OKC r. Bearded figure standing to front, the head laureate, turned to the right, the right hand at the side; wears boots; the robe leaves the upper part of the body and the right arm made, while a fold of it falls over the left fore-arm.

My collection. Pl. XII. No. 15,

Paris. Mionnet III. 612, 351; Sestini, Lett. vii. p. 61, Pl. IV. 7-

Cat. Allier, p. 97.

Inv. Waddington, No. 4515, where the statue is described as Chrysippos.

19. Æ 29.— HOMPHIONOASITON E, OKC I Bust of

Athena to r., with helmot and acgis.

Rev. Apollo nude, standing to front, the head to left, the legs crossed. In the right hand he holds a laurel branch, in the left the lyre, resting on a column.

Florence.
Paris. Miounet III. 612, 352.

Pl. XII. No. 16.

20. At 26.—⊕KC I. Bust of the Stoic Chrysippos (?) to right, with cloak, the left hand touching his beard.

Rev. ΠΟΜΠΗΙΟ L. ΠΟΛΕΙΤΩΝ r. Bust of the poet and astronomer Armos (?) to right, wearing clock, looking upward.

Paris. Miounet III. 612, 353.

Mus, Hunter, Pl. XLIII, 23 (Visconti, Icon. gr. Pl. XXIII.)

where the date, half obliterated, is wrongly given as OP.

Brit. Mus. Zeltschr. für Num. ix. p. 118 and 127, Pl. IV. 12 and 13, where the names of the portrait heads are interchanged. Imboof, Forträtköpfe, p. 89, Pl. VIII. 31-32, cf. Schuster, Portrats der griech Philosophen, 1876, p. 22, Pl. IV. 2. Pl. XII. No. 17.

Mua Basel.

From the correspondence of date and from the types in coins 15-20 it is safe to conclude that they were all struck to commemorate some great festival in the year 164, perhaps the dedication of some grand building, new

or newly-restored, and adorned with statues of famous men. Marcus is so well-known as a lover of learning and its representatives and as a generous patron of the sciences, that we may further conjecture that he himself provided the funds for the structure or its adornment.

Similar examples of coins struck for special occasions or festivals

are described elsewhere 1; it would be easy to add to the list,

No commentary is necessary on the portrait-heads in No. 20, except to say that they have sometimes been called Chrysippos and Aratos, sometimes Aratos and Chrysippos.² I am inclined for the present to prefer the former interpretation, because in antiquity, as now, every unbiassed person must have recognised the meditative philosopher in the design on the obverse, and in that on the reverse the poet and astronomer with his eyes raised to heaven.

The standing figure in No. 18 is probably not, as Babelon supposes, meant for Chrysippos. The presence of the laurel wreath makes it more likely that the head represents Marcus Aurelius as Emperor and Philosopher. The statue on No. 17, on the other hand, may very well represent Chrysippos, for there was in the Kerameikos at Athens a statue of him, seated indeed, but with the hand stretched out.³

21. Æ 32.—AVT.K.M.ANT. ΓΟΡΔΙΑΝΟΌ CEB., in the field Π. | Π. Bust of the Emperor to right, with radiate crown and cuirass.

Rev. ΠΟΜΠΗΙΟΠΟ L, ΛΕΙΤΩΝ ζΤ (306) A and in the field I τ. Apollo laureate, nude, standing to left, with chlamys, bow over the left shoulder, and boots. In the lowered right hand is a laurel branch, and in front of him a flaming altar.

My collection.

Pl. KII, No. 18.

Brit. Mus. Similar, without the altar.

22. Æ 33.—Obverse, similar.

Rev. Π OM Π HIO Π OA \in IT Ω N, in the field r. A2 and 2T (306). Bust to right, beardless, draped.

Inv. Waddington, No. 4525, Pl. XI. 18. Pl. XII. No. 19.

Babelon describes the bust as a portrait of Chrysippos; in reality it represents neither Chrysippos nor Aratos, but some other celebrity of Soloi, perhaps (if we may rely on references like Strabo 671) Philomon.

⁴ Grieck, Musses, p. 50-58. Schastopolis in Pontes, No. 82-71.

^{*} Circum de fin. bon. et mal. 1, 39.
* According to Arigoni II, Pl. 40, 864, there is a similar coin with Geta.

^{*} Greeke, Johns. d. Arch. Inst. V, 1896; Beil, p. 58—58.

Rev. HOMPHIONOA. (AT (311), below 5. Bust of Chrysippes (?) draped to right, the right hand touching his chin, which is bearded.

A. Löbbecke.

Pl. XII. No. 20.

Inv. Waldington, No. 4528, Pl XI. 19, where the date is incorrectly read as LAT and the portrait described as Aratos.

24. Æ 30. — AY. KE. Γ. OVIBI. TPEBΩ. ΓΑΛΛΟΝ [CER.], in the field Π. | Π. Bust of Gallue to right, with radiate crown, cuirass, and cloak.

Rev. HOMPHIO L. HOAITAN r. in the field A | S-

Apollo as on No. 21 without the altar.

My collection.

Paris, Mionnet III, 615, 365, described as 'femme debent tenant une branche.'

The signs A5 do not stand for the date, but probably indicate the value of '6 assaria.'

TARSOS.

 AR 28.—Head of Antiochus IX. with diadem, alightly bearded, to right. Fillet-border.

Rev. [BA]ΣΙΛΕΩΣ | ANTIOXOV r., ΦΙΛΟΠΑΤΟΡΟΣ | & Δ! I. The so-called Monument of Surdanapalos with an eagle on the summit.

Gr. 16, 30,

My collection.

Pi. XIII. No. 1.

Among the various examples of the tetradrachm of Antiochus IX. lately come to light, this one is distinguished by the execution of the portrait, which is unusually well modelled for the period.

26. Æ 24.—Bust of Tycle, with turreted crown, veil, and earning, to right. Fillet-border.

Rev. TAPSEON r. \tilde{A} l. Asiatic god to right, standing on the back of a winged lion with horns.

Gr. 8, 70.

My collection.

This piece is overstruck on an example of the following coin of Adana.

Obc. Head of a goddess with veil r.

Res. ADANEON r. Zous Nikephores seated L

 A. 25.—Bust of Tyche to right, with turreted crown and veil. Border of dots.

Rev. ΤΑΡΣΕΩΝ r.. ΑΣΚ | ΓΛΥ l. The so-called 'Monument of Sardanapalos,' with an eagle on the top. Border of dots.

Gr. 9, 05.

My collection.

Pl. KIII. No. 2.

Similar pieces have \$\Delta 10. \$\Theta EO. MAP. XAP. and CAN. \$\Phi IAI. L. in the field, while as a rule coins with the types of Nos. 26 and 27 have only

monograma.

I have elsewhere given more detailed descriptions of the design on the monument, and two additional ones will be found under Nos. 28 and 29. This figure was formerly called Sandan, the Asiatic Herakles; Babelon considers that it ought to be identified with Zeus of Doliche, whose worship was somewhat widely spread in late Roman times. But this new suggestion is not entirely satisfactory.

The god whose image persisted almost unchanged on coins of Tarsos from the period of the Seleucidae to Gallienus is certainly a local divinity associated with the city from the most primitive times, and there is no evidence to prove his identity or even relationship to the Syrian god in Doliche. It was not until shortly before the breaking up of the old religious that the cult of Jupiter Dolichenus seems to have gained much ground. Hence we are not justified in giving to a purely Tarsian representation the name of a composite divinity of late Roman date with characteristics foreign to the ideas of the ancient Kilikians. Rather we must be content for the present to use a purely general name such as 'Asiatic god.' For the figures on old Asiatic monuments which are most nearly approached by the type of Tarsos, as, for instance, those on the Babylonian cylinders and on the rock-reliefs of Jasilikaia near Bogazköi (north of Tavien) have not yet been explained with any certainty.

The 'Dolichenus' of Roman times, a figure of Zeus usually standing on a bull, should probably with more reason be referred back to one of the Syrian gods which appear with various attributes, and sometimes scated or standing between two bulls, on coins of Antiochos XII., of Rosos, Hieropolis, Gabala,

and Dion.10

28. A 26.—AVT KAI. ΘΕ, ΤΡΑ, ΠΑΡ, VI. ΘΕ, ΝΕΡ, VI. ΤΡΑΙ, ΑΔΡΙΑΝΟΣ ΣΕ.

¹ Rooms unus., 1854, Pl. IV. 20; Inv. Waddington, No. 4000 and 4610; Brit. Mas.

Monn. prospens, p. 366, 54-57, Pl. F 23-25; 433, 96; 435, 112-118; Pl. H 14; Two-and

Pflowenbilder, p. 70, Pl XII. 7-9.

* Hand-Rechette l'Hernile Amprice, 1848, Pl. IV 16 and 17; Lajard, Culte de Vénne,

1849, Pt. 1V 11-12

2 Loc at. p. 440, 8 Pt. VII. 228.

Moun. Gal. Math. p. 89, Pl. XIV, 10; Lajard, Calle de Vinne, Pl. V. 5.

² Les Role de Sprie, p. civi S. Ct. K. Meyer, Roscher's Lexikon, I. p. 11916. According to Mayer, the cuit of Dollahemus can only be traced back to the include of the 2nd century s.p. and was of splanmark againstance.

Perrot and Chiping, Hist, at Fidet, IV (1850), Pl. VIII. E, and No. 637, where one of the gods who stand at lines appears with a sword at his side and a double axe and staff in his hand.

Moun, prespect, p. 487, 121, Pl. II 15. Strangely enough, Lee Block, in Rescher's Leedlan, Korn p. 1814, ranintains that this bearded figured is female, and represents a draped late.

Grind, Milman, p. 235, 772-775, Ph. XIV.
 7.

¹⁹ Lajard, the cil Pl. IV. 6; do Sabley, Nam. do Terre-minte, Pl. XIX. 2. Cf. nine Walters, Zens Heliopolites, dimer. Journ. of Arch. ci, 1820, p. 65-8 (illimitation); Studnicaka, Bildunybeans Cornamium, Archaeol. --proc. Mills. and Contex.-Unpura. cib, p. 64, Pl. II.

Bust of Hadrian, laureate, with cuirass and drapery to right. Rev. ΤΑΡΣΕΩΝ L. ΜΗΤΡΟΠΟΛΕΩΣ τ.

Bearded god standing to right on the back of a horned lion. He is dressed in a short chiton and cloak; on his head is a Persian tiara crowned with a top-piece; behind the left shoulder is a quiver in front of which is a projection like a bow. At the left side is a sword, and in the left hand a double are and wreath. The right hand is stretched out. Countermark with the head of an emperor, laureate, to right, and A | M | K under it.

Gr. 9, 75, My collection.

This type, which has just been discussed, and occurs in different varieties of die on silver coins of Hadrian, is well illustrated in Imboof and Keller's 'Tier- und Pflanzenbilder,' Pl. XII. 8.1

The head in the countermark appears to represent Caracalla; the three letters are the initials of the well-known titles of the city, πρώτη, μεγίστη, καλλίστη.

As a variety of the 'Monument' figure the following is also remark-

able :-

29. Æ 32.—AY. KAI, Γ. MECC, KYIN, ΔΕΚΙΟΣ ΤΡΑΙΑ-NOC, in the field Π | Π. Bust of the Emperor to right, with radiate crown, cuirass, and cloak.

Rev. TAPCOV 1. ΜΗΤΡΟΠΟΛΕΩC r., in the field r. A. M. K. Γ. B. The type is similar to that of No. 28, but instead of standing on the lion, the god is mounting the animal from behind by placing his left foot on its back.

Call Gonzenbach, St. Gall.

Pl. XIII. No. 3.

To judge by coins of the Empire, Apollo Lykeios (or Tarsons) and Persons were two of the divinities whose cults enjoyed most prestige in Tarson. They are often represented together. The figure of Apollo is usually of archaic style. He is nude and stands to from with the legs close together. His long hair falls sideways over his shoulders, and his head is adorned with a laurel wreath. The god stands on the Omphalos, on either side of which lies a bull; in his bands he grasps the fore-legs of two wolves that are standing up on their hind legs on either side of him. Sometimes a high column occurs as a basis for this group.

The creatures which the god holds by the fore-legs are not deer or antelopes, as was formerly assumed, nor are they greyhounds, as Babelon seniectures, but icolosis. This is placed beyond a doubt by the form of the

Cf. also de Layers, Num. dei Satropies, Pl. Bull. de Corr. Hell, vii. (1883), p. 285 ft.
 VII. 1.
 * Inv. Waddington, Nov. 4638, 4659.

² Monn. grocques p. 351 ; Waldington,

long tail represented, as a rule, not turned upwards as in a dog, but hanging down. Add to this that the wolf is one of the well-known and wide-spread symbols or attributes of Apollo, while the dog is not.

The cultus image of Apollo occurs on coins from Hadrian to Gallienus. Sometimes the emphalos is indicated merely by a small arch, without the attendant bulls, and on some late coins the archaic character of the status has been missed through lack of skill on the part of the die-engraver.

As the following list will show, the statue of Apollo often appears erected before Perseus sacrificing, or as an attribute of Perseus. Perseus was represented in various ways as founder and hero of the city, and was honoured as $\beta o\eta\theta \delta s$ (No. 41 and 42) and $\pi a\tau \rho \hat{\varphi} os$ (No. 48).

L.—Apollo.

1. The Cultue image on the column.

See below, Persons, Nos. 45-47.

2. The Cultus image without the column

30. Æ 31- PAYCTEINA I, CEBACTH r. Bust of the younger Faustina to left.

Rev. ADPIANHE TAPE OV MHTPOHOAERE. The cultus image with the two wolves to front standing on the omphalos between two recumbent bulls.

Paris

Mionnet iii. 627, 435; Lajard, Recherches sur le culte de Vénus, p. 70, Pl. V. 1 and Archaeol, Zeitung, 1854, p. 215; Overbeck, loc. cit. Coin-plate I. 30.

31. Æ 32.—Obv. Macrinus.

Rev. [CEYH. MAKPEINIANHC | MH]TPO, TAPCOY and in the field [A.] M. K. The cultus image stamling on the outphalos, head to left.

Berlin, Zeitschr. für Num, viii p. 10, Pl. II, 6.

32. Æ 29.—AVT. KA. M. AVP. ANTΩNEINOC. Bust of Elagubalus, laureate, to right with cuirass and drapery.

Rev. TAPCOV | MHTPO. The cultus image on the omphalos to front; in the field two stars.

Library of Bologna.

Pl. XIII. No. 4.

Num. Chronicle, 1873, p. 35 (incorrect).

" Cf. Ecklint Num. vyf. americki, p. 89.

¹ Cf. sur illnerrations and Overbeck, Apollon, p. 29, Pl. L 30 and 31.

33. Æ 38.—A. Κ. M. A. CEOY. ΑΛΕΙΑΝΔΡΟΣ CEB and in the field Π. | Π. Bust of the Emperor to right, laureate, draped.

Rev. AΛΕΙΑΝΔΡΑΝ: C| EO. AΔ. MHT. TAPCOV. and in the field r. A. M. K., L. Γ. Π Β. The cultus image to front, head to left.

Rollin and Fenardent.

Pl. XIII. No. 5.

Overbeck inc. cit. Coin-plate L 31. Paris of Mionnet iii. 638, 496 and 497 (with 'deer.') Brit. Museum.

34. Æ 37.—AYT. K. Γ. IOV. OVH. MAXIMEINOC and in the field Π. | Π. Bust of the Emperor to right, with radiate crown, draped.

Rev. TAPCOV THE | MHTPOHOAEWC and in the field I.

A. M. K., r. F. B. The cultus image to front

Vienna. Frölich, Quatuor Testamina, p. 318; Cat. Mus. Caes., 129, 11; Micanet, Suppl. vii. 276, 481, with 'dogs' or 'deer.'

35, Æ 37,-Similar.

Rev. Inscription the same. The cultus image on the omphalos to front, head L, in the r, hand a wolf, in the L hand a bow.

My collection.

Pl. XIII. No. 6.

Cf. Mionnet, iii, 640, 509.

Brit. Museum, which also possesses the same type on a coin with Balbinus.

36. Æ 30.—ANNIAN AITPOVCKIAAAN CE. Bust of Etruscilla to right, with crescent at shoulders.

Rem. TAPCOY MH | ΤΡΟΠΟΛΕΩC and in field I. A.M. K.,

r. F. B. Cultus image on the omphalos, head to r.

Brit. Museum. Ci. Haym, Thes. Brit. ii. Pl. XLVII. 4. 'Artemis with two stags'; Mionnet, iii. 653, 595, 'with dogs.'

37. Æ 30.—AVT. K. Π. A. OVAΛΕΡΙΑΝΟΝ CE and in the field Π. | Π. Bust of the Emperor to right, laurente and draped.

Ecc. TAPCOV MHT | POΠΟΛΕΩC, in the field L A . M . K ., r. Γ . B . The cultus image on the emphales turned slightly to left, head to right.

rov (alsowhere unusual) stands for specadefautes, v. Waddington, Bull. do Corr. Hell. vii. p. 285. Whering this initial has the same significance here is uncertain, because the letters I. EII (species) are absent.

In the first word of the immeription either I has dropped out after P or an should read "Acefarép(airh) 'Arifversument), as on a coin of the Brit. Museum with the same superor and the type of Pallas. On contemporary goins the letter II in the field of the

Vienna, Mus. Theup. p. 1081/2; Mionnet Suppl. vii. 287, 531; the animals are called dogs or deer.

Cat. Greppo, No. 1106, described as nade Hekate with dogs,

3. The Emperor sacrificing before the cultus image.

38. Æ 34.—AVT. KAI.M. AVP. CEVHPOC ANTONEINOC and in the field Π . Π . Bust of Caracalla to right, laurente and draped.

Rev. ANTONEINIANHC CEVHP. ADPI. TAPCOV and in the field A. M. K. The cultus image standing to front on the omphalos between bulls' heads, with the two wolves; beside it the Emperor in toga, standing to left before a flaming altar, holding a patera in his right hand.

Paris. Mionnet, iii. 632, 465. Pl. XIII. No. 7. Cf. De Witte, Cat. Greppo, p. 151, No. 1106, 'Apollo with antelopes.'

4. Other seenes of sucrifice before the cultus image.

See below, Perseus, No. 45-47.

5. The cultur image as attribute of Persons.

See below, Perseus No. 41 and 42, No. 48 and 49,

II .- Perseus.

1. Persons with harps,

39. A 26.—Obv. Hadrian.

Rew. ΤΑΡΣΕΩΝ ΜΗΤΡΟΠΟΛΕΩΣ. Persons, nude, with winged sandals, stands to left, the harpe and drapery in his left hand; he holds out his right hand to Apollo, who is nude and standing to right with crossed legs, leaning on the tripod. A laurel-branch is in Apollo's left hand, and between the legs of the tripod rears a snake.

Gr. 9, 68,

The Hague. Imhoof, Zeitschr. f. Num. iii, p. 383, 1, Pl. 1X. 3; Overbeck loc, cit. Apollon; Coin-plate V. 16.

2. Persons with harpe and Gorgoneian.

40. Æ 35.—AVT KAIC Δ KAIA BAASSINGC CES. and in the field Π . | Π . Bust of the emperor laureate to right with cloak.

Rev. TAPCOY M | HTPOΠΟΛΕΩC and in the field L.A.K., r. M.B.Γ. Perseus as on No. 39 except that he holds the winged Gorgoneion in his lowered right hand.

Cat. Gréau, No. 1953. Sabatier, Revue Num. Belge 1865,

Pl. XVIII, 25.

Similar with Maximinus, Mionnet iii. 640, 510, and with Gordian, Mionnet iii, 644, 534.

- 3. Perseus with harps and Cultus-image of Apollo.
- 41. Æ 27.—AΔPIANHE TAPCEΩN. Head of the bearded Herakles crowned with oak-leaves to right; club behind the shoulder.

Rev. MH | TP L. OHOAEGE r. Persens, nude, with winged sandals, standing to left, harpe and drapery in his left hand, and on his outstretched right hand the cultus image of Apollo (with the two wolves) standing to front on the omphalos. In the field L. BOH | GOY, and below, at the feet of the hero, a bull to left attacked by a lion from the side.

Gr. 19, 52,

My collection.

Pl. XIII. No. 8.

Löbbecke.

- Cf. Mionnet iii. 623, 417; Leake As. Gr. 129, 1; Inv. Waddington No. 4625-7 Pl. XII. 6, the animal group not described.
- 42 Æ 29.—Similar, with ΑΔΡΙΑ NHC TAPEEΩN and MH TPO ΠΟΛΕΩΕ.

Gr. 11. 65.

My collection.

Brit. Mus. T. Combe Pl. X. 18 = Mionnet Suppl. vii. 259, 405.

The attribute in the right hand of the Perseus and the animal group at his feet seem hitherto to have escaped notice on all known coins of this type.\(^1\)
The representation of the fight of the lion and bull is identical with that on the silver coins of Hadrian;\(^2\) on later coins the bull appears seized from behind.\(^3\) The fight is certainly meant to be symbolical, and must be brought into connection with Perseus as Helper ($\beta o\eta \theta \dot{\phi} \dot{\phi}$).

43. Æ 36.—[AVT.] K.M.ANT. ΓΟΡΔΙΑΝΟΣ ΣΕΒ. and in the field Π. | Π. Bust of the Emperor to right, with radiate crown, shield and spear.

¹ Cf. Monatablast d. nam. Gualisch. Wan, 1896, No. 156, p. 379/80, Inv. Washington, No. 1025, where the cultur-image is recognised.

Mionnet Suppl. vii. Pl. VII. 4; de Laynes Suca. des Satrapies, Pl. VII. 7; and here Pl.

xiii, No. 9 (Gr. 10. 65, my collection).

8 Examples with Gordian, Miconset III. 645, 543-47; with Dectus, Miconset III. 662, 500-1, Rev. cass. 1854, Pt. VIII. 50.

Rev. TAPCOV MHT | POΠΟΛΕΩC and in the field I. M. A. | K., r. B. | Γ. Perseus with the cultus image as on No 41; in addition to the harpe he holds a fishing basket in his left hand.

Berlin,

Pl. XIII. No. 10.

44. Æ 35.—AV KAI. Γ. OVIBION TPIBΩ. FAAAON and in the field Π. | Π. Bust of Gallus to right, with radiate crown, cuirass and cloak.

Rev. TAPCOV MH TPOΠΟΛΕΩC and in the field L. A. M. K., r. B. Γ. Perseus with the cultus image as on No. 41. My collection.

Pl. XIII. No. 11.

Paris. Mionnet Suppl. vii. 286, 528 (and 529 after Sestini) where the cultus-image is described as 'two small figures on a prow' or as 'bow inverted' and the drapery is mistaken for a Gorgoneion.

4. Perseus sucrificing before the Oultus image.

45. Æ 38.—AVT. KAI. A. CEΠ. CEYHPOC ΠΕΡ. and in the field Π. | Π. Bust of the Emperor, laureate, to right, with cuirass.

Rev. AΔPI, CEYHPIANHC TAPCOY MHTPOΠOA[EWC] and in the field above . Γ. Β. The cultus image of Apollo with the wolves stands to front on a column on the omphales between recumbent bulls. To the right of the image is a flaming altar, in front of which stands Perseus to left, with curly hair, drapery round the hips and left arm, paters in his right hand and harpe in his left.

Waddington. Pl. XIII. No. 12,

Cf. Inv. Waddington No. 4638, where Perseus is wrongly described as an emperor.

46. Æ 40.—AVT.K. ANT. ΓΟΡΔΙΑΝΟΣ CEBA, and in the field Π. | Π. Bust of the emperor to right, with radiate crown, cuiraes and cloak.

Rev. TAPCO V MHTPOHOAEAC and in the field, A. M.K. B. r., F., L. An alter with a zebu-ox lying to left in front of it. Behind the alter are visible the upper parts of two draped figures with heads to right, between whom towers a high column bearing the cultus image of Apollo and the wolves. At the right aids of the alter stands Persens to left, wearing drapery on his hips and arm, and winged sandals on his feet, and holding in the left hand harpe and in the right paters. At the left side of the alter stands the goddess of the city to right, in a long robe and wearing a turreted crown (?); both her arms are raised to the cultus image.

Milan, Brern, Mus. Sanclementi III. p. 85, Pl. XXXII. 337.

Pl. XIII. No. 13.

Num. Chron. 1873, 36, cf. Inv. Washlington, No. 4673, Ph. XII.
13.

Variants of this representation (up till now unpublished) may be seen in Inv. Waddington, No. 4655, with the head of Sev. Alexander, and in the following example.

47. Æ 35.—AV, KE, Γ, MEC, KOV, ΔΕΚΙΟΣ ΤΡΑΙΑΝΟΣ EV. EVCEB, and in the field Π, | Π. Bust of Decius to right, with radiate crown, cuirass and cloak.

Ecc. TAPCOY MHTPOΠΟΛΕΩC and in the field τ. A. M. K., in the exergue Γ. B. An alter with a zebu-ox lying to left in front of it; on the left, beside it, a high column supporting the cultus image of Apollo. Behind the alter is a standing figure, the head to left; the right hand rests on a spear and there seems to be a shield on the left arm. To the right of the alter stands Perseus to the left, nude, holding in the left hand a harpe and drapery and in the right a patera. To the left of the column Tyche with turreted crown stands to right with both arms raised

My collection. Pl. XIII. No. 14.
Cf. Num. Chron. 1873, 36, with a fanciful description of the

The goddess of the city standing before a sanctuary in the attitude of prayer occurs again on a coin of Tyros.

5. Persons and the Fisherman.

48. Æ 38.—[AVT., K. M.] AVP. CEV. AΛΕΊΑΝΔΡ.... and in the field Π.] Π. Bust of the Emperor to right, laurente, draped.

Rev. AACIANΔPIAN. A | N. AΔ (?)... In the field above A M, K., at the sides Γ. | B. and in the middle ΠΑ | ΤΡΩ | OC. Persons, nude, with winged sandals, standing to right. His long cloak is fastened round his neck and hangs down behind, covering his back. In his right hand he holds the harpe, and in his left, which is raised, the cultus-image of Apollo and the wolves. Opposite the hero stands a hearded fisherman in a short chiton. The figure is turned slightly to right and the head to left. A fishing rod is in his outstretched hands, with a fishing basket hanging at the upper end and a large fish at the lower.

Coll. Waddington. Pl. XIII. No. 15.

Cf. Inv. Waddington, No. 4654, Pl. XII. 10.

49. Æ S7.—AVT. K. ANT. ΓΟΡΔΙΑΝΟΣ CEB, and in the field Π. | Π. Bust of the Emperor to right, with radiate crown, cuirass and cloak.

Imhoof, Autike Münchilder in the Jukes, d. erobiol. Incl. (1888), p. 286, O'L 9, 4).
H.S.—VOL, XVIII.

Hev. TAPCOV M H L, TPOTIOAEMC r., and in the field, in the middle, A. M. K., L. B. and r. F. Similar group, only the fisherman standing to left is beardless and of relatively smaller stature than Perseus. The little cultus image has no distinguishable attribute.

My collection Pi. XIII. No. 16.

Brit. Museum, with Br on left and the small cultus image with distinct wolves.

Paris. Mionnet III. 647, 561, described as with two fish; cf. Mionnet Suppl. VII. 283, 512 (after Vaillant) and 513 from a bad illustration in Gessner, *Impp.* CLXXIII. 24, and p. 730, 206 bis; Leake, As. Gr. 130, 1,

50. Æ 36.—AV, KAI, Γ, MEC, KVIN, ΔΕΚΙΟΣ ΤΡΑΙΑ-NOC and in the field Π, | Π. Bust of Decius with radiate crown cnirass and cloak to right.

Rev. TAP | COV MHTPOΠOΛΕΩC, in the field above A. M. K. and in the exergue Γ. B. Persons nude, with winged sandals, standing to left, in an attitude of surprise, mising his right hand to his mouth, and holding in his left harpe and drapery. Opposite the hero stands a beauded fisherman to right, in short chiton and books. He holds in his left hand, over his shoulder, a fishing-rod and booket, and in his right a large fish.

My collection. Pl. XIII. No. 17.

Cf. Mionnet III. 652, 587 and Leake Suppl. 100; both call the object in Perseus' right hand a gorgonoion. Cf. also Sabatier in Rev. Num. Belge. 1860, Pl. V. 5, where the ⋉ in the field is mistaken for a small Nike, the fish for an altar, and the fisherman for the Emperor.

Cavedoni's view is that the type of the coins No. 48-50 represents a meeting of Perseus and the fisherman Diktys, who drew Danaë and her son from the sea with his not, and was afterwards made king of Seriphea. It is, however, obviously much more likely that the scena represented is some local legend of Tarsos, but as this legend has not been otherwise handed down, attempts at explanation of the types would be useless. It is worthy of notice that the figure of Perseus on No. 50 seems to express by his attitude surprise at the offering of the fish, and that in No. 43 he has taken over the fisherman's basket as an attribute.

The Kronos type on coins of Tarsos, of which the following piece is an example, is easy to distinguish from Perseus.

51. Æ 33.—AV. KAL. H. AL. OVAASPIANON CE. Bust of the Emperor to right, with radiate grown, cuirass, and cloak.

Rev. TAPCO V MHTPOΠΟΛΕΩ C, in the field LA.M.K., r. Γ. B. Kronos bearded, walking to left. His r. breast and arm

¹ Spicilegio, most, p. 211.

are bare, and on his head (which is turned to right) is a small crown with three peaks. His robe is drawn over the back of his head, in his outstretched right hand he holds the harpe, and on the left hand is an imperfectly defined object.

Mus. Athen. No. 5800.

Pl. XIII. No. 18.

Cl. Roscher's Levikon ii. p. 1558, Fig. 8 where the drapery and crown on the head of Krones have passed unnoticed.

The worship of Kronos in Kilikia is proved by Stephanus Byz. s.v. "Ačava, and by coins of Mallos and Flaviopolis."

52. Æ 38.—AV. ΚΑΙ. ΠΟΥ. ΑΙ. ΟΥΑΛΕΡΙΑΝΟΣ CE and in the field Π. | Π., Bust of the emperor to right, with radiate crown, cuirass, and cloak,

Rev. TAPCO V MHT POHOA and in the exergue EAC.

A.M.K.F.F. Three nude beardless male figures standing side by side to front. The two to the left have the head to right, the one to the right has the head to left. Each figure with one hand places a crown (turreted crown 7) on his head. The middle figure holds in the left hand a palm-branch which rests on his shoulder, the two others also hold each a palm branch in the lowered hand.

My collection. Pl. XIII. No. 19.

Cf. Mionnet iii, 655, 611 and Suppl. vii. 289, 543 = Sestini, Mus. Hed. ii, 299, 44; Cat. Moustier, No. 3163.

The attitude of the three men is identical with that of the victors in festival games. As other coins of the time of Valerian show three prize rases with the inscriptions KOPAIA, AVFOVCTIA and AKTIA. it is likely that the three figures represent the three victors in the games.

53. Æ 33.—From the same die as the preceding.

Rev. TAPCOV M | HTPOΠΟΛΕΩC, in the field I. A. M. K., r. Γ. Γ. Amphiloches, in a short tunic and boots, standing to left, a branch in the right hand, and in the left a sceptre and cloak. In front of him a boar walking to I.

Löbbeeke.

Pl. XIII. No. 20.

The explanation of this type is to be found in representations of the seer Amphiloches on coins of Mallos.³

54. Æ 31.— ΑΔΡΙΑΝΗ ΚΟΜ ΟΔΙΑΝΗ ΤΑΡΌΟ Η MHTPOΠ OAIC. The Tyche of Tarsos seated to left with turreted crown and veil. In her right hand are two ears of corn

Immoof in Roseher's Leether, tl. 1872-

Minnnet, iii. 656, 615 and Suppl. vil. 220,
 545 A 546; Pellerin, Recount, iii. p. 280 (Hinster).

^{*} Imboof, Muller (Assessive de la Sec fr. de Num., 1883) p. 118, 59 : 119, 62 & 63, P1 vi. 38 & 43, and in the present article above, No. 60.

and a poppy head; her left hand rests on the seat, which is adorned with a griffin standing to left. At the feet of the goldless is the apper part of a figure (the river Kydnos) swimming to left, and turning his head, which is wreathed with sedge, towards Tyche.

Rev. KOINOC KIAIKIAC TAPCOY ΔΙΟ ΝΕΩΚΟ POY.

A wreath or bandeau with hanging fillets, and set round the outside with eight heads. Of these three male and one female are turned to left while two male and two female are turned to right. The male heads are apparently all bearded and without crowns.

Gr. 14. 80. My collection.

Pl. XIII. No. 21.

This example (similar to Mionnet Suppl. vii. 257, 394 = Babelon Annuaire de Num. vii. 1883, p. 24, Pl. H. 5, where Tyche is called Kybele and the eight heads are conjectured to be those of divinities, perhaps goddesses of the cities belonging to the xocrop) was first made known by Sabatier in the Revue Num. Belge 1860, Pl. V. 4 (= Cat. Gréau, No. 1945). and this notice was plagiarized by Boutkowski in his Dictionnairs Num. i. p. 1487, No. 2484. Sabatier in his illustration represented the male heads as laureate, and called them (counting from left to right) Sabina, Hadrian, Pius, M. Aurelius, L. Verus, Commodus, Faustina and Crispina. Cohen (on the other hand), in the Cat. Greau, supposed them to be Pius, M. Aurelius, L. Verus, Commodus, Severus (with radiate crown), Faustina, Crispina and Domna. The new phototype shews that the bearded heads are not crowned. The coiffure of the female heads is that which is known from portraits of the younger Faustina, Lucilla and Crispina. The series as a whole gives the impression of being intended for portraits of the Antonine family. Though the size is too small to admit the possibility of a real likeness, yet certain individual characteristics can be traced.

Another coin of Tarsos with the wreath, of which a good example is preserved, makes it evident that the heads represent neither goddesses of the city nor other divinities.¹

55. Æ 32.—AVT. KAL. M. AVP. ANTΩNEINOC. Bust of Elagabalus, laurente, to right, with cuirass and cloak.

Rev. TAPCOV THE MHTPOΠΟΛΕΩC. and in the exergue A. M. K. An alter wreathed; over it a large wreath; to the right beside it a bandeau with fillets thus adorned: I two boys' heads to right; then Γ, female (?) bust to left beardless head laurente to left and similar head laurente to right; then B, and two male busts draped, to right, in all seven heads.

My collection. Pl. XIII. No. 22.

Cf. Mionnet iii. 637, 491 with nine heads; 492 with two handenux, each with six or seven heads; Suppl. vii. 274, 468, with seven heads;

¹ See Waldington Bull, de Corr. Hell. vil. 1883, p. 288-7.

Inv. Waddington No. 4646 Pl. XII. 9 with six heads. Cf. also the coins with Maximus and six heads, Inv. Waddington No. 4661, Pl. XII. 11; with Gordian and two circles, each with seven heads, Mionnet iii. 646, 548 (Pellerin Mel. ii. Pl. XXXI. 5), Inv. Waddington No. 4668 and many others.

The head in the middle of No. 55 may possibly be meant for Elagabalus;

for the others no names can be conjectured.

On a coin of the time of Volusianus letters stand above and between the eight small busts of the bandeau; but they do not help to interpret the heads as they seem to be the usual series of initials $A \cdot M \cdot K \cdot \Gamma \cdot B \cdot \Gamma \cdot \xi$. (the two last possibly standing for γ' $\ell\pi\alpha\rho\chi\iota\hat{\omega}\nu$) and partially to repeat the inner inscription of the bandeau.

F. IMHOOF-REUMER.

Winterther, May, 1898.

INDEX OF THE PRINCIPAL TYPES, INSCRIPTIONS, ETC.

A =-Pompelopolis. No. 21-24 Aogh with gorgonnion-Soloi 9-11 Akropolis - Amaurbos 4 Amphilocho-Maltos 65, Tursos 58 Antiochos in -Tarson 25 Aphrodits on a bull-Sold 9 H., Stasloikus Pl. XII. 10 Apoilo, sianting-Lames & Science I, & Penspelapolis 19, 21, 24 - Lykeies or Tarnetts (maltus image)-Tarses 35 ff. 39 Austos, portrait-Pompsiopolis 20 Sayes (Persons)-Tarner 41, 12 Bull Bakehow v. Diony, our Chryslepos, statue-Pompelopolis 17 - portrait-Panquiopalla 20, 23 Countermark-Turne 28 Dionyson, bust-Augusta 5 - bearded and horned-Solot 12 Dolichenus - Tursse 27 f. Texangle-August I Elple-Amaza bee 3 25-29 Beigarlerarer Haises-Algeri 2 Era of Antumn 68 or 10 s.c. Mallow 6" 66 n.c. Pempolopolis 12 TE 47 n.c. Aigeni I 8F 18 19 m.c. Anmarlus 3 & mir. 20 A.D. Augusta 5 54 B. Ейусныя вывейя быорькой Масебория—Аідреі 🥸

Fastival coins - Pompulopolis 15-20 Festival games, Victors in-Taxon 52 Fisherman and Persons-Turnes 48-50 Г. Е(экрхийг) - Тигион 65 Topk x6Act (1) went Approxixon Mallin 60 from rai ovan Auguldzon Mallus 60 Krouoz, standing - Tarace 51 Lion and bull-Turson 41,42 Marcus Aun lius (1), status-Pompelopolis 18 μητροφολίε της Δημώτιδος- Lanion fi Oversariking-Tar-a 28 surpport (Persona)-Tarana 48 Persons Tarme 35 ff. - and Balancian - Turson 18-50 Phileman (III. pertrait-Pomperapolis 22 Bourginsol-Pempetopolla 12, 13 Hope the Pompelopalis 15 Pompeius, parirait-Pempeapoles 18-16 II pounde fou les ! Tares 31 Sacrifico, scenes of-Turson 38, 45-47 Sardanapalos, so-called assumment of-Tanas Stasioficos-II f. Tyaha, scand-Aigeai 4 Mallas 4. Pampelapolls 15, Tarmer 54 - minring-Thron 4th, 47 Wreath addressed with human hands-Tarana

I Imboof in Zettehr. f. Nom iii. 342, 33.

THE ARABS IN ASIA MINOR (641-750), FROM ARABIC SOURCES.

Considering the attention now paid to the geography of Asia Minor, it has struck me that a collection of the notices relating to the Arabic invasions of that district, which are scattered here and there in the Arabic annalists and must be sought through thousands of pages of Arabic print, would serve a very useful purpose. These extracts not only throw light on geography and the Arabic nomenclature of the localities, but, when compared with the accounts of the same events in Greek and Syriac writers; are of great value for the study of chronology.

The writers from whom extracts are given under years are the following :-

- The chronicler known as Ibn Wadhich or Al Ya'kubi, who wrote about 900. (ed. Houtsma, Leiden, 1883).
 - (2) Al Tabari d. 923. (ed. Barth and others. Leiden, 1879, &c.).
- (3) The Khitab Al 'Uyun (Book of Springs).¹ (ed. de Goeje, Leiden, 1871). This work, though dating not earlier than the middle of the 11th century, preserves several valuable notices relating to this period.
- (4) Ibn Al Athir (d. 1232). (ed. Tornberg. Leiden, 1851, &c.). This author generally copies Al Tabari, but occasionally has notices not found in that writer, and is useful for the period before AH 40, for which Al Tabari's text is not extant.

Much valuable information is also to be found in the work of Al Baladhuri (d. 898) (ed. de Goeje. Leiden, 1868), who gives a connected narrative of the compact of each district; but, since his work is not arranged in annalistic form. I have not given the extracts from it with those of the other writers, but separately at the end. Notices derived from the same source as those of the Mohammedan writers are also to be found in the bilingual chronicle of Elijah of Nisibis (written 1019), most of these being quoted from the work of Mahamet the Khawarizmi (circ. 835); but, since this portion of Elijah's chronicle has been translated into German by Dr. Baethgen (Abh. fill die Kunde des Morgenlandes Bd. 8), there is no need to repeat the notices here, but it will be sufficient to give references to them in the margin. The authority most frequently quoted by the Arabic writers is Al Wakidi (d. 823). Most of the notices are merely annalistic cutries; but sometimes, especially in Al Baladhuri, longer accounts are given. These I have

The expant portion of this work begins with the secondary of Al Walld I, (705).

A few are also quated from the (Amunicle of the Arab Kings, a work of the 10th century.

been obliged from considerations of space to shorten; but, however important for Arabic life and character the omitted passages may be, nothing essential to the purposes of this article is last by their suppression. Only the long and interesting narrative of the expedition of 716-718 in the Khitab

Al 'Uyan I have been obliged to pass over altogether.

In the margin of the annalistic notices I have given references to notices of the same events in other writers (not necessarily derived from the same source), including, besides Elijah of Nisihis, in Greak Theophanes and Nikephoros, and in Syriac Michael the Syrian, the chronicle of 775 falsely attributed to Dionysics. and the Chronicle of 846 (Zeitsche, d. deutsch, margent, Gesellsch. vol. 51, p. 569). In the extracts from Al Baladhuri, to avoid repetition. I have generally referred only to the preceding manufactic extracts. To avoid possibility of misleading, I have given all geographical names in the first instance in the Arabic form, placing the usually received names in brackets following, wherever they can be identified. I have added a few notices relating to Armenia and Syria, which are so closely connected with those referring to Asia Minor that it appears unreasonable to omit them.

CALIFHATE OF UMAR L

A. H. 20 (Dec. 21, 640-Dec. 9, 641).

Ibn Al Athir. And in this year, I mean the year 20, Abn Bachriyyn "Abd Allah, the son of Kais, made a raid into the land of the Romans; and he was the first who entered it, as it is said (and it is also said that the first who entered it was Maisra, the son of Masruk, the 'Ahsi'), and he carried off prisoners and spoil.

CALIPHATE OF UTIMAN.

25 (Oct. 28, 645-Oct. 16, 646).

Ibn Al Athir. And in this year Mu'awiya made a raid upon Roman territory and reached 'Ammuriya (Amorion); and he found the fortresses between Antakhiya (Antioch) and Tarsus descried, and he stationed in them a large number of the men of Al Sham (Syrin) and Al Gazira (Mesopotamia), until he returned from his raid. Then after that he sent Yazid, the son of Al Chur, the 'Absi, upon a raid in the summer; and he gave him orders, and he acted accordingly; and, when he went out, he destroyed the fortresses as far as Antakhiya.

28 (Sept. 25, 648-Sept. 13, 649).

Ibn Al Athir. And in this year Chabib, the son of Muslama, made a raid upon Suriya, in the land of the Romans

of. p. 191, note 3.

In the Arable question in this British Мамит M8. Or. 1402.

[&]quot; Published, with trunsiation, by the Abid Challet (Park, 1895)

This seems to show that Antroch in Pinidia is here meant, though the provious mention of

the many rather points to the Syrian city. * i.e., Syria; the name were to be used by the Araba to denote Euphratesia and Cilicia. But perhaps we should reset Sauriya (Isentia) :

32 (Aug. 12, 652-Aug. 1, 653).

Sabors 3, 36 Ibn Al Athir. It is said that in this year Mn'awiya, the son of Abu Sufyan, made a raid upon the straits of Al Kustantiniyya (Constantinople); I and with him was his wife 'Atkha, the daughter of Karaza; and it is said also that his sister was with him.

33 (Aug. 2, 653-July 21, 654),

The Al Athir. In this year was the raid of Mu'awiya upon the fortress of Al Mara, in the land of the Romans, in the neighbourhood of Mulatya (Melitene).

CALIPHATE OF MU'AWIYA.

41 (May 7, 601-Apr. 25, 662).

Ibn Wadh.. He sent Chabib, the son of Maslama; and the Roman commander made peace, and did not care to engage with him.

42 (Apr. 26, 662-Apr. 14, 663).

Though AM Al Tab. And in this year the Mosiems made a raid upon the Romans and inflicted a severe defeat upon them, as men record, and killed many of their patricians.

43 (Apr. 15, 663-Apr. 3, 664).

Kt. Nis. 43. Ibn Wadh. Busr, the son of Abu Arta, made a raid into the land of the material and wintered thore.

Al Tah adds: Until he reached Al Kustantiniyya, as Al Wakidi asserts; and some of the authorities deny this, and say that Bust did not winter in Roman territory at all.

44 (Apr. 4, 664-Mar. 23, 665).

23. Nie 44. Din Wadh. Abd Al Rachman, the son of Khalid, the son of Al Walid Theoph AM made a raid until he reached Akluniya (Koloneia).

Al Tab. Among the events of this year was the invasion of the Roman territory by the Moslems under 'Abd Al Bachman, the son of Khalid," the son of Al Walid, who wintered there, and the sea expedition of Bust, the son of Abu Arta.

45 (Mar. 24, 665-Mar. 12, 666);

Theopis AM The Wadit. Abd Al Rachman, the son of Khalid, the son of Al Walid, made a raid and wintered in the land of the Romans, and reached Antakhiya. (Antioch in Pisidia).

¹ This expedition is elsewhere recorded only by the Armenian Selsco, who makes Mu'awiya march to Chalkedon in the 13th of Constanting (653-4).

[&]quot; Son of Khalid' has dropped out of Al

Tab, a best, and I insert it from the Al Athir.

The Syriae fragments published by Dr.
Keldeke (Z.D.M.O. 29, p. 7881.) agree in the date, giving A.S. 970 (Oct. I, 953-Sept. 50, 604).

Al Tab. And in this year was the wintering of 'Abd Al Rachman, the son of Khalid, the son of Al Walid, in the lund of the Romana.

46 (Mar. 18, 666-Mar. 2, 667).

Ibn Wadh. Malikh, the son of 'Abd Allah, the Khath'ami made a raid: and it is said that it was Malikh, the son of Hubaira, the Sakhuni; and he wintered in the land of the Romana

Al Tala. And among the events of this year was the wintering of Malikh, the son of 'Abd Allah," in the land of the Romans; and it is said also El. Nia 46 that this was 'Abd Al Rachman, the son of Khalid, the son of Al Walid; and it is said also that it was Malikh, the son of Hulmira, the Sakhuni.2 And in this year 'Abd-Al Rachman, the son of Khalid, the son of Al Walid, returned from the land of the Romans to Chims (Emesa); and Ibn Uthal the Ansari gave him a poisoned drink, as it is said, and he drank it, and it killed him.

47 (Mar. 3, 667-Feb. 19, 668).

Ibn Wadh. . Malikh, the son of Hubaira, the Sakhuni, made a raid and El Niz 17 wintered in the land of the Romans,

Al Tab. And in this year was the wintering of Malikh, the son of Habaira, in the land of the Romans, and the wintering of Abu 'Abd Al Rachman the Kaini at Antakhiya

48 (Feb. 20, 668-Feb. 8, 669).

Ibn Wadh.; 'Abd A! Rachman the 'Athi made a raid and reached Antakhiya tho black,"

Al Tab. And in it was the wintering of Abu Abd Al Rachman the Kaini at Antakhiya, and the summer expedition of 'Abd Allah the son of Kais, the Fizari, and the raid of Malikh, the son of Hubaira, the Sakhuni, by sea, and the raid of 'Ukba, the son of 'Amir, the Guhani, by sea, with the men of Misr (Egypt) and the men of Al Madina; and over the men of Al Madina was Al Mundhir, the son of Zubair, and over their combined forces was Khalid, the son of 'Abd Al Rachman, the son of Khalid, the son of Al Waliel.

49 (Feb 9, 669-Jan. 28, 670).

Ibn Wadh. Fudhala, the sou of 'Ubaid, made a raid; and by his hands God made captives and carried off many prisoners,

Al Tab. And in this year was the wintering of Malikh, the son of Hubaira, the Sakhuni, in the land of the Romans. And in it was the mid of Fudhala, the sen of Ubaid, upon Garabba; and he wintered at Garabba, and Though AM

El. Nia. 49 8169(7)

Imprio la perfurpe la tenidod.

² Test 'Ubuld Allahi' we may correct from Dig Al Athir and Ilm Wadle .

[&]quot; MSS. 'Finari': we may correct from Um Al Athie and Dm Wadh. .

^{*} I do not know any other anthority for this ejather; if it is resaut to destinguish this Antioch from that mortioned above, Antioch in

^{*} The words 'Khalid, the sou of, are not in the MSS., but are supplied by conjecture in Therbecke's text. Otherwis- we should have a glaring southalletion to the statement of Al Tab. out num. 46.

it was captured by his hands, and he made many prisoners in it. And in it was the summer campaign of 'Abd Allah, the son of Khurz, the Bagli. And in it was the raid of Yazid, the son of Shagara, the Rahawi, by sea; and he wintered at the head of the men of Al Sham. And in it was the raid of 'Ukba, the son of Nafi', by sea; and he wintered at the head of the men of Misr. And in it was the raid of Yazid, the son of Mu'awiya, into Roman territory, till he reached Kustantiniyya; and with him were Ibn 'Abbas, and Ibn 'Umar, and Ibn Al Zubair, and Abu Ayyub the Ansari.

Though AM 0159

Instead of the last sentence Ibn Al Athir has; In this year (and the year 50 is also mentioned) Ma'awiya sent a powerful force upon a raid into the territory of the Romans; and he appointed Sufyan the son of Auf to the command, and ordered his son Yazid to join the raid; and he was disinclined to do so and made excuses, and his father abstained from pressing him. And during their raid the men were attacked by famine and grievous disease.

And, when Mu'awiya heard of his verses, he enjoined him to join Safyan in the land of the Romans; in order that whatever befell the men might befall him. And he went, and with him was a large body of men, whom his father sent with him; and in this force were Ibn 'Abbas and Ibn 'Umar and Ibn Al Zubair and Abu Ayyub the Ansari and others, and 'Abd Al 'Aziz, the son of Ruzara, the Khilabi. And they advanced into the territory of the Romans until they reached Al Kustantiniyya; and the Moslems and the Romans fought for some days, and the battle was severe between them.

Then Yazid and the army returned to Al Sham.

50 (Jan. 29, 670-Jan. 17, 671).

The Wadh. Bust the sen of Abu Arta made a raid; and Sufyan the sen of 'Auf wintered.

Al Tab. And in this year was the raid of Busr the son of Abu Artz.

Theoph. All and Sufyan, the son of 'Auf, the Azdi, into the land of the Romans. And it is said that in it was the raid of Fudhala, the son of 'Ubaid, the Ansari, by sea.

51 (Jan. 18, 671-Jan. 7, 672).

The Wadh. Mahomet the son of 'Abd Al Rachman made a raid; and Theoph AM Fudhala, the son of 'Ubaid, the Ansari, wintered.

Al Tab. And among the events of this year were the wintering of the Nis. 51 Fudhala the son of 'Ubaid in the land of the Romans, and the raid of Busr the olds son of Abu Arta in the summer.

52 (Jan. 8-Dec. 26, 672).

Ibn Wadh,. Sufyan the sen of 'Auf made a raid; and he died and appointed 'Abd Allah, the sen of Masada, the Fizari, to take his place.

doke (non p. 184, note 0) places the expedition of Varid to A.S. 971 (400), but, as that was a time of peace, the date is clearly wrong.

⁴ I omit personal annologes which have no bearing on the expedition.

[&]quot; The Syrba chronicle published by Nől-

Al Tab. And Al Wakidi states that in this year was the raid of Sufyan, El. Nia 53 the son of 'Auf, the Azdi, and his wintering in the land of the Romans; and that he died during the year and appointed 'Abit Allah, the son of Mas'ada, the Fizari, to take his place. And other authorities say: No, the man who wintered in the land of the Romans this year at the head of the men was Busr the son of Abu Arts, and with him was Sufyan, the son of 'Auf, the Azdi. And Theoph AM in the summer of this year a raid was made by Mahomet, the son of 'Abd Nikeph p. 32 Allah, the Thakafi.

Theoph. AM 6165(1)3

53 (Dec. 27, 672-Dec. 15, 673).

Ibn Wadh. Mahomet, the son of Malikh, made a mid; and it is said that Tarsus was taken this year, its captor being Gunada, the son of Aba Umayya, the Azdi.

Al Tab. And among the events of this year was the wintering of Abd El Nic 5400 Al Rachman, the son of Um Al Chakham, the Thakan, in the land of the Romans. And in it Rudus (Rhodes), an island in the sea, was taken; and its capter was Gunada, the son of Abu Umnyya, the Azdi; and he settled the Moslems in it, as recorded by Mahomet the son of 'Umar'; and they sowed seed and acquired flocks and berds in it, which they pastured all round it; and, when men approached, they took them into the fortress; and they had watchmen who gave them warping of anyons upon the sea who wished to make war upon them, and they were on their grand against them. And they were the greatest annoyance to the Romans, and they attacked them on the sea and cut off their ships. And Mu'awiya supplied them pientifully with provisions and pay; and the enemy were afraid of them. Mu'awiya was dead, Yazid, the son of Mu'awiya, removed them.

Ibn Al Athir adds: And it is said that it was taken in the year 60,

54 (Dec. 16, 678-Dec. 5, 674).

Al Tah. And in this year was the wintering of Mahomet, the son of Malikh, in the land of the Romans, and the summer campaign of Ma'n, the son of Yazid, the Sulumi. And in it, as Al Wakidi states, was the capture by Gunada, the son of Abn Umayya, of an island in the sea near Kustantiniyya, called Arwad. And Mahamet, the son of 'Umar, records that the Moslems remained in it for a space, as he says, of seven years, and the commandant was Mugahid, the san of Gabr.

There follows in Al Tubari a long personal story, the substance of which is expressed by Ibn Al Athir in the sentence;

And, when Ma'awiya died, and his son Yazid succeeded to the government, he ordered them to return, and they returned.

[&]quot; Michael the Syrlan records what seems its be the same expedition under the 2nd of Constantino=A6 PS2 (Oct 1, 676-Sept:50, 671) " La Al Wakidh

[&]quot; This were to be a more daplicate of the postipation of khodes resurded under the pre-YOUNG YOUR.

55 (Dec. 6, 674-Nov. 24, 675).

El Ni. 58 Ibn Wadh.. Malikh, the son of 'Abd Allah, the Khath'ami, made a raid and wintered in the land of the Romans.

Al Tab. And among the events of this year was the wintering of Sufyan, the son of 'Auf, the Azdi, in the land of the Romans, as Al Wakidi says; 1 and some of the authorities say; No, the man who wintered in the land of the Romans this year was 'Abd Allah, the son of Kais, the Fizari; and some say; No, it was Malikh, the son of 'Abd Allah.

El, Nac. 55 Though, AM 5166

56 (Nov. 25, 675-Nov. 13, 676).

Et. Nis. 57 Ibn Wadh... Yazid, the son of Mu'awiya, made a raid and reached Al Kustantiniyya; and Mas'ud, the son of Abu Mas'ud, wintered; and the commander by land was Yazid, the son of Shagara, and by sea 'Iyadh, the son of Al Charith.' All these things are also said to have happened in the year 57.

Al Tab. And in this year was the wintering of Gunada, the son of Abu III. No. 34(1) Umayya, in the land of the Romans; and it is said that it was 'Abd Al Rachman, the son of Masud; and it is said that this year Yazid, the son of Shagara, the Rahawi, made a raid by sea, and 'Iyadh, the son of Al Charith, by land.

57 (Nov. 14, 676-Nov. 2, 677).

Theoph. AM

Ilm Wadh. 'Abd Allah, the son of Kais, made a raid.

Al Tab., And this year was the wintering of 'Abd Allah, the son of Kais, in the land of the Romans,

58 (Nov. 3, 077-Oct. 22, 678).

El. Nis. 28 raid; and it is said that 'Amir, the son of Yazid, the Guhani, did so; and Yazid, the son of Shagara, was killed at sea.

At Tab. And this year Malikh, the son of Abd Allah, the Khathami, made a raid into the land of the Romans. And in this year Yazid, the son of Shagara, was killed at sea on a ship, as Al Wakidi says. He says: And it is said that 'Amr, the son of Yazid, the Gahani, was the man who wintered in the land of the Romans; and it is said that the man who made the raid by sea this year was Gunada, the son of Abu Umayya.

Ibn Al Athir. This year Malikh, the son of 'Abd Allah, the Khath-'ami, made a raid into the land of the Romans, and 'Amr, the son of Yazid, the Guhani, by sea; and it is said that it was Gunada, the son of Abu Umayya.

It is hard to reconcile this with the statement under A.H., 52 that Al Wakidi placed Sufyan's death in that year.

^{*} MS. Al Chart. Al Charith is an obvious correction of Houtana; cf. Al Tab. . The name 'Charh' does not take the article.

According to Houtema's text, "It is said

that Y., the sur of S., (made a said) by sea"; but by the change of a point ('kntilla' for 'kila') we get the same as in Al Tab.

^{*} I omit the copula before the verb with MS, C. The printed text must be condered 'it was 'Amiand be was the man who wintered.'

59 (Oct. 23, 678-Oct. 12, 679).

Ibn Wadh. Amr, the son of Murra, the Guhani, 1 made a raid by land, El Na. 58(1) and there was not that year any raid by sea.

Al Tab. And that year was the wintering of 'Amr, the son of Murra, the Gulmai, in the land of the Romans on land. Al Wakidi says: There was not that year any raid by sea. And others say: Not so: Gunada, the El Nic 50 son of Abu Umayya, made a raid by sea.

60 (Oct. 13, 679-Sept, 30, 680).

Al Tab. And this year was the raid of Malikh, the son of 'Abd Allah, upon Sauriyya (Isauria), and the entry of Gunada, the son of Abu Umayya, into Rudus, and his building of the city there, as Al Wakidi says.

CALIPHATE OF YAZID I.

61 (Oct. 1, 690-Sept. 19, 681),

Ibn Wadh. Malikh, the son of 'Abd Allah, the Khath'ami, made a raid in the summer; and this was a raid upon Sauriyya."

CALIPHATE OF AED AL MALIER.

70 (June 25, 689-June 14, 690).

Al Tab... And in this year the Romans rose up and assembled together against the Moslems in Al Sham; and 'Abd Al Malikh made peace with the Thoops. AM king of the Romans on condition of paying him a thousand denurii every Mich. fal. 260; assembly-day, fearing danger from him to the Moslems.

(without date) Chron. of 840 (without date)

75 (May 2, 694-Apr. 20, 695).

Ibn Wadh .. Mahomet, the son of Marwan, made a raid in the summer ; Thoops. AM and the Romans came out against Al A mak, and they were slain by Aban, the son of Al Walid, the son of 'Ukba, the son of Abu Mu'ait, and Dinar, the son of Dinar.

Eb. Nin. 75 Mich. AS 1000 Chrone of 846 AS 1000

Al Tab. Among the events of this year was the mid of Mahomet, the son of Marwan, in the summer, when the Romans came out from before Marash (Germanikeia).

I There can be little doubt that this is the mana as Amir, the son of Yazid, the Gulami. Pader 58, where the Arabs have the Yazid, EL. Nia has Ibn Murra.

^{*} Al Tab, has probably confused Al Wakidi's date for the compution with that for the evacuation; cf ann 53, 54.

² This must be thrown back to 679, airce peace was mad before Marawaya's death (Apr. n. 680).

^{* 6.4.} Priday. Though, 'every day's so Michael!

⁴ d.z. the valleys, the name of a place between Germanikela and Antioch. The MS, has Al A'man, but Hontema's correction is no doubt right, and Al A'mak is the same given by Al Baladhuri (see p. 207); cf. also ann. 112. The Syriac writers call the place the velley of Anticeh."

76 (Apr. 21, 695-Apr. 9, 696).

Yachya, the son of Al Chakham, made a raid in the summer Ibn Wadh, at Marg al Shacham between Maintya and Al Massisa (Mopsouestia),4

Theophi. AM Ibn Al Athir. And this year Mahomet, the son of Marwan, made a #IE97 raid upon the Romans in the region of Malatya.

77 (Apr. 10, 696-Mar. 29, 697).

El. Nia. 77 Theoph AM 6189

Ihn Wadh. Al Walid, the son of 'Abd Al Malikh, made a raid upon Atmar; and his raid was in the region of Malatyn. And Chassan, the son of Al Nu'man, made a raid by sea.3

Al Tab, . And this year Al Walid made a raid in the summer.

78 (Mar. 30, 697-Mar. 19, 698).

Al Tab. And 'Abd Al Malikh sent Yachya, the son of Al Chakham, to make a raid this year.

79 (Mar. 20, 698-Mar. 8, 699).

El. Nis. 79. Theoph. AM 6122 Al Tab. And this year, as it is said, the Romans fell upon the men of Mich. 64, 2517 Antakhiya. Ibn Al Athir adds: and defeated them. (without date),

80 (Mar. 9, 699-Feb. 25, 700),

Al Tab. And 'Abd Al Malikh sent his son Al Walid upon a raid this year,

81 (Feb. 26; 700-Feb. 14, 701).

Al Tab., I was informed by 'Umar, the son of Shabba; he said: I was told by 'Ali, the son of Mahomet; ' he said; 'Abd Al Malikh sent his son 'Uhaid Allah "upon a raid in the year 81; and he took Kalikala (Theodosionpolis-Karin in Armenia).

82 (Feb. 15, 701-Feb. 3, 702).

Ibn Al Athir. And this year Mahomet, the son of Marwan, made a raid upon Arminiya (Armenia) and routed them. Then they asked him for peace, and he granted it to them; and he appointed Abu Shaikh, the son of 'Abd Allah, governor over them, and they acted treacherously towards him and killed him. And it is said also that they killed him in the year 83.

Theoph, AM 6195(f)

According to Yakut Marg Al Slinchen was near America. Similarly El. Nis. (ann. 23) makes Mu'awiya take Ankyra and advance to Marg Al Shaoliani.

^{*} Armenta IV. according to Theoph, .

² This is Houtmus's correction. The MS, her 'Al Bachr (=the sea) the son of Ch. the son of

Al W. made a taid. After this several lines are missing down to AH, 83.

^{*} Better known as Al Madalui, a writer of the early part of the Dth century.

We should probably read 'Alst Allah, since no much unme as 'Ubsid Allah appears among the some of 'Abd Al Malikh.

83 (Feb. 4, 702-Jan. 23, 703).

Du Wadh, . 'Abd Allah also I made a raid and took Al Massisa, and El Nia 83, built a small fortress in it.2 Theorie. All

El. Nis. 83, 84 Theoph. AM 6198 Mich. AS 1015, 1017 Chron. of 846

84 (Jan. 24, 703-Jan. 13, 704).

Al Tab. And in this year was the raid of 'Abd Allah, the son of 'Abd Al Malikh the son of Marwan, into Roman territory; and in it he took Al Massisa. Such is the record of Al Wakidi.

AS 1015

85 (Jan. 14, 704-Jan. 1, 705).

Ibn Al Athir. And this year Mahomet, the son of Marwan, made a raid Theorh. AM into Arminiya and passed summer and winter in it.

CALIPHATE OF AL WALLD I.

86 (Jan. 2-Dec. 22, 705).

Ibn Wadh.. Maslama made a raid and took two fortresses.

El. Nic 86

Al Tab.. Maslama, the son of 'Abd Al Malikh, made a raid into the land of the Romaus.

87 (Dec. 23, 705-Dec. 11, 706).

Al Tab.. And in this year Maslama, the son of 'Abd Al Malikh, made a raid into the land of the Romans; and with him was Yazid, the son of Gubair, and he met the Romans with a great force at Susana (Sision) in the neighbourhood of Al Massisa. Al Walcidi says: This year Maslama met Maimun the Gurgani (and with Maslama were about a thousand fighting men of the men of Antakhiya) at Tuwana (Tyana); and he killed many men among thom, and God took the fortress by his hands (and it is said that the man who made a raid upon the Romans in this year was Hisham, the son of 'Abd Al Malikh); and God took by his hands the fortress of Bulak and the fortress of Al Akhrim and the fortress of Bulas (Pylai') and Kamkim; and he killed of the Musta'ribs of about a thousand fighting men, and carried their children and their women into captivity.

Though, AM 6196

Though, AM 6201

This word seems to show that Ibn Wallh, recorded an expedition by 'Abd Allah in the previous year.

^{*} Though, and the Chronisle of 846, mention the building only. El. Nis and Mich. record the capture and the building under separate years.

Al Tab, omits to mention the result of the assetting, which according to Thooph, was a great defeat of the Araba. A comparison with Though, makes it probable that the subject of the hat clause is not Maslama but Yazid ("AGGo:

³ res Xavrel).

^{*} This neares Hyromian; but we should no doubt read 'Gurgmanni,' the Arabic name for the Mardaites, which is the title applied to Mainure by Al Baladhari (see p. 203).

This seems to be an anticipatory statement, since Al Tab, afterwards records the capture under 88, to which year it is also assigned by the Kutaiba, the surfices extent Arabic historian (d. 884).

^{*} Arabe not of pure birth.

88 (Dec. 12, 700-Nov. 30, 707).

Ibn Wadh., Maslama and Al 'Abbas, the son of Al Walid, made a raid and took Suriya (Isaura !), and Al 'Abbas took Ardaluniya.

Theoph. AM 6201 Nikuph. pp. 43, 44 Mich. AS 1019

Al Tab. And among the events of this year was God's capture by the hands of the Meslems of one of the Roman fortresses called Tuwana in Gumada II. (May 9-June 6), and they wintered at it; and over the army were Masiama, the son of 'Abd Al Malikh, and Al 'Abbas, the son of Al Walid, the son of 'Abd Al Malikh. And Mahomet, the son of 'Umar, Al Wakidi, records that Thur, the son of Yazid, told him on the authority of his masters; he said: The capture of Tuwana was effected by the hands of Maslama, the son of Abd Al Malikh, and Al Abbas, the son of Al Walid; and the Moslems routed the enemy that day, so that they went to their church; then they returned, and the men " were routed until they thought they should never recover from it. And Al 'Abhas remained, and some men with him, among whom was Ibn Muchairiz, the Gumachi; and Al Abbas said to Ibn Muchairiz, "Where are the men of the Kuran who are seeking Paradise?" And Ibn Muchairiz said, "Call to them to come to you." And Al 'Abbas called out, "Ye men of the Kuran!" And they came all together; and God routed the enemy, until they entered Tuwana.

And in it Maslama also made a raid into Roman territory, and by his hands three fortresses were taken, the fortress of Kustantin and Ghazala (Gazelon) and the fortress of Al Akhrim, and he killed of the Musta'riba about 1,000 men, besides carrying their children into captivity and taking

possession of their property.4

Khitab al 'Uyun. And in the year 88 Maslama and Al 'Abbas, the son of Al Walid, made a raid upon Tuwana and wintered at it. And the Romans assembled against them; and they met, and God Most High routed the Romans, and 50,000 of them were killed. And God Most High took Tuwana and another fortress near it with prisoners and spoil.

89 (Dec. 1, 707-Nov. 19, 708).

El. Nis. 39

Throph, AM 020E(1)

Al Tab.. The Moslems in this year took the fortress of Suriya; and over the army was Maslama, the son of 'Abd Al Malikh. Al Wakidi states that Maslama made a raid into the land of the Romans this year, and with him was Al 'Abbas, the son of Al Walid; and they entered it together; then they separated, and Maslama took the fortress of Suriya, and Al 'Abbas took Adhruliyya; and he encountered a force of Romans and routed them. And others besides Al Wakidi say: Maslama went to 'Anunuriya (Amorion) and encountered the Romans there, a large force, and God routed them: and he

slege of nine months.

This is the MS, reading. Housans would read Admilya; of Al Tab ann. 89.

MS. It adds 'the first of it' (May 9), while the Al Athir has Gumeda I. (Apr. 9-May 8). Mich. places the capture in May 708, after a

I bu Al Athir 'the Mosloms."

⁴ The last clause is clearly a duplicate of the notice under the preceding year.

THE ARABS IN ASIA MINOR, FROM ARABIC SOURCES. 193

took Hirakin (Herakleia) and Kamudiya (Nikomedeia ?),4 and Al Abbas made a summer campaign in the neighbourhood of Al Budandun (Podandos).

90 (Nov. 20, 708-Nov. 8, 700).

Ihn Wadh. . 'Abd Al 'Aziz, the son of Al Walid, made a raid and took a El Nis so fortress.

Al Tab. And in this year Maslama made a raid into the land of the Romans, as Mahomet, the son of 'Umar, records, in the neighbourhood of Suriya, and took the five fortresses in Suriya. And in it Al Abbas, the son of Al Walid, made a raid, some say, till be reached Al Arzan," and others say, till he reached Suriya. And Mahomet, the son of 'Umar, says: the account which says 'till be reached Suriya' is right.

Theoph. AM G202(1)

91 (Nov. 9, 709-Oct. 28, 710).

Ibn Wadh. Abd Al Aziz, the son of Al Walid, made a raid,

Al Tab. And in this year, as Mahomet, the son of Umar, and others record, Abd Al 'Aziz, the son of Al Walid, made a raid in the summer: and over the army was Masiama, the son of 'Abd Al Malikh.

92 (Oct. 29, 710-Oct. 18, 711).

Ibn Wadh. . Mahomet the son of Marwan, made a raid.

Al Tab. Among the events of the year was the raid of Maslama, the son of 'Abd Al Malikh, and 'Umar, the son of Al Walid, into the land of the Romans; and three fortresses were taken by the hands of Mashama; and the people of Susana migrated into the interior of the land of the Romans.

93 (Oct. 19 711-Oct. 6, 712).

The Wadh. Al Abbas, the son of Al Walid, and Marwan, the son of El Nic 92 Al Walid, and Maslama made a raid and took Amasiya (Amaseia) and the Theoph AM 0204 fortress of Al Chadid. Mich. AS

Al Tab. And among the events of this year were the raid of Al 'Abbas, the son of Al Walid, into the land of the Romans, and God's capture of Chron. of Sto Sabastiyya (Sebasteia) by his hands. And in it was also the raid of Marwan, the son of Al Walid, into the land of the Romans; and he reached Khangara. And in it was the raid of Maslama, the son of 'Abd Al Malikh, into the land of the Romans; and he took Masa (Amaseia) and the fortress

1023

AS 1021

will, Kullya and Kamuliyah. Kansouliana in Cappadacia L may be meant. Thu Al Athir has 'Kamuniya.' The mention of Herableia (Ponton 7) points to Kikomedeta, but it is circums that its capture should not be recorded by the Greek writers.

Arra should be Arrangue or its chief town, tent this is clearly out of place here.

^{*} The MSS, have signastiyya: I emend from H.S. - VOL. XVIII.

Ibn Al Athir, who odds and Al Marshanain and Too (cf. ann. 96). It is possible, however, that Misthuia is muant (of Thooph, A.M. 6201; Nikeph. p. 48; Chron of 816 A. S. 10211

⁴ cl. Gaugea. Mich. seconds the capture of 'Gargarun' in A.S. 1622. On the other hund, Yakut mentions Khangara, 'a district in the territory of the Romans. CE also sun. 109.

of Al Chadid and Ghazala and Tarchamah in the neighbourhood of Malaxya.

94 (Oct. 7, 712-Sept. 25, 713).

Ibn Wadh. Al 'Abbas and 'Umar, the sons of Al Walid, made a raid.

El. Nist, 94 Thought, AM 6205 Mich. AS 1023 Al Tab. And amongst the events of this year was the raid of Al 'Abbas, the son of Walid, into the land of the Romans, and it is said that in it he took Antakhiya. And in it, as it is said, 'Abd Al 'Aziz, the son of Al Walid, made a raid into the land of the Romans till be reached Ghazala; and Al Walid, the son of Hisham, the Mu'aiti, reached the land of Burg Al Chamam; and Yuzid, the son of Abu Khabsha, reached the land of Suriya.

95 (Sept. 26, 713-Sept. 15, 714).

El. Nis. 03.

Al Tab.. And this year was the raid of Al 'Abbas, the sen of Al Walid, the sen of 'Abd Al Malikh, into the land of the Romans, and God took three fortresses by his hands, as it is said, and they were Tulas, and Al Marzhanain, and Hirakla. And in it Al Wadhdhachi was killed in the land of the Romans, and about 1,000 men with him.

96 (Sept. 10, 714-Sept. 4, 715).

Ihn Wadh. Bishr, the son of Al Walid, made a raid.

Al Tab. And this year, as Al Wakidi says, was the mid of Bishr, the son of Al Walid, in the winter; and, when he returned, Al Walid was dead.

CALIPHATE OF SOLOMON.

Theoph, AM 0200(f) Might AS 1026 Ibn Wadh. Masiama made a raid and took the fortress of Al Chadid, and wintered in the lands of the Romans; and 'Umar, the son of Hubaira, made a raid by sea; and they occupied all between Al Khalig* and Al Kustantiniyya, and they took the city of the Slavs; and Solomon sent them reinforcements under 'Amr, the son of Knis, the Khindi, and 'Abd Allah, the son of 'Umar, the son of Al Walid, the son of 'Ukba.

The W. also has a duplicate account as follows: And Solomon went out in the direction of Al Gazira and took up his abode at a place called Dabik," in

⁴ This is the reacting of the MSS. Gubbl would cond Bargama, which differs only by points. Eargama, however, is the Arabic name for Pergama, which seems quite out of plane here. The capture of Pergamas is recorded by Minhael and the Chronicles of 840 maker A.S. 1927 (710). Theophanes also records it under 716 (A.M. 6208), but, as he makes it contamporancous with Lee's accession, he must man to plane it in 717.

I do the forest of the pigeon.

Since Suriya (Syria, see p. 183, note 4) and Sauriya (Imuria) differ only by a point, it is often impossible to my which is usent; at ann; 90.

⁴ Her Al Athir, 'he took Hirakla and ather

places. He has already recorded the capture of Al Marzhanin and Tim (Tubar) under AH 93 (p. 193, note 3). The hast usine might stand for Deans, which would go well with Schastela, but not with Heraklein, united Heraklein-Kyliners is mount. Another resuling is Dimas. Al Marzhandin — the tree marzhane.

^{*} s.v. the canal. The sum covers the Hellespout, Propentis, and Resports.

^{*} Find Bannary (Hist. Grey, of John Minor, p. 431) identifies the city of the Slave with London near the Cilician gates; but the city here mentioned would even to have been near Constantinople.

[&]quot; MS, Dhanile,

the province of Kinnasrin (Chalkis); and he sent Maslama, the son of Abd Al Malikh, upon a raid into the territory of the Romans, and told him to go to Al Kustantiniyya, and remain before it till he took it. And Maslama went on till he reached Al Kustantiniyya, and remained before it till he had sown and caten of what he had sown; and he entered and took the city of the Slavs. And the Moslems were smitten by searcity, and hunger, and cold; and Solomon heard of the condition of Maslama and his men, and sent them reinforcements under 'Amr, the son of Kais, by land; and he sent 'Umar, the El Nie 97 son of Hubaira, the Figari, to make a raid by sea; and that because the Romans had made an attack upon the city of Ladikiya (Laodikeia), in the province of Chims, and had burnt it, and had carried away some of what was in it. And Umar, the son of Hubaira, reached the canal (khalig) of Al Kustantiniyya.1

97 (Sept. 5, 715-Aug. 24, 716).

Al Tab .. And among the events of this year was the equipping by Thoopia AM Solomon, the son of 'Abd Al Malikh, of the armies intended to march to Al Kustantiniyya, and the appointment of his son David, the son of Solomon, to conduct the summer expedition; and he took the fortress of Al Mara, And in it, as Al Wakidi records, Maslama, the son of 'Abd Al Malikli, made a raid into the land of the Romans; and he took the fortress which had been taken by Al Wadhdhach, the chief of the Wadhdhachiyya. And in it Umar," the son of Hubaira, the Fizari, made a raid by sea upon the land of the Romans, and wintered in it.

Mich AS 1027

98 (Aug. 25, 716-Aug. 13, 717)

Al Tab. And among the events of this year was the sending by Solo- El. Nis 98 mon, the son of 'Abd Al Malikh, of his brother Maslama, the son of 'Abd Al Theoph. AM Malikh, to Al Kustantiniyya; and he told him to remain before it till he Niksph. p. 53 took it or an order from him came to him. And he passed winter and AS 1028 summer there. I was told by Achmad, the son of Zuhair, ou the authority of 'Ali, the son of Mahomet: he said: When Solomon assumed the government, he made a raid upon the Romans; and he stationed himself at Dabik, and sent Maslama in front, and the Romans were afraid or him; and Leo appeared from Arminiya And the patricians said to Leo, 'If you deliver us from Maslama, we will make you king'; and they made a covenant with him. And he came to Maslama and said, 'The people know that you will not make serious war upon them, but will give them a respite, as long as the corn lasts with you: and, if you burn the corn, they will submit.' And he burned it; and the enemy remained, and the Moslems were straitened until they nearly perished. And

I Though in the test these events are satisfied be the summary to 96; we should very probably tend 97, when Ibn W, has already recounted the wrunts of 96 under the Caliphate of Al Walid. This author records the exceptions not under

each year in the marrative, but all regether at the and of main Caliphare.

[&]quot; the Al Ath. The land of the Wadhillies chiyya

Text " Ame. I corrego from the Al Athir-

that happened to the force which had never happened to an army before, until a man was afraid to go out of the camp alone; and they ate the beasts of burden and skins and the trunks and leaves of trees and everything except dust. And Solomon remained at Dabik, and continued there through the winter; and he was not able to send them help till Solomon died.\(^1\) And this year the city of the Slavs was taken. Mahomet, the son of 'Umar, says: 'The Burgan (Bulgariaus) made an attack in the year 98 upon Maslama, the son of 'Abd Al Malikh, and he had few men with him; and Solomon sent him help under Mas'ada or 'Amr, the son of Kais, with a military force; and the Slavs made a treacherous attack upon them; then God routed them, after they had killed Shurachil, the son of 'Abda.

And in this year, as Al Wakidi states, Al Walid, the son of Hisbam, and 'Amr, the son of Kais, made a raid, and some of the men of Antakhiya were cut to pieces; and Al Walid attacked some men in the outlying districts of the Romans, and took many prisoners from among them.

AS 1028(1)

'Abd Al Malikh, made a raid into the land of the Romans, and took the fortress of Al Mara near Malatya.²

99 (Aug. 14, 717-Aug. 2, 718),F

Ibn Wadh. Solomon, the son of Abd Al Malikh, sent his son David to the land of the Romans, and Maslama was remaining quiet before Al Kustantiniyya; and David took the fortress of Al Mara, in the neighbourhood of Malatya.

CALIFFRATE OF UMAR II.

During his government in the year 99 'Amr, the son of Kais, the Khindi, made a raid in the summer.

Theoph, AM 6210 Nikeph, p. 55

Al Tab. And in this year 'Umar, the son of 'Abd Al 'Aziz, sent to Maslama, who was in the land of the Romans, and told him to return from it with the Moslems who were with him: and he sent him some high-bred horses and a large quantity of corn, and he urged the men to go to his assistance. And the number of high-bred horses which he sent to him was, as it is said, 500 horses.

100 (Aug. 3, 718-July 23, 719).

Al Tab. And in this year 'Umar, the son of 'Abd Al 'Aziz, sent Al Walid, the son of Hisham, the Mu'aiti, and 'Amr, the son of Kais, the Khindi, of the men of Chims, to make a mid in the summer.

There is a much longer account of the expedition against Constantinople in the Khital Al 'Uyun; but it would take too much space to translate it here.

³ The Chronicle of 846 makes David take the

fortness of "Antigun" in A. 8, 1028 (Oct. 1, 716 —Sept. 30, 717). For Al Mars of, ann. 33.

⁸ We should perhaps road 98, smoo Ibn W. mentions an expedition of 99 mules the reign of 'Umar.

Ibn Al Athir. In this year 'Umar, the son of 'Abd Al 'Aziz, ordered the men of Taranda (Taranton) to withdraw from it to Malatya; and 'Taranda is in the Roman territory, three days' journey from Malatya; and 'Abd Alfah, the son of 'Abd Al Malikh, had settled the Moslems in it after he had made a raid upon it in the year 83; and Malatya was at that time deserted; and he introduced among them a military force from Al Gazira, to be stationed among them until the snow came down and they returned to their district. And this state of affairs went on until 'Umar succeeded to the government; and he ordered them to return to Malatya and left Taranda unoccupied, through fear of injury to the Moslems from the ensury; and he left Taranda deserted, and appointed as governor of Malatya Ga'wana, the son of Al Charith, one of the sons of 'Amir, the son of Sa'sa'a.

CALIPHATE OF YAZID IL.

102 (July 12, 720-June 30, 721).

Ibn Wadh. Under his government in the year 102 'Abd Al Walid, the son of Hisham, made a raid at the head of the men into the land of the Romans, and encamped at the ford near Antakhiya. And 'Umar, the son of Hubaira, attacked the Romans in Fourth Arminiya, and routed them and took 700 prisoners from among them.

Al Tab. And in this year 'Umar, the son of Hubaira, made a raid upon the Romans in Arminiya, and routed them, and took many men prisoners

from among them-it is said 700 prisoners.2

Ibn Al Athir adds: And in this year Al 'Abbas, the son of Al Walid, the son of 'Abd Al Malikh, made a raid upon the Romans, and took Dalisa (Dalisandos?).*

103 (Jul. 1, 721-June 20, 722).

The Wadh. Al 'Abbas, the son of Al Walid, made a raid; and the men El No. 103 were cut to pieces in detachments. And 'Abd Al Rachman, the son of Solomon, the Khalbi, and 'Uthman, the son of Chayyan, the Murri, made a raid, and encamped against a fortress, and took it.

Al Tab. And in this year Al 'Abbas, the son of Al Walid, made a raid

upon the Romans, and took a city called Rasala.

104 (June 21, 722-June 9, 723).

Ibn Wadh.. 'Abd Al Rachman, the son of Solomon, the Khalbi, made a

According to Theoph. See attack of 'Aid Allah on Taranton in A.M. 6193 (701) was unsuccessful. The occupation of Taranton is placed by Michael in A.S. 1022 (711), and by the Chronicle of \$46 in A.S. 1021 (710). According to both these authorities the capter was Maslame.

[&]quot; Hay Al Athle "and killed 700 prisoners."

The difference between 'kila' lit is said) and 'karala' (killed) is only one of painting.

^{*} See next note.

vvil, Ohsula and Wassla. Ibn Al Athir
 Dazala. Forhaps Oussaila is the place securit;
 but it seems probable that it is the same as that mentioned nucler the previous year under the name of Dalisa (the yourcle are doubt(al)).

raid on the south in the summer; and 'Uthman, the son of Chayyan, the Murri, made a mid upon the north in the summer.

105 (June 10, 723-May 28, 724).

Ibn Wadh. . Sa'id, the son of 'Abd Al Malikh, the son of Marwan, made a raid; then he returned and made a raid upon the regions of the Turks.

Theoph. AM

Al Tab. And in this year was the raid of Sa'id, the son of 'Abd Al Malikh, into the land of the Romans; and he sent out a detachment of about 1,000 fighting men, and, as is recorded, they were all out to pieces.

Ibn Al Athir. And this year Marwan, the son of Mahomet, made a raid upon the south in the summer and took Kuniya (Ikonion) in the land of the

Romans and Khamkh (Kamachos).1

CALIPHATE OF HISHAM.

Khitab Al Uyun. And this year Marwan, the son of Mahomet, made a raid at the head of the forces of Al Gazim and the forces of Al Sham (and he was governor of Al Gazira in the name of Hisham), and with him was Sa'id, the son of Hisham, at the head of the forces of Al Sham; and he entered by the road of Malatiyya and took a fortress called Muwasa by storm, after he had beseiged them and assaulted them with engines. And they asked him to grant a capitulation, and he refused to grant them anything but a surrender at discretion. And, when he had taken it, he decided to kill the fighting men and carry the children into captivity; and he divided them among the Moslems, and destroyed the fortress.

106 (May 29, 724-May 18, 725).

Ibn Wadh. And during his government, in the year 106, Mu'awiya, the son of Hisham, made a raid at the head of the men; and he sent Al Wadh-dbach, the chief of the Wadhdhachiyya, and he burnt the crops and the villages, because the Romans had burnt the pasture lands. And Sa'id, the son of Abd Al Malikh, made a raid upon the north in the summer.

Al Tab. And in this year Sa'id, the son of 'Alai Al Malikh, made a raid

in the summer.

107 (May 10, 725-May 7, 720).

Throph. AM

Du Wadh. Mu'awiya also made a raid.

Al Tab. Maslama, the son of Abd Al Malikh, made a raid by land.

El. Nis. 107 Khitab Al 'Uyun. Maslama, the son of 'Abd Al Malikh, made a raid Thooph. AM upon Kaisariyya (Kaisareia), and that is between Malatiyya and Khamakh AS 1040 (Kamachos), and took it.

of Mich. and Chron. of 846 AS 1057 (Neoknisarota)

There is nothing to show whether the author would place this expedition before or after the death of Yazid (Jan. 724)

Al Tab, makes that a mid upon Cypria, which does not come within the limits of the article.

108 (May 8, 726-Apr. 27, 727).

Ibn Wadh, . Maslama, the son of 'Abd Al Malikh, made a raid in the summer on the south; and 'Asim, the son of Yazid, the Hilali, made a raid in the summer on the north.

At Tab. And in this year was the raid of Maslama the son of 'Abd Al Malikh, until he reached Kaisariyya, a city of the Romans on the borders of Al Gazira; and God took it by his hands.

And in it also Abraham, the son of Hisham, made a raid and took also

one of the fortresses of the Romana.

109 (Apr. 28, 727-Apr. 15, 728).

The Wadle. Mu'awiya, the son of Hisham, made a raid, and with him El No. 108
was Al Battal in command of his advance-guard, and he took Khangara.

The ph. AM
6218

Al Tab. And amongst the events of this year was the raid of 'Abd Allah, the sen of 'Ukba, the sen of Nafi', the Fibri, at the head of a force by sen, and the raid of Mu'awiya, the sen of Hisham, upon the land of the Romans; and he took a fortress in it called Taiba, and some of the troops of Antakhiya in his company were cut to pieces.

110 (Apr. 16, 728-Apr. 4, 729).

Al Tab. And in this year, as is recorded, Mu'awiya, the son of Hisham, Though AM made a raid upon the land of the Romans and took Samala. And in it 'Abd Allah, the son of 'Ukba, the Fihri, made a raid in the summer; and over the sea forces, as Al Wakidi records, was 'Abd Al Rachman, the son of Mu'awiya, the son of Chudaig.

Khitab Al 'Uyan. Mu'awiya, the son of Hisham, made a mid in the summer; and he sent 'Abd Allah Al Battal in command of his advance-guard, and he took a fortress in the territory of the Romans, and in it some men were cut to pieces by them; and Mu'awiya, the son of Hisham besieged*

111 (Apr. 5, 729-Mar. 25, 730).

Ibn Wadh. Mu'awiya, the son of Hisham, made a raid in the summer upon the north, and Said, the son of Hisham, made a raid in the summer

upon the south.

Al Tab. And among the events of this year was the raid of Mu'awiya, the son of Hisham, in the summer upon the north, and the raid of Sa'id, the son of Hisham, in the summer upon the south until he reached Kaisariyya-Al Wakidi says: In the year 111 'Abd Allah, the son of Abn Maryam, made a mid at the head of the sea-forces; and Hisham appointed Al Chakham, the

The Al Ath. adds: 'and that is a celebrated city.' He also records under this year the raid recorded nucler 107 by Al Tab... 100 ann 93.

3 vl. Tains : possibly to be identified with ' readorpose 'Areans (Theoph. A.M. 6219).

^{*} As there are no points in the MS, the name might also be read 'Gangra,' Mich. records the capture of Gangra under A.S. 1042 (731). Cf.

⁴ The name has fallen out. Perhaps it is Nikaia, the siege of which is remarked by Mich. under A.S. 1042 (731).

son of Kais, the son of Makhrama, the son of 'Abd Al Muttalib,' the son of 'Abd Manaf, to command all the men of Al Sham and Misr.

112 (Mar. 26, 730-Mar. 14, 731).

Ibn Wadh., Mu'awiya, the son of Hisham, made a raid upon the Romans; and he did not succeed in entering their territory, but remained at the frontier at Al 'Amk." in the district of Mar'ash.

Theoph, AM 8222 Mich. A8 1042 Al Tab.. And among the events of this year was the raid of Mu'awiya, the son of Hisham, in the summer; and he took Kharshama (Charsianon) and burnt Farandiyya in the district of Malatya.

Khitab Al 'Uyun. And this year 'Abd Al Wahhab, the son of Bukht, was killed while in company with Al Battal, in the land of the Romans; and that because the men were scattered from Al Battal and put to flight; and 'Abd Al Wahhab. advanced towards the enemy and mingled with the host and was killed, and his horse was killed.

113 (Mar. 15, 731-Mar. 2, 732).

Al Tab.. And among the events of this year was the death of 'Abd Al Wahhab, the son of Bukht; and he was with Al Battal 'Abd Allah in the land of the Romans. And Mahomet, the son of 'Umar, records on the authority of 'Abd Al 'Aziz, the son of Umar, that 'Abd Al Wahhab, the son of Bukht, made a raid with Al Battal in the year 113, and the men were scattered from Al Battal, &c. (the rest as in Khit, Al 'Uyun, ann. 112).

And among the events was the raid of Mu'awiya, the son of Hisham, into the land of the Romans; and he stayed on the frontier in the district of Mar'ash and returned.

114 (Mar. 3, 732-Feb. 20, 733).

Iba Wadh.. Mu'awiya, the son of Hisham, and Maslama, the son of Abd Al Malikh, made a raid.

El. Nic. 114(3) Theoph. AM 8224

Al Tab. And among the events was the raid of Mu'awiya, the son of Hisham, upon the north in the summer, and the raid of Solomon, the son of Hisham, upon the south in the summer; and it is recorded that Mu'awiya, the son of Hisham, smote the suburbs of Akran (Akroinon), and that 'Abd Allah Al Battal and Constantine met with their forces; and he routed them and took Constantine prisoner. And Solomon, the son of Hisham, reached Knisariyya.

115 (Feb. 21, 733-Feb. 9, 734).

Ibn Wadh. Mu'awiya and Solomon, the sons of Hisham, made a raid, and over the advance-guard was 'Abd Allah Al Battal; and he met Constantine and took him prisoner and routed the Romans.

Al Tab., And among the events of this year was the raid of Mu'awiya, the son of Hisham, upon the land of the Romans.

⁹ The text of Al Tak has Al Muttalib. I ² f.z. the valley; see ann. 75 and note. inner! 'Abd from the Al Athir.

Khitab Al 'Uyun. Mu'awiya the son of Hisham, made a mid in the summer, and with him were the men of Al Sham and the men of Al Gazara. and 'Abd Allah Al Battal. And, when the Moslems and the Romans met, and over the forces was Abd Allah Al Battal the Romans were routed, and the Moslems fell upon them and unde great slaughter, and took many captives, and took possession of their cump and made spoil of their property.

116 (Feb. 10, 734 Jan. 30, 735).

Ibn Wadh. . Mu'awiya, the son of Hisham, made a raid.

Al Tab. And among the events of this year was the raid of El Kis 116 Ma'awiya, the son of Hisham, in the summer, upon the land of the Thooph AM Romans.

117 (Jan. 31, 735-Jan. 19, 736).

Ibn Wadh. . Mu'awiya and Solomon, the sons of Hisham, made a raid. Et Nia 117 Al Tab. And among the events of this year was the raid of Mu'awiya, Theoph AM the son of Hisham, upon the north in the summer, and the raid of Solomon, the son of Hisham, the son of 'Abd Al Malikh, upon the south in the summer in the neighbourhood of Al Gazira; and he scattered his detachments over the land of the Romans.

118 (Jan. 20, 736-Jan. 7, 737).

Al Tab. Among the events was the raid of Mu'awiya and Solomon, El Nis US the sons of Hisham, the son of Abd Al Malikh, upon the land of the Though AM Romans.

119 (Jan. 8-Dec. 28, 737).

Al Tab. . Among the events was the raid of Al Walid, the son of Al Ka'ka', the 'Absi, upon the land of the Romans.

120 (Dec. 29, 737-Dec. 17, 738).

Al Tab . Among the events was the raid by Solomon, the son of Hisham, Thomps, AM the son of 'Abd Al Malikh, in the summer, and his capture, as is recorded, of Sindira (Sideronn).

121 (Dec. 18, 738-Dec. 6, 739).

Ibn Wadh. . Maslama, the son of Hisham, reached Malatya. Al Tab. Among the events was the raid of Maslama, the son of Hisham, the son of Abd Al Malikh, upon the Romans; and in it he took Matamir,

122 (Dec. 7, 739-Nov. 25, 740).

Ibn Wallh . Solomon, the son of Hisham, made a raid upon the district Theoph. AM of Malatya

From this point down to 121 the text of The Walls, is defective.

Al Tab. In this year 'Abd Allah Al Battal was killed with a force of Moslems in the land of the Romans.

Khitab Al 'Uyun. Al Battal, the son of Al Clussain, (his name was 'Abd Allah) and Constantine met with large forces; and God Most High routed them, and Constantine was taken prisoner. And Al Battal advanced with the captives, and he was attacked in the rear and killed, and with him was killed Malikh, the son of Shu'aib.

Ibn Al Athir. In this year Al Battal (and his name was 'Abd Allah Abu'lChusain, the Antakhi) was killed with a force of Moslems in the land of the Romans; and it is said also that it was in the year 123.

123 (Nov. 26, 740-Nov. 14, 741).

El Nie 123 Ibn Wadh. Solomon, the son of Hisham, made a raid in the summer.

124 (Nov. 15, 741-Nov. 3, 742).

El No. 124 Ibn Wadh. . Solomon, the son of Hisham, made a raid, and he mev Leo, the Emperor of the Romans, and Artiyas (Artavazd); and he returned, and there was no battle between them.

Al Tab. And in this year Solomon unde a raid in the smumer, and he met Leo, the king of the Romans, and carried off captives and spoil.

125 (Nov. 4, 742-Oct. 24, 743).

Though AM Ibn Wadh. Al Ghamr, the san of Yazid, the son of 'Abd Al Malikh,

Al Tab. . Among the events was the raid by Al Nu'man, the son of Yazid, the son of 'Abd Al Malikh, in the snmmer.

CALIFHATE OF AL WALTD II.

The Al Athir. This year the Romans came out to Zibatra, and that is an ancient fortress; and it had been taken by Chabib, the sen of Maslama, the Fibri; and the Romans demolished it at that time; and it was rebuilt without strength; and the Romans demolished it again in the days of Marwan, the sen of Mahomet, the Ass. . . And in this year Al Walid sent his brother, Al Ghamr, the sen of Yazid, to make a raid.

¹ El. Nia, 'the son of Leo'; and this modernamly right, since Leo died in June 741.

² Petween Melitens and Samesota and Al Chalath (see p. 208) according to Yakut. Perhaps it should be identified with Debs (mod. Tehebat). Aba'l Fide (Tab. Syr. op. 28, 20) places. Zibatm. two days' journey south of

Melliens and in let. 36° 50°, long, 61° 20°, 2 °The ass of Al Gazira' was a nickname of Marwan II.

⁴ the Wadh, is therefore wrong in saufflying this raid to the reign of Hisham, who in fact died in Feb. 749.

EXTRACTS FROM AL BALADHURI.

The Affair of the Unragima,1

And in the days of Ibn Al Zubair, after the death of Marwan, the son of Cr. p. 189 Al Chakham, when 'Alad Al Malikh was seeking the auccession to the Caliphate, . . . and was calling for the help of the men to go to Al Irak to fight against Al Mus'ab, the son of Al Zubair, a Roman army went out to the mountains of Al Lukham (Amanos) under one of their generals; then they went to Lubman (Lebanon), where was collected a large force of the Guragima and Nabataeans and rumway slaves of the Moslems. And 'Abd Al Malikh was compelled to make peace with them on condition of paying 1,000 denarii overy assembly-day; and he made peace with the Emperor of the Romans for the amount which he was to pay him in order to prevent him from fighting against him, and because he was atraid he would go out to Al Sham and conquer it. . . . And this was in the year 70, And Maimun the Gurgunami was a Roman slave bolonging to the sons of Um Al Chaklam, the sister of Mu'awiya, the son of Abu Sufyan, and they were Thakans; and by birth indeed he came of the Guraginia, so that he joined them and went out to Mt. Lubnan with them. And 'Abd Al Malikh heard that he was a man of prowess and valour; and he asked his masters to set him free, and they did it; and he gave him command of a military force and sent him to Antakhiya; and he made a raid upon Al Tuwama in company with Masiama. Ct p. 191 the son of 'Abd Al Malikh, (and he was at the head of 1,000 of the men of Antakhiya), and he was nurtyred after showing distinguished courage. And 'Abd Al Malikh sent a large army to make a raid upon the Romans in order to exact vengeance for him.2

The Frontier of Al Sham (Syria).

I was informed by some elders of the inhabitants of Antakhiya: they said: The frontier of the Moslems in Al Sham in the days of 'Umar and 'Uthman (God be gracious to them) and the succeeding sovereigns, was Antakhiya and other cities, which Al Rashid called "Awasim"; and the Moslems used to raid the country beyond just as now they raid the country beyond Tarsus. And between Al Iskhandaruna (Alexandria by Issos) and Tarsus the Romans had fortresses and armour-stores like the fortresses and armour-stores by which the Moslems pass at the present day. And sometimes their inhabitants left them and fled into the territory of the Romans

I for Murdaites.

I This amount is at variance with that of Al Tab., at least according to the most abvious meaning of that willing words, for he ordalaly sworm to tepresent Maintan as being on the Ruman side. The occurat of Theophanes (dra-

orpanious Mucalpit sal ABail the Thorne bid the marker row departurbleron experied were re-Managur art Managury (woonly with Al liste-

F i.e. defences.

in fear; and sometimes Roman fighting men were moved into them to occupy them. And it is said that Herakleies brought men with him and stationed them in those cities, when he retired from Antakhiya, lest the Moslems should come and colonize the land between Antakhiya and the territory of the Romans. there is a difference as to who was the first to pass the Cates (these are the Gates of Baghras (Pagrai)). And some say; They were passed by Maisara, the son of Masrak, the 'Absi, who was sent by Abn 'Ubaida, the son of Al Carrach; and he met a Roman force accompanied by some Mustariba from Ghassan and Tanukh and Iyad, who were going to join Herakleios; and he attacked them and slow a large number of fighting men from among them. Then he was joined by Malikh Al Ashtar, the Nakhari, with reinforcements from Abu Ubaida, who was at Antakhuya. And others say: the first who passed the Gates was Umair, the son of Sa'd, the Ansari, when he was sent on the matter of Gabala, the son of Al Aiham.

And Abu'l Khattab the Azdi says; I have heard that Abu 'Ubaida himself made a summer raid and passed by Al Massiss and Tarsus; and the population of these places and the neighbouring fortresses emigrated; and he passed through the Cates, and his raid extended as far as Zamla 1 And unother account says: he sent Maisara, the son of Masruk, and he reached Zanda.

I was informed by Abu Salich Al Farran, who had it from a man of Dimashk (Damaseus) called 'Abd Allah, the son of Al Walid, who had it from Hisham, the son of Al 'Az, who had it from Ubada, the son of Nusa, as Abu Salich thinks; he said; When Mu'awiya made a raid upon 'Ammuriyya in the year 25, he found the fortresses between Antakhiya and Tarsus deserted; and he stationed in them a force taken from the men of Al Sham and Al Gazira and Kinnasrin, until he returned from his raid; then a year or two years afterwards he sent Yazid, the son of Al Chur, the 'Absi, on a summer raid; and he gave him orders, and he acted accordingly, and the officers did his bidding. And this man said; And I found in the book of Aug. 23, a51-the raids of Mu'awiya that he made a raid in the year 31 in the district of Aug. 11, 552 Al Massisa, and reached Daraullyya ; and, when he went on the expedition, he did not pass by any fortress between him and Antakhiya without destroying it.

And I was informed by Mahomet, the son of Sa'd, on the authority of Al Wakidi and others: he said: In the year \$4 'Abd Allah, the son of 'Abd Al Malikh, the son of Marwan, made a raid in the summer, and he entered by the Gates of Antakhiya; and he came to Al Massisa and built its fortress upon its old foundations. And he planted in it a colony taken from the army, among whom were 300 men, whom he had selected from among those possessed of valour and distinguished courage; and the Moslems had not

(if m 18)

CL p. 183

Cf. p. 101

¹ Yakur mentions Zaindan near Mayanguatia and quotes Khalifa, the son of Khayyat, or mording a mid apon it by "Abit Allah the son of So'd the son of Abn Sarch la the year 31

² Perhaps we should read Adhirallyya or Ardaluniya (see p. 192). Dorylaion seems impossible, though that is the name remaily represented by Durantiyya.

colonized it before that time. And he built a mosque in it close to the hill of the fortress. Then he went on with his army till he made a raid upon the fortress of Sinan and took it; and he sent Yazid, the son of Chanin, the Tai, the Antakhi; and he made an incursion and then returned to him. And Abu'l Khattab the Azdi said. The first in Al Islam who built the fortress of Al Massisa was 'Abd Al Malikh, the son of Marwan, acting through his son, 'Abd Allah, the son of 'Abd Al Malikh, in the year 84 upon its old foundations; and the building and garrisoning were completed in the 'Aziz, journeyed till he came to the grammy of Al Massisa; and he wished to destroy it and to destroy the fortresses between it and Antakhiya. And ho said, "I am atraid of the Romans besieging the inhabitants of it." And the men told him that it had been colonized in order to keep the Romans who were in it away from Antakhiya; and, if he laid it waste, there would be nothing to stop the enemy until they came to Antakhiya. And he gave up the idea and built a general mosque for the inhabitants in the district of Khafarbayya. . . , He said : Then Hisham, the son of 'Abd Al Malikh, built the suburbs; then Marwan, the son of Mahomet, built the booths on the east of the Gichan (Pycamos), and round it he built a wall, and set up a wooden gate in it and dug a trench. . . .

The Frontier of Al Gazira (Mesopotamia).

They said: When 'Uthman, the son of 'Affan, (God be gracious to him) became Caliph, he wrote to Mu'awiya, appointing him Wali of Al Sham; and he made 'Umair, the son of Sa'd, the Ansari, Wali of Al Gazira; then he superseded him, and united Al Sham and Al Gazira and their fortresses in the hands of Mu'awiya. And he ordered him to make a raid upon Shimshat (Samosata), and that is in Fourth Arminiya, or send someone else to make a raid upon it. And he sent thither Chabib, the son of Maslama, the Fihri, and Safwan, the son of Mu'attal, the Sulami: and they took it some days after

See Tonnachek, Zur Historiaden Topogr. v. Kleinarien, p. 71 (Winner Akal, Sitzungsbor, St. 126).

Near Mepropositia perceding to Yakut.

From Al Bah p. 159 it appears that this place was cless to M4. Amanos

they had encamped before it on the same terms as the capitulation of Al Ruha (Edessa); and Safwan remained in it, and there he died at the end of the Caliphate of Mu'awiya. And it is said: No, the man who made the raid upon it was Mu'awiya himself, and Hadhan with him; and he made Safwan Wali of it, and he settled in it and died there.

And they said: Chabib, the son of Maslama, made a raid on the fortress of Khamkh after the capture of Shimshat, and could not take it. And Safwan made a raid upon it, and did not succeed in capturing it. Then he made a raid upon it in the year 59; and that is the year in which he died; and with him was 'Umair, the son of Al Chubab, the Sulami; and 'Umair mounted the wall and never coased fighting upon it alone until the Romans retired, and he gloried in this and was glorified for it. Then the Romans recovered it, and Maslama, the son of 'Abd Al Malikh, took it;' and it never ceased being taken and being recovered by the Romans.

Malatiyya. And they said: 'Iyadh, the son of Ghanm, sent Chabib, the son of Maslama, the Fibri, from Shimshat to Malatiyya, and he took it; then the gates were shut. And, when Mu'awiya became Wali of Al Sham and Al Gazira he sent Chabib, the son of Maslama, thither, and he took it by storm; and he settled a colony of Moslems in it with an administrator. And Mu'awiya came to it when he wished to enter Roman territory; and he garrisoned it with a force taken from the men of Al Sham and Al Gazira and others. And it was on the road of the summer expeditions. Then its inhabitants migrated from it in the days of 'Abd Allah, the son of Al Zubair, and the Romans came out and pulled it down; then they left it, and some

Armenian and Nabatean Christians settled in it.

And I was informed by Mahomet, the son of Sa'd, on the authority of Al Wakidi in his tradition; he said: The Moslems settled in Taranda after 'Abd Allah, the son of 'Abd Al Malikh, had made a mid upon it in the year \$3; and they built houses in it: and it is about 3 days' journey from Malatiyya, in the territory of the Romans; and Malatiyya was at that time deserted, there being no one in it except some of the subject-peoples, Armenians and others. And some scouts from the army of Al Gazira used to come there in the summer and remain in the town until the winter came on ami the snow fell; and, when this happened, they withdrew. And, when 'Umar, the son of 'Abd Al 'Aziz, (God be gracious to him) succeeded to the government, he removed the population of Taranda against their will; and this was because he feared danger to them from the country.

Then he settled them in Malatiyya, and laft Taranda deserted; and he made Ga'waum the son of Al Charith, one of the sons of 'Amir, the son of Sa'ssi'a, Wali of Malatiyya.

They said: And 20,000 Romans went out in the year 123 and encamped against Malatiyya; and the inhabitants shut their gates, and the women mounted the wall with turbans on their heads, and fought. And a messenger

Cf. p. 197

Theoph. records live entire under AM 6200 (711). Another captain in 723/4 is toocided by Day Al Athir (above, p. 128)

from the inhabitants of Malatiyya went out to ask for help, and the courier rode on until he came to Hisham, the son of Abd Al Malikh, who was at Al Rusafa (Resapha); and Hisham despatched the men to Malatiyya. Then the news reached him that the Romans had withdrawn from it, and he called the messenger and told him; and he sent with him some horsemen to keep guard in it. And Hisham conducted a raid himself; then he came down to Malatiyya, and stayed in it until the building was completed.

And they said: Abu'Uhaida, the son of Al Garrach, when he was at Maning (Hierapolis), sent Khulid, the son of Al Walid, to the district of Marash; and he took the fortress upon condition of the people migrating. Then he left it deserted; and Sufyan, the son of 'Auf, the Ghamdi, when he made a raid upon the Romans in the year 30, started from before Marash, and marched Sept 4, 650-And Ma'awiya built the city of Aug. 23, 651 through the territory of the Romans. Marash, and stationed a military force in it. And after the death of Yazid, the son of Murawiya, the Roman attacks upon them increased, and they withdrew from it; and 'Abd Al Malikh made pence with the Romans after the death of his father Marwan, the son of Al Chakham. . . . And in Theoph AM closing, 50ksph. p. 3025 the year 74 Mahomet, the son of Marwan, made a raid upon the Romans, and which tall 20 all the collections (without substitute) broke the peace. And in the year 75 Mahomet, the son of Marwan, also made a summer raid; and the Romans came out from before Marash to Al A'mak' in Gumada I, and the Moslems overcame them; and their commander was Aban, the son of Al Walid, the son of 'Ukba, the son of Abu Mu'ait, and with him was Dinar, the son of Dinar, a mauli3 of 'Abd Al Malikh, the son of Marwan, and he was governor of Kinnasrin and its territory. And they met in the valley of Marash and engaged in a stubborn fight, and the Romans were routed, and the Moslems pursued them, slaying and taking prisoners. And this year Dinar met a Roman force at the bridge of Yaghra, which is about 10 miles from Shimshat, and defeated them. Then Al Abbas, the son of Al Walid, went to Mar'ash, and stayed there and fortified it, and removed the men into it. And in the days of Marwan, the son of Mahomet, when he was occupied in fighting against the inhabitants of Chims, the Romans came out and besieged the city of Mar'ash, until its inhabitants capitalated on condition of being allowed to migrate. And they went towards Al Gazira and the province of Kinnasrin with their families. Then they destroyed it. And Marwan's governor over it at that time was Al Khauthar, the son of Zufar, the son of Al Charith, the Khilabi; and the Emperor at that time was Constantine, the son of Leo. Then, when Marwan had finished the affair of Chins, and had destroyed as wall, be sent an army

DE 10 100

¹ See p. 189, note 5.

¹ Aug. 18-Sept. 26, 691. The Syman writers place the buttle to AS 1006 = AH 70, in which Gum. 1 = Aug. 17 Sept. 15, 096.

A Lat above or freedmiss.

[.] Perhaps the bridge over the Singas. This, however, according to Esepert's map is 25. Homan miles from Samuela. There is a smaller river

about II miles from Samounts, which may purhaps to mount. The lake Al Yaghra war the Syrun Gates (Tomaschek p. 74) is of comme out of the question. Abull Fida (Tab. Syr. p. \$53) makes the river Al Yaghrs a tributary of a river which flows into the Lake of Anticoh. but no such river poses anywhere usus Rattameta.

to build Marash; and it was built and re-founded. And the Romans came out during the civil war and destroyed it.

They said: And the fortress of Al Chadath1 was among those that were taken in the days of 'Umar, its captor being Chabib, the son of Maslama, in the name of 'Iyadh, the sen of Ghanm; and Mu'awiya restored it after that. And the sons of Umayya called the gute of Al Chadath 'Al Salama Al Taira,' because the Moslems were cut to pieces in it; and that was Al Chadath, as some men say. And some say: A young (chadath) lad with his companions met the Moslems at the gate, and fought against them; and it was called the gate of Al Chadath. And in the time of the civil war of Marwan, the son of Mahomet the Romans came out and destroyed the city of Al Chadath, and removed the said: And Malikh, the son of 'Abd Allah, the Khath'ami, who was called 'King (malikh) of the summer raids' and was one of the men of Filastin (Palestine), made a raid upon the territory of the Romans in the year 46, and carried off much spoil. Then he retired; and, when he was about 15 miles from the gate of Al Chadath, at a place called Al Rahwa, he stayed there three days and sold the spoil and divided the captured arrows; and that Al Rahwa was called Rahwa Malikh. They said : And Marg 'Abd Al Wachad was a pasturage reserved for the horses of the Moslems. And, when Al Chadath and Zinatra were built, they had no need of it, and it was sown. They said: And Zinatra was an old Roman fortress; and it was taken at the same time as the old fortress of Al Chadath, its captor being Chabib, the son of Maslama, the Fibri. And it stood until the Romans destroyed it in the days of Al Walid, the son of Yazid; and it was rebuilt without strength; and the Romans encamped before it in the days of the civil war of Marwan, the son of Mahomet, and razed it to the ground.

E. W. BROOKS.

(M. Tr. 185

A Between Melitens and Samousta and Germanikels according to Yakut.

I fee the meanable security."

So the MSS.: de Gooje would substitute 'Zibatra,' which differs only by a point and is the form given by Bu Al Athir (see p. 202).



ADDENDUM.

P. 208, Note 3.—Zibatra is no doubt the Sozopetra of Kedrenos (2, p. 130); but, as there seems to be no earlier authority for this name, it is perhaps only a Hellenization of Zibatra

ON SOME KARIAN AND HELLENIC OIL-PRESSES.

This paper is an attempt to interpret certain stones, which have come to light recently on ancient sites in Karia, as parts of ancient oll-presses, on the ground that they are well adapted to fulfil certain purposes which are still essential to the modern native process of oil extraction in that part of Asia Minor and in the adjacent islands. The inference is that the ancient process closely resembled the modern in the principal features which are recounted below.

I.

The Modern Method of extracting clive oil consists of the two processes of grinding and pressing.

In the most primitive mode of grinding which is still in use, the clives are crushed either on a flat stone by a roller, or in a stone trough by a milistone rolling on its edge. In more modern grinders two mill-stones are used, which revolve in a circular trough, as in the grinding of kaolin or cement. The process of grinding seems never to have varied, except as regards the power which is employed; horses having been substituted for men, and steam for horses. In Algeria and Tripoli the circular trough goes back at least to Roman times.

The crushed olives are called **upphpa*, a term which properly refers to the broken kernels. The **upphpa* is exposed to the pressure in bags of hair-cloth, which in large presses are piled one upon another, after being well drenched with hot water. In the ordinary process, each bag is pressed twice, and is drenched again with hot water in the interval, to facilitate the extraction of the oil. Owing to the supply of water which the process demands, oil-presses are generally established near a well or a spring.

The simplest oil-press, which is still in use in many of the Turkish villages in Anatolia, consists only of a stone or wooden trough in which the bags of wupnea are placed, with a wooden plank above them, on which men mand to press out the oil. The trough is of oblong form, and is furnished with a spout by which the oil runs into a wooden tank. Similar troughpresses, cut in the rock, are common in many parts of Palestine, and almost

¹ K.g. in the Tripoliter off-mills described below, p. 215.

² For Alguria: cf. Tranct, L'Afrique Romeron I p. 288: A Tripolitan example in

published as a laver by H. SWAINSON COWPER, Antiquery, Feb. 1896. = Hill of the Granes (1897), p. 131.

indistinguishable from the wine-presses. There is a good example among the old olive-trees at Gethsemane.

Much more effective and elaborate presses, however, are in use in the islands and in some parts of the mainland; and several stages of advance can be traced, leading to the steam and hydrantic presses which have lately been introduced in Leabos and elsewhere to meet the increased crops of olives.

In the common screw press which may be seen in most parts of the Levant, ten or twelve bags of \(\pi\tilde{p}\gamma\) are piled between two wooden plates, of which the lower is fixed while the other is brought down upon the pile by the screw. The lower plate, or press bed, is covered by a shallow iron trough, and in some cases is itself of solid iron. The screw is still often of wood, though




Fig. 1.—On Press encentry is use at Angledera in Karyanos.

[The presided and maght-done are madeded.]

first by means of single levers set in the screw-head; afterwards, as the work proceeds and more power is required, by auxiliary levers which are attached to the first by a rope, and turn on a second shaft at a little distance from the press. In a Cretan press with iron screw, seen by J.L.M. at Ag. Theodoro in Selino Province in 1893, a regular tackle was used instead of an auxiliary lever.

In the presses above described, the head of the screw bears directly upon the upper plate of the press, as in a hand printing press. But a simpler and probably very archaic example is still in use, in which the screw acts on the

processes now in use in Palestine, Terstham, Le. p. 338-9,

¹⁷ Mican vi 45; Benzinana, Hebridache Architalogie, p. 212; Taiarhan, The Landanof the Book, p. 207; and for the more claimate.

plate indirectly, and with increased effect, by means of a long lever. An example (Fig. 1) seen at Arginunta in Kalymnes will serve to illustrate this type.

The press is set near the wall of the house, and consists of a large stamplock, with a circular channel in its upper surface (of smaller diameter than the ancient press-beds described below) by which the expressed oil runs off into its tank. In the wall is a large square hole, to serve as fulcrum for the smaller end of a squared tree-trunk, which forms the beam of the press. The upper side of the beam-end is fashioned so as to offer a good surface to the upper side of the hole, in every position of the moving beam. The larger end of the beam is traversed vertically by a screw-hole, in which the great wooden screw travels, with free point upwards, and lever-fitted shank downwards. The wide head of the screw carries a perforated board, from which a large block of stone is suspended by wooden tenons dovetailed into morrised sockets in its sides. The head of the screw revolves freely beyond the board in a cavity in the upper surface of the stone.

Consequently, when the apparatus is adjusted above a pile of bags of \u2224 vep\u0394va, a forward turn of the screw lifts the stone from the ground, and brings its full weight into play at the end of the long lever. This arrangement, though the maximum pressure is reached at once, when the stone is lifted, and can never be very great, is free from the danger of excessive strain, to which a timber-frame press is liable, in which unlimited pressure can be applied directly by the screw.

Such oil-presses were formerly common in Kalymnos, but only two survive. In the figure (Fig. 1) the whole of the woodwork is drawn from that of the modern press of Arginanta; but the bed of the press is that from Emperio.

An almost identical press is described by Carsten Niebuhr (Reisen 1, p. 151, Pl XVII, D.) as being in use in Egypt; the only difference being that the solid beam is replaced by a substantial box (practically a hollow girder), which is filled with stones to give additional weight.

II.

The Ancient Method closely resembled that which is still in use, as may be inferred from the literary sources, and from the following fresh data.

(1) Monolithic troughs for grinding the olives are to be seen in the Milesian territory, e.g. two seen by W. R. P. (22 Sept., 1893) on the read between Yeronda (Branchidae) and Akkaui (v. map*). But they have not been noted near the oil-presses of Karia and Kalymones which are described below, though they are an essential part of the apparatus for every known process of extraction. It is curious also that no presses have been seen

I W. R. P. writes from Kalymnes (31 Oct. verted into a more modern type. 1896) that even this example has been con-

associated with these troughs, but it is possible that some of them may represent the prototype of the Anatolian tread-press described above; on the other hand, the press-beds may have been of wood. These Milesian troughs are found in a region which is now quite denuded of its olive-trees, on sites which are so thickly strewn with pottery that they must have been occupied during a long period. Unfortunately no pottery of characteristic styles has yet been noted on these sites, and much might very well be medieval.

(2) Actual oil-presses have been observed on several sites: the most important are as follows:—

(a) On a roughly fortified summit in the Monteshe valley on the north-east side of Latmos, a large flat stone was found by W. R. P. in situ at a short distance from the wall of the building or enclosure. The dimensions of the block, which is represented in figure 2, were L. 25 m. x B. 24 m. In the middle of one of the shorter sides a rectangular projection was left, level with the top of the block, about 0.4 m. broad, and standing out 0.2 m from the side. In the top of this a deep channel of 0.15 m, diameter was cut, so that the projection served as a spout. The channel was continued to meet a




Fig. 2.—Parse Ren from the Menteric Valley in Kama.





Fig. 8.—Perso Bed from Senam et-Ragud in Tai-



Fig. 4.—Press Bed from Kurosio in Kaltures.

circular channel of the same dimensions cut in the top of the block, nearly in the centre, but a little towards the side of the radial channel. The spout and channel were directed away from the wall of the enclosure above mentioned; and in this wall, exactly in the same line with it, was a horizontal hole 0.60 m high, 0.40 m, wide, and 0.36 deep from the face of the masonry. Its structure shows that it was intended to hold a large beam, and that the beam was intended to resist a thrust either from above or from below. In Fig. 3 is represented an essentially similar stone from a Roman site Senum el-Ragual in the African Tripoli; figured by H. Swainson Cowper, Antiquery, Feb. 1890. = The Hill of the Graces (1897), p. 149, and described by him as an 'altar' of prehistoric date.

It can hardly be doubted that we have here the press-bed of an ancient olive-press. The bag of crushed olives, which must in this instance have been



m reck cut galvenny (of, defents I and 2); & tower with door on the linest side a., presectors; d. presected (cf. Fig. 4 above); Fig. 5.—Hellerto Ponteres and Outques of Eurobio in Kartwerk

Diskild.—1. elevation of the root and jumb of the externey, a to left on entering with lar-sacket at 2, plan of the same gateway; 3, plan of the decrease of the tower A: 4, second Richard Spin and Spin e, eletora into which the oil should flow from the press.

mentions a- : c-d. [The sharked parts in I must to are the ber-speciete,]

single, and very large, would be placed within the circular channel, and the receptacle for the crude oil beneath the spout. The hole in the wall would receive the fulcrum end of the great lever; while the power would be applied to the free end, beyond the oil vessel. In this instance, however, it is not clear by what means the power was applied.

(β) A similar press-bed was noted by W. R. P. in the same neighbourhood, and here also there was a hole in the wall, in the same position.

(γ) The press-bed at Azajik near Myndos indicated in our plan (J. H. S. xvi. p. 206, Fig. 6) lies, not as at Menteshe and Emporio inside the fortified enclosure, but outside the gate. It has one large circular channel with a spout, and closely resembles those from Menteshe.

(8) A more elaborate oil-press, approximating even more closely to the modern type, was found by W. R. P. in a fortified enclosure at Emporio in Kalymnos, of which the plan is given in Fig. 5, and a drawing of the press-bed in Fig. 4. The building (c) which contains the press is oblong, with the



Fen 6.

door in one of the long sides. The press stands at the further end of the opposite side. The bed of the press (d) is a heart-shaped stone, with a pair of circular bases like that of the Menteshê press, but surrounded by channels which widen and then converge into a common spout. Below the spout is a permanent tank (e) for the oil, oblong in form, and bounded on its further side by a strong wall of masonry, which probably served some purpose in connection with the press. The whole press presents the closest analogies to the Menteshê presses above described; and there is no reason to believe that it is of other date than that of the fort, which is of the fourth or third century a.c.

(c) A press-bed of very simple type, Fig. 6, was recently excavated by peasants on the acropolis of Lykastos (modern Astritza) in central Crete, and examined in 1895 by J. L. M. In this case the upper surface of the stone is completely hollowed into a shallow flat-bottomed trough of ovoid outline, with the spout at the pointed end: small channels are cut in the bottom to

We know no special reason why these sites. That at Emporiô, as the plan shows, can proceed are so frequently associated with fortified. hardly have been a more place of residence.

direct the oil towards the opening. The absence of a central platform for the bag of olives seems to indicate an earlier, at all events a less advanced, type of press, even than that of the Menteshè press.\(^1\) It is difficult to explain both the large diameter, and the circular shape of the press-beds from Menteshè and Emporiò: that at Arginanta is oblong, and this is the common modern form. The facts also, that they are of stone, and so much larger in area than the modern press bods, and that no grinding troughs have been found near them, perhaps indicate that they were employed also, with a cylindrical roller, for the preliminary crushing. This view was also expressed to W. R. P. by the experienced workman who remodelled the press at Arginanta, and in



Fin. 7.

the modern domestic oil-mills of the African Tripoli a raised cylindrical pedestal of 6—8 feet diameter built of rubble, with a slightly concave upper surface paved with hard stones, is used in a similar fashion, the olives being bruised under a roller, which is usually a fragment of a granite column.

(ζ) Mr. Cecil Smith has kindly permitted the publication of yet another type of press-bed (Fig. 7) photographed by him at Klimatovini in Melos, near the site of the Hellenic town. The stone is much damaged, but appears to

¹ Cf. the even ruder, and spontless tranghafigured in Prof. Flinders Petric's Tell-tl-Hosp, p. 55 (from Somernh), p. 58 (from Wadge)

Dirack); and described by him as weahing troughs.

have been rectangular; the trough is circular, and well worked, with a flat bottom and no central pedestal. The drain is in the rim at one side. The stone bears round the rim of the trough, in well-cut sixth century Melian letters the inscription Εὐρνανακτιδάν, doubtless the name of the family to whom the press belonged. The inscription has been published by M. Holleaux, B.C.H. II. (1878), p. 521; who, however, falled to recognise the purpose of the block, and defends the erroneous reading Εὐρναμακτιδάν. It will be found under No. 36 in Hiller von Gaertringen's forthcoming volume of the Island inscriptions.

(3) The mechanism by which the power was applied is not indicated in

any of the above examples.

(a) A stone with two sockots (Fig. 5, No. 4) which lay near the oil-press at Emporio, may perhaps represent the clamped stone which weights the screw




Fig. 8.—Whighrenouse.

u. —c. from Kalloni in Leabau: 2 u. —c. from Arginánia: 8 a.—c. from Amorgos. In each case α=top view, δ=longitudinal section, c=end view.

at Arginunta: but it is without close parallel, either ancient or modern, and looks much more like a common type of door-sill.

(β) A stone, however, photographed by J. L. M. in Amorgos in 1893 (Fig. 8, No. 3) corresponds very closely with that at Arginiana. The dovetailed sockets for the suspension beams are clearly visible; the size and general proportions are nearly the same as in the Kalymniote example; and it was found close to a building of similar appearance and date to that at Emporio, one section of which seemed to have been used as a vat or cistern. The press-bed, however, was not to be seen, and the walls were too far destroyed to leave any sign of a beam-hole.

It still remains to be shown whether the Amergine stone was attached to a screw, or was raised by tackle so as to bear upon the end of the beam: but the close likeness between the two stones suggests that the whole mechanism

was of the same type in both cases.

An essentially identical stone, from Kasr Semana in Tripoli, is figured by Mr. Swainson Cowper, and others are frequent on the sites of the Roman oil-factories throughout that district.

- (7) An even closer parallel is given by a stone found by W. R. P. on the west shore of the Gulf of Kallani in Lesbes (Fig. 8, No. 1). In this the grooves in the sides are not mortised, but run with parallel edges down the whole side; so that the stone must have been set in a regular frame. On the other hand, the hollow in the upper surface, to receive the screw-head, is a detail which is wanting in the example from Amerges. This example is unsymmetrical, a peculiarity which still needs explanation; but perhaps the stone has been mutilated.
- (δ) The stones figured in Koldewey's Lesbes, p. 35, etc. and pronounced by him to be parts of wine-presses, are perhaps also from oil-presses of the same type.

W. R. PATON. J. L. MYRES.

⁴ Antiquary, Feb. 1806. =Hill of the Graces (1897), p. 150.

A SUGGESTED CHARACTERISTIC IN THUKYDIDES WORK.

The matter of this paper has been a subject of consideration with me for some time past, and I venture to put forward the conclusion I have arrived at, not because I consider it to be a certain one, but as possibly affording a working hypothesis providing an explanation of what has been to me, and may have been to others, an obscure and difficult point. That the subject demands the carnest attention of these who study Thukydides will, I think, be generally admitted, and this, together with the fact that I have formed the conclusion on a certain amount of first-hand experience may afford some excuse for the publication of my views.

The vast majority of the incidents in the Peloponnesian War are treated by Thukydides with great brevity, in some cases with a brevity disproportionate to their importance. There are, however, according to the ordinary acceptation, three incidents into which he enters with a peculiar and striking

amount of detail.

(1) The Siege of Plataes.

(2) The operations at Pylos and Sphakteria.

(3) The Siege of Syracuse

I say 'according to the ordinary acceptation' advisedly, because I venture to think that there are really four narratives, viz.:-

- (1) The Siege of Platnea.
- (2) The Siege of Pylon.
- (3) The Siege of Splakteria.
- (4) The Siege of Syracuse.

i.e. thus (2) in the original list consists of two different stories.

I came to that conclusion in 1895 after an examination of the region of Pylos and Sphakteria, on the intrinsic evidence of the story as compared with the site, but I had not then had time to take a comprehensive view of the general problems which the story of Plataca, which I examined in 1892-3, taken with the Pylos-Sphakteria narrative, presented.

The first consideration that naturally suggests itself in reference to the matter is that these incidents upon which Thukydides enlarges in so noticeable a manner are all of them narratives of sieges. It would on the face of it seem likely that there was some special reason for this. Furthermore there is at least one noticeable omission from the list—the siege of Potidaca, which, though of such importance and magnitude, is dealt with in his history with far less detail.

A second consideration on the general question is that Tlinkydides was an historian contemporary with the events which he described. It must almost necessarily be the case that the interests of such an historian should be less wide than those of one who is writing, like Herodotus, for example, of events which are past to him. He must necessarily be affected by the interests of his audience, an audience, in the first instance, contemporary with the events which he is describing. To every audience the interest must lie mainly in that which is novel to it, meaning thereby everything which differs from the wonted circumstances of their life. The criticism may not be original, but I think that it is to this that we must ascribe the peculiar limitation which Thukydides places upon the subject matter of his story. His history is a narrative of incidents rather than of institutions, whether political or social, because in the latter the contemporary historian would find little or nothing save what would be perfectly well known to a contemporary audience. Regarding his work as a military history some of his most noticeable omissions must, I think, be attributed to this fact. He talls us, for example, practically nothing of the Athenian army system, and but little of the naval organisation, simply, I take it, because these things were institutions so well known to the readers for whom he immediately wrote, that the occount of them was not likely to excite much interest, nay, would rather add an anattractive feature to his work.

Even if we knew nothing of the military history of the period preceding that in which and of which Thukydides wrote, we might then perhaps suspect from the elaboration of detail with which this contemporary historian deals with these four cases of siege operations that there was something in this department of it which was peculiarly novel; that the operations relative to the attack and defence of fortified places had entered on a new phase of development within the limits of the historian's own personal experience. Fortunately we possess evidence of this being the case.1

To the student of Greek history, there are, I venture to think, few questions which so frequently and persistently call for consideration and solution, as the contrast which is presented in the military history of the fifth century between, on the one hand, the peculiar strength of the natural positions which the character of the country afforded for the Acropolis of its towns both great and small, and, on the other, the peculiar incapacity which the typical Greek army displayed in the attack on such places. The dilcinina becomes more striking still when we consider the most prominent individual case among Greek armies, the Spartan, whose reputation for incapacity in this respect was notorious. And yet, in spite of this, this very army was able to maintain the begemony of its country over a large part of Greece, thickly sown with fortifications of great natural strength. In attacking these, its only method was blockade. Nor were the other prominent

and this is by no means fully authentieried. or the reported use of siegs engines by Parilifes Erferos.

The encline example in the Grack world, at the siege of Samos, c. Diod. xii. 28 and Plut. Peril 27 Both passages are from

Greek armies, at any rate until the time of the Peloponnesian War, really in advance of the Lacodaemonians in this respect. The Athenians had indeed a reputation that way, but it was evidently the reputation of the one-eyed among the blind, of those who know little, among those who know nothing. Such details as we have of the siege of Poticinea show that at the beginning of the Peloponnesian War the Athenians were not far advanced in the science of attack on fortified places. The old passive system of blockade is the one adopted, and though it is in the end effective, the cost is enormous.

The question naturally arises—how is it that the Greeks after a long and frequent experience of warfare with one another, had never carried this special branch of the art to a higher pitch of development than that at which we find it at the beginning of the Peloponnesian War? Furthermore how did it come about that a state like Sparta, in spite of its notorious incompetence in this department, was able, in face of what was at times the most serious opposition, to exercise the strong political influence which it exercised over neighbouring states whose towns were provided with all but impregnable Acropolis? The answer to this question seems to me to lie in the special nature of the land of Greece south of the Kithaeron-Parnes line.

It is hardly necessary to say that the major portion of the area of this part of the country consists of mountains incapable not merely of cultivation but of affording aught but meagre pasturage. Interspersed among these mountains there are indeed plains of great fertility, but of very small extent compared with the area of the uncultivable land, and on the produce of these plains the population of those states which had not facilities for foreign trade was absolutely dependent. It is quite certain that in that part of Greece south of the Kithaerou-Parnes line the amount of cultivable land, rich though it was, was not more than enough, if enough, to support the then population of the region, and in the case of Attica the inhabitants had long been dependent on the supply of foreign corn. This special characteristic must of necessity be true of every mountainous country, but it is peculiarly true of Greece.

It was this fact that rendered it easy for a force unskilled in siege operations to keep control over the country south of Kithaeron, and more especially over the Paloponnese. City states such as Teges and Mantineia for example, if disposed to kick against the pricks of the Spartan hegemeny, could always be brought to order by defeat in the field. And Sparta could fore them to take the field. It is perfectly true that, had they shut themselves up in the Acropolia of their towns, the Spartan army could have done them but little pursonal injury. But they could not afford to do this. In the first place there can have been no appreciable surplus of food supply, especially in the early summer, the beginning of the campaigning season, wherewith to provision an acropolis against a prolonged blockade. But more than this, They could not afford to leave their year's crop to be ravaged and destroyed by an army in the country. That would have meant possible starvation in the coming winter, without even the prospect of being able to obtain some sort of supply from

their neighbours, who themselves would require all the food staff they could grow. The average Greek state, then, when invaded by a hostile army, had to take the field with its own force and match hoplite against hoplite in the open, and in this department of the art of war the professional army of Sparta was infinitely superior to the unprofessional citizen soldiery of her neighbours.

North of Kithaeron the natural circumstances of the country are different, though not in direct contrast to those south of that line until the great plain of Thessaly is reached. Still, what is true of Thessaly is partially true of Bocotia The typical Greek army in Thessaly was like a fish out of water. It had to meet circumstances for which it was wholly unadapted. The extensive fertile plains of that country permitted of the use of cavalry, in which arm the typical Greek army was wholly deficient, and furnished so large a supply of food stuff, and so large an area of cultivation, that its fortified places could be provisioned against a long blockade, and could afford, too, to see a part of their land ravaged. The form of pressure which Sparts could employ in Arkadia would be ineffective in Thessaly, for the devastation of a large area of country is a work of months, not days, nor even weeks-a fact not always recognised, but of which the history of the invasions of Attica during the Peloponnesian War supplies conspicuous proof. We can see this cause, amongst others, at work in determining the history of such districts as Bocotia and Elis. The natural circumstances of these countries placed them in respect to a food supply in a position more approximating to that of Thessaly than to that of the poorer territories. Consequently, though not wholly safe-guarded against external pressure, they were much less open to it in the form in which, for instance, Sparta exercised it.

The reputation of Athens among the Greeks at the time of the Persian War in the attack on strong places, though evidently but ill deserved, was very possibly due to the fact that in her frontier wars with Bocotia she had been brought face to face with circumstances in siege operations in which passive blockade would be more or less ineffective, and she may well have been forced in attacking Bocotian border towns to employ something of the

nature of active operations.

But by the time of the Pelopomesian War a new factor had arisen in Greek warfare which had, in the circumstances of the time, very seriously curtailed the effectiveness of the old method of blockade. The genus of Themistokles had devised, and the foresightedness of Perikles had brought to completion, the great linked fortress of Athens-Piracus. Blockade of so extensive a fortification by land would have been almost impossible, and would be in any case decless unless the highway of the sea could be closed. No amount of devastation of their territory could force the possessors of such a stronghold to take the field against their will and to risk all on a battle in the open. Even among the Spartans there were men of ability who were quite able to appreciate the extent of the possibilities which this new invention, thus carried out, opened in Greek warfare. Archidamas' speech as reported in the first book of Thukydides is sufficient evidence on that point. Here was Sparta's great rival occupying a home territory in which, owing to

the poverty of the land, the old system of blockade should have been peculiarly effective, in possession of an angine which would render that system null and void. Others might well follow her example, and if so, the

days of the Spartan begemony were numbered.

In Attica itself the Athens-Piraeus fortress rendered it possible moreover for Athens to maintain adequately the defence of other strong places in the country, such as Oinou, Phyla, and Dekeleia, since, owing to their nearness to the great central fortress, it would not be difficult to supply them also with the sea-borne provisions, the obtaining of which the possession of the great fortiess, backed by a powerful fleet, rendered so easy. The details which Thukydides gives us of the attack on Oinoë in the first invasion of Attica by Archidamos seem to suggest that Parikles' original plan in the Peloponaesian War included the occupation of certain strong places outside Athens-Piracus itself There is no doubt that this part of his design, if it over existed, was subsequently modified. I would suggest, however, that this did form part of the original design, and that the subsequent modification was due, partly, at any rate, to the fact that Perikles and the Athenians suddenly discovered that the eyes of the Spartans had been opened to the necessity of adopting a plan of siege operations in accordance with the new conditions which the fortification of Athens-Piracus had imposed on the enemies of Athens. It must have been a severe shock to the military authorities in Athens itself to find that slow-moving Sparts had stolen a march in military science on their own enterprising state. That is evidently what had taken place. If Thukydides' evidence as to the war debate at Sparta be reliable, and he had ample opportunity of discovering in later years the outlines of what then took place, we must conclude that there did then exist in Sparts itself an able minority, led by Archidamos, who were capable of forming a just estimate of the chances and accessities of the coming war. They apparently saw that under the then present conditions Athens was practically invulnerable, if merely the old methods were employed, and so they introduced into Greek warfare in Greece an innovation, which, rightly learnt and rightly employed, offered a possible prospect of a decisive result. It was not rightly learnt, nor was it rightly employed, as the details of the siege of Plainea show us, but nevertheless it was an innovation which offered great possibilities. Whence the Greeks and especially the Spartans learnt the new system of attack we cannot perhaps say with confidence, but there is reason to suppose that the idea of it was introduced into Greece from Sicily.

The point, however, on which I wish to insist is that active siege operations in any form were a movelty to the generation in which Thukydides fived, and as such were just the sort of matter which would be seized upon by the contemporary historian as providing a subject which could hardly fail

to interest his immediate audience.

It is to this cause that I would attribute the fact that Thukydides chose these four incidents of the Peleponnesian War as subjects for detailed descriptions.

But there is a further point that is noticeable with regard to the subjects chosen.

The sieges described are in no two cases of the same kind. They resemble one another in being all of them active attacks on or defences of places fortified by nature, or by art, or by both, but there this resemblance ceases.

Plataca is a case of a siege of an inland town of considerable strength of position with permanent fortification.

Pylos is an example of the siege of a position of great natural strength

defended by improvised works.

Sphakteria of the siege of an island without artificial defence, but, owing to the peculiar difficulty of landing upon it, and therefore of attacking it, a naturally strong position.

Syracuse is an example of the siege of a great maritime town.

In respect to diversity the examples are well chosen. There are however, two other characteristics of these narratives which may or may not be taken as significant.

(1) In the three cases chosen in which some artificial form of defence is

employed, the attack is a failure.

(2) In all four cases the superiority of the attacking party either in respect to numbers, or, in the case of Syracuse, in respect to sullitary preparation, equipment, and experience is represented, either by implication or by direct statement, as being most marked.

As I have already said, I have had the opportunity of examining three of these narratives on the spot, viz. those of Plataes, Pylos, and Sphakteria. The reports of those examinations I have published, and with the exception of the modification of one view expressed with regard to the blocking of the harbour entrances at Pylos [which has also been published]. I have not

since seen reason to change my views in any one particular.

The result of these examinations is that I have not found a single statement of fact in either narrative which is not either wholly or partially confirmed by the circumstances observable at the present day. I do not mean to say that Thukydides was infallible. What I mean is that he did get good information, though I have had occasion to point out that owing to his not being personally acquainted with the ground of which he was writing, he was liable to misapply his information.

Thus far I am merely stating personal views which I have already expressed. I now pass on to other considerations of a more widely reaching and therefore more difficult kind on which I did not at the time of the publication

of my papers venture to state an opinion.

The impression of truth of detail which these narratives conveyed to me, was accompanied by an impression, which I could not dismiss, that the historian had deliberately, without any departure from truth of fact, intended to convey to the reader a general idea in all these cases, of operations on a much greater scale than might be deduced from a close and critical consideration of the narrative of events which he gives.

This idea is conveyed with marvellous art. It is impossible to point to any single detail in any one of the narratives to say 'This is a distinct case of exaggeration.' I believe that in any single instance in which a reader attempted to bring such a charge against any single passage, it would be seen that the historian might fairly retort. The exaggeration is not in what I

state, but in the meaning you attach to my statement."

I will take as an example the narrative of Plataes. I know that the impression which that take creates in the mind of the ordinary, and not perhaps critical, reader of Thukydides is that it is an account of siege operations of considerable magnitude conducted, at any rate on the side of the attack, by a considerable force. One need only read Müller-Strübing and those who take similar views on this question to see that this impression is by no means confined to the uncritical student.

I have already said that I fully admit that it is conveyed. But the real

questions with regard to it are, as it seems to me :-

(a) How is it conveyed !

(b) Is it deliberately conveyed I and if so, why?

Thukydides tells us that he aimed at getting hold of the facts of history and at stating them truthfully. Taking him as we find him, it is exceedingly unlikely that a writer of such marked intellectual acuteness would, after making such a positive statement, have allowed, in cases in which he wished to go a little beyond the truth, the fact of his so doing to be plain This is noticeably the case in the Plataes narrative. on the face of it. Thukydides, if impeached on the score of exaggeration in that narrative, would have a terribly strong defence, and would have no reason to fear to enter the witness box for examination and cross-examination. Could such a charge be proved in face of the defence that the historian expressly states that Plataen was 'not a large place' and that the number of defenders was 480 in all? The exaggeration is too artful, too impalpable, to be laid hold of by any ordinary means of extracting evidence. Yet the mere fact that the story has conveyed a wrong impression to generation after generation of readers is sufficient proof that the exaggeration is existent in it, though in a form hardly susceptible to literary analysis. It is the 'Krypton' in the air of the story.

Its effectiveness is due to the natural tendency of readers in all ages all the world over to take the most obvious conclusion as being the only conclusion possible. Into this literary trap the writer could recken on his readers falling. The demonstrable exaggeration is in what is implied, not in what is stated, and yet after all the demonstrability of even this form of exaggeration rests on the strictly unsound basis that the most obvious implication is the most true or even the only true one. To take the most noticeable instances of this in the Plataes story. Thukydides never informs us of the number of the army which Archidamos took with him to the siege of Plataes. It is true, of course, that he does not tell us the actual number of the Peleponnesian armies which in previous years had invaded Attics, though he does tell us that in the first instance the army consisted of two-thirds of the effective

of the various allies, i.z. its numbers must have amounted to many thousands. Does Thukydides mean to imply by his language in ii. 71,-[The following summer the Peloponnesians and the allies did not invade Attica, but marched against Plataea. Archidames the son of Zeuxidamos, king of the Lakedacmonians, was in command,']-that this army was equal in numbers to the invading armies of previous years? I am inclined to think that he does and he does not. He is quite willing to give the impression of magnitude without in any way committing himself. That he has succeeded in so doing is evidenced by the interpretation which modern writers have put, not upon his words, but upon his silence. Numbers varying from 60,000 to 120,000 have been seriously put forward as the probable size of the besieging force, and, it need hardly be added, that on such premisses most destructive arguments have been founded as to the credibility of the historian. It is perhaps numecessary to say (I) that such numbers are absurd on the face of them, and (2) that the historian says nothing which could in any strict sense be taken to imply numbers so huge, or indeed numbers in any way resembling them. Let us consider for one moment what the attack and defence of Platsea meant to either side.

From a negative point of view its possession by the Peloponnesians was of the utmost importance to them. It all but blocked the land communications of the allies of the League north of Kithaeron with those to the south of that line, save when Attica was in occupation of the Pelopounesian army. I have elsewhere had occasion to point out that there are only two passages across this range from the north which do not debouch on Attic territory, viz. that very difficult route round the west end of the range to Aegosthems, and the pass on the Plataca-Megani roud. The latter was blocked, practically, by Plataca: the former was too difficult to be really useful. This fact must have been apparent from the very beginning of the war to the leading commanders of the Peloponnesian League. There can be no doubt that the Thebans saw it, and we may attribute the attempted surprise of Plataea to their apprehension of the part the town might play in the war which was imminent. Archidemos seems to have been aware of it, too, and the very first measure he took in the war aimed at its reduction. In Thuk, ii. 18, the historian describes the first invasion of Attica. He tells us that Archidames first led the League army against Oinoë and besieged the place. Why of all places in west Attica should be attack Oince first? It lay right out of the way of an army invading the country from the side of the Megarid, via the route which would naturally be taken, i.e. via the Thrissian plain. But, as those who know Attien will recognize, as indeed may be recognized from a map of the country, it commanded the only road from Athena to Plataca. He did not take the place, and therefore he had for strategic reasons to postpone the attack on Plataea, until experience had shown him that nothing would induce Perikles to risk his land force beyond the walls of Athens. Then and then only could be afford to ignore Oince, a small place in itself, which could only become formidable to a force besieging Plataca in case the Athenian main army chose to march out and use it as a base of operations against those engaged against the town. When an unmistakable indisposition to do this was displayed by the Athenians, then, and

not till then, did be undertake the siege.

It would be difficult, then, to overestimate the value of Plataes to either side, and it is unfikely that Archidamos would employ a force inadequate for the siege of it. But it was not a large place, as Thukydides tells us, and the defending force amounted to only 480 men. It is exceedingly unlikely that large contingents would be drawn from the allies for an operation which could in reasonable expectation be accomplished by a comparatively small percentage of the whole disposable force of the League. There were very forcible reasons for not employing more men than were absolutely necessary. For several years past large percentages of the able-bodied male population. of the Pelopounese had been taken away at a time of year when they could very ill be spared from the harvest, a most serious disadvantage, we may say an insuperable disadvantage, to a population dependent entirely on the products of their country. The disadvantage was all the greater at a time when a more or less effective blockade of the Peloponnese remiered the importation of foreign food stuffs difficult. On the hard probabilities of the case there is far more reason for supposing that the force which Archidamos commanded at Plataea was a small one, amounting at most to a few thousands, than that it was one of considerable size. There is even some reason for supposing that the enterprise may have been but little appreciated at Sparta, and the support accorded to it but lukewarm. The authorities there seem to have been just as incapable at this time as at others of forming any just estimate based on large views of policy or of strategy. It is, for example, impossible to fail to see the correctness of the estimate of the chances of the war as sketched in Archidamos' speech at Sparia, yet his views, in spite of his high position, found apparently but few supporters. His object in the attack on Oinoë was completely misunderstood, and the attack itself much blamed, so much unappreciated indeed that Thukydides in his inquiries into the Peloponnesian side of the war some years later seems not to have heard aught of the design which Archidames entertained, manifest though it is. Archidames appears to have been of a capacity and insight far above the average of that of his race.

Thukydides, and indeed, the Athenians of his time, must have had a pretty clear idea of the magnitude of the army which engaged in the siege of Plataca, viz. that it was not a large host such as has been imagined by later writers on the subject, but a comparatively small force suited to the demands of the situation, both as regards the requirements of the attack itself, and also as regards the circumstances of those states from whom the army was drawn. Nor is there a word in Thukydides' marrative of the siege which would accessively convey any other impression. So far the story was for the immediate audience, the contemporary audience. But there was another audience which the writer could not forget, the audience of the future: *πημα τε ές ἀεὶ μᾶλλον ἡ ἀγῶνισμα ἐς τὸ παραχρήμα ἀκούει» ξύγκειται. For them the case was different. The novel feature in the art of Greek warfare

would not be merely an interest to contemporaries, but, if properly set forth, an interest to future generations as first examples of a new introduction into that always interesting department of history, military history. To be effective the examples must be varied and striking, and to be so, must give an impression of scale. With the sole exception of Syracuse the examples which lay to the historian's hand were not great in actual scale, and the impression had to be created artificially. And so it was created. A certain amount of artistic reserve was introduced into the narrative: the historian abided by the strict truth in every positive statement he made, but by a certain amount of negative repression created a general impression of magnitude which the positive statements did not in reality support. Had he not said: of γάρ ἄνθρωποι τὰς ἀκοὰς τῶν προγεγενημένων, καὶ ἡν ἐπιχώρια σφίσιν ἢ, ὁμοίως ἀβασανίστως παρ' ἀλλήλων δέχονται !

In what relation, then, does the story stand to the strict truth? In some such relation, I take it, as the type stands to the individual. The historian wished to create a type of this special kind of siege conducted after the new fashion. His very aim necessitated that the actual incidents should be placed before his readers in what he judged to be their typical form; his art consists in having done this rather by the creation of impression, than by deviation

from the actual truth.

This characteristic of the method employed by the historian is not less striking when the details of the Plataca story are taken into consideration. An examination of the theatre of events must convince the inquirer that there is a solid basis of truth at the bottom of every one of them, and yet in each case there is an impression of magnitude conveyed which a strict examination of what is stated does not support. Even the tale of the mound, and of the works undertaken by the besiegers to counteract it, is peculiarly supported by the natural circumstances of the ground. It is the impression which it conveys which has led to discredit being cast upon it by modern criticisms. But whatever the scale on which the operations were conducted, the general character of them, and the variation of method employed are peculiarly interesting at this stage in the history of Greek warfare. There was a combination of the old and the new fashion of attack. Of the new fashion I have no doubt that Archidamos was the champion, and that his advocacy had to meet a stubborn opposition from the proponderant conservative element in the army. Hence the new method never got a real trial, and in so far as it was employed seemed a failure. At the same time it is impossible to read the military history of this time without seeing that the opposition to the new system was not necessarily the only cause of its failure in this instance. We must take into account the inexperience of those who were now putting it into operation for, what was to them probably, the first time. Furthermore the Greek soldier of this period, nuless led by a Brasidas, was not conspicuous for dash, and dash was required for the taking by assault of a place such as Plataea, manned by a garrison animated with the contage of despair The new method was the first employed, the stockiales being, no doubt, a concession on the part of Archidames to military conservatism.

The new method was a failure, and the old method of circumvallation was resorted to.

For my present purpose I have said all I wish to say about the Plataca narrative, save this in summary. As a narrative, it seems to me a model of artistic acuteness. The writer, great artist as he is, has drawn for us a word picture which conveys, and which he intended should convey, an impression

greater than his subject.

The Pylos-Sphakteria narratives partake of the character of the Plataca narrative, though they are not identical with it. I have already stated my belief that they are two stories, not one, and were really regarded as such by the historian, though they were contiguous in place and time. I expressed this view of the separate character of the narratives in a paper which appeared in the Helleniz Journal some two years and a half ago (Vol. xvi.), but I am afraid that the arguments by which I supported this theory were formed on bases of which the cogency would not be apparent to the classical scholar, whose attention is seldom directed to questions of physiography, and to whom, therefore, arguments founded on that basis do not appeal. Dr. Frazer, for example, in his recent edition of Pausanias, is quite severe with me on this question, evidently for the sole reason that he is unacquainted with the

problems which physiography presents.

In so far as I am able to learn, those who are interested in ancient history have as a rule accepted the view that the lagoon of Osmyn Aga was existent in some form or other at the time of the events at Pylos and Sphakteria. Furthermore the view has been stated, though unsupported by evidence, that this lagoon was an integral portion of the bay, i.e. that the sand-bar did not axist to any practical extent. So simple a statement, which everybody can understand, is sure to find acceptors. It has the further advantage of leaving the criticism on the historical character of the narrative much where it found it, viz. Thukydides made certain gross errors, as Arnold and others have pointed out, and, as to their explanation, you are free to adopt any you like. This last-mentioned method of working out the problem has the merit of simplicity and freedom, and is therefore attractive. For myself, I am convinced that those who attempt to work out the problem on these premisses are labouring at lest labour. I am also convinced that this fact must be recognized by the majority of students of ancient history, if only the matter be stated in a comprehensible form, avoiding, as much as possible, pure technicalities. I will therefore state the opposing view, and put in as clear a form as possible what seem to me the overwhelming reasons for it, and against the contending theory.

The view is simply this: that at the time at which the events at Pylos took place the lagoon was much as it is now, save (1) that the sand-bar had not yet extended quite up to Pylos itself, i.e. there was still a channel at the west end of it, and (2) that the water, at any rate in the west end of the

lagoon, was deeper than it is at the present day.

I am re-stating the reasons for this view, because I feel that, in my original paper, I did not perhaps put the matter in a form which would be comprehensible to every student of the subject.

The reasons are as follows :-

- (1) The area in the neighbourhood of the bay where detritus has been deposited is for all practical purposes co-terminous with the present site of the lagoon and its immediate shores, [with the exception of the plain of Xerias on the east side of the bay, which has nothing to do with our present subject.]
- (2) On this area the detritus brought into the north part of the bay by the action of rain and streams has been deposited.
- (3) The streams are small, and practically non-existent save in rainy weather,
- (4) The formation of a sand or mud bar in the case of such deposits occurs, as can be seen all round the coasts of the Mediterranean, at a very early stage in the process of deposit.
- (5) This process of deposit must have been going on ever since the hay of Navarino was formed.

Now I ask, is it conceivable that in the countless ages that intervened between the formation of this bay and the events at Pylos, this process had proceeded so slowly that this north end of the bay was still an integral part of it, whereas in the (geographically speaking) brief period which has intervened between those events and the present time, the lagoon has become a lagoon, i.e. at least half the work of deposit has been accomplished?

There can be only one answer to this question: it is impossible, even absurd to suppose such a thing. The other theory is more simple, but it will never lead to any elucidation of the Pylos narrative, since it supposes a state of things which neither did exist, nor could have existed at that time. There were two harbours at Pylos at that time, if physiography can tell us aught on the subject, and there are two narratives in the history of the events at Pylos and Sphakteria, as given by Thukydides, and these two narratives refer, though the author never apprehended the fact, to two different harbours. For the purpose of the historian, writing, as he was, an essentially military history, the centiguity of the narratives in respect to time and place, was purely accidental. His aim was to create typical early examples of a new kind of siege operation, and events offered him the two examples in close proximity to one another. Pylos is practically ignored in the Sphakteria narrative. The two series of events were really separated in his intention.

It is not necessary here to point out in detail the effect which this 'two-narrative' theory has on the criticism of the whole 'Pyles-Sphakterin' story. I have already done this in the previous paper on the subject. It does, however, clear up much that is otherwise obscure in Thukydides' Pyles narrative, and the error in the story becomes attributable to a very natural mistake made by the author as to the identity of 'the harbour' of which his informants spoke, and not to his stupidity, the last defect, perhaps, of which those who know his work could suspect him. I cannot but be glad that the 'two-harbour' theory does elucidate the narrative, but, in any case, I say with conviction that whether it did or did not do so, it is, leaving the history

aside altogether, in reality not merely a theory, but a solid fact which students of Thukydides will have to take into account

It is very difficult to say whether we have in these two narratives instances of suppressed exaggeration similar to those which are present in the Plataea story. The historian had better, i.e. larger material on which to orect his typical examples; and the desirability of increasing the scale of action for the writer's purpose, was not so evident. There is one feature present to which the Plataea story affords no parallel, namely the colouring of the tale in order to enhance the services of an individual, in this case Demosthenes. Thukydides had evidently a weakness for men of his type, who were ready to play for big stakes in the war game without reckning the possible cost, but it need hardly be said that he carried his weakness at times too far, when he detracted from the merits of a rival in order to favour the object of his admiration. It seems to me that this is the only means of accounting for the way in which the historian treats what was perhaps the most brilliant incident in the two sieges, the surprise of the Peloponnesian fleet by Eurymedon and his colleague.

In the Pyles story there is one incident the account of which does not carry conviction with it; I refer to the tale of the attack from the sea side by Brasidas and his fleet. I have pointed out that of the two simultaneous attacks by the Peloponnesians, viz. this one by Brasidas, and the one on the north, wall. Thukydides can only give us details of the former. He tells us that the total number of assailant vessels was ferty-three, whereas Demosthenes had only sixty men with him. Even taking into account the difficulty of landing. I am strongly inclined to suspect some exaggaration here, either in the form of over-estimate of the numbers on one side, or under-estimate of those on the other. Perhaps the real fact is that the ships, though their number is correct, had only small complements on this occasion, a fact the author has studiously suppressed. At any rate it is noteworthy that we have here a numerical disproportion strangely resembling that at Plataes, and success is on the side of the infinitely weaker number in both cases. Was there an implied moral to the two stories (Was Thukydides a conservative

in military matters?

There is, too, in the Sphakteria narrative a very possible example of the exaggeration of impression. Had all the ships which Kleon used for his disembarkation on the island had anything like their full complements the force landed would have been enormous.

In the case of Syracuse the need for exaggeration did not present itself: the operations were on a sufficient scale to provide an impressive example of the type of siege the author wished to create, though here the novelty was rather in the defence.

One word before I close this article. I have, as it will be seen, sought to explain two points in Thukydides' work:—

- (1) The cause of his choice of subjects for peculiarly detailed narrative.
 - (2) Certain peculiarities in three out of the four stories.

A SUGGESTED CHARACTERISTIC IN THUKYDIDES WORK 231

The explimation seems to me to be :-

- (1) He was ambitious to create typical examples of a novelty in the military art.
- (2) To achieve his object satisfactorily he had certainly in one, possibly in three, out of the four instances to create an impression of scale where he did not find it existing.

G. B. GRUNDY.

BATTLES, ANCIENT AND MODERN.

PROVESSOR BURROWS ON SPHAKTERIA.

In the last number of the Hellenic Journal Professor Burrows has once more attacked Pylos and Sphakteria, this time with the aid of certain allies from the Peloponnese and a whole battery of photographs. I am, I confess, loth to dye this ink-stained field a deeper hue, and I have certainly no intention of sending friends of mine to Pylos with a view to reviving a controversy which has gone for enough. At the same time I do not wish to appear to undervalue the evidence of Messrs. Carr Bosanquet, Crowfoot, and Lindsay, though it is not of a very decisive character. I should therefore like to point out, as briefly as possible, its true bearing, and in doing so I have the satisfaction of not having to treat it as heatile, though brought into court by the other side.

It is rather difficult to deal with Mr. Lindsay's evidence, as given by Professor Burrows, relating to the south end of Pylos. Had we had Mr. Lindsay's first-hand account of the matter, it would no doubt have been easier to understand. I do not understand it sufficiently in its present form to attempt to discuss it in detail. I see, however, that Professor Burrows now not only imagines a sand-spit at the south-east corner of Pylos, but even nakes Demosthanes draw up his ships there; and further, refers to this imaginary sand-spit [against whose existence the physiographical evidence at present obtainable is very strong] the expression \$\delta \pi \Omega \delta \alpha \sigma \sigma \delta \alpha \delta \alpha \sigma \delta \alpha \delta \delta \alpha \delta \alpha \delta \alpha \delta \delta \alpha \delta \delta \alpha \delta \delta \alpha \delta \delt

The photographs which are appended to the article justify to an eminent degree the distrust with which I have always regarded such aids to topography. If it be merely a question of the appearance of an object which can be taken at a distance of a few yards, then, no doubt, the picture is of value, but to found arguments dealing with minute detail on such photographs as those numbered Fig. I and Fig. 4 in Prof. Burrows' article is simply misleading. Fig. I (of the south-east angle of Pylos) has at first sight all the

appearances of a photograph of a gradual slope. It is not until you examine it closely that you see how steep the slope is. , No photograph taken from the front of a slope can over give anyone who has not seen it a true appreciation of its angle. The foot of the slope appears relatively much nearer to the eve than the top of it, and consequently the slope itself appears much more gradual than it really is. The angle is, as a fact, 36'. Moreover I have used the term 'slope' for want of a better word. It is really in parts precipitous, and perhaps the word 'cliff' may be taken as more nearly describing it. Can Professor Burrows quote any example from the fifth century of a Greek force attempting, in face of opposition, an assault on such a slope, or on anything resembling it? Fig. 4, which gives the same in profile from above, exaggerates somewhat in the opposite direction, and as it is out of focus the detail is lost in a distance. Still either photograph will justify, in the eyes of those who are not accustomed to imagine the Greek hoplite as making his. way over ground which a deer stalker would with difficulty climb, my assertion that the practicable approach at the south-east angle of Pylos was so narrow that, even if landing there had been easy, which does not seen to have been the case, a few men could have defended it against immensely superior numbers, and a wall was neither required nor built by Demosthenes there.) The existence of the Venetian tower and wall at this point dates, of course, from times when the sand-bar had reached the foot of the cliff, and therefore affords no argument for the necessities of the case 2,000 years before.

The value of photographs in topography depends, as I have said, altogether on the use which you are content to make of them. They are of value in giving those who have not seen ground a general impression as to its appearance. For minuter details, unless taken of objects a few yards from the camera, they are absolutely misleading to those who have

not first-hand knowledge of the ground they represent.

The question of the blocking of the chaunels is dependent on a far larger question, the condition of the lagoon at the time the events on Pyles took place. I have expressed my views with sufficient clearness on this point in another article in this number of the Journal. I have not the slightest doubt that Thukydides had very good grounds for his repeated assertion with reference to the intended blocking. The difficulty to him was, and to us is, that he failed to recognize the existence of two sheets of water, both of which

though he has quoted my setual words, he has misroad them. He says the photograph shows in profile the slope to which I refer. It does not. It shows in profile the slope to the southern, not the eastern foot. To this southern slope I referred in the Classical Réviese of Nov. 1896 in the words 'The cilff is slaty feet high within fifty yards of the Sikia.' But it is the cast slope which is of importance to the question between us. As to comment we are in agreement,

I Prof. Burrows on p. 149 of his article has quoted a long passage from a previous paper of mine, in which occur the words: 'at this conth end of the cast cliff, the summit of the cliff rises to a vertical height of sixty feet above its castern foot, which is only at a horizontal distance of eighty-one feet from that summit.' Professor Burrows disposes of this remark by an appeal to the photograph, and says 'Comment is needless.' The effect of this orthograph is unfortunately magazived by the fact that

he designated as 'the harbour.' The vagueness of his assertions on this point is all in accord with the caution of a cautious man who is not quite clear as to his information.

Mr. Lindsay's evidence with regard to the position of the north wall is, considering the fact that he had the opportunity of ascertaining in detail Prof. Burrows' views before he went to Pyles, and went there, apparently, at the latter's request, not unfavourable to the views I have held. As to the tifth century (sie) wall, Mr. Carr Bosanquet speaks with the characteristic caution of an experienced archaeologist. He says 'it may well be rough fifth century work.' Of course it may be, but is it in the slightest degree likely that it is? It may just as equally well be the work of 5, 10, 15, or 20 centuries later. There is no special characteristic to determine its age. The Greek and the Cumberland shepherds at the present day build the same kind of wall (v. Figs. 6 and 7, in Prof. Burrows' article) in constructing a sheep shelter; so would anyone also constructing a wall with similar material. The survival of such a wall on a site which has had such a subsequent history as that of Pyles is so improbable as to render identification valueless for historical purposes.

I doubt whether anything can be gained by attempting to determine the date of this wall. Though the importance of Pylos is at present almost nil, it stood to the Venetian trade with the East in mediaeval and modern times in much the same relation that Gibraltar does to our own Eastern trade. It was the scene of repeated attack and defence, and even so recently as 1825 was maintained by the insurgent Greeks for six weeks against the assaults of Ibrahim Pasha's force. On ground such as this, which does not afford soil for entrenchment, the rough stone wall is the only form of defence

possible.

The opinion of the professional architects of the French expedition, quoted by Mr. Bosanquet on p. 155 of the J.H.S. Vol. xviii must surely be of greater weight than that of the archaeologist, M. Bory de St. Vincent, Archaeologists are not exempt from the unfortunate tendency to believe

what they wish to believe.

Of the identity of the site of the makado epupa there can be no dankt. I am in full agreement with Professor Burrows on this point. I was also inclined to think that he had found traces of the work above ground which I myself had missed. His original account of the remains he had discovered lad me to believe that they possessed definite characteristics pointing to an early origin. But if these photographs, Figs. 2, 8, 9, in Professor Burrows' article, and the print Fig. 11 in the text convey a correct impression, these wall-remains present no such definite characteristics. That marked Fig. 9 I have not seen. Those marked Figs 2 and 8.1 have. I have never seen walls elsewhere in Greece which at all resemble them, except such as are notoriously modern (e.g. the remnants of the breastworks erected by the Greeks at the siege of Tripolitza), roughly put together of the material lying at hand. Nor must it be imagined that this site has not passed through vicissitudes in mediaeval and modern times which must

have led to the construction and reconstruction of numerous rough walls upon it.

The north end of Sphakteria is the key to Pyles and Navarino, as Hussein Djeritli pointed out to Ibrahim Pasha. Apart from the question of artillery fire-(and it was here that the Egyptians established their batteries in 1825 in the attack on Pylos -it was an essential point d'appui for any force attacking this peninsula, affording as it did a bird's-eye view over threequarters of it, and what more natural than that such a force should guard the summit with a rough wall, since the soil for entrenchment is conspicuous by its absence. Compare, too, the wall of Fig. 2 alleged to have been built by the Messenians with the so-called fifth century wall of Fig. 6. The latter is more perfect than the former, but they are the same in character. Either might belong to any age. Mr. Crowfoot's careful plan temis more towards conviction, but presents this difficulty. How is it that the wall-foundations in the hollow show not merely a want of connection but, in the case of the northern one, a manifest disconnection with the fortification of the summit? The exigencies of the ground, if Mr. Crowfoot's plan be, as it seems to be, absolutely correct, demand no such thing. And yet it might be supposed that people who were, as the plan shows, acquainted with the use of flanking towers, would not have constructed their work in this form. In fact it does not seem as if the wall on the summit and the walls in the hollow were part of the same design. If so, which is the remnant of the makazor covera, and which is not?

I see that Mr. Lindsay, in deference, no doubt, to Thukydides, suggests an improvement on Professor Burrows' design of taking the Messenian captain and his men in boats to the bottom of the cliff beneath the summit of Sphakteria. The remodelled theory rests on the insecure foothold of an imaginary path from the Panagia to that point. How insecure the foothold is will be seen by reference to the Admiralty chart, where the cliff is shown as going down sheer into a depth of between thirty and sixty feet of water for three-quarters of the distance between the Panagia and the bottom of Professor Burrows' chimney.

MR. WOODHOUSE ON PLATAEA.

Those who are interested in Greek history should certainly read Mr. Woodhouse's able article on Plataca. I think he exaggerates the differences between our views, though absolute concord on so complicated a question is not to be expected. He also seems to forget that I had to take up the work of inquiry practically ab initio and to construct a practical basis on which to found an explanation of the battle.

The points of difference between us are (1) as to the position of the Gargaphia spring, (2) as to the site of the Heroou of Androkrates, (3) as to the identification of stream A 1.

(1) Gargaphia.—That the identification proposed by Leake and myself is

capable of dispute, I admit: but Mr. Woodhouse's main arguments against it appear to me to be badly founded.

(a) He, identifying it with the Apotripi Spring, says that the Gargaphia of Leake is nearer the 'Island' than the Apotripi. The distance is almost

exactly the same,

(b) He further says that the Gargaphia was by implication 10 stades from the R. Moloeis and the temple of Eleusinian Demeter. He evidently assumes that it was milkin the second position of the Greeks, and that, as they moved 10 stades before arriving at the Moloeis, etc., the spring must have been 10 stades from the latter.

It seems to me, however, that the detail of the taking of the Spring by the Persian Cavalry, while the Greeks were still in the second position, shows pretty clearly that the spring was not within that position, though, of course it must have been near it. The position was the top of the Asopus ridge: the spring was at the bottom of it.

(2) The Heroon of Andrehrates.

Mr. Woodhouse would place it on the Asopus ridge, on the site of the Church of St. John. I cannot see how Thukydides' language can be so interpreted. He says, iii. 24, 'The Plataeans started from the ditch and took in a body the road leading to Thebes, having on their right the Heroon of Androkrates, thinking the beseigers would be less likely to suspect their having taken the road towards the enemy's country, and seeing, too, the Peloponnesians with torches going in pursuit along the way towards Kithairon and Dryos Kephalai which leads to Athens. For 6 or 7 stades the Plataeans went along the Thebes road, and then, turning, took the way leading towards Enythrai for Hysiai, and having taken to the hills, escaped to Athens.'

All the ways mentioned can be identified with case, and are, in two of the three cases, existent.

The fugitives took the Thabes road, which must have been more or less identical in line with the present route from Kokla, which stands just above the rains of Plataea, to Thebes, having on their right the Heroon. After going 6 or 7 states they turned, evidently with intent to reach the trackway which leads from Thespiai via Pyrgos to the pass of Dryos Kephalai and the sites of Hysiai and Erythrai, and, without ascending to the pass, took to that high bastion of Kithairon which projects into the plain east of Erythrai. It seems to me that Thukydides implies that the Heroon was in the angle through which they turned, and I am inclined to think that the remnants of it will be found at one of the two stone heaps marked on my map, about half a mile north-east of the remains of the 'Acropolis' of Plataea. They must have left the site of the Church of St. John far away, not on the right, but on the left.

(3) Al and the Asopus.

In a note at the end of his article Mr. Woodhouse repeats the charge which Dr. Frazer makes in his Pausanias. He accuses me of inventing this identification of A1 with the Asopus with a view to the subsequent identification of the 'Island.' This charge is utterly unwarranted by what I have said in my original paper, and I may add that at the time the difficulty with regard to Herodotus' use of the name 'Asopus' and its solution occurred to me, I had not identified the 'Island,' which came in the very last part of my survey. Dr. Frazer has withdrawn the charge in a letter which he has given me leave to publish, if I wish, wherein he admits that what I have said affords no justification for it.

There is in the article much beside what I have mentioned, but it is matter which I should not like to discuss without further consideration. I shall certainly take it very seriously into account in dealing with the wars of the 5th century in book form, as I hope shortly to do.

G. B. GRUNDY.

WOMEN IN PTOLEMAIC EGYPT.

MR MAHAFFY in his preface to The Empire of the Ptolemies states among other problems raised by Ptolemaic history the following: 'How far does the observation, that we only know of one crown-prince with a wife (Soter IL) account for the divorce of that wife after his accession, and for the other apparent heartlessnesses in Ptolemaic history? Is the hereditary title recognised in the princesses, which no doubt led to their marriages with their reigning brothers, a relic of Pharaonic ideas, or a mere imitation of the successful experiment of Philadelphus?' This article is an attempt to show that the former hypothesis is the true one, and that the marriages of the Ptolemies were dictated by their policy of conciliation, and were based on deeply rooted native prejudices. No doubt the difficulties in accepting such a hypothesis are very great. Why, for instance, should such a survival have come into comparatively greater prominence under a late dynasty! I have endeavoured to sketch a possible explanation of this in the relations of that dynasty with the priesthood of Osiris. The hypothesis seems to clear up several dark spots in Ptolemaic history and to lend the instification of diplomacy to actions that otherwise stand condemned by their arbitrary egotism and unmeaning cruelty.

As the question seems to me to be closely bound up with the relations subsisting between the priesthood and the State and with the social and political aspect of the country generally, I shall begin by a brief examination of the condition of the priest-class at the time of the Ptolemaic occupation.

It is plain that if the Ptolemies were to gain any hold over the population of Upper Egypt, they could only do so by conciliating or subduing the priest-class. The most striking characteristic of Egyptian monarchy in Upper Egypt and in Aethiopia had always been its entire dependence on the priesthood. The influence of the priest on the people was unbounded. Under the New Empire the priest-class had risen to a temporal and spiritual power unknown to earlier times. The old nobility and nomarchs had disappeared: the soldier-class had dwindled owing to the amployment of mercen-

Mah. ale Life aries; the payings or military landowners under the Ptolemies were and Thought, impoverished and had but a small and insignificant rôle to play; they had p. 171. ceased to be landed proprietors. In fact the land was entirely in the hands of the king or of the priests.

> Now this rise of the priesthood as a class under the new Empire is especially traceable in one place in Egypt-at Abydos, that is to say in the

Erman. p. 104, eeq.

Mah. Emp. of Pr. Introd.

The Roy

Erman, 11, 293,

cult of Osiris. From this time onwards we find Osiris-worship more prominent throughout Egypt, and this prominence increases with the degradation of the prestige of Thebes and the Amon cuit as a national religion. and also with considerable internal modification of the nature of the priesthood. Thus, as Erman points out, the lay element disappears almost entirely from the priesthood. As the priests grow in temporal power they guard it more jealously, and it was by the formation of this close oligarchy that they were enabled to bid defiance to the Pharaohs and finally to thrust them aside on sit p. 162.

Erinau, p. 265.

and absorb the supreme power into their own order,

The removal of the seat of government to Lower Egypt left the priesthood a powerful and discontented body with almost unlimited influence over the laity, ready to foster any signs of disaffection to the crown in the hopes of regaining something of their lost prestige and restoring to Thebes its former sovereignty. This of course applies mainly if not entirely to the priest-class of Thebes, centring round the cult of Amon-Ra; and it was thus in the treatment of Thebes and in compating the influence of its priesthood that the main difficulty, I believe, of the Ptolemnic government lay. Subsequent history shows how frequent revolts in this quarter were.

> Erman. p. 200; mg.

To overcome the sullen defiance of the Theban priesthood seemed impossible, so the Ptolomies gradually adopted the policy of giving their special state patronage to the cult of Osiris and elevating its priesthood to a national importance which was justified by the wide-spread influence of the cult. There were obvious reasons why this cult lent itself to their policy better than any other. It was more generally diffused and less local in its connections than any other. The Osiric cycle, belonging originally to Abydos, had lent itself to the tendency towards amalgamation which was so marked a feature of the religion of the New Empire. It was less rigid and more human, and perhaps less exclusively native than the rival cult of Thebes; its mythology adapted itself to more modern requirements and appealed to the human sentiment of its worshippers. Osiris in his aspect of God of the Dead was accepted throughout Egypt as one of the great gods, and continued to absorb and assimilate other gods and cycles of gods after they had developed beyond the strictly local stage, till finally he was Main Empa of closely connected with Ptah of Memphis and worshipped in combination with the latter as Osirhapi. On the other hand the Amon cycle and its priesthood resisted this new anti-polytheistic tendency and remained comparatively impervious to the influences of the age. That its predominance therefore remained local and centred chiefly round Thebes is not surprising. The development of its mythology seems to have been arrested; the texts do not enlarge upon it as they do in the case of the Osiris-saga.

Prop Te Ecquin.

p. 200.

Ermun. P. 272. Ibale, Eucy. Eril. p. 718.

p. 714.

It was doubtless this adaptability of the Osiris cult that recommended it to the Ptolemies and enabled them to graft upon it the Hellenistic elements. of the Serapis cult. Moreover, its marked Samitic character brought it into Poole, op. cd. closer affinity with the religion of the foreigners-Phoenicians, Jews.

^{&#}x27; Similarly Sokaria of Memphia and the pillar of Ded were identified with Osiria,

Samaritans, Syrians-who were so much encouraged by the state to settle in

Egypt at this period, probably from commercial reasons.

We can easily understand that the Osiric priesthood gladly lent themselves to a policy which seemed to promise a temporal aggrandisement new to them. They found, however, that this temporal power was to be of a strictly limited nature, that the firm rule of the Ptolemies did not admit of a dual power in the state. The priesthood indeed was treated with deference and generosity; their temple-lands were secured to them, their cults were elaborately honoured: in return they were expected to give religious sanctity to an upstart race of king-gods, and to use their influence in Upper Egypt to secure the loyalty of the subject and to counteract the uncompromising hostility of Thebes, which found vent in the frequent rebellions of Upper

Egypt under the rule of the later kings.

It was naturally of paramount importance to Ptolemy I to secure the loyalty of Upper Egypt for the sake of the trading interests of his empire. Probably here at the outset he came into conflict with the policy of the priestclass, who saw that any commercial opening up of the country would tend to draw away still further the life of the country to the sea-board, and strip them more completely of their former power. Perhaps it was this same dread on the part of the priests in early times that led to their intervention when the energetic and progressive Necho II, was engaged in constructing the prototype of the Snez Canal-a canal connecting the Nile with the Red Sea-and thus opening up the Red Sea for commercial enterprise. At any rate they seem to have had the king well under their control, and according to Herod in 158. Herodotus he gave up the undertaking owing to their representations : Nexwy μεν νυν μεταξύ δρύσσων έππύσατο μαντηίου έμποδίου γενομένου τοιούδε, το βαρβάρφ αὐτὸν προεργάζεσθας! In the New Empire the country east of the Delta, being on the highway to Syria, became opened and Tanis developed into the powerful capital and consequently a formidable rival of Thebes. Hence we see that the fears of the priesthood were by no means unfounded.

It is in the Osiric cycle alone of all Egyptian cults, as they have come down to us on the monuments, that the female divinity plays a prominent part. Ra is rarely associated with my consort, as Lepsius points out, whereas Osiris figures constantly with Isis. Isis appears, moreover, as the wife of Chemmis, the Egyptian Pan, the productive principle. Hather herself is in later times identified with her. She is 'the goddess who is wiser than all men, than all gods and spirits.' She finds out the secret name of Ra, so that the sun-god loses his vigour and even mankind becomes hostile to him and begins a rebellion.

Now as the foundation and supreme tenet of the Osiric cult we find the

Fools, Egypt, Egypt, Ency, Fr. Brugsch, Goog, Insched, 213 mg.
Turin Papers, Erman, p. 265.

th may have been owing to similarly function and anti-progressive pressure from the same quarter that Darius likewise desisted before completing this canal. More definite accentific objections had to be brought to bear on the Parcian king—the fact of the dangerously.

higher level of the Red San! But the 2mil Prolemy, as we should expect, overcame the Drod. i. 33, 2 imagined physical difficulty by his gardrexed at Edoporous, the spiritual one by his firm treatment of the priesthood.

holy marriage of the god with his sister Isis. But Isis is not merely wife and queen-consort of Osiris and after his death queen-regent: even during the lifetime of her husband she enjoyed more than the honours of a queen-consert. Thus we find του 'Οσιριν την των όλων ηγεμονίαν Ισιδι τη γυναικί παρα- Died L 17. ворта: moreover Diodorus states expressly that this illustrious precedent established the custom of marriages between brother and sister in Egypt' and led to the greater prestige of women generally : Νομοθετήσαι δέ φασι τούς piod L 27, 5. Αίγυπτίους παρά το κοινον έθος των ανθρώπων γαμείν άδελφας διά το γεγουάς της Τσιδος επίτευγμα . . . διά δε ταύτας τας αίτίας καταδειχθήναι μείζονος έξουσίας και τιμής τυγχάνειν την βασίλισσαν του βασιλέως και παρά τοις ίδιώταις κυριεύειν την γυναϊκα τάνδρας, έν τη της προικός συγγραφή προσομολογούντων των γαμούντων άπαντα πειθαρχήσειν τη γαμου-This surprising statement Mr. Mahaify dismisses in a foot-note as Mah. Emp. Iv. probably too strong, though he admits that the remark gives a true general it 414, note 2. impression. And indeed recently found papyri point to a remarkable degree of legal and social freedom of women. Egyptian women (as the two names-Greek and Egyptian-prove them to be) appear frequently in the papyri concluding bargains, stating accounts, making petitions, lending money, even selling land. The Egyptian woman is legally 'capax'-a fact which no doubt horrified and perplexed the Greek conquerors and, in deference no doubt to these scruples, we find in some documents that the woman's husband or a male relative is added as her legal κύριος in transacting business: but Grenfell, this is not till the time of Ptolemy Philopator, and the innovation is intro
GR. Pap. 1.

Auced by a royal rescript (πρόσταγμα) during the earlier part of the reign of that unpopular and anti-nationalistic king. It seems then literally true that Horal, il. 55, al yuvaixes ayopaζουσι και καπηλεύουσι, and the remark is not due merely to the bewilderment of the simple Greek traveller in the land where the inhabitants τὰ πολλά πάντα έμπαλιν τοίσι άλλοισι άνθρώποισι έστησαντο ήθεά τε και νόμους. The maxim ascribed to Osiris that 'it is a virtue in woman to let neither her person nor her name cross the threshold '(Synes, doprov. i. 13.) obviously belongs, as Wiedemann points out, to a late date when Wiedemann, Hellenic ideals were attributed by an anachronism to early Egypt,

At any rate we find women figuring in a prominent position in the Grenfell Papyri. In one (xviii) we find Apollonia, or Semmonthis, the wife Granfell, Alex. of Dryton, lending wheat without interest to Apollonius and his wife Herais; in the next (xix) the same Apollonia appears lending money to Nechoutes; and again in xx to Saeis and Harmais and their mother.2 In the third will of Dryton (Pap. xxi) we find it expressly stated that his wife is to retain her earnings: όσα δ' Δυ φαίνητ αι έπ]ικτη έχουσα ή Σεμμώνθις όντα αυτήι συνούσα Δρύτων, κυριευέτω αὐτών. In xxvii Sebtitis codes to her daughter half an aroura of corn-land; in xxxiii we again find women selling land. In

Harod ii. 10 148.

Brotis Frag.

Grow. Gk Pap. I XIX

TX. XXI.

XXVIII EXXIII

ILS - VOL. XVIII.

It is appelless to point out that it must have been the other way about. The custom gave rise to the myth : the myth did not give rise to the custom. Such 'actiological' mythe are of universal occurrence. Every social fact

works out its divine protetype.

² In all these cases, however, Apollonia seta with her husband us adores according to the re-cript of Philopator mentioned above.

reil

xvii two women claim to be reinstated in the possession of property inherited by them from their father. The testimony of this papyrus is exceptionally interesting. From it it appears that the property had devolved on the daughters as the natural heirs-at-law-του πατράς ήμων καταλιπόντος ήμων τὰ ἐψάργοντα αὐτῶ άδι άθετα, while the nearest male relative apparently took advantage of the introduction of Greek ideas, and violently took possession —κατά το συγγενικον επελθοντες [άγχι]]στείαν άπογραψάμενοι ούτε κατά διαθήκην. And this, too, though the plaintiffs had duly paid the succession duties to the queen, i.e. the fiscus—ἐνήλικοι δὲ [ἡμεῖς γενό]μεναι τὰ καθήκοντα τέλη θεωι Βερενίκηι κυρίωι έδωκαμεν. The demotic marriage-contract of the Records of the reign of Ptolemy Philadelphus translated by Révillent in the Records of the Past shows how carefully the wife's interests were safeguarded.—'Thy pocketmoney for one year is apart from thy toilet-money; I must give it to thee each year, and it is thy right to exact the payment of thy toilet-money and of thy pocket-money, which are to be placed to my account. I must give it to thee. In case I should despise thee, in case I should take another wife than thee. I will give thee twenty argentens. The entirety of the property which is

mine, and which I shall possess, is security of all the above words, until I have accomplished them according to their tenor The writings which the woman Tahet, my mother, has made to me concerning one half of the entire property which belonged to Pohelchons, my father, and the rest of the contracts coming from her, and which are in my hand, belong to thee, as well

as the rights resulting from it."

Hercel ii. 35,

Such being the Egyptian woman's legal privileges we need not wonder at her legal obligations so puzzling to Herodotus: τρέφειν τους τοκέας τοίσι μέν παισί οδδεμία Ανάγκη μή βουλομένοισι, τήσι δὲ θυγατράσι πάσα άνάγκη και μό βουλομένησι. Similarly contracts have frequently been found binding a wife to bury her husband and maintain his temb, and one which seems to exact this tribute from a daughter towards her father. This seems to indicate that the family tomb may have in some cases been the special property of a woman-heir, a fact which is paralleled amongst the Nabataeans, in which people the position occupied by women is very high, as we know from coins, The tomb, as Robertson Smith points out, is one of the sacra of the family and was practically entailed; that such sacra could be transmitted in the female line is very significant and points to an old law of female kinship. up of p. sis. The old family system, he adds, obsolete in political life, prevails in the

Whelemann, Her, il. p. 183 Pap, Balan. x. 2.

> Robertson Ben(th. Knaday and Marringe, 11. 313.

on oil p. 84, grave. Again he says, 'in the system of marriage with female kinship,

there is no object to be served by excluding women from rights of property. The woman remains with her brothers, and her children are their natural heirs." The independence of women in Egypt, therefore, socially, legally and

politically, seems to lend some justification to the theory that it may be a survival based on female kinship.

Coming new to the history of the individual Ptolemies, I shall try to illustrate these principles from the different reigns.

Ptolemy I, had come to Egypt fully imbued with Alexander's views; he

had already participated in the scheme of Oriental matrimony, having married Artakama, daughter of Artahazus. At first he ruled merely as satrap under the boy king Alexander IV. He did not assume the title of king till about the year 305 n.c. according to Lapsius, though Alexander IV. died in Laps JAL. 314 B.C. At one time he entertained the idea of rendering his sovereignty legitimate after the fashion of the Diadochi by marrying a member of Diad az 37. Alexander's family, but this was before he had dared to believe in the possibility of founding an independent sovereign line. His marriage with Alexander's sister, Cleopatra, was frustrated by Antigonus, but doubtless Mak Emp. Pt. Ptolemy had already begun to recognise that nothing was to be gained by alliance with the house of Alexander. He had no intentions of laying claim to the Empire, and he had every reason for avoiding the jealousy of the Diadochi, pertain to be evoked by such a marriage. His object, therefore, was to establish the divine right of the Lagad family and to get the priests to recognise the foundation of a new sacred line of kings. For in Egypt, more Leps. 16th. than in any other ancient country, it was the unbroken chain of succession alone that constituted the sacred nature of sovereignty. Hence Alexander the Great and his nominal successor Alexander IV, are set uside by the cults as irrelevant.2 Soter could not succeed Alexander IV .: the only way to establish his divine right was to glorify or discreetly conocal the pedigree o the Lagidae 2 and to ignore the line of Alexander, when they had once made up their minds to abandon the theory of their descent from Philip, mentioned as a current Macedonian belief by Pausanias. I am tempted to believe that Paus t 0, 2 Ptolemy's third marriage with Berenike was a diplomatic move in some way connected with this policy, and that there were reasons of state, probably urged by the priesthood, for accepting her as the foundress of the future limof Lagid kings rather than Queen Eurydike. The marriage with Eurydike, the daughter of Antipater, in the early part of Ptolemy's reign (321 B.C.) had been dictated entirely by foreign policy. Four years later (317 B.C.) we hear of his marriage with Berenike, a grand-niece of Antipater, who had come to Egypt Mah. Sup. Ft. in Eurydike's suite. As Mr. Mahaffy says, ' Polygamy was now the rule among the Diadochi, but so distinctly political were their marriages, that a new alliance did not imply even a divorce of sentiment between the husband and his previous wife. In the present case there is no evidence that Eurydika was divorced, neither do we hear of any domestic conflicts between Eurydike and Berenike.' Mr. Mahaffy, however, does not allege any political reasons for this new alliance, nor does he try to explain why Eurydike so meekly suffered herself to be set aside. Now the only extant statement with regard to

466

p. 87.

How strongly the idea of forming a dynasty took hold of the Prolemies is seen, as Lepsies remarks, by the unvarying reputition of the name Ptolemy with each king, as well as by the similar temlency to repeat the same names in the case of the oldest daughter of the royal family.

² Alexander is not Peta, und at Alexandria. only these he have a pricat,

⁴ It is abguilleant that Porphyrius, in giving the parentage of Soter, puts his mother's same Brut - Brahaming & Aparengs and Adver with (Maller Fr. h. Gr. 3, 719).

Lepa. dhi.

450.

Berenike's parentage is that of the scholinst on Theocritus, who says that she was a daughter of Lagus, hence a step-sister of Ptolemy. This, Mr. Mahaffy points out, is probably a missonception arising from the formula wife and sister' applied to Egyptian queens; but it seems to me possible that the statement, whether true or not, indicates the beginning of a deliberate attempt to patch up a Lagid family-tree in accordance with Egyptian notions. According to Maspero (Comment Alexandre devint dieu en Egypte, Annuaire de l'école pratique des hautes études, 1896-7) La noblesse de chaque membre d'une maison pharaonique et ses titres à la couronne se mesuraient sur la quantité de sang divin, qu'il pouvait prouver ; celui qui en tenait de son père à la fois et de sa mère prenaît l'avance sur celui qui n'en avait que par son père ou par sa mèra seule. Mais là, une des lois égyptiennes qu'on observait avec le plus de rigueur intervenait pour établir des distinctions qui ne peuvent plus être observées dans nos civilisations modernes. Le mariage entre frère et weur était le mariage par excellence, et il acquérait un degré de saintelé ineffable lorsque le frère et la soonr qui le contractaient étaient nés eux-mêmes d'un frère et d'une some isms d'un mariage identique un leur. Cette particularité des moeurs égyptiennes, qui nous paraît un caffinement d'inceste, avait produit des conséquences importantes pour l'histoire du pays, et tout un ensemble de dispositions légales ou de fictions religieuses était destiné à en assurer l'effet dans les questions de succession royale, ou à remédier aux insuffisances de legitimité qu'elle entramait souvent parmi les héritiers mûles.' Thus in the traditional way Ptolemy Soter was to marry a kinswoman who was to be the ancestress of the royal line, and it was only when such a line had been founded that divine honours could be paid. Hence, possibly, the delay in the Schol Theory delification of Ptolemy L, which seems not to have taken place until after his M. xvil 17 ff. death in 271 B.C. That Soter was not fully acknowledged in the cult till Mah. Emp. Pt. late in his son's reign, is shown by the Aswan stele on which the series of gods begins with the gods Adelphi and omits all mention of Alexander and the gods Soteres; on the other hand this late recognition may be explained by the fact that the stele was connected with an Amm foundation, in which cult the Lagids may have been less readily acknowledged. Similarly we are not surprised to find the cult of Soter at the colony of Ptolemais at a time when it was not yet established at Alexandria. At any rate it seems clear that the divinity of the Lagid line was not duly recognised till established in the second generation, and that Alexander and his house were studiously set aside. Kaerst (Die Begrindung des Alexander- und Ptolemacer-Kultes in Aegypten, Rhein. Mus., 1897) connects the deification of Ptolemy Soter closely with that of Alexander. It is, according to him, no reiner Aegyptismus' but has an Hellenic basis, though wir finden insbesondere in Bezug auf die Ptolemaeer eine fortschreitende Aegyptisirung des Königskultes, sodass zuletzt das lagidische Königthum als ein verjüngtes Abbild der alten Pharaonenherrschaft erscheint. On my theory the conscious 'Aegyptisirung'

³ Theoretins himself in unhellende fashion calls her 'Arrivira: Suydrap and avoids all mention of her father.

begins earlier and is already discernible in the matrimonial policy of Soter.

In 285-4 B.C. Ptolemy Soter definitely decided the succession question by associating his younger son, Ptolemy, in the government, practically abdicating in his favour,1 It is apparently only at this point that Eurydike and her children withdrew: hence we may infer that the question was an open one till this date. On the assumption that there were no diplomatic reasons for considering Berenike more suitable to be the royal ancestress of the new line, this act was a mere arbitrary solution of the difficulty. Ptolomy Philadelphus seemed the most capable successor; Ptolemy Soter felt himself secure enough to enforce his choice; so the natural heir was set aside and his more competent younger brother preferred. On the other hand if there is any truth in the theory put forward above, the accession of Philadelphus was due to an undercurrent of political and priestly intrigue. I shall try later to show how such a theory bears on the actions of the disinherited children of Eurydike, and how they availed themselves in the next reign of party politics to further their personal claims. It is well to note in passing that Arsinoe, the eldest child of Berenike, who plays such an important part in the following reign, was at this time outside the range of Egyptian homepolitics, having been married in 300 B. C. to Lysimachus of Thrace.

This abdication of Ptolemy I., to whatever motives it was due, was well Mah. Eng. Pt. received, and the coronation of the new king was an occasion of great public rejoicing. That the step, however, was an experiment prompted by political expediency seems likely from the testimony of Porphyry and Diogenes Lacrtius, who imply that the old king continued his kingly functions in op. cit. p. 196. partnership with his son.

mile I. op. 10%, p. 488

The idea that a king should abdicate voluntarily while in full possession not on p. 10d. of his faculties is a very usual one in primitive forms of civilisation, as Mr. Frazer points out in The Golden Bough, and is in such cases probably based on animistic conceptions of the function of the king. He is the sacred receptacle and guardian of the aggregate vitality of his people, and this vitality he must transmit intact to his successor while his faculties are still unimpaired : in fact the death of the emeritus monarch was usually held to be essential to the preservation of divine kingship. Now there are various traces of this primitive custom in Egyptian and Aethiopian records down to a comparatively late date, whence I argue that the action of Ptolomy I, would be not only comprehensible but even fraught with a religious significance to the less civilised portion of his subjects. I do not mean for a mement to

Poole, Egypt, Ency. Hr.

In a similar way Sett L., was of the married Rameses L, having strengthened his claime by marrying a granddaughter of Amenophia III .. associated as his colleague in the sovereignty his son, the legitimate heir, Ramuses II. As this position was ignored owing to its vagueness, Seti finally abdiested altogether.

² Cf. Diod. L 72, 4 of yap advor to abetuum

rur leptur while nat outlings fragers of ear Alyperos oby eles persuase no recres not the balur tür beapydetur abrais ayabür topaterifor by the the Beaudius dopadeius.

It is to be feared that the unitives which actuated this solicitude were less strictly alteristic and loyal than the historian imagined.

imply that he was consciously influenced by any consideration of the kind; but I think it might possibly enter, as an additional advantage of the step, into the calculations of his advisers the priests, who were well versed in such popular superstitions, and know how to work them for their own advantage.

We may infer from the unflinching severity with which this otherwise humane king treated his dangerously near relatives, and from the actions of these relatives themselves, that the new king's succession was by no means Page 1. 7, 1. left unchallenged. At the beginning of his reign he killed his elder stepbrother, Argaeus, and perhaps, according to Pausanias, another brother as well. His full-sister, Arsmoe, as I have pointed out, was at this time safely disposed of-one of a series of diplomatic marriages uniting Egypt at blab Emp Pa this period with Thrace. In the same way a half-sister of the king's, Lysandra, was also wisely relegated to a distant land. Similarly Theoxens, a p. 11%. daughter of Berenike by a former marriage, had been disposed of by her step-

father, Ptolemy I., in 307 B.C. But naturally the chief danger was to be expected from Keraunes, the

dispossessed son of Eurydike. If Philadelphus found it necessary to deal so harshly with his other brothers, it is probable that Keraunos was not without supporters, and we may be sure that this crafty and unscrupulous prince knew well haw to work party politics for his own advantage. He never lost sight, I believe, of his ultimate object—the throne of Egypt—and his schemes in Thrace were merely stepping-stones towards this end. On being ousted from the succession he withdraw to Thrace, where he espoused the cause not Mah Emp. P. of his full-sister, Lysandra, but of his half-sister, Arsinoc. In fact, he recognised that, since Berenike had been accepted as the queen-mother, Arsinoe, her chiest child, would according to Egyptian notions have claims on Justin, 24, 2 the throne in her own right. Hence, as Justin fully describes, he persuaded the reluctant Arsinoo II. to marry him, at the same time craftily writing to assure Philadelphus that he has 'laid aside all resentment at being deprived of his father's kingdom. No sooner had he gained his point than he murdered Arsinoe's children before her eyes. Having been discredited in Thrace he fled to Selenkos in the hope of stirring bim up against Egypt, but his career and further claims were here abruptly cut short by his death in battle against the Gauls.

Another troublesome calation was Magas of Cyrone, Philadelphus's halfbrother. Being a sen of Berenike, the acknowledged queen, Magas would not consider himself so entirely outside the line of succession as modern ideas would lead us to suppose. To quote Lepsius: 'nach Ptolemaischem Erbrechte scheint es, dass nach dem Tode des Königs zunächst seine Wittwe den Thron beanspruchen konnte und nur genöthigt war, den mannlichen et p tot. Thronfolger zum Mitregenten anzunehmen, and again, das Recht der Thronfolge musste auch das der Uebertragung der Mitregentschaft auf einen Genuald oder einen Sohn einschliessen. With this compare Justin xxx. 3. 1, 'inter has regui Syriae parricidales discordias moritur rex Aegypti Ptolemeus (Euergetes II.), regno uxori et alteri ex filiis, quem illa elegisset, relicto. It is thus possible that the queen-mother may have had some choice in the

Lapa. Abb. ji. 173.

p. 115.

note 1.

matter; we find Cleopatra III, apparently preferring and dismissing her sons at her own pleasure. At any rate we can imagine that the rights of the queen-mother would naturally often lead to family intrigues. Therefore the revolt of Magas may have been based on these to us shadowy claims, especially as Berenike is said to have favoured thus rebellion. At the have been wish-sharps, vol. 1 ful to single out Magas as her co-regent. This disaffection in Cyrona may be the reason of the omission of this province from the list of Egyptian possessions given by Theocritus; while the similarly puzzling omission of Cyprus Theory axis may be connected with Pansanias's remark, ἀπέκτεινε δέ καὶ ἄλλον ἀξελφον Pans. 1.7, 1 γεγονότα ἀξ Εὐρυδίκης, Κυπρίους ἀφιστάντα αἰσθόμενος, and point to a similar state of disturbance there. The claims of Magas were finally silemed by the betrothal of his infant daughter Berenike to the cream prince Europetes, Instin. 24, 3, which united the claims of the brothers.

This betrothal was nearly broken off owing to the plats of Demetrine the Fair, another pretender, I believe, to the throne of Egypt. This Demetrius was the son of Demetrius Poliorketes and Ptolemain, a daughter of Eurydike Plut. Don. 47. and Ptolemy I. Apane, the mother of the young Berenike of Cyrene, or Man. Zoon Pt. rather the anti-Philadelphic party in Cyrene, conceived the plan of uniting the claims of the rival branches by marrying the young princess to granddaughter of Berenike I.) to Demetrius (a grandson of Eurydike) and thus strongthening and combining the opposition to Philadelphus. Justin gives Justin, 26, 2. an account of this scheme and of its frustration owing to the fickleness of Demetrius: sed post mortam regis mater virginis Arsinoe (Apame) ut invita se contractum matrimonium solveretur, misit qui ad nuptisa virginis regnumque Cyrenarum Demetrium a Macedonia arcesserent, qui el inse es illio Ptolemei (Soteris) procreatus erst. His subsequent intrigue with the queunmother having been discovered. Demotrius was put to death, the anti-Philadelphic party was discredited, and the former betrathal of Bereniko to Energetes was confirmed. Itaque versis omnium animis in Ptolemei filinm insidiae Demetrio comparantur.

Such, then, were the difficulties which beset Philadelphus during the early part of his reign. There is another member of the family worth commenting on, not from the difficulties she occasioned, but from her apparently meek submission to state exigencies, -I mean Philotera, the king's full-sister, Mah. Hop. Ft. who seems to have remained unmarried. In return Philadelphus paid her more than the usual honours of a royal princess: she accompanied the king sirabe, 18, 4, 5. and queen on royal progresses, and cities were called after her. This, as Sharpe points out, was no idle compliment; the princess probably received Sharpe, vol.). p. 314. the crown revenues from these cities, just as we know that Arsinoe II. received the revenues of the Arsinoite nome. Indeed Letronne goes so far Letronau. as to assert that all the colonies founded by Philadelphus were named after his second wife or his sister Philotera, -his two full-sisters. Mr. Mahaffy, how- Mah. Engs. Pt. Pr 17h P. 135.

likewise profited personally less than we nuglit Mah. Esop. Fr. suppose from the revenues of these foundations. Chronal Table, p. 201.

However, since there is remon to believe, as we shall see below, that this was merely a convenient state action, perhaps Philotera

ever, denies this, stating that he has found other village-names mentioned in the Petrie Papyri, such as Lagis, Lysimachis, etc., founded by this king; though this perhaps scarcely refutes Letronne's statement regarding the establishment of colonies. I fail, moreover, to understand why Mr. Mahaffy cites the colony of Philadelphia (Rabat Amon) as an exception to the rule. Mah. Emp Pt Surely that name more than any other stamps the colony as a foundation in р. 112. поје 1. honour of his wife Arsince II., who alone at this period bore that name, op. co. p. 116. Philotera was further honoured as a goddess with a shrine at Memphis, a cult established according to Mr. Mahaffy by Philadelphus, though Lepsius assigns

its foundation to Euergetes.

This brings me to what is the crucial point in my argument—the second marriage of Ptolemy Philadelphus. The date of this event is uncertain, but Lepsius and Mr. Mahaffy place it about 277 B.C., that is, a few years before the second visit to Pithom. It seems possible that the step may have been advised by the priests during the consultations of the previous visit soon after the death of Lysimachus, and its accomplishment may have been postponed by Arsince's meantime falling a victim to the schemes of Keraunos. We have seen above the numerous difficulties which beset Philadelphus and prevented his full recognition as monarch. On my theory these difficulties could be finally settled only by this alliance with his sister Arsinoe. This Mali. Ruys. Pt. Arsinoe was the eldest child of Ptolemy Soter and Berenike, and, if the rights Table, p. svil of Eurydike's children were to be set aside, might claim to be the legitimate heir.

Вгоуман. Hell. 11. p. 234 seq.

Chronola

Lepu. Abb.

p. 500.

The reasons usually alleged for this marriage seem to me inadequate and unconvincing. Droysen (and with him Strack) believes that it was due to the proprietary claims which Arsinoe had on certain cities of the Euxine such as Cassandrea and Pontic Heraclea. But if it is true, as we hear, that Philadelphus had later to carry on an elaborate naval war to bring these cities into submission to Arsinoe, one is tempted to fancy that he might have helped himself to them, even without the sanction of matrimouy, had they been his sole object.

Koepp Received Koepp thewise connects the seep with the widow of King Lysi-Keepp likewise connects the step with foreign policy. According to his Mah. p. 132. machus, to attach the old subjects of the Thracian King to his cause in the war against Syria. We must remember, however, that Arsince, not long after the death of Lysimachus, had consented to marry the usurper Keraunos, her step-brother. Besides, immediately after this marriage she had been Mah Emp P. banished by Keraunos to Samothrace, where she seems to have lived in retirement during the few years before her return to Egypt. It does not seem likely then that an alliance with her would have greatly strengthened the bond between Thrace and Egypt.

P. 199

⁴ If we are to accept the date 277 m.c. as the approximate time of her marriage to Philadelphus, though Wiedemann (Philol. N. F. L. \$1), puts it as late as 278 u.c. Lysimachus

died in 281 p.c. : presumably she did not Justin, 24, 2. marry Keraumos quite at once, as Justin dwells on her reluctanon.

Holm, on the other hand, believes that the marriage was due to personal Holm, Or, affinity of character:—'ich glaube die Hauptsache war die Uebereinstimmung Gend. vol. iv. der Charaktere. Beiden war das Höchste Herrschaft, Intrigue, Lebensgemuss. Sie verstauden, halfen sich gegenseitig und verziehen einander ihre Fehler. Even accepting this estimate of their characters, one does not feel the cogency of the reason: the history of the period parades before our eves a long succession of personages of both sexes sufficiently endowed with such qualities, and one cannot belp believing that Philadelphus might easily have found a congenial consort, without shocking his Hellenic subjects by such a serious departure from Greek customs. Besides, he cannot up till close on the time of the marriage have seen much of this sister; we must remember that she was married to Lysimachus in 300 a.c. when Philadelphus was only eight years old! Nor can she have been long in Egypt immediately before the marriage (if we accept the date 278-277 B.C. for that event 1), for after 281 she married Keraunes and lived some time Mab. Eleg. Pt in Samothrace, long enough indeed to become imbued with Samothracian celigion, as she built a temple there to the Kabeirol,

Mr. Mabaffy also inclines to the theory of personal attraction, though he is anxious to discount the flatteries of court poets: he dwells on her remarkable intellectual ability and the tact with which she adapted herself to her position; he believes that she was by no means good-looking. We must remember that she was about forty, considerably older than the king, and that her life had been a troubled one.

But the most serious objection, which applies to all these theories alike. seems to me the fact that they treat the marriage as an isolated instance and do not take into account the subsequent brother-and-sister marriages in Ptolemaic history. Everything, therefore, seems to point to the conclusion that the marriage was due to diplomacy. There is no trace of any violent rupture with Arsinoe I., who seems to have lived afterwards in semi-regal state at Koptos. It is true that she is reported to have plotted against her Mah, Koop, Fr. husband's life, but no definite evidence of this is forthcoming, and it seems p. 187, note 2 very unlikely from what we know of her subsequent position at Koptes. It is just the sort of rumour that would inevitably arise to explain her retirement to the Hellenic world. On the other hand, Arsinoe II., being herself Theory, 17 childless, adopted the first queen's children. On the stelae of Pithom and of Granfall and Mendes Energetes is actually represented as the son of Arsinoe II.2; so too Mah. Remove on the Canopus stone he figures as the son of the θeol ἀδελφοί. Strack Pos. Introl.

p. 280.

p. 189.

p. 141.

¹ From Mr. Mahaffy's own argument there Mah. Emp. Pt P. 133. seems to be no special reason for dating the marriage much before 273 a.c., the date of the second visit to Pithom mentlaned above, though he firm on 278-277 a.c. This seems to growd too much into the years 281-278 a.c. and I should feel much more satisfied with a later op. cit, p. 139, date. Mr. Mahatfy points out that there is nothing in the Pithem inscription to show that

the marriage and deification were quite recent. But, on the other hand, is there anything conclusive to prove that it was not ! Kaurst (die Begründung des Alexanders und Ptolemocrkultes in Aegypten, Rhein, Mus. vol. 52) prefers the year 274 a.c.

It is impossible, as Mr. Mahaffy points out, Records Page to believe that the Pithom stele represents an Introd. p. xxii. unknown shild of Aprince II.

Canopus Begree, L. L. (die Dynastie der Ptolemaer p. 88), admits that this suppression of his. mother's name looks like an attempt to establish in the eyes of the priesthood the legitimacy of his succession. He considers, however, that the 'Berühmtheit' solely of Arsince II was a sufficiently strong motive to influence the priests. Arsimo seems to have immediately taken up a position of influence in the country, somewhat perplexing unless based on her own heiress-rights, It is she who is deified with the title Philadelphus which later historians extended to her husband; in the Revenue Papyrus she is referred to simply ns ή φιλάδελφος, whereas Ptolemy is merely one of the θεοl άδελφοί. Thus he appears to owe his divine honours mainly to his wife, as indeed the representation of Arsinoe conferring honours on her husband at the top of the Pithom stele would lead us to conclude.

The testimony of coins, too, is somewhat similar. To quota Strack (op. cit., p. 17) steht ein Fürst an der Spitze des Staales, so beweist sein Name und sein Bildniss auf den Münzen seine Souveranität. Die Ptolemder haben In fact we find on their coins Kopfe und des wenig acht gebaht.' Außehriften von verschiedenen Königinnen.' It is rare to find Philadelphus alone on them; he appears frequently with Arsince II. and she frequently alone. On one struck by Philadelphus we find on the one side the head of Arsinge, on the reverse the double cornucepiae and the inscription "Aporrons Φιλαδελφου (Poole, Pl. VIII. 1); on the reverse of another, which likewise lms Arsinoe's head on the obverse, is the royal eagle and the same inscription (Poole, Pl VIII 3). A noteworthy point concerning the coinage of this reign is the fact that Ptolemy in the first half of his reign does not date his coins from the year of his accession. In Sharpe's words: it is not till the nmeteenth year of his reign, som after the val i p. 335. death of his mother, that he made an era of his own and dated his coins by the year of his own reign.' Thus we have come with the heads of Soter and Philadelphus on one side, on the other the head of Berenike. Now if Berenike died some time before 266 B.C. the nineteenth year of the reign, and if it is possible that the marriage with Arsince II., as I have tried to show, may have taken place rather later than 277 B.C., in fact, immediately before the second visit to Pithom in 273 a.c., it seems not impossible to connect the two events and to find in them the immediate reason for the marriage of Ptolemy at that particular date with Berenike's heiress daughter, and for the beginning of his own comage. This argument would apply equally well, however, even if the marriage took place shortly before Berenike's death; as Berenike grew old Philadelphus would no doubt see the advisability of strengthening his position by the new alliance; there may even have been

Sharps,

Prolemy II. was sutablished," We should usturally expect that the title would first be extended to the king in the Greek city Ptolomais; similarly, as we have seen, it is in this place that the cult of the Soteres in first recognised. The colony was mader the special protection of both Sotor and his son.

¹ In Grandell's Great Pappers, No. XII. (date Grenfell, Alox Eros. Fc. v. 148 a.u.) Piolemy II. is mentioned as Phila-P. 00. delphus. This, Mr. Grenfill observer (note 7, p. 31), is the earliest known reforence to him with this title; thus 'there our be fittle doubt that it was used in the list of kings among the priesthood of Ptolemuis, when the priesthood of

a party in the state ready to put forward the independent claims of Arsince, a party which may have had a section of the priesthood at their back. At Mah. Box P. any rate the same year probably, the nineteenth (266 p.c.), in which Philadel- Table, p. rin phus began his coinage, saw the accomplishment of the climax of Arsinoe's deification-a Canephorus of Arsinoc Philadelphus is established at Alexan-Two years later a further concession is made—we have the first mention of the gods Adelphi. In the same year the third visit to Pithom took place and along with it we hear of fresh religious endowments—a quid Table, p. xix. pro quo, and is tempted to believe,

op, vit.

But the culminating point of Arsinoe's political importance is still to be mentioned. I mean the transference of the awonorpa, or tax of one sixth on wine and fruits, from the temples to the queen in the year 262 B.C. a detailed record of which transference has been preserved in the recently found Revenue Papyrus. This transference, as Mr. Mahaffy observes, puts a very different complexion on the attitude of Ptolemy towards the priesthood. On the priestly monuments we hear only of fulsome votes of thanks to the king for the generosity of his endowments. We know now that his munificance was to a large extent merely a clock to cover this great revolution in taxation. Emp. Pt. which reduced the clergy to the condition of state-pensioners and diverted this great source of revenue into the public treasury. The money went to the fiscus, but it was claimed in the name of the deified Arsinos. As a

Forp. Pt. 1s. 142 mg.

goddless identified with Isis she might claim the Erry without outraging on eit p. 160 national scruples.

As Mr. Grenfell says, It is hardly necessary to point out that the exry Res. Poss. was collected and paid sis to Bagiline's like any other tax. The Ovotar nal cal 35, noted. owordal was an ingenious but transparent fiction to cloak the disendowment of the temples.' The result is that it is one and the same thing for all practical purposes whether the payment is made els 70 Barrareon or to the goddess Arsince -in fact we now know from the newly recovered fragment of Mah. Atherthe Mendes stelle that the queen had died some years earlier, in 270 n.c.

noism, Jan. 16, 1897.

This brings me to the most difficult and intricate point in the reignthe reclaiming of Lake Moeris, and the connection of this event with the queen, Mr. Mahaify, writing before the early date of the queen's death was discovered, is much exercised to decide whether Arsince was dead or alive at the time, whether the renouncing of ber rights to the district was a gift or a bequest. But taking this settlement of the Fayyum in close connection with

Elsep. Pt. p. 150

prouse was not complete till the King's twenty-third year, when the absorbed mu of the great revenues of all the Egyptian gods."

Grons & Mah. Rev. Peps Introd.

According to Mr. Mahaffy; "We know from independent yours that the deideatlen of Areinoa Philadelphus was gradual; that the attrined divin honours, first at one, then at another of the Egyptian temples. The estableshment of a Camphorns or openymous prisates in her honour at Alexandrie, which dates back as far as the year 10 of the rolph, according to demotic documents, opposer to be the climax or consummation of this gradual anothermis. We now know that practically the

As proof that this was the high-order much of her defination one may remember that it is always in connection with this Cinephores of Alexandria that her name is mentioned specially (as well as with her hunband) m one of the seef elekged in the data formulas of subsequout reigns, e.g. Grenfall, Papyri X., XII., XXV., XXVIL

the policy of the preceding years, I would suggest that the explanation is to be

Herock iii. 91, 5

p. 178.

found in the same fact, that the use of Arainoe's name is again nothing but a state fiction,1 that the queen personally gave up nothing, but that the so-called renunciation of her rights merely cleaked the re-organisation of the crownproperty, formerly \(\hat{\eta} \) \(\lambda \eta \psi_n \), now reclaimed land to a large extent. It seems likely from a remark of Diodorns that the proceeds of the fisheries of the lake may have belonged according to ancient tradition in quite a special Died I. 52, 5. way to the queen for her personal expenditure— mpos unpa rai ror allow At the same time Herodotus in referring to these same. καλλωπισμόν, fishery-revenues says that they brought annually two hundred and forty Hered il. 139 talents es ro Barianior and again he alludes to them as part of the state revenues in Persian times. Therefore probably the reclaiming of the land meant not that Arsinoe renounced her personal property for the benefit of the state, as Mr. Mahaffy assumes, but rather that the government to suit its own ends chose to give up at least part of these revenues and by reclaiming the lake gained fartile land which was wanted at the time for special political purposes. Just as the ἀπόμοιρα was diverted into the fiscus in the queen's name, so here the extension of the Lake province and its better irrigation was Mail Boys Pr. attributed to her: we hear of the 'Aporton's Your and hereafter the district

> was officially known as the Arsinoite nome. The position which Arsmon held from the time of her return to the country points strongly to the recognition of her rights as heiress. At the top of the Pithom stele the queen is represented as a deity conferring honours on the king her husband. On a tablet recently discovered at Tanis (Egypt. Explor Fund, Tanis pt. ii., Petrie p. 30, No. 165), Arsince is called 'the Net, the regent of the two lands, princess, lady of thrones'; another tablet from the same place (op. cit. p. 32) represents Ptolemy II, in Egyptian dress offering land to Khem and Arsinoe. There was a cult of Arsinoe Philadelphus at Alexandria as early as 267 p.c.; and even earlier, with the title Philadelphus. she had been associated as σύνναος θεά in the cult of various Egyptian gods. For the deification at this time of her husband in his own right there is no evidence: he merely figures along with Arsinoe as one of the 'Gods Adelphi,' On the other hand the deification of the queen was carried out step by step. as Droysen (Berlin Sitzb, for 1882) points out, leading up to the final stage late in the reign, when a very practical meaning was given, as we saw, to the sovereign lady's divinity. In the face of all those facts and with no single piece of evidence that Ptolemy IL bore the title Philadelphus in his life-time. is it possible to believe with Strack (op. cil. p. 116 ff.) that the title was transferred to Arsinoe from her husband? We have, he admits, examples in later Ptolemaic history of the transference of similar titles from a queen to the king associated with her in the crown: e.g. Soter II, receives from his mother the title Philometer, and later from his daughter the title Philadelphus. He admits, too, that in public documents of the reign Ptolemy II.

how nominal her part in the transaction must have been

As we now know that the more was already dead when the reform took place, we may judge

bears only the dynastic name, and shelters himself behind the rarity of such documents. But surely his theory that 'Philadelphus' was the proper name of Ptolemy II. 'den er nach Erhebung zum Thronfolger mit dem dynastischen vertauscht habe, der dann nicht aus dem Gedächtnis geschwunden und später wieder hervorgeholt sei, als es sich um einen Namen handelte unter dem er verefirt werden konnte' is hardly convincing. And we are asked to believe, that this 'Individualname voll guter Vorbedeutung' was bestowed ou Ptolemy II in his infancy 'dem Stiefbruder (Keraunos) gegenüber, der spliter dle Krone tragon witrde'! If on the other hand, as I believe, Ptolemy II, here the name of Ptolemy in his childhood, the fact that he was given the dynastic name usually bestowed on the crown-prince seems to point to the conclusion that the marriage of Soter with Berenike was a diplomatic move and that Berenike's son was from the first destined for the succession. The deification of Arsinoe as 'Philadelphus' indicates, I believe, her identification with Isis. Other names of the Ptolemies suggest a similarly close connection with the Osiric cult. Dionysus is applied to Philopator and to Auletes; Isis to Cleopatra VII.: Philadelphus again to Auletes and to Ptolemy the son of Cleopatra VII. Possibly Euergetes belongs to the same cycle, for Plutarch (de Iside et Ostride, 42) says: то б' ётерог биона του θεού (Osiris) τον "Ομφιν εύεργέτην ο Ερμαίος φησι δηλούν έρμηνευόμενον.

Coming now to Euergetes we are first struck by the date of his marriage. which took place according to Callimachus in the year of his accession. We know that he had been betrothed to his consin Berenike for years; we know, too, that he must have been about thirty-three (taking Lepsius's date, 281 B.C., for the first marriage of Philadelphus) at the time of his accession, while Berenike must have been of a marriageable age before this date, if she was old enough at the time of the crisis at Cyrene in 258 B.C. to play the part described by Justin.1 Why then had the marriage been delayed so long ! Mr. Mahaffy suggests that 'there must have been some law or Justim xxvi 3. tradition of the old Pharmonic royalty on account of which the wife of a Mah. Emp. Pt. prince royal could not be elevated to the dignity of reigning queen.' He goes on to point out a fact most important for my argument: 'It was not the habit of Ptolomaio crown-princes to get married before they ascended the throne." Elsewhere he says: 'In most other monarchies a suitable bride is found for the crown-prince as soon as he is of age : in Ptolemaic Egypt I have observed Mala Introd. with surprise that this is against the practice of the court, though the reigning Page, it xxx. Ptolemies marry as soon as possible. Philadelphus, though grown-up in 290 B.C., does not apparently marry until his assumption of royalty-in the opinion of some critics, not till his father is dead. Euergotes, though long grown-up, seems to have no wife till his accession; Philopator, succeeding at about the age of twenty-four, has no wife till some years later. We hear of no wife of Energetes II. till he mecceds in middle life and marries the widowed

Elile. Cheutfun, p. 289 my.

Lepu Beel. AH 11. 503.

p. 491.

Mah. Emp. Pt. 1 To explain this discrepancy it has been seven at the time of the disturbance, which p. 136, note l. assumed that Berenike was a child of six or seems scarcely likely.

would doubtless have been married before his early death, but for this curious court tradition. A satisfactory explanation of it I have not yet found. Mr. Mahaffy suggests that only the child been in the purple was legitimate; but with the remark of Lepsius (already quoted) we may perhaps find a sufficient ground for this 'court tradition' in the full rights of the late king's widow to nominate her successor and the necessity for that successor to form an alliance in accordance with Egyptian notions with a view to increasing 'la quantité de sang divin."

To apply this solution in detail. Philadelphus apparently did marry before his mother's death. Hence the comparatively insignificant part played by his first wife, and her repudiation perhaps at the time of the queen-dowager's death, leading to the marriage with the great queen Arsinon II., and the beginning of the personal coimage of Philadelphus. If on the other hand this second marriage took place before the death of Berenike, it is probable that the first important step in the deification of Queen Arsinon (266 B.C.) at least followed closely on the death of the queen-mother. As the deification did not begin till four years after her own death, it can hardly be directly dependent on that event. Hence I argue that her recognition by the priesthood was connected with the queen-dowager's demise.

What then can have delayed the marriage of Euergetes to his cousin Berenike (We know now that his mother, Arsinoe, had died years before, and Euergetes himself had been already associated for years in the government. There seems, therefore, no reason for the puzzling delay. We know, however, that his betrothal to Berenike, the daughter of Magas, was occasioned by State emergencies. May we not suppose, therefore, that, the emergency having been tided over, there was a party in the State which expected the heir apparent to ally binaself duly with his own sister Berenike? Such dissensions may serve to explain the change in the formulae in public documents. The name of Euergetes appears in them frequently in the 19th, 21st and 24th years of the reign of Philadelphus (all subsequent to the death of Arsince). In the 27th year the name of Euergetes disappears. Now in the 27th year, 258 s.c., the plot of Demetrius the Fair at Cyrene was discovered, and the betrothal of Energetes to the daughter of Magas was ratified. At this time the other Berenike was not disposed of; and if there was a party which advised a marriage between Euergetes and his sister, it may have been strong enough to bring about the withdrawal of the Crown Prince's name from public documents when he was betrethed to his cousin. In the year 248 B.C., probably, the policy favouring the marriage with the Cyrenaean Berenike once more triumphs. Berenike, daughter of Philadelphus, is married to Antiochus II., and in the following year—the year of his accession-Euergetes at length marries his cousin Berenike. Prolemaic history hardly justifies un in regarding these events as a final solution of

Lumbrous, Hist, d'éco., pel, sous les Lagides, p. 172.

¹ Cl. Lumbroso, 'Il arrivant nontefous que le rel constituit son successour en conflit le chaix il son éponsé (Justin 29, 1).

the difficulty. This solution comes only with the death of Berenike in Syria in the following year, an event entailing the dissolution of the party favouring her interests and perhaps connected with the "domestic revolution" which, according to Justin and S. Jerome, recalled Euergetes from his campaign in Asia. These disturbances were finally settled in 238 B.C., when the priests in assembly at Canopus conferred on the king and queen Canopus Dec. well established monarchy -οί θεοί δεδώκαστε αύτοις εὐσταθούσαν την βασιλείαν καὶ δώσουσιν τάλλ' άγαθὰ πάντα είς τον ἀεὶ γρόνον. Το understand the queen's position we must remember that she was the grandlaughter of Ptolemy I, and Berenike I.1 It is the queen's head that appears on the obverse of aix copper coins quoted by Svoronos (Coll. of Joh. Demetrius), Justin, Justin while on the reverse is the inscription II rolepaiou Barilésis. Hence on the d'arch Num

vol. L. pt. 2, 1808

king's coins appear the insignia of the queen."

Lope Haw Denr. p. Bl.

It is not known whether the child Berenike so exceptionally honoured in the Canopus Decree was the eldest child; but this assumption alone seems to account for the supreme honours conferred on her at her early death, and it is Camp. Der corroborated by the evidence of the heraldry on her crown ;- eivas δέ την έπιτιθεμένην βασιλείαν τηι είκονι αυτής διαφέρουσαν της επιτιθεμένης ταίς είκοσαν τής μητρός αυτής έκ σταχύων δύων, ών άνα μέσον έσται ή άσπιδοειδής βασιλεία (Hieroglyphic version translated by Lepsius—' seiend eine Urausschlange zwischen ihnen '). Strack (op. cit., p. 5) bases his argument that the title Bagilioga does not in itself imply association in the government on the fact of its application to this young princess. He argues that it is impossible to suppose that the title implied anything of the kind in her case, We know, however, that Epiphanes was associated (and possibly also Philameter) while still an infant. Strack admits, moreover, that Cleopatra II. and Cleopatra III. were queens regnant and yet they contented themselves with the simple title Bao (λισσα,

Ptolemy IV. Philopator must have been grown up on his accession in 222 R.C., for demotic scholars say that he was formally associated with his Mah. Emp. Pt. father in the sovereignty and probably did some of the official work during his father's decaying activity. He was not married, however, nor did he marry for many years after his accession. We know that his mother Berenike II. survived her husband : even assuming that she was thirteen or fourteen at the time of the crisis at Cyrene, she may quite well have lived up till the date of her son's marriage in 213 B.C., as she would only be about sixty then. She may, however, have died some years carlier, when Philopator was too much occupied with his foreign campaign to think of matrimony," Hence the delay of probably nine years between his accession and his marriage Main Emp. Pt

Lorger Abh P. 503.

Chronol. Table, p. 20.

before Bereafke's marriage, and that Emergetes appears on them merely as the betrothed of Berenike.

In the Adultan inscription in the Hat of U LO. 5127. Mah. Emp. 17. territories which Energetss received from his ji. 199, note 3: father raphable raph too rather there is naturally no mention of Cyrene which came to him from his wife.

I tunnot believe with Sycremes that these coins are Cyrenian, belonging to the paried

In fact there were reason to suppose that Mah. Elect. Philopator cancel his mother to be put to p. 248 k m. t 4 death. Polyhins, zv. ch. 25.

with his sister, Arsince III., in 213 B.C., in which some year the king and queen were deified as gods Philopatores, - an event which, I believe, marks a change in his policy and a compromise brought about by the native revolt of the same year. The revolt may have been largely caused by this very delay in his marriage; his mother being now dead, national prejudice saw no reason for loyalty to the son, or perhaps allegiance may have even been transferred to Mah. Emp. Pt. the late queen's heiress-daughter : in fact we know what an important part

p. 205. Polyh v. 69. this princess played in the Raphia campaign.

With regard to Epiphunes the evidence is neutral. His mother. Arsince III., wife and sister of Philopator, was dead before his accession and he himself was an only child. If we accept the testimony of Polybius xv. 25, the murder of Arsince III, was doubtless instigated by Philopator because of her presumptive royal rights, and in the same year (according to Lepsius) Epiphanes was associated in the crown. In the three dedications quoted by Strack (p. 11), the queen's name occurs, as Strack points out, in the two first, while in the third it is omitted, and the epithets and titles of Philopator, her husband and murderer, have become more fulsomely flattering. know that Arsinoe III. was honoured with a cult at Alexandria.2 appears frequently on coins (Poole, Pl. XV. 6, 7). Her death left her only child, Epiphanes, in the exceptional position of sole claimant to royal rights. Hence his marriage was unessential to his full recognition, and at his Anneleteria he received at the age of fourteen complete divine honours, as we know from the Rosetta Stone. There he is already treated to a two-fold divine title - Goos Emidaris Euxapioros. Indeed as Mr. Mahaffy says, These honours are far more extravagant than those given to Energetes, and are to be compared to the henours assigned to the dead child Berenike."

Male. Emp. Pt. p. 320

Struck, op. cu., p. 12, note 1.

Crenfell.

Gk, Pap. x. 1. 3.

Lague 1933.

Of the mysterious Eupator's brief reign (in the year 182 B.C.) and matrimonial prospects we know nothing. If, however, he was the elder son of Epiphanes and Cleopatra I., as seems certain from his position in the nine hieroglyphic lists mentioned by Lepsius, where he appears as 'der von einem Red. Ak. p. grossen Vater entsprossene Gott, in each case immediately preceding Philometor, the absence of all records of this short reign may be due to preference on the part of the queen-mother for her younger son. One is tempted to see traces of two rival parties in the names conferred on these two brothers. In any case, the unobtrusive manner in which the child-king (he cannot have been more than ten years old) appeared and disappeared is easily accounted for by the ascendency of the queen-mother. The government centred in her and the death of one son and the assumption of another as co-regent were matters of little importance. The younger brother, Ptolemy VII Philometor, succeeded in the same year, the queen-mother, Male Evep. Ft. Cleopatra I., surviving till 174 a.c. In the following year Philometer married

P. 324

Granfell, Pap. X. mouttimes a lepela 'Aperedne Dinondropos ir 'Anstardpelas, So too, Paje XII. 1: 5 and XXV. col. 2, 1: 6, and XXVII, col 2. This privatess of Aminos frequently appears in

date formulas with the Athiophorus of Berenike and the Camphorus of A. Philadelphus, -all these princesess having, I believe, claims on the throne in their own right.

p. 530.

his sister Cleopatra II., though he was at that time only fifteen years old. It seems likely that this early marriage was prompted by reasons of state. As Epiphanes and Cleopatra I. had married in 193 s.c. and Philometer was not born till 188 g.c., Cleopatra II. as well as Eupator may have been an older child (Strack, op. cit. p. 197 note 19). Strack however considers Eupator to be a son of Philometer and Cleopatra II., and believes that Cleopatra reigned jointly with him for a few weeks after Philometor's death (Strack op. cit. p. 182).

It is interesting to observe that the history of Egyptian royalty for a whole century from this time onwards practically means the history of the three queens, Cleopatra L. II. and III., whose ascendency forms an all but unbroken chain. We hear of the 'wise regency' of Cleopatra I, during her Male Blap, Pt. One is tempted to believe that the title conferred on son's minority. Ptolemy VII. may have been a public recognition of her good government; just as, I believe, the title Philopator may have been a national expression of gratitude to the nationalistic Energetes perhaps forced on his reactionary son. Of this queen, Strack says (p. 3) 'sie hat sich mit den Rechten eines Vormundes begnügt und sich nicht zur regierenden Fürstin gemacht." must remember that she was a Syrian princess and not a blood-relative of the late King Epiphanes. 'Erst thre Nachfolgerin (Strack, p. 3) Kloopatra II. hat diese Stellung für sich in Anspruch genommen." Cleopatra II. was the sister and wife of Ptolemy Philometer.

On the death of Cleopatra I she becomes the prominent figure in the state, and continues to be so in the troubled times that follow, only sharing her power towards the end of her life with her daughter and rival Cleopatra III. Before the year 172 a.c. (Strack p. 183) we find Cleopatra II, married to her brother Philometer. It is she who reconciles the rival brothers Ptolemy Philometer and Ptolemy Energetes II., and induces them to reign jointly for a time (from 170 s.c.). On a Theban monument we find the three-the two brothers and their sister Cleopatra II.-offering to Leps. Ald. Amon-Ra as the three Philometores.

On the death of Philometer in 146 s.c. the exiled Energetes II returned to claim the throne and the hand of his sister and brother's widow Cleopatra II. He carries his point, and, according to Justin, on the very day Justin, 38, 3. of the wedding murders his bride's probably already grown-up son. This son is no doubt the second κωφον πρόσωπον of the dynasty-Ptolemy VIII. Philopator Neos. Here again the title seems to indicate that he may have been the candidate favoured by the party opposed to the queen-mother's claims. Mr. Mahaffy doubts the fact of his murder, and believes that Philopator Mah. Esq. Pt. may have died a natural though opportune death; but party-politics seemed p. 350, note 2

Lopin. Abh. Bert, At F. 465.

death of the mother; hence in it the name of Prolemy occurs alone-seconling to Mr. Greafell's restaration (Sanakebover Brokepalov voi. Ck. Pap. & du Hooksanion and Kasawispas Buin stribunio l. I. mote I. From dybook.

Berl. Ak. P.

467.

Ale. p. 447;

Letroune and Groufell and others, however, assign the marriage to a later date, 165 a.c. Lapsius is uncertain.

In either case the Grenfell Pap. X. (174 h.c.) belongs as it were to fine watershed between the two Chopatras, immediately after the H.S.-VOL XVIII.

Justin, 38, 8. Laps. Berl. . I. p. 170.

Lepa. Abh. Berl. Ak. p. 470.

p. 391,

to necessitate the death of Philometor's son, and from what we know of Physicon's character it is not likely that he would hesitate to take the proper steps to secure his authority. Accordingly, no sooner had Cleopatra II. in the following year (145 B.C.) borne the king a son, called Memphites because he was born at the time of the coronation in Memphis, than the king divorced her and married her daughter Cleopatra III .- vielleicht nicht bloss ihrer grösseren Jugend wegen, sondern auch, weil sie als Tochter seines Bruders Philometor nach Aegyptischen Erfolgerecht, welches die weibliehe Linia nicht ausschloss, für sich oder ihren Gemahl die Krone hälle beunspruchen können, as Lepsius says: 'diesen Zweifeln kam er durch die neue Verheirathung zuvor, nahm aber dennoch bald darauf deren Mutter, seine erste Frau, wieder su sich. Kakergetes was determined to secure the right of succession; and in this way he made it doubly sure by being married simultaneously to both generations of heiresses. We may judge to what extent this extraordinary According to Lepsius coalition worked from the evidence of inscriptious. the triad appear together as gods Euergetae on the monuments in the years 141 and 136 s.c.; after the latter date Ptolemy appears with Cleopatra III. alone in the years 126, 125, 124; in 124 again and in IIS (that is, to the death of the king) the king appears once more with both queens, the precedence being invariably given to Cleopatra the elder. In the years Mah. Eurp. Pt. 130-129 Ptolemy seems to have been in exile and Cleopatra II, reigns. may have been at this time that the king in revenge murdered his son (by Justia, 38, 8. Cleopatra II.) Memphites. Nevertheless the three seem to have been once more associated in the government-probably till the death of Cleopatra II. On the king's death in 117 n.c. Cleopatra III, is thus left in undisputed authority, being, as daughter of Philometer L, sole heir.

Mah. Emp. Pt. F. 392 Lapa. Abh. Berl. Ak. p. 504, note 1.

This queen begins her long supremacy by associating first one son in her regency, then, some years later, she deposes him and chooses another. The elder son, Ptolemy Lathyrus, seems to have rebelled against his mother's authority, and she on her part tried to undermine his position. She forced op. rit, p. 472 him to divorce his elder sister and wife, Cleopatra IV. and marry the younger sister, Selene, whose name does not appear on inscriptions.\ As Mr. Mahaffy says, 'We can hardly doubt that by this arrangement she meant to avoid the association of the young queen with her son's and her own name in public acts, as had been the case when she herself had been the younger Cleopatra. for there was probably some strong Egyptian sentiment against giving these peculiar royal and divine honours to the younger members of the family." The queen-mother and her older son reign together till 107-6 B.C. as

Lein Abh. Berl, Ak P. 478 P 402

Emp. Pt. p. 40%

> gods Philometores Soteres. In inscriptions the queen takes precedence : e.g. Grenfell Papyri xxvii, xxv, Greek Protocol of Paris Papyrns of Osoroeris, Demotic Papyrus of Berlin, No. 13 (Leps. Berl. Ak. p. 493). Lepsius calls attention to the fact that in this demotic papyrus (Berlin 13) the king does not receive the title \$\textit{\textit{e}}\textit{\textit{e}} \textit{\textit{e}}\textit{\textit{e}} \textit{\textit{e}} conjunction

Sharpe, vid. ii. p. 16. Visconti, Icon. gree, Ph. 54,

up. Scaliger.

p. 104.

coin of this period with the enstomary royal I Queen Seiene's head, however, is found sagle and the name of Ptolemy on the severs. 7 Porphyr. (if the coin has been rightly read) on a

with his mother. This subordinate position was no doubt galling to Lathyrus; he divorces Selene and tries to free himself from his mother's control, but in vain. In 110 n.c., indeed, we find him reigning alone, but the queen-mother is too powerful: Lathyrus is exiled and Cleopatra III, recalls her younger son Alexander I. to be co-regent 107 &c. In 99 a.c. we find the latter married to his niece, Berenike III., the daughter of Lathyrus and according to Lepsius and Poole, of Cleopatra IV., hence the direct heir. In the same year the queen-mother, the king and queen, appear in an inscription in the following order-Ptolemy Alexander I., Cleopatra III., Berenike III. In 90 B.C. Ptolemy Alexander likewise conspired against his mother's ascendency and On the death of both Alexander I. and Lathyrus, Mah. Emp. Pt. put her to death. Berenike III.1 succeeded and reigned alone for six months; but soon after her accession the son of Alexander I, and his first wife, Ptolemy XII, Alexander Il. returned to Egypt from Rome and immediately married and murdered Berenike III, his step-mother and the legitimate ruler, whereupon he himself fell a victim to the household troops.

If this king's will bequeathing the kingdom of Egypt to Rome is genuine, we may perhaps believe that he meant something different by this Mah. Kop. Pt. coup 2 from the usual conventional policy of state murder: he may have recognised that only by thus extinguishing the line of succession and entrusting his unhappy country to the firm control of Rome could be put an end to the hateful intrigues of his house and the miseries entailed by them on the kingdom. There is nothing, it is true, to prove this except the alleged will and the fact of his stay at Rome, where he may well have learnt to louthe the traditional policy of his ancestors. Moreover, his guards killed him, as Appian, Rell, Con 1 102. Appian tells us, as άτοπωτερου σφών, οία Σύλλα πεποιθότα, έξηγούμενον.

But the plan, if such it was, was frustrated by Egyptian national feeling. An heir to the vacant throne was found in Ptolemy XIII. Neos Diouysos Philopator III. Philadelphus II., an illegitimate son of Soter II. This king is looked on as immediate auccessor to his step-sister Berenike III., and the two Alexanders are omitted from the official lists of this time, as the claims of Neos Dionysos go back to his father Soter II. and thus exclude these kings from the succession.

Now I would suggest that the so-called 'illegitimacy' of Neos Dionysos was due to a misconception on the part of Greek and Roman historians of Egyptian rights of succession. Pausanias says of Berenike III.:—ἡ μόνη Ραμ. 1. 9, 5. γνησία οί (i.e Ptolomy Soter II.) των παιδίων ήν. Similarly Strabo implies that the great Cleopatra was illegitimate: - rovron wer (Auletes) of Strate, p. 70c. Αλεξανδρείς εξέβαλον, τριών δ' αὐτῷ θυγατέρωνζούσῶν, ῶν μία γνησία ή πρεσβυτάτη, ταύτην ἀπέδειξαν βασιλισσαν. Lepsins objects to this state- Leps Abb.

IL 598.

D. 425.

Berl At p. 450.

p. 42d.

Lepu. Abh. Berl, Ab. p. 485.

p. 479.

nothing of the fact.

Champellion-Figure and Letrome take this sp. 22, p. 479. to mean 'one of whom (who was) logitimate and the eldest was proclaimed queen." But this, as Lepsius points out, is linguistically lanpoissible.

¹ Berenike III. here the title Philofelphnea title which seems to have been transferred to her father Soter IL on his return from Cyprus (Strack, Dyn. der Ptol. pp. 4 and 63.)

¹ It does not seem to be almobitely certain that he murdered Berenike: Appian maya

ment on the ground that it is highly improbable that such an important fact about the great Cleopatra should only receive this casual mention. He ascribes the misstatement about Beronike to a confusion on the part of Pausanias between Berenike III. and Berenike IV. I believe that in neither case does it mean that the other children were illegitimate, but that the Egyptian idea of the heiress-rights of the eldest daughter confused the Greek mind and led to the misconception that they were so. Besides, it is manifestly absurd to say that Berenike III. was 'the only legitimate' child of Soter II, when we know that he had two children by his second wife and acknowledged queen, Selene.1

Laps, Berl. Ak. p. 505.

Hence I take both passages as a Greek mistranslation of the Egyptian idea the eldest daughter (and shild) i.e. the only legitimate heir. And while on the other hand it seems not unlikely that the claims of the eldest daughter in Egypt (if she was the eldest child) conveyed the idea to the Hellenistic mind that she alone was yungla, it seems possible that the very idea of illegitimacy was foreign to the Egyptians. We have the express statement of Diod. 1. 80. 3. Diodorus to this effect: - γαμούσι δέ παρ' Αίγυπτίοις οι μέν ίερεις μίαν, τών δ' άλλων δσας αν έκαστος προαιρήται και τα γεννώμενα πάντα τρέφουσιν έξ άνάγκης ένεκα τής παλυανθρωπίας. . . . νοθον δ' ούδένα των γεννηθέντων

voultovouv.

I would suggest, therefore, that Neos Dionysos was not illegitimate, but that he was a son of Soter II. and his second wife, Selene, the younger sister of Cleopatra IV., and was one of the children repudiated along with her. Lepsius says of Soter II.1 'er verstösst Selene mit zwei Kindern.' We do not hear what became of the children. What so likely then as that the Egyptians, on the extinction with the death of Berenike III. of the older branch descended from Cleopatra IV., reverted to the children of the younger sister, queen Selene?

Barl. Abh. Ak. p. 475.

Of the wife of Auletes, Tryphaena Cleopatra V., Lepsius says: 'sie heisst in den Inschriften zugleich Schwester des Königs and scheint daher, wie er selbst, ein illegitimes Kind des Soter gewesen zu sein.' It is not impossible that this is the other child of Selene, whom he immediately proceeds to marry in orthodox Ptolemaic fashion, and thus the succession is duly handed on in the younger line. That Selene considered herself the legitimate heir on the death of her sister is proved by the fact that we hear of her even claiming the throne for her sons by a later marriage with Antiochus Grypus. Hence it seems to me extremely unlikely that the two children of her first marriage with her brother Soter II, should not be claimants, if still alive, for the kingdom, and it is to them that one would a priori expect the Egyptians to turn on the extinction of the older branch of the family.

Clo. in Ferrena, it. 4. 27.

appear from history as if they had no right to Mah, Rev. Fop. Introd. the throne, unless indeed Anlates was one of IL BEVIL them, and he is always spoken of as ille

¹ Mr. Mahaify says: "I cannot but think that Mali. Esop. Pt. the comtant as ertion of the illegitimacy of Egyptish princes and prime was an favortion of Hellemistic historians in the interest of the Rossans

[&]quot; Mr. Maliadly says : 'Those two children dis-

[&]quot; One of the king's titles is Philadelphus

In 58 B.C. Neos Dionysos (Auletes) is banished, and his wife and sister Tryphaena Cleopatra V. reigns with her eldest daughter Berenike IV, as coregent. The following year Cleopatra V. dies and Berenike IV. reigns alone for a year, during which time she selects and rejects a first king-consort and marries a second. But in 55 n.c. Auletes is restored and puts his daughter to death. On his death in 51 B.C. he left the throne to his daughter Cleopatra VI, his eldest surviving child, and to her brother Ptolemy XIV. Notlong after Cleopatra was driven out by the supporters of her brother, but on his death she was once more established as queen with Roman assistance, this time with her younger brother Ptolemy XV, as co-regent and nominal husband, and on the death of her boy-husband she assumed her son Caesarion as co-regent. We possess no inscriptions with the name of Cleopatra and her three successive co-regents, but as Lepsius remarks :- wahrscheinlich ging Berl. Ald. Alt. ihr Name als des altesten Kindes dem ihrer Bruder voraus, und die letzteren p. 500, note 1, wurden, wie später ihr Sohn Ptolemy XVI. Caesar, nur als Mitregenten

angesehen."

On this theory we see the same stereotyped principle of succession at work throughout the whole of the Ptolemaic period down to the extinction of the race, even Roman intervention conforming to it, and one consistent explanation is found for the most unhellenic feature of Ptolemaic history: whereas Strack (whose book on the Ptolemies appeared after the main part of this paper was written) is obliged to adopt three separate explanations of the Strack, op. se brother-and-sister marriages: - firstly, in the isolated case of Philadelphus the marriage is explained by Arsinoe's rights to certain cities of the Euxine: secondly, in other cases the marriages were due to a desire to avoid dangerous alliances with foreign states: thirdly, from Cleopatra II, onwards the princesses had emancipated themselves and were really queens regnant, and the marriages represent an adjustment between the two claimants. Can we believe that the first two shadowy inducements were sufficient to cause this purely Hellenic dynasty to embark on a course so strangely at variance with Greek sentiment? The marriage of Philadelphus alone seems a clear indication that the reaction had already set in, that Philadelphus, whether he would or not, could not stem the advancing tide of Argyptisirung which closed over his successors. And yet we are told (Strack op, cit. p. 104) that in the matter of succession the first half of the dynasty 'sind griechischen Sitten getren geblieben.' Can the persistent mention in public acts of both parents of the sovereign be looked on as a Greek custom? Strack assumes two distinct periods; in the first period down to the time of Cleopatra II, the royal princesses had no rights of succession; in the second period they emancipated themselves and 'es war durch diese Gleichstellung der Konigin Strack op. est. der natürliche Gang der Erbfolge gestört, der meht besser wieder hergesteilt werden konnte, als wenn die zwei Gleichberechtigten durch Heirath ihre Ausprüche vereinigten." Is it more unnatural to assume that the same principle was involved all along, a principle which became more defined certainly in the later half of the dynasty but which was none the less surely at work in the background from the beginning? It is true that the early

queens of the dynasty were not queens regnant in the sense that the Cleopatras were queens regnant. But from the point of view of the divinity of the sovereign their position, I hold, was paramount, and on the divinity of the sovereign depended his recognition as king. Till he was recognised by the priesthood the loyalty of his Egyptian subjects was not worth much. And as Strack says (p. 128) 'eine Consekrierung als Landesgott kann nur von ihnen (i.e. the priests) ins Werk gesetzt werden, nur durch sie volle Gültigkeit orlangen.' That such an idea was no new invention of the Hellenistic dynasty there seem sufficient indications on early Egyptian monuments to testify; by a thorough investigation of the principle in Ptolemaic times much light, I believe, might be thrown on Pharnonic history social and political, and the imperfection of the record to some extent supplied.

Of ancient Egyptian royal matrimony Erman says: 'There was only one

Erman, p. 79.

legal wife, the queen; she was of royal or of high noble birth, and indeed she may have been the "daughter of the god" a.c. of the late king, and therefore the Erman, p. 74. sister of her husband. Again :- The queen appears as a rule to have been of equal birth with her husband; she took her share in all honours.' After the death of her husband the queen still played her part at court, and as royal mother had her own property, which was under special state management.' The queen of the Old Empire is called: 'She who sees the gods Horns and Set ' (i.e. the possessor of both halves of the kingdom); under the New Empire she is called: 'The Consort of the god, the mother of the god, the great consort of the king, and her name is enclosed like that of her husband in a cartouche. Though polygamy is the exception Erman points p. 15% out that royal double marriages frequently occur; in these one of the two is apparently due to political reasons. Such double marriages are found too in the case of private individuals, for, as Erman adds, many daughters of rich men in Egypt possessed valuable rights of inheritance in their father's property."

p. 150.

According to Erman again: 'The esteem which the son felt for his mother was so great that in the tombs of the Old Empire, the mother of the deceased is as a rule represented there with the wife, while the father rarely appears. On the funerary stelse of later times also, it is the usual custom to trace the descent of the deceased on the mother's side, and not as we usually do, on that of the father.' Moreover, the maternal grandfather was considered Erman, p. 156, the natural protector and guardian of a young man. When a youth gets an appointment, then 'the father of his mother thanks God,' In the New Empire a post is conferred on a young man 'for the sake of the father of his

^{&#}x27; The case of Amony, 'the great man of the South, who probably died at the beginning of the reign of Amenembet II., reminds one of Philadelphns and of the relations subsisting Erman p. 151 between the two first Arsinosa Of Amony's two wives, one, Nabot-Sochat-ent-Re, may have been his nice; she bore him two sens and five daughters; by the other, Hunt, he had

certainly three daughters and a son. 'A curious circumstance shows us,' says Erman, that the two wives were friends, for the lady Nebet-Sochet ant-Re called hat second daughter Hunt, and the lady Hunt carried her courtesy an far as to name all her three daughters Nebet-Sochet-ent-Re.

mother'; and when he goes to the wars he 'gave his property into the charge of the father of his mother.

Such prominence of the maternal male relatives is, as we know, a marked feature of the 'maternal system.' Tylor objects to the term Matriarchate: 'The term matriarchal,' he says, 'takes it too much for granted that the women govern the family. It is true that in these communities women enjoy greater consideration than in barbaric patriarchal life. but the actual power is rather in the hands of their brothers and uncles on the mother's side.' In the same article he alludes to the custom of the heiress-husband where the incoming husband marries the daughter of the house to which he succeeds in his wife's name: ' and again ' from Africa may be quoted Livingstone's account of the Banyae in whose country the wives are masters. 'It is in Africa,' says McLennan, 'that beenah marriage is now McLennan, most prevalent; there are parts of Africa in which it is quite commonly met Theory, p. 43. with-usually alongside of, and in some sense contending with, a system of marriage by purchase-the two systems, indeed, being generally in use even among the same people, the one preferred in some cases, the other in others."

Tylor, Ninoteonth Century, July 1896

It would be outside the scope of this essay to examine the traces of similar survivals in other countries. I should like to mention, however, an instance of what appears to me a Hellenic idea based on this Egyptian point of view: I mean the Libyan Medusa (Médouca), 'the reigning lady,' in whose snake-girt head I would trace a Greek representation of the royal uracussnake on the reigning queen's crown,1

We know from Manetho of a legendary law which under Binothris, a king of the second dynasty, was passed establishing the lawfulness of female vol. i p. 23. succession to the throne, The rule of women, however, as Poule remarks, Psole, succession to the throne. The line of months are omitted in the lists \$2,0, p. 781. seems to have been disliked, and the queens names are omitted in the lists \$2,0, p. 781. made under dynasty XIX, 'when the royal family seems to have been affected by Semitic influences.' It is in the immediately preceding dynasty, however, that we find the most striking instances of queens regnant and of powerful queens-consort married to a brother. As Erman says: 'In the royal Erman, p. 154. family of the XVIIIth dynasty, we find that A'hmose-nefert-'ere married her brother A'hmose; a lady named A'hmose was consort to her brother Thothmes I., and A'rat to her brother Thothmes IV., and so on.' Similarly the bitter rivalry between the brothers Thothmes II. and Thothmes III. and their sister the great queen Hatsen would not strike us as out of place if it were recorded on a page of Ptolemaic history. Hatasu reigned first with the elder of her brothers, Thothmes II., as her husband's co-regent; on his death Eman, p. 43.

Patrie.

rather to indicate that female succession was sensing to be looked upon as an undisputed fact-that Egypt was gradually turning its back on the matriarchate and tending towards a system of aguation.

It is enrely significant that this queenconsort had the name of a former king,

McLeanan, Pringities Marriage, p. \$17.

I It would thus be significant that the head of the slain gorgon is deploted on the shield of the motherless Athene, 'the symbol of the overshrow of motherdom and of gynankocracy' as she has been called. Cf. McLennan, Print-Nes Marriage, p. 258.

^{*} I mumot regard such a law at this early singe as a "progressive measure": it seems

10 43:

-of which she was perhaps the author-she became sole ruler, though the younger brother, Thothmes III., was nominally co-regent. After a reign of twenty years she was succeeded by Thothmes III., who forthwith erased her mune from the monuments: " again we cannot help, says Erman, suspecting violence to have been the cause of the change of government."3 Hatasu seems to have tried to evade the projudice against petticoat government by having Rawlinson, Empt. p. 178, herself frequently represented in masculine attire and with a beard. In some of her inscriptions she is called 'the king,' though the personal pronouns referring to her remain feminine, such jumbles arising as 'His Majesty herself.'

Petrle, Hot. of According to Petrie, Hatasu was the sole legitimate heiress of Thothmes I. Eg. vol. ii. Thothmes II. being his son by another and not royal wife, and Thothmes III. 19. 95-98. a nephew of Hatasu. Of Hatasu he says: 'Her father about five or six months before his death associated his daughter with him as she was the heiress in the female line, in which royal descent (like that of private families) was specially traced.' 'It appears that on failing health the king p. 0%, placed the power in the hands of his eldest child, who had the sole right to it by the female inheritance, and then, just a few weeks before his death, married Thothmes II. to her, perhaps to secure his receiving some respect for

his position if not for his character,'

Two other queens, both belonging to the XVIIIth dynasty, seem to deserve special notice,-Tyi, the wife of Amenhotep III., and Nefertiti, the wife of Akhenaten (Amenhotep IV.). On the question of these ladies' rights we have the conclusive testimony of Mr. Petrie. Of Tyi he says: 'her titles Hist, of Eg. vol. II p. 182. are noticeable: she is called "princess of both lands" and "chief heiressprincess of all lands." These titles seem to imply hereditary right; indeed it is very doubtful if a king could reign except as the husband of the heiress of the kingdom, the right to which descended in the female line like other property.' This Tyi was the mother of the heretic king Akhensten. Petrie says again of her: 'There can be little doubt of the influence of Queen Tvi; she appears closely associated with the king on his monuments, her figure is seen side by side with his on scarabs, her name appears along with the king's on immunerable objects, a temple was built in her honour and she acted as Petric, Hist. of regent for her son during his minority. 'The beginning of the reign of Amenhotep IV. is obscure. That Tyl for a brief time held the power at Tell el Amarna, is indicated by her name appearing alone in a quarry at that place, -and this though Amenhotep IV. had probably already been associated as co-regent with his father in the years before his marriage.

Petrica Hist. of Eg. vol. ii. p. 208

Ro. p. 207.

Petrie.

Mr. Petrie, however, calls Thethmes III. a asphio of Halam. Petric, Hist of Eq. vol. 1., indebted for the continuance of her memory among mankind to the sendent that the stone. Rawlinson, masons employed to many list name were too Eg pt 187. careless or bils to carry out their work completely. It does not seem altogether function, therefore, to bulliave that the record of other queens may have perished more effectually owing to similar multirats of hatred on the part of their male relatives or of projudice in their иппоравоть.

Report

[&]quot; According to Mr. Griffith it was the later Ramsaes II. who cannot her mane to be Eg. Er. Fund replaced by that of Thothurs II., 'not conaldering Hatasu a legitimate accordign of 1895-c, p. 7. Egypt.' By the time of this king's reign Semitic influences were strongly marked.

^{*} As Rawlinson remarks, this great queen is

Of Queen Nefertiti Petrie says: 'That Nefertiti had a hereditary claim to the Egyptian throne, is shown by her titles. She was "the great heiressprincess of all women" and "princess of South and North, the lady of both lands." These titles, like those of Tyi, imply an hereditary right to rule Egypt.

It is unnecessary to point out the similarity of these titles to those

applied, as we have seen above, to Arsinoe Philadelphus.

Thus there seems sufficient evidence to show that the position of Arsinoe II. and of subsequent Ptolemaic queens was by no means anomalous

in Egypt, but was based on Pharaonic precedent.

It is certainly more difficult and hazardous to maintain that such a position of women was a survival from the Matriarchate, and to assign to its place in the development of society in the direction of Agnation such a custom as brother-and-sister marriages.4 On the other hand the assumption that these rights of women, which, as we have seen, go back to the beginnings of Egyptian history, were due to a huge progressive movement, is surely far more incredible when one remembers how slowly the current of change flows-or rather stagnates-in all other aspects of the history of that nation."

It seems to me from all these facts given above that brother-and-sister marriages in Egypt may have been a relic of some primitive system of marriage based on female rights of property; that such marriages point to a stage of growing prejudice against women's rights of inheritance and to an attempt at compromise; a that these rights and this compromise were supported by the priesthood and notably by the Osiric cult (with its supreme tenet, the holy marriage of Osiris and Isis), in deference to the less civilised portion of the Egyptian nation; hence that it is this controversial and transitional stage that is most prominent under the New Empire and in Ptolemaic history.

This, I think, is corroborated by the fact that it is the divine rights of the queen that are most insisted on. All political rights claimed for her were based emphatically on her rights as a deily, as we see in the case of the transference of the awountpa in Ptolemnic times; and hence, too, the importance of the different stages of her deification. We may almost look on the exaggeration of the spiritual claims made for her as a sort of compensation to her for the loss of temporal power, the salve with which the troubled

ch. vi.

* Cf. Numbers, ch. xxvii. 1-11 and xxxvl.;

also Lowy-de Civili Conditions Mullerum Graccarcur (Vrathdaviac, 1885), p. 59 : Si out mayun filli sant legitimi neo a definactis fillis popoles, e lege lam Mossics hereditatem filme consequentur ; quarum quillem unbere intra gentem aat, nt conserveint res familiaris. In Gracois de filia hereditaria praecipuas leges scriptas exstant, at ucous families or exetinguatur, Quanquam filmo pou ipeas hervées essa, sed and can heredie proximis gener obtingers videntur.

p. 200.

McLouman. Primitties Marriage, chap. vii. Diod. i. 80. Strabo.

^{17, 824,} Lane, Modern Byyptlane,

To do so would involve the question whether primitive Egyptians were embaraments or erogamous. It seems probable at any rate that the Egyptians did not practise infanticide,

Fraces of the former independence of Egyptian wamen seem to have survived down to the present day, Mr. Lane says of median Manners and Egypt: I believe that in Egypt the women Castoms of the are generally nucleo less restraint than in any other country of the Turkish Empire."

public conscience soothed itself while gradually depriving her of actual

political power.

This applies, I believe, to the rights not only of the queen but of women in all ranks. Thus we find that in the New Empire women assume a new and important rôle in connection with temple ritual. In all temples we find Erman, p. 293. female singers or musicians in great numbers. Indeed Erman says: 'we Of Wieden scarcely meet with one lady under the New Empire, whether she were IL p. 151, married or single, the wife of an eccleaiastic or of a layman, whether she belonged to the family of a high-priest or to that of an artizan, who was not ep. oil p. 152 thus connected with a temple.' Wiedemann says that at this time almost

every god and goddess had a priestess.

It is precisely this sacred side of woman's functions that we should expect to find preserved among the changes of developing civilisation.2 Professor Ramsay shows how in the religion of Phrygia traces of the earlier Bishopries of Lydian substratum of the Matriarchate are preserved, while socially the Phrygia, p. 7. Patriarchate established by the conquering Phrygians has all but blotted out 19. 61, p. 94. the native system. He says: 'long after a higher type of society had come into existance in Phrygia, the religion preserved the facts of the primitive society, but it became esoteric, and the facts were only set forth in the mysteries.' Similarly, whatever the incoming patriarchal element was in Egypt-whether Semitic or not-it is, I believe, in the religious side of native life that we must look for the most certain traces of the older state of society, and I have tried to show that it is chiefly the Osiric system which affords such survivals; and hence the greater development and diffusion of that cult and its adoption in a fashion as the state religion by the Ptolemain government would explain an apparent revival of principles which seem to have formed a dim and half-realised background throughout Egyptian history -'the dust of antique time' which has lain unswept in the most conservative of all lands, inhabited by a people θεοσεβέες περισσώς έσντες μάλιστα πάντων άνθρώπων.

RACHEL EVELYN WHITE

manualiticall potestatom propteres feminas habent quod antiquitm in libertatem vindicari servas non poterat alsi alieni des consecratus qui hiorodulus fieret (Curtins, Anned Delph p. 10 egg.); consecrate autom ipal number)

For a similar religious survivat of, the inviliation at Rosso of the rex semificulus on the abolition or rather disintegration of the kingship.

¹ Cf. Can. St. Il. 64-73 for these chrical and lay (rais &xxais expedients rais Bouloperais) fomale temple-musiciane in Ptolemais times. By this decree the wives and daughters of the priests come in far a share of the speed or The isper = printegers of the dead princess Bergalke.

[&]quot; Cf. the Greek woman's power of manumission: Lawy-de Civili Condiciona Mulierum Gracearum (Vratislaviao, 1885), p. 25 :

ILLUSTRATIONS TO BACCHYLIDES.

[PLATE XIV.]

THE EDITORS of this Journal have reason to think that a considerable body of its readers will be glad to be furnished with reproductions of the monuments, mainly vase paintings, that are discussed in connexion with Bacchylides. Even those to whom the published illustrations are readily accessible will probably find it convenient to have them brought together for reference, in a collection made from this point of view.

III. The story of Crossus.—In the story as told by Bacchylides, Crossus voluntarily ascends his pyre, with wife and daughters; he invokes the gods, and more especially Apollo; he orders the pyre to be kindled; Zeus extinguishes the flames, and Apollo takes Croesus and his children to the land of the Hyperboreans. According to Herodotus, Croesus with his companions is placed on the pyre by order of Cyrus. After Cyrus has changed his mind, and his servants have made ineffectual attempts to extinguish the pyre, Croesus invokes Apollo, who extinguishes the flames. Fig. 1 shows the well-known vase in the Louvre, representing the subject. It had already been interpreted, before the discovery of Bacchylides, as evidence of an alternative version of the story, in which the sacrifice was voluntary," Croesus sits enthroned, and makes a solemn libation, while an attendant Euthymos is busy with the pyre. Some of the commentators interpret the objects that he holds as torches, but they are quite unlike torches, as usually represented (cf. J.H.S. xi. Pl. 6), and resemble more nearly the whisks for sprinkling lustral water. If this is the correct interpretation their use further emphasises the ceremonial character of the scene.

The vase is an early red-figured one, dating from the close of the 6th century or the first years of the 5th century 8.0.4


M. Thoodors Reimach's edition (Promes Chesias de Bacchylide, per Eugene D'Exclubral et T. E.), which has appeared since this article was put in hand, has to some extent covered the same ground, for these parts of the poet with which he deals. The same monuments appear, in several cases, in both collections, but this is inevitable in connection with the less-frequent myths.

^{*} Monumenti dell' Init. 1., Pl. 54; Welcker, Alte Denkingeler, Pl. 33; Baumeinter, Denkmurler, p. 796; Relmach, p. 25, etc.

² M. Curtine, Griech. Gench., 6th od., h., p. 574.

^{*} Cf. notes by H. Stnart Jenes and Miss Harrison, Class Rev. 1828, pp. 84, 85; Jebb, Milanges Henri West, p. 237.

The extinction of a pyre by the influence of Zeus is strikingly illustrated by the vase of Python, in Vol. XI. Pl. 6 of the Hellenic Journal. There Alcmene is seated on an altar, before which the pyre is piled, and Antenor and Amphitryon apply the torches. Zeus listens to the appeal of Alcmene,



Fin. L.

and has cast his thunder-bolts. Copious rain is poured on the pyre by the Hyades, and also falls from a rainbow-like cloud.

A red-figured erater in Belt. Mus., No. F. contury a.c.
149. Formerly at Castle Howard. Late fourth 2 Murray, J.H.S. xi., p. 224,

The poet does not say in what way the god conveyed Croesus and his family to the country of the Hyperboreans, but one may guess that on this occasion, if the poet had been more explicit, he would have given him the

swan rather than the Gryphon or the Tripod.

The Gryphon was primarily an artistic type, inherited by the Greeks from the East, and thence introduced into literature, and not in the first instance, with special reference to Apollo. In literature, it curiously happens that the earliest passages that have been pointed out, which definitely refer to the Gryphon as an attribute of Apollo, are in Claudian and Sidonius Apollinaria. In art, the association of the Gryphon with Apollo is not common before the 4th century. Apollo also travels on his Tripod, but not on a Hyperborean expedition.

On the other hand, Alcaeus had sung how Apollo had travelled in a chariot, drawn by swans, from Delos to the Hyperboreans, and from the Hyperboreans to Delphi. When Pindar describes how Apollo carried off Cyrene to Africa, he says that he hore her in a golden chariot. A late gem, at St. Petersburg, shows the rape. Apollo stands in a chariot, drawn by a

pair of swans, and clasps Cyrene by the waist with his right hand.

V. Herueles and Meleager. - This episode has already been the subject of

much discussion.6 I need only indicate the artistic types involved.

Hernoles and Cerberus. For this type, see the drawing published elsewhere in the present volume of the Hellenic Journal from a late sixth-century black-figured vase, recently acquired by the British Museum. No monument has been identified with the conversation between Heracles and Meleager.

The Death of Meleager is vividly represented on a large Amphora from Armento, in the National Museum at Naples, of about 400 n.c. (Fig. 2).

The young Meleager is seen in agony, supported by his brother and sister, Tydeus and Deianeira, while a third figure, who has been variously named, but is probably Althaea, approaches in haste from the left. Oineus stands as a spectator. Above him is another group of Aphrodite and Eros. Near Eros, where his name might be expected, is the inscription \$\phi\delta\cop{vos}\$. It would be out of harmony with the usual direct simplicity of vase inscriptions, if we look for any conceit, such as that Love and Envy are near akin. It has been suggested

Americano Frambilder, Fla. 120-181. For rod-figured vasse, see Wisner Forlogoblätter. Series E. Pla. 1-4. For a list of forty-nine representations of the subject, see Walters, J.H.S. aviii., p. 200.

De VI. Cons. House, 39.

^{*} Corm. il. 207; xzii. 67. See Stephani, Compte Ronde, 1864, p. 57.

Bergk, Pictor Lyr. Gr., 4th ed. iii., Alcama.

^{*} Pindar, Pyth, Ix. 6.

^{*} Gverheik, Grisch Kunshmythologis iv.,

Robert, Herono xxxiii., p. 151; Graint, Milanges Henri Weil, p. 73; Roinach, p. 4.
7 J.H.S. xviii., p. 295.


For black-figured rass, see Gerhard,

⁹ Arch. Zeit. 1807, Pls. 220, 221; pp. 33, 97. Heydemann, Foreignsumingen des Mus. Nucronale in Nurpel, Santangelo, No. 11 (where see references to varier literature). Howher, Levilon, it., p. 2020; Reinach, Euchylide, p. 5.

as a possible explanation that the inscription refers to a personification that has been omitted in the transcript from a larger composition.

Peleus and Thesens sit below in the attitude of mourners. They are probably introduced as two of the most noted of the companions of Meleager in the Boar hunt.

The reverse of the vase has a scene in the lower world with Heracles leading Cerberus—but unfortunately without Meleager.



Frc. 2.

IX. Death of Archemores.—This subject occurs on several monuments,¹ but in no case in such a way as to contribute to the interpretation of line 13.

The scrpent is attacked by several of the heroes, while the child lies near, or encircled by it, but there does not appear to be any representation of the moment before the death of the child.

Overbeck, Gallerie Hernischer Bildtwerke, Ph. 3, 4; White Athenian Vasce in Brit. Mus. Pl. 18.

The funeral rites are shown on a large vase now in the National Museum at Naples, and frequently published.\(^1\) In the foreground, the body of Archemoros is laid out on a couch, tended by several persons, of whom the Pedagogue alone is named. Above, within a tetrastyle Ionic building, is Eurydice in conversation with Hypsipyle and Amphiaraos. To the right are Parthenopaios and Capaneus, to the left Euneos, and probably Thoas, the sons of Hypsipyle. In the upper tier are Zeus and Nemea (on the right) Dionysos and a Satyr, restored, (on the left.)



Fra 3.

Thebe (ix. 54 and x. 30) is seen personified on the Cadmos vase of the late Italian painter Assteas (Fig. 3). She is shown as a female figure seated above the spring which is guarded by the dragon.

It is probable that she also occurs on a kindred vase now in the Louvre's as a richly dressed maiden, who watches Cadmos making his onslaught on

the dragon.

XI The healing of the daughters of Proctos. - This legend has hitherto

been known in two principal forms:-

(1) Melampus, with the aid of a band of vigorous young men, chased the Proctidae to Sikyon. Iphinoe, the eldest of the daughters, died on the road, and the others were cured.*

(2) Melampus cured the Proctidae at Lusus or Lusi.

Bacchylides places the cure at Lusus, but altogether emits to mention

Heydemann, No. 3255; Overbeek, Lc. Pl. 4, Fig. 3.

Millingen, Ancient Unwilled Monuments, Pt. 27.

^{*} Millin-Dubsie Malsonneuve ii., Pl. 7:

⁸ Reinach, Printiure de Fasce entiques, recueillies per Milles, etc., ii. 7.

⁴ Apollodorus, Bibl. ii. 20; et. Paus. u. 7, 8.

Paus vili. 18, 7.

the agency of Melampus. The bringing of Melampus to Lusi seems to be due to a confusion of two stories, but that it was current in late times is shown e.g. by the epigram over the fountain near Lusi—

φεύνε δ' έμην πηγήν μισάμπελον ένθα Μελάμπους λυσάμενος λύσσης Προιτίδας άργαλέης \ κ.τ.λ.

The subject is believed to be represented on a fourth-century vase in the National Museum at Naples 2 (Fig. 4). Three maidens are grouped in humble positions round and near a xoanon before which is an altar, and a tripod on an Ionic column. The xoanon is probably that of Artemis.²

On the left are an elderly figure with a sceptre, and a rustic old man, who has been called Silenus, with a thyrsus. On the right is Dionysos.

On the version of the legend which brings Melampus to Lusus, the bearded man has been so named. One of the three maidens, the wild figure behind the column, has been called Lussa or Madness by Wieseler,* on the ground that Iphinoe is already dead.

If, however, we study the vase in connexion with the text of Bacchylides, the bearded man would be Proctos, who comes to Lusus, and makes a prayer to Artemis on behalf of his daughters.

The presence of Dionyses as a spectator may be due to the fact that according to Hesiod (so at least we are told by Apollodorus) the madness of the daughters was due to their not accepting the mysteries of Dionysos.

It may be supposed that there was already a cult of Artemis at Lusus, when Proctos made his prayer there, but in any case it is a very easy prolepsis for the artist to show us the altar, xoanon, tripod and votive tablets indicating the temenos which was established by Proctos in gratitude for the cure.

A cameo, formerly in the possession of M. de Witte, was thought by its owner to represent the same scene. In this instance the supposed Melampus holds up a young pig, which was specially employed for rites of purification in the case of persons recovering from insanity. If, however, it is correctly interpreted the cameo evidently represents a different version from that of Bacchylides.

XIII. Heracles and the Nemson Lion.—The invulnerability of the Lion, upon which the poet lays stress, was not a fixed point in the story as told by the early vase painters.

roanou of Hera."

¹ Vitt. vili. 9, 21.


Millingen, Pass Astignes, 12, 52, and S. Reinach, op. oil. Millingen 52; Heydemann, No. 1760; Muller-Wieseler, Denkmacker U., Pl. 2, No. 11; The Witte, Onc. Arch. v., p. 126; France, Paumulus iv., p. 259.

² It has also been thought to be an image of Hurs. According to Acusilans, the Proctions had gone mad because they disparaged a


⁶ In Miller's Description, i.e. Compare the introduction of Lussa by Enripides in the Herenkes Furens and of Mania in the vasa of Asstens, Mon. doll' Inst. viii. 10.

[&]quot; Bibl. ii. 26.

⁸ De Witte, Gaz. Arch. v., Pl. 19, Fig. 1: of De Witte, ibidem.



The scheme of the strangling occurs in the majority of the black-figured vases I and in the more occasional red-figured representations of the scene. But the sword also occurs, e.g. on the black-figured amphora in the British Museum, No. B 160 (Fig. 5), and elsewhere. In literature, the invulnerability of the brute is suggested by Pindar (Isthm. v. 47) and explained by Bacchylides and Theorritos (xxv. 274). This, however, may fairly be regarded as a case in which the current artistic type gives the lead to the poets. The wrestling scheme was predominant, and was accounted for by the tale of invulnerability.



Bia, b.

XVI. The last sacrifies of Heracles,—A scene of preparation for the sacrifice on Mount Kenaion by Heracles, in the presence of Lichas and Hyllos (†), is represented on certain fragments at St. Petersburg, derived from a sort of Moute Testaccio, near Kertch (Fig. 6). Heracles appears to have put on the robe (we know from Sophocles that he had time to sacrifice

Cf. the collected list of types, Walters, B. M. Catalogus of Passe, E., p. 13.

⁹ Cf. the vases quoted by Reisch, Athen. Mitt. 1887, p. 128.

In the group dedicated by Hipporton of

Tarentum at Olympia, Reizeles must the how Para, v. 25, 7

Stephani, Compte Rendu, 1869, Pl. 4, Fig. 1 and (more complete) ib. 1876, Pl. 5, Fig. 1.

the first twelve of his hecatomb before the poison began to work) and holds out with both hands the fillet for the adorpment of one of the victims.

Bacchylides introduces a new incident in his account of the events on Mount Kenaion, when he includes victims sacrificed in honour of Athene and Poseidon. This raises once more the question of the interpretation of certain fragments already published in this Journal. Heracles assisted by two youths



Li[chas] and Philoctetes (?) is sacrificing at a stone altar, before a draped xoanon, while Athene herself stands and watches the ceremony.

⁴ C. Smith, J.H.S. ix. Pt. 1, p. 1; again in Cat. of Viscos in the British Museum, iii., Pl. 16. No. E 494. In the later publication the fragment at the right of J.H.S., Pt. 1 is shown.

as part of the Heraclur; the Athens is disconnected from the other fragments; Al (part of Lichas)) is preserved above the youth.

The subject has been called, by several interpreters, Heracles sacrificing at the altar of Chryse, and by Mr. C. Smith, writing before the discovery of the

Al, a sacrifice on the Acropolis.

The presence of Lichas strongly suggests the sacrifice on Mount Kenaion, while Philocetes might be introduced in place of Hylles, through some confusion between the sacrifice on Mount Kenaion, and the subsequent self-immolation on Mount Octa. That Bacchylides should include a sacrifice to Athene, removes a part of the difficulty of finding her so conspicuous, where Zeus was the deity to be honoured. The presence, however, of Philocetets at the sacrifice, shows that the fragments cannot be made to agree plainly with any known form of the story in literature.

XVII. Theseus and the King.—The story of the descent of Theseus in pursuit of the ring and the wreath, has been closely analysed by Prof. Robert,

in successive papers.

He has pointed out that the story consists of two elements, namely the giving of the wreath by Amphitrite and the story of the ring. Both incidents are mentioned by late authorities, by Hyginus and by Pausanias describing the picture of Mikon in the Theseion, but we do not know that both were represented by Mikon, since Pausanias expressly states that Mikon did not

tell the whole story, though he does not say what part was omitted.

Judging from the vases first known (nos. 1-3 below), the incident of the ring seemed to be comparatively recent, and its invention was formerly attributed by Prof. Robert to Euripides. The Tricase vase (no. 4), if it in fact contains a representation of the ring, points to an older source than Euripides for the ring incident, and this is now proved by Bacchylides. The fact, however, that Bacchylides has nothing to say about the recovery of the ring seems to show a want of homogeneity in the story. Also, it seems to indicate that it is not he who devised the incident. A poet who conceived the story would probably make it complete, and would hardly omit the conclusion of the finding of the ring on the ground that beside the present of Amphitrite it became quite insignificant.

The illustrations that follow are taken from the four red-figured vases at present known, which deal with this subject. In two, the principal action is between Theseus and Amphitrite, and in the other two it is between Theseus.

and Poseidon

 Cup of Euphronios, in the Louvre—a very fine red-figured vase found at Caere, of about 500 a.c. (Plate XIV.).

Theseus, who is supported under his feet by a Triton, greets Amphitrite,

i Scotla charvatlans by Mr. Murray, prefixed to E. 494, in the Cat. of Passe, iii.

We awe the new illustration of the value to the kindness of Mr. A. van Branteghem. Sealso Mon. Green de l'Ass. of Rindes Green, 1872. Ph. 1: Klein, Emphronies, p. 182; Reimach, Pl. 4, etc. The new drawing by M. Davillard gains greatly in faces and effect as compared with the older, but excellent, engraving, by having the internal blacks rendered as solid.

Robert, Arch America, 1889, p. 141; Marenthanochlacht in der Poikile, p. 50; Hermee, xxxiii., p. 182, Ct. Jebb, Milanger Hinri West, p. 235, Mine Harrison, China, Review, 1898, p. 85.

Polmit, Herman, Lc. p. 140



in the presence of Athene. Three swimming dolphins mark the sea. The wreath is not shown.


(2) Crater, in the Museo Civico at Bologua 1-a fifth century red-figured

vase (Fig. 7).

In this vase, Theseus, supported by a Triton, clasps in suppliant manner the knees of Amphitrite, who holds out the wreath in both hands. Below, Poseidon reclines on a couch, like one who is in his own house—on the right an Eros is pouring out wine for him—and watches the scene. On the left we see the stern of the ship of Theseus, and Helios rising from the waves. Here also the ring seems to have no part in the story.

(3) Vase from Girgenti,2 now in the Bibliothèque Nationale at Paris-

an early fifth century red-figured crater (Fig. 8).



F10. 8.

Poseidon, enthroned, clasps the hand of the young Theseus who stands before him. Poseidon is identified not only by his trident, but also by the decorative row of dolphins on his foot-stool. Behind Poseidon stands a

¹ Ghirardial, Masso Rakiana et Ant. Class. iii., p. 1, Pl. 1.; Furtwarngler and Robert, Arch. Anariges, 1889, p. 141; Reinach, p. 66; Robert, Nekyia des Polygoof, p. 41; Hermes xxxiii., p. 135.

Mon. dell'Inst. 1., Pin. 52, 53; De Luynes, Dener. de quelques l'asse printe, Pla. 21, 22; Welcker, Alts Denkmacker, Pl. 25, Reinsch, p. 64 (reverse skid, p. 61).

Nereid, or perhaps Amphitrite, holding up the wreath. Here also there is no indication of the ring, though the main action is with Poseidon.

On the reverse of the vase, a seated figure, probably a Nereid, seems to be twisting the wreath. She sits between a figure with cinochoe and patern, ready to pour a libation, and a figure with hand extended as if she is speaking.

(4) Vase of the middle of the fifth century, tound at Ruvo, and now in the possession of the Princess di Tricase (Fig. 9).

Theseus and Poseidon clasp hands. The other figures are Nercus, a figure prepared to pour a libation as in the last example, and a figure with the wreath.



Pra. P.

In his left hand Theseus holds what has been described as a box or shell, and assuming that the draughtsman has correctly understood his vase, this may be, as Petersen suggests, a receptacle for the ring. It looks, however, in the drawing as if it might be a fold of drapery brought over the girdle, and it would be strange if the ingenuity of the vase painter could not approach nearer to a representation of the ring, than a case to hold it. It is noticeable that in the figure on the right the hand and drapery have evidently been wrongly drawn. In any case, however, this is the only attempt that the vase painters make to represent the ring incident

¹ Potermu, Rosmische Mitthellungen 12., Pt. 8.; Reinach, p. 79.

The red-figured case in the Brit. Mus. E 201

⁽Wiener Vortegeht, 1890-91, Pt. 3), interpreted as Thomas recognised by his purents, is in many respects parallel to the Triusse was



A scene from the François vase is also quoted by Mr. Kenyon, at the Instance of Mr. van Branteghem, as having reference to the incident (Fig. 10).

In this we have the ship of Theseus close to the shore to which it is drawn up, stern first. One nude figure swims ashore, while the occupants of the ship express emotion and surprise in various ways. Theseus, as a cithurist, leads in set array the seven youths and seven maids, who walk alternately, hand in hand, led by Epiboia or Eriboia.

It is at first sight an attractive suggestion that the swimming figure is Theseus, but the objections adduced by Prof. Robert seem conclusive. The action takes place close to the shore, while Bacchylides, Pausanias and the Bologna wase represent the action as taking place at sea. Also the whole band probably represents a single incident, and the firstal procession is most appropriate to the subsequent landing at Delos.

XIII. Thesens.—The Thesens cycle is already well represented in this Journal by several vases, to which it is only necessary to give a reference.

(1) Kylix in the British Museum, No. E. 84* (J.H.S. iii pl. 10, p. 57, for the interior. The same scenes are repeated on the outside of the vase.).

(2) Kylix, formerly in the collection of Mr.

Tricoupi (J.H.S. x. pl. 1, p. 231.),
(3) Fragment of a kylix from the De L.

(3) Fragment of a kylix from the De Luynes collection in the Bibliothèque Nationale (J.H.S. x. pl. 2, p. 234.)

(4) Kylix at Vienna, with Theseus and Skiron (J.H.S. ix. p. 272.).

For further lists of Thosens vases, see Milant, in Museo Italiano di Antichità Classica, iii. p. 200, pls. 2-4.

A. H. SMITH.

* Reproduced by Reinsch, p. 25.

¹ From Mon. dolf Lies, iv., Pl. 50, supplemented with notes supplied by Mr. Cecil Torr.

ON SOME BLACK-FIGURED VASES RECENTLY ACQUIRED BY THE BRITISH MUSEUM.

[PLATES XV.-XVII.]

Since the publication of the official catalogus (Volume II.) in 1893 the British Museum has been enriched by several black-figured vases of considerable interest and importance, which I propose to describe and discuss in this paper. Excluding the Odysseus and Kirke vase which I published in vol. xiii of this Journal, the total number amounts to eight, one of which bears an artist's signature, while another is a unique example of a very interesting class. Three others again are interesting from a typological point of view. I will take the vases in a roughly chromological order.

L

Corinthian omochoe, 8 in high, from Aegina (Fig. 1). It has a trefoil mouth and squat neck round which is a moulded ring. The handle does not rise above the mouth of the vase, and is quite plain, with cylindrical section. The vase is in good condition, except that the foot is somewhat chipped, and the black varnish is dull and frayed on the lip. It has been imperfectly fired, and the varnish has turned to red in some places. The clay ground is of a buff colour, and the clay itself appears to be rather gritty in texture.

The design presents no very remarkable features. In the centre stands a Siren to the right, of a type frequently occurring on Corinthian vases. Her hair is long, and falls in masses on the neck, and on the top of her head is what appears to be a small fillet. The wings are recurved, and are spread out on either side of the body, the left one being advanced at an impossible angle, in that false perspective of archaic art which arises from the desire to render as much as possible of an object visible at once.

On either side of the Siren is a panther turned in her direction, but with face towards the spectator; their tails are curled over their backs. The field is decorated with ten resettes of the usual type, but instead of being scattered about promisenously they are arranged symmetrically along the upper and lower edges of the design. The rest of the vase is varnished except for a narrow band of clay left visible towards the bottom of the body.

The style of the decoration is rather like that on a lebes from Naukratis in the Museum (B 101), which appears to have Corinthian affinities.

П.

Amphora (Plate XV, and Fig. 2) of the class formerly known as Tyrrhenian, and now usually called Corintho-Attic, but which may perhaps be more conveniently styled Peloponnesian. It was probably found in Italy. The vase stands 15 in. in height, and presents in its shape the usual features of this class, a slim neck separated from the shoulder by a plastic ring, plain handles, and slim egg-shaped body not marked off from the shoulder. The mouth, handles, and toot are covered with black varnish, which, however, is much frayed; two rings of purple have been painted round the foot with a brush while the vase was on the wheel. The decoration of the body is arranged in three friezes, the upper one being considerably wider than the



Fig. 1.—Computeray Ofnocume.

other two; on the latter are bands of animals. On either side of the neck is an ornament consisting of a combined lotos-flower and palmette, from which extend tendrils, those on the one side meeting those on the other except where they are interrupted by the handles. The lotos-flowers have three petals, as always on Attic vases, opposed to the Corinthian and Chalcidian vases, on which they have only two. Bound the shoulder is a roughly-painted 'tongue-pattern' in alternate purple and black, and round the foot

¹ See Leeschake in strek. Zon 1876, p. 100.

tapering rays shoot up: The foot has been repaired and apparently repainted, but otherwise the vase is in good condition.

The 'Peloponnesian' vases have been collected and discussed by Holwerda in the Jahrbach d. Arch. Inst. 1890, p. 237ff.; an interesting one has since been added to the list by Hauser (op. cit., 1893, p. 93). Holwerda gives a list of fifty, of which forty-six are amphorae; two are in the British Museum, (B 47 and B 48), and twenty-six in the Louvre. Most of their typical features are illustrated by the vase here described, as is pointed out incidentally in the following discussion of it. Their style is for the most



Fig. 2 PRIOPONOSOAN AMPHORA: Reverso.

part coarse and clumay, but often rises to a higher standard of merit. The lines are often mechanically drawn and lifeless, a result of the slavish imitation of Corinthian prototypes. Details of drapery are seldom shown; although the dresses are often richly decorated, yet the folds are never indicated. The date of this series is probably not later than the middle of the aixth century 8.c.

The inscriptions are a very interesting and important feature of the class. Like those on our vase they are generally in the Attic alphabet, but from time to time a Corinthian or Chalcadian letter occurs, which may be dis-

Feg. the Q and B on Bellin Car. 1704, and the Chalcidian < on Brit. Man. B 47 (see Jahrb. d. Arch. Inst. 1880, p. 243, No. 84).

tinguished even in the meaningless imitations of inscriptions which occur on so many examples. This is of course mother result of copying; and a curious development is the occurence of two forms of the same letter side by side as in the QK and BE of the Berlin vaso (1704). As regards the meaningless inscriptions, the same combinations of letters have been noted as occurring on different vases, and the collocations seem at times to be due to something else than mere chance.

The ordinary scheme of decoration on these vases is as follows: On the obverse, a mythological subject, on a wide band extending from the neck half-way down the body; this is balanced at the back by a genre-scene of some kind, combats, riders, or dancers, or even animals. The painter appears to have devoted all his energies to the mythological scene, and for the other to have employed only stock types from his repertory. Sometimes these seem to be merely decorative. Or again, we get a single figure taken from a large composition (see Loescheke in Arch. Zeil., 1876, p. 108 ff). Below these are almost invariably two friezes of animals.

The range of mythological subjects is not very extensive, and all the subjects are characteristic of early b. f. vases. Commonest are: Nessos carrying off Deianoira; Combat of Herakles with Anazons; Birth of Athena; and Calydonian boar-hunt. Other subjects which only occur on isolated examples are: Herakles and the Hydra; Perseus and the Gorgons; Theseus and the Minotaur; the Niobidae; Prometheus; Combat over the body of Treilos. Dionysos appears once, accompanied by Satyrs and Macnads; but Bacchie scenso are always rare on early b. L vases. The chief subject of the vase now under discussion occurs also on the specimen published by Hauser in the Johnbuch (but cit.).

Our vase is no exception to the general rule for scheme of decoration. The chief subject, as is plain at a glance, represents the Sacrifice of Polyxena. This we will now proceed to describe in detail. In the centre of the scene, on the level of the ground, is seen a mound-shaped object, with a flat top. It is not easy to say whether this is intended for the tomb of Achilles or an after; probably the former, although the natual type of tomb on black-figured vases is in the shape of a conical tunnalus (e.g. B 239, B 543 in British Museum). It is decorated with a disper pattern of alternate plain purple squares and black squares on which crosses are incised with white dots between the turns. On or behind the temb is a sort of stand or table, on which a lire burns; this of course may be intended for an alter, like that on the B.M. vase, B.S0; but for a mound-shaped alter, compare the \$\overline{\text{Rounds}}\overline{\text{Compare the Bounds}}\overline{\text{Our the Compare the Bounds}}\overline{\text{Compare the Bounds}}\ove

On the left of the altar, Neoptolemos strides forward to deal the decisive blow to Polyxena. In his right hand he holds the sword, which he plunges into her neck; a purple stream of blood gushes out from the wound. His left hand he places on Polyxena's head with a view to steadying himself. He is armed in the usual Greek fashion, but one or two small details of his costume call for notice. On the cheek-pieces of his helmet and on his

greaves are borders of small white dots, which appear to be intended for the stitch-holes generally seen in bronze belmets or greaves.\(^1\) His short, close-fitting chiton is painted white and is apparently of fine crinkled linen; his cuirass is coloured purple. He is apparently intended to be bearded, but the hairs are not indicated.

The body of Polyxena is carried up by three men, and is held in a horizontal position, quite straight and rigid, the chest downwards, and the head slightly raised towards Neoptolemos. One is at once reminded of the type of Odyssens and his companions boring out the eye of Polyphemos; the pole is carried in very much the same fashion by the three men. That type does not occur on any vases of this class, but as it is found as early as the Aristonofos vase, the composition under notice may well be a reminiscence of it. It is a type that belongs almost exclusively to the early black figure period, and must have been well established by this time.

The flesh of Polyxena is painted white where it is visible, with a thin incised line on the neck to indicate a necklace; her hair curls over the fore-head and falls in a long thick wavy mass down the back. She is dressed in a long chiton which is adorned with incised crosses and purple spots; the dress lies stiff and devoid of folds. We are reminded of the line in the Haudia (569); πολλήν πρόνοιαν είχεν εὐαχήμως πεσείν. Her name is inscribed above her: ϶ͶΞ+ἐνΛΟΠ. The alphabet, as in the case of the other inscriptions, is purely Attic; it may be noted that the +¿ are treated as one letter, and therefore not written retrograde as in the name of Phoenix below. Her three bearers are Amphiloches, Antiphates, and Ajax son of Oileus, who hold respectively the upper part of her body round the breast, her waist and thighs, and her feet. They also have their names inscribed: ἐΟ+ΟΝΦΝΑ, ἐΞΤΑΦΙΤΜΑ, ΑΙΑΣ ΙΕΙΑΔΕ[ἐξ.* The three warriors are all armed with swords, and wear helmet, enirnss and greaves; these are ornamented with patterns in purple and white.

The names of Amphiloches and Antiphates call for some remark not merely on account of their epigraphical form. Neither name is to be found in the Iliad, but Antiphates is mentioned by Tryphilodores, 180, and Tzetzes (Post-Hom. 648) as one of the warriors who were inside the Wooden Horse, and Amphiloches the son of Amphilaraes by Quintus Surymaeus (xii, 322) in a similar list. One is tempted to see in the name 'Apphiloches an error for 'Aprilocyes, and the son of Nester (Quint. Smyrm, ii. 244) would be appropriate here in the company of his father (v. infra). In the description by Quintus Smyrmaeus of the sacrifice of Polyxena (xiv. 257 ff.) no mention is made of any of these heroes, nor do their names occur elsewhere on vasca; so that it is difficult to account for their selection here,

⁴ E.y. B. M. Cett, of Bronzes, Nov. 74, 249, 2421, 2928, &c.

^{*} Mes. dell'Int. lx. 4; of, also dell, 1 7, ng. 2; Brit. Mns. B 154; Berlin 2123.

The forms 'Asplacyor, 'Apropersy seem to suggest a reciprocal confusion between the u of aust and the cof arris but see infra.

In Quint. Source xix, 200, Amphiloches remains with Calchas at Troy after the departure of the Greeks. He was a ser, and would therefore be appropriately present at a secritice, as Calchas on the Tabula Biaca. There is another Antiphales mentioned in Od. xx, 242 as grandfather of Amphilonos.

The title Alaş Ἰλιάδης (for Ὁ ιλιάδης) is of course unusual. As a rule where the name of Ajax Ollindes or Telamonios occurs on vases, the patronymic is omitted, but it is a common feature of this class of vases to add surnames, e.g. Ἑρμῆς Κυλλήνως; and so we have Νέστωρ Πύλιος below. As regards the form, Ἰλείθνα (on B 147 and E 410 in Brit. Mus. and Mon. dell' Inst. vi.-vii. 56) and Ἑλείθνα on the Berlin vase No. 1704, which belongs to our group, are not really analogous, as there the vowels | and Ε represent a diphthong. The form Ἰλιάδης does not appear to be quite unknown in literature. In Il. xiii. 203 the scholiast Zenodotos reads it for the vulg. ὑιλιάδης, which form also occurs in Quint. Smyru. vi. 556 and elsewhere.¹

To resume our description of the scene, three figures still remain for discussion. Phenix moves away on the extreme right, with elenched right hand and spear in the other; his name is written \(\frac{1}{2} + |\mathbf{M}| \Operatorum \text{Beyond him}\) is a folding stool. On the left stand Diomede (\(\frac{2}{2} \Delta \Delta MO| \Delta\)) and Nestor (\(\text{NE} \gamma \text{TOP} \cap \Tau \text{LO})\), the former holding two spears and shield. Nestor is not represented as of any great age, but has black hair and board. He wears the long white linen chiton of the chariotem, and holds a spear; his figure exactly balances that of Phenix.

The death of Polyxena is not a common subject in Greek art. It occurs in several 'Himpersis' scenes, but in those cases we have merely the figures of Neoptolemos and Polyxena, and sometimes there is nothing to identify them, or the type is approximated to that of Ajax seizing Cassandra, as on the Brit. Mus. vase F 278. Pausanias alludes to it among the paintings in the Pinakotheke of the Propylaca (i. 22, 6): τοῦ δὲ 'Αχελλέως τάφου πλησίου μέλλουσά ἐστι σφάζεσθαι Πολυξένη.² He tells us (x. 25, 10) that he had seen another painting of the subject at Pergamos on the Kaikos. Overbeck 'gives a list of vasos, gems, and Etruscan uras, on which the subject is to be found 'to these may be added:

- (1) 'Peloponnesian' vase, Jahrlnich d. Arch. Inst. viii. (1893), Pl. I.
- (2) Robert, Homerische Becher, p. 73, with figures of N. and P., Odysseus, Agamemnon, and three unnamed heroes; subject taken direct from Eur. Hec. 558 ff.

See Resychius; Find. Ol. 1s. 167 and Schol.; and Pape, Or. Eigennances under each form respectively. known Township cists in the first. Mas. (Cat. 743) can only be regarded as a doubtful one. There is no section indication that the figure of the victies is feminine, and the proportions would suit equally well for a boy, while the whole design is somewhat underfinet. On the other hand, the connection of the scene with the death of Neoptolemos on the other side of the cists is an argument in favour of the received interpretation.

Overheek (Arch. Miss. 1887, p. 10) has suggested the possible identity of this pointing with one by Polygnotos for, according to another reading, Polyklaftes) described in an epigram (Asih, Plan, iv. 150).

^{*} Her. Bildweele, p. 661 H

It may be noted that the most important of the examples given by Overbeck, the welf-

As part of an Illupersis scene the subject occurs on the following examples:

- (3) Brit. Mus.: F 160,
- (4) Naples: 2422 (the Vivanzio vase).
- (5) Louvre: Kylix by Brygos (Heydemann, Hupersis, Pl. I.).

It will be interesting to compare with our vase No. (1) in the above list, an amphora in the Bourguignon collection at Naples, published by Hauser (loc, cit.)

The types are startlingly different. The painter of the Bourguignen amphors appears to have adopted another 'Himpersis' type, that of Priam's death on the altar of Zeus, for the figure of Polyxena.\(^1\) The moment represented is not quite the same; Neoptolemos has already accomplished the deed, and is hastily mounting his chariot (this again is a borrowed motive, from the Amphiaraos vase in Berliu). None of the figures are inscribed; Polyxena has fallen, not on an altar, but on a tunnulus which represents the burial-place of Achilles.

The subject on the reverse of our amphora will not compare with the obverse in interest, but yet calls for some attention. It represents a revel of four men dancing in somewhat grotesque attitudes, flunked on either side by a cock. This is a common type on Coninthian wases and on more than one class of imitations of Corinthian wares, where they supply the place of the Satyrs on Ionic and Athenian fabrics. A list of instances is collected by Körte in Jahrbuch d. Arch. Inst. viii. (1893), p. 90, note 58; to which we may add:

- (1) Berlin Cat, 1662 (Corinthian),
- (2) Brit. Mus. B 42 " (subject : return of Hephnistos).
- (3) Brit. Mus. B 44 (imitation Corinthian).
- (4) Furtwaengler, Coll. Sabouroff, i. Pl. 48.
- (5) 'Eø. 'Apx. 1885, Pl. 7.
- (6) Amphora at the Hague (Jahrbuch, v. (1890), p. 244), of 'Pelopon-nesian' fabric.
- (7) Vase in Athens, published by Locscheke, Athen. Mittheil, xix. (1804), Pl. 8, p. 519 ff. (subject: return of Hephalstos).

The meaning of these figures has been subject to some discussion. Furtwaengler, von Rohden, and formerly Locscheke, have regarded them as

Hadaer ad too, p. 60,

In reference to this wase, which Locacheke (Ath, Mitth. 1894, p. 516) claims to be 'sofit Korinthisch,' and which is the entalogue I have included among 'Imitations of Corinthian fabrics,' it may perhaps he worth while to mention that my view accords with that of the late F.

Durantiler, who prenounced the vans to be Sicyonian, and classed it, on stylictle grounds, with the Berlin vans No. 1147 which bears a Sicyonian inscription,

⁴ dun dell Inst. 1877, p. 450 and 1878, p. 301; Banmeister, Denkindler, iii. p. 1962.

terrestrial votaries of Dionysos. Duenumler lirst raised the question whether they should not be regarded as $\delta ai\mu over$ of some kind, a question which now seems to be solved by their appearance on Nos. (2) and (7) accompanying Hephaistos and Dionyses. Loescheke, in publishing the latter vase, has definitely pronounced for this view. He points out that their correct title is $\Sigma \dot{\alpha} \tau \nu \rho ai$, and that they represent the Satyrs as they appeared in the oldest Satyric dramas of the Peloponuose.

The attitude in which these Σάτυροι are usually depicted, with one legraised and pointing outwards, appears to illustrate the word ρικνοῦσθαι,⁴ interpreted by Pollax (iv. 99) as τὸ τὴν ὁσφὺν φορτικῶς περιάγειν, and by Sophoeles (apud Phot.), τὸ καμπύλον γίγνεσθοι ἀσχημόνως, καὶ κατὰ

συνουσίαν και (κατ') δρχησιν, κάμπτοντα την δοφύν.

The remaining decoration of the vase, as already indicated, consists of two friezes of animals arranged in heraldic fashion: (1) on the upper row, a pair of Sirens confronted, with a pattern of two lotus-flowers and two palmettes between; two groups of a panther and a ram divided by a swan; (2) on the lower row, two groups of a ram between panthers.

III.

Kantharos, 10% in, in height, 7% in, in diameter, with sharply-pointed handles bent round to form an inverted semi-circle with the lower edge of the body (Fig. 3). The vase is said to have been found at Athens, near the Payx, and was originally found in fragments; these were put together, not without a considerable amount of restoration, which has now been removed. The lavish use of purple and white for details gives a pleasing appearance to the vase, while its shape is not ungraceful. The white pigment has faded to a considerable extent, and turned to a blaish colour on the black varnish. The ornaments consist of a tongue-pattern round the rim, and a row of small black dots along the bottom of the design, and round the upper part of the stem is a chequer pattern in squares. Underneath the cup, above the stem, is an interlacing lotos-and-honeysuckle pattern, resembling that on the neck of the Polyxena vase just described, a small detail which indicates that the yase, although by an Athonian painter, is by one who has not yet freed himself from Corinthian influences. We shall see that the choice of subjects and their treatment also recall us to Corinthian archetypes. The handles, and all the foot, except the lower edge, are covered with black glazie.

The kantharos is not a common shape before the fifth century a.c. Its form being essentially suited to metal, it was never popular in pottery at any time, in spite of the fact that it is one of the most beautiful shapes conceivable; but black-figured examples may be counted on the fingers. One other exists in the British Museum (B 370), and three in Berlin (1737, 4012, 4013); of the latter, No. 1737 is early Attic work (with Inscriptions), and

Ann. will. Inst. 1855, p. 129 janu are pl. [1] Soph. Frog. 297 : Lucian. Lexiphones, 8.

is grouped by Klein, Emphronies, p. 73, with B 147 in Brit. Mus., and other vases of the school of Klitias and Ergotimes. On the other hand, the frequent occurrence of the kantharos as an attribute of Dionysos or as a device on shields! implies that the form was quite familiar at this period.

On either side of the cup is a subject, the meaning of which is clear enough, but there is room for doubt as to whether or no it is of mythological import. The one side rapresents the departure of a warrior in his chariot, the other, a combat over a fallen warrior. One is tempted to see a connection between these two scenes, and if they are mythological, we must look for some known type to which they correspond. Now, as regards the first, the well-known Corinthian krater in Berlin (No. 1655), with the departure of Amphiarnos, gives a well-defined type; as regards the second, in order to



FIG. S.—ATHENIAN KANTHAROS.

arrive at a connection with the other side, we are at once reminded of the combat over the body of Polyncikes. Thus the two sides of the vase may represent two episodes from the story of the Seven against Thebes. This interpretation must, of course, be received with caution; its correctness cannot be proved, but it is at least a permissible suggestion.

On vases in Brit. Mns. as shield-device: B 207; in Berlin: 1790, 1865; as attribute of Dionymer: B 149, 158, 178, 179, 180, 195, 198, &c; in Brit. Mns.

² See for these two representations in ancient art, Overbeck, Her. Bildse. pp. 91-135. He gives several inacribed vases with the departure of Amphianae, and other conjectural instances,

is regard to which he points out that if they have any mythological ununing it is probably this. But he denies the existence of any representation of the 'Brüderkampf' earlier than the Etruscan sepulchral arms. He can'le, herewer, the inscribed mirror in the Brit. Mas. (Cot. No. 621) which is not later than the 3rd cent. here and probably earlier.

We proceed to describe the two scenes more in detail.

(1) The departure of Amphiaraos (Plate XVI.). The main portion of the scene is occupied by a four-horse chariot standing to the right. The charioteer (Baton) is of the usual type, clad in a long chiton of crinkled white linen, and holding a goad in one hand and reins in the other. His hair and beard are painted purple. The hero, or Amphiaraos if he may be so termed, mounts the chariot from the further side. Of his attire all that is visible is a short chiton, with ornamental border. On the near side stand three figures, a woman and two warriors. The first of these holds up a helmet in his hand for Amphiaraos to put on, the other holds up a bow, and carries a shield, with device of a snake; but there is no authority from which we may derive names for them. Their position on the near side of the chariot is an unusual one; in scenes of this kind the 'Nebenfiguren' generally stand in a line on the further side of the chariot, as in such instances as Gerhard's Auserlesene Vasenbilder, Pls. 136-140, 249, 252. The horses all have topknots; at their head stands a bald, bearded old man, wearing a chiton and himation, both embroidered, but the patterns are faded away. Behind him is a woman drawing forward her himation like a veil over her head; this attitude is familiar as indicating a bride in the presence of her husband; it is possible that she may be intended for Eriphyle, but there is no necklace to characterise her, as on the Berlin vase. The scene is closed by a bearded man wearing a chiton and himation, whose figure has almost entirely disappeared, and had been much restored.

On the left side of the scene are three figures balancing the three on the right: a woman wearing an elaborately decorated chiton and a purple and white wreath; a warrior fully armed, whose shield bears a star of seven points as device; and a bearded man who appears to be in conversation with

the warrior.

On the whole there is so little characterisation of the figures, and so little to differentiate this from other compositions of the kind that I am inclined to regard it as merely a 'departure of a warrior' scene, in spite of the possibility of a connection with that on the reverse.

The reverse (Plate XVII, Fig. 1) is in worse condition than the obverse; it represents, as has been said, a combet over two fallen warriors, which, like the other scene, is a very familiar type on black-figured vases. There is nothing to indicate that either of the warriors is slain; they merely appear to be temporarily rendered horse de combat. One leans on his right elbow; the other is fallen on his knees. The latter carries a Bocotian shield; of his person the legs alone now remain. Over them stand a pair of warriors lighting, with spears, of whom the right-hand one is now lost, and on the right were no doubt two other pairs of combatants, but this part had been entirely restored. On the left is another pair fighting with spears, but the left-hand warrior runs away while he turns back to thrust at his pursuer; his shield-device is a tripod. If the interpretation suggested above is to be accepted, the central figure would of course be Eteokles, and the fallen one Polyneikes.

Throughout this scene the work has been very careful, with minutelyincised lines and a lavish use of purple and white pigments; all the armour is treated in elaborate detail; but the effect has been much marred by the restorations.

The exact position of this vase and its relation to the masters of Athenian black-figure vase-painting is not easy to determine. We have seen here and there a suggestion of Corinthian sources, but the general tone and style is Athenian. Though free from the mannerisms and affectations of the Klitias and Ergotimos period (represented by the François vase and the Brit. Mus. vase B 147, with the birth of Athena), it yet comes near to this class; while in the crowding of figures and elaboration of detail we see an anticipation of Glaukytes and Nikosthenes. Novertheless it would be rash to assign this work to any one painter or school; we can only say that it must be dated about the middle of the sixth century B.C.

IV.

Kylix of the 'Kleinmeister' type, from Aegina, 7½ in. in height and 10½ in. in diameter. The style is that of Glaukytes or Nikosthenes, and in general appearance the vase is very similar to one signed by Glaukytes and Archikles, published in the Wiener Vorlegeblätter for 1889, Pl. 2, fig. 2c. We may also compare the kylix by the former artist now in the Brit. Mus. (B 400).

The designs are painted on a red band round the cup, which is of the shape characteristic of the period (see B.M. Cat. of Vases, ii. Pl. 5, fig. 16). The rest of the vase is covered with black varnish, with the exception of a circle of 3½ in. diam. in the centre of the inside, a red band round the bottom of the bowl, and the foot.

The subject on either side is the same, with little variation: the preparation and departure of warriors for battle. On the obverse (Fig. 4) are four warriors; one mounts his chariot accompanied by a small groom; the next is moving away on foot; the third is putting on his greave (a familiar b.f. vase motive); while on the extreme left is a warrior domning his helmet and accompanied by his dog. This last motive appears to be a new one; it does not occur on any other b.f. vase in the Brit. Mus., or in the Berlin collection. Usually the warrior's helmet lies on the ground, or else it is handed to him by a woman. Interspersed with these figures are twelve draped 'Nebenfiguren,' one of whom is a woman.

The reverse is almost identical, but the warrior putting on his helmet is omitted, and one of the bystanders, making a total of fifteen figures in all, against seventeen on the obverse.

In the field on either side are various collocations of letters representing inscriptions, but all quite meaningless. The cup is much broken, and has been restored in places; the colours are faded, and the work is rather careless.

V.

Fragments of a kyathes, about half remaining (Plate XVII. Fig. 2). Shape as B.M. Cat. of Vases, ii. Pl. 7, fig. 1; height 24 in. These fragments probably come from Italy, but no information has been received. They have a special interest inasmuch as they bear the signature of the potter Nikosthenes, thus adding another to the already long list of his known works. Klein gives two vases of this shape as signed by Nikosthenes, but neither has been published, nor are their present possessors known. Judging from his description the first exactly resembled our present example: 'Kelle mit einem Henkel Tanz von fünf Silenen und vier Mänaden. Darüber die Inschrift.'

The handle is covered with black varnish; the cup itself is covered with glaze of a rich buff-red colour, and both purple and white pigments are employed. The decoration consists of Satyrs and Maenads dancing in pairs, the latter wearing long girt chitons with white spots. One wears a χιτών σχιστός, another kicks up her leg behind.

VI.

Amphera from Aegina, 171 in. high, with designs in panels on either side (Figs. 5, 6). This wase appears to be of comparatively late date, as is shown by (1) the shape, which is characteristic of amphorae of the Andokides and Euthymides schools, (2) the almost complete absence of purple and white pigments, (3) the borders of ornamentation surrounding the panels, which are also seen on early r. f. amphorae, and on hydrine of both methods. The handles are quite plain; there is a rather sharply-marked division between neck and shoulder, but it is curvilinear, not angular, as in the red-bodied amphorae. The black varnish is rather worn, but on the whole the vase is in good condition. The ornaments consist of inverted lotos-buds above the panels, rows of dots down the sides of the panels, and rays shooting up from the foot.

Both the subjects on the panels are of considerable interest: the obverse represents Herakles bringing Kerberos out of Hades, the reverse, two heroes playing at draughts in the presence of Athene, both being familiar subjects on b. f. vases. The former was not previously represented on any vase in the Brit. Mus., but the latter occurs fairly often (see Faze Cat. ii. p. 27 and also E 10).

On the obverse of our vase Herakles, with club in hand, short chiton, and lion's skin tied over his head, hands the two-headed Kerberos along with a chain. He moves towards the left, and looks back at his prize, the two necks of which are adorned with purple collars. A richly-curling mane runs

¹ Meisters, ² p. 60, Nos. 54, 55,



FIG. 4.-ARBING OF WARRIORS.

down the back of the monster. On its further side is seen Hermes, with face to right, but feet to left. His hair is looped up behind in the κρωβύλος, and he is attired in the usual style, with petasos, chlamys, and high boots with large tags in front. The petasos is painted white with a purple brim. The locality is here indicated by a Doric column with white capital, which is artistic short-hand for the palace of Hades, and within the palace is Persephone, holding a sceptre capped with a pomegranate; she stands away from the scene, but looks back at Kerberos. She wears a chiton and himation.

On the reverse is a plain block of stone in the centre, before which stands a statue of Athena with face to left, the left hand up-raised, and a



PIO. 5.—AMPRORA: HRECES PLAYING AT DRAUGHTS.

spear couched in the right. This position of the goddess is new to the type; she is usually placed on the further side of the block. The two heroes are draped, not armed, but each has two spears in the left hand, and the one on the right has a sword. Behind each is a shield, the one on the left being inscribed OXO, while the other has a tripod as device; and above each shield is a belinet. The space above is filled in with branches. The warrior on the right holds an object between his fingers, presumably a wegges; the same

Studniocka in Jahrb. d. drch. Inst. (1898), p. 248 ff.

I have refrained from styling this object an alter, we it has been hitherto called, since it

has been pointed out by Blinkenberg (Ath. Mittheil. xxiii. (1898), p. 9), that it really represents the table on which a board was marked out for playing the game of tel viers γραμμών.



En. 6, - HERAKLES URINGING KERBEROS OUT OF HADIS.

action occurs on B 193 in Brit, Mus., but no pessi are here visible on the

table between them as is usually the case.1

The subject of Herakles and Kerberos occurs on no fewer than 36 black-figured vases, as against 6 red-figured, and 7 of later date. Several lists of them have been made, the first by Gerhard in his Austricence Vasenbilder, ii. p. 157: he gives there 13 examples; supplemented by Conze in Ann. dell' Inst. 1859, p. 398, who adds 11 more. Dr. F. J. Schneider in his Zwölf Kümpfe des Herakles, p. 45, gives a more complete but somewhat inaccurate list, which has been partly corrected by Hartwig in Jahrbuch vii, (1893), p. 158. As Hartwig does not give a revised list in full, I have thought it advisable to do so here, pointing out where possible the variations in the type. Soveral of the vases in Gerhard's list are only vaguely and superficially described, and even now it is possible that there may be one or more duplicates; but as far as possible every item has been identified.

10	MARTINE	SHOVENI-	COLLECTION.	CATALOGUE	SUBLICATIONS.	spanial spanial	abitation Dist.
			1. BLAC	ok-figure	D VASES.		
		A. With En	rystheus in pithe	e ; no palace	of Hades; K. has three heads		
1	Cacrelan Hydria	Corretri	Louve	679	Mon dell' But, vt. 36	-	1. 23
2	Caerotan Hydria	Cervetri	Castellani	-	Bull dell Ind 1869, p. 249	-	24
		B. 2	to palace of Had	es of Enrysil	iens ; K. has two heads.		
3	Ampliora	-	Minich	153	Inghirami, Fast Pitt ii.	.5	1. 1
1	Amphora		Munich	1200	190-190	Ē	2
5	Amplura	200	Berlin	1825	2	6	5
9	Amphora	Vulci	Berlin	1880	-	- 0	20
7	Amphore	Rhodes	Lonvre	482	_	_	-
7	ymbpota	(Campana Coll.)	St. Potendang	192	-	E	19
0	Amphora	(0016-)	Warsburg	250	Gerhard, dusert Passak ii.	d	8
-			as measure	-8400	97. 3	5.8	0
0	Amphons	Corneto	Corneito	-	Bull, dell Inst. 1878, p. 178		14
1	Amphure.	-	Duratal	809	Gerhard, Assert, Passab, it.	-9	18
0	A served by travel	/ University of	Complete Control of the Control of t		129		
2 0	Amphora	Cervatri	Cartellani Depoletti		Bull. dell' Inal. 1885, p. 145	-	7
1	Amphera		Candelori			0	9
5	Amphora	Orvieto	Catholica (1)		Ann. dolf Ind. 1877, p. 123	3	10
6	Amphora	Chiusi			Inghirami, Past Pitt. 1, 40	0.	10
7	Amphora	_	-	-	Gerhard, Ansort, Vanonte il.	787	15
8	Amphons	=	-	_	[K. has three houses]	k	11
0	Hydrin		Baseggio		Bull, dell Inn. 1847, p. 28	q	17

Another interesting variant of the Bretzspiel' type is given by a Cypriote-Attic oinochoe from Poll in the Museum at Nicosia (Myres,

Coppus Mus. Cut. p. 84, No. 1603); behind such player is an attendant warrier.

	5833E	FROTERIA CHOR.	- Alexander	paralables.	FRALIO 47000L	ernamo e crescr.	可以被 医色色 中国等。
	****		Camponari			(a	18
12	Hydria Kyliz Xanoklesi	=	Durand	A5	R. Rochette, Mon. Isol. pl.	D	12
12	Kylix Lekythov	Toscanella Corretti	Castellani	271 Collian-	Bull. dell' Just, 1889, p. 74 Bull. dell' Jant, 1869, p. 250	-	9 <u>9</u> 0 4
25	Lekythos	_	Athena	on) 209 (Collign-	-	-	3
				(0)		1	
				alice of Hade	The same of the sa		
20 27 26	Amphora Amphora	Cornete	Hrit. Mos. Moscow Nuples	SA 207	J. H. S. xviii, p. 295 Bull, dell' Inst. 1859, p. 131 Jahrbuch d. Arch. Inst. viii.	2	IL D
10	Amphora	=	Rome	_	(1893), p. 157 Museo Gregoriano, u. pl. 52,	-	н
30	Amphora Pellos	Magna	Durani	ä10	Camponia Cirk iv. 507 [K. has two dogs' and one	11.	A
82	Hydria	Oraccia	Naples	3378 185	Serhard, A.F. i. 40	=	E
33 34 35	Hydria Hydria Hydria	Vulei	Whitsburg	=	Bull. dell Inst. 1840, p. 124 Gerhard. A. F. ii. 131		G K
36	Skyphos (Corinthlan	Argus	-	-	frek. Zeit. 1859, pl. 125 [K. has one head.]	-	18
			20.00		s ar Little		
0		15.7	A. Withou		VASES, r palace of Hades.	1 2	25 & M
37 39 40	Kylix Kyliz	Canino Chinsi !		Eurysthous o 406 352		= =	
98 98 98	Kyliz Kyliz	-	A. Withou Munich Würzburg Berlin Naples (Bour- guignen)	Eurysthous o 406 352	Jahrbuch, 1893, p. 182 Jahrbuch, 1893, pl. 2; p. 161 Jahrbuch, 1893, p. 160	. =	20 & 27
88 89	Kylix Kyliz Piuax	Chlast 1	A. Withou Munich Würzburg Berlin Naples (Bour- guignen)	t Eurysthous o 406 352	Jahrbuch, 1893, p. 182 Jahrbuch, 1893, pl. 2; p. 161 Jahrbuch, 1893, p. 160	. =	20 & 27
39 30 40	Kylix Kylix Piuax Amphora (Andokides	Chlast 1	A. Withou Munich Wirzburg Berlin Nuples (Bour- guignen) B.	t Eurysthous o 406 352	Jahrbuch, 1893, p. 182 Jahrbuch, 1893, pl. 2, p. 16; Jahrbuch, 1893, pl. 160 Hades:	=	26 & 27
99 99 40	Kylix Kylix Piuax Amphora (Andokides	Chinsi I	A. Withou Munich Würzberg Berlin Naples (Bour- guignen) B. Lauvre Altenburg	With palace of	Jahrbuch, 1893, p. 182 Jahrbuch, 1893, p. 182 Jahrbuch, 1893, p. 180 Hades: Durand Coll. 311 Jahrbuch, 1893, p. 163 [K. has one head]	=	26 & 27
\$9 40 41 42	Kylix Kylix Piuax Amphora (Andokides Kylix	Chiasi Vuloi	A. Without Munich Witzbarg Berlin Nuples (Bourguignen) B. Lauvre Altenburg APULIAN VA	With palace of K. has three 1/270	Jahrbach, 1893, p. 182 Jahrbach, 1893, p. 182 Jahrbach, 1893, p. 180 Hades: Davand Coll. 311 Jahrbach, 1893, p. 163 [K. has one head] mattions of Cudorworld). heads.; Wiener Vorl. E. 6, 1	=	26 & 27
39 40 41 42	Kylix Kylix Pluax Amphora (Andokides Kylix Kylix Kylix	Chinsi Valet UI.	A. Without Munich Würzberg Berlin Naples (Bourguignen) B. Lauvre Altenburg APULIAN VA	With palace of K. has three 1 270 2222	Jahrbuch, 1893, p. 182 Jahrbuch, 1893, p. 182 Jahrbuch, 1893, p. 160 Hades: Duvand Coll. 311 Jahrbuch, 1893, p. 163 [K. has one head] matrices of Cuderworld). heads.; Whener Verl. E. 6. 1 E. 2 E. 6. 5	=	26 & 27
\$39 40 41 42 42	Kyliz Kyliz Piuax Amphora (Andokides Kyliz Kyliz Krater Voluto-krat Voluto-krat Voluto-krat	Chinsi Chinsi Vulci UII. Apulia _ er Altamure or Armento or Armento	A. Without Munich Würzbürg Berlin Naples (Bourguignen) B. Lauvre Altenburg APULIAN V. Brit. Mus. Naples Naples Naples	With palace of S272 K, institute of S272 SA 11 SA 709	Fakrback, 1893, p. 182 Jahrback, 1893, p. 182 Jahrback, 1893, p. 180 Hades: Durand Coll. 311 Jahrback, 1893, p. 163 [K. has one head] matrices of Cuderworld), heads.; Wiener Varl. E. 6, 1 "E. 2 "E. 6, 5 "E. 8, 2	=	T- 20 % 52
28 000 40 41 42	Kylix Kylix Pluax Amphora (Andokides Kylix Kylix Krater Voluto-krat Voluto-krat Voluto-krat	Chinsi I Vulci Vulci LII. Apalia Altamurr cel Armento er Armento er Carnens	A. Without Munich Würzbarg Berlin Naples (Bourguignen) B. Lauvre Altenburg APULIAN V. Bris. Mus. Naples Naples	With palace of K. has three 1 270 2222 SA 11	Jahrbuch, 1893, p. 182 Jahrbuch, 1893, p. 182 Jahrbuch, 1893, p. 160 Hades: Duvand Coll. 311 Jahrbuch, 1893, p. 163 [K. has one head] matrices of Cuderworld). heads.; Whener Verl. E. 6. 1 E. 2 E. 6. 5	=	T- 20 % 52
\$1 42 42 41 41 41 41 41 41 41 41 41 41 41 41 41	Kyliz Kyliz Piuax Amphora (Andokides Kylix Kylix Kylix Volute-krat Volute-krat Volute-krat Volute-krat	Chinsi I Vulci Vulci LII. Apalia Altamurr cel Armento er Armento er Carnens	A. Withou Munich Witzbarg Berlin Naples (Bourguignen) B. Louvre Altenburg APULIAN V. Brit. Mus. Naples Naples Naples Munich Karbsrubs	With palace of K. has three 1 SA 11 SA 709 S49	Jahrbuch, 1893, p. 182 Jahrbuch, 1893, p. 182 Jahrbuch, 1893, p. 160 Hades: Duvand Coll. 311 Jahrbuch, 1893, p. 163 [K. has one head] matterns of Cuderworld): heads.; Whener Verl. E. 6, 1 E. 2 E. 5 E. 5 E. 5 E. 5 E. 1 E. 3, 1	=	26 & 27

VII.

Lekythos from Greece, 6½ in. high, with black figures on white alip ground (Fig. 7). The style is late and careless; there appear to have been purple accessories, but they are faded away. The shoulder of the vase is left in red, and palmettes are painted on it in black; round the top of the design runs a band of macander. The black varnish is very poor in quality; the handle

has been repaired.

The subject represented is one usually associated with the earlier b.f. period: the combat of Herakles and Geryon. Our example presents several features in which there is a marked deviation from the ordinary type, as will be seen from the description. Herakles kneels on his left knee to the left and discharges an arrow from his bow at the monster, which is separated from him by a rock, on which grows a tree. On this rock Herakles has laid his lion's skin or some piece of drapery. The figure of Geryon is represented in the traditional manner (τρείς ανδρες άλληλοις προσεχόμενοι). One body (apparently the middle one) has fallen forward wounded; he still clings to his spear, but his helmet has fallen off. The other two are armed with spears, and wear helmets and cuirasses. Behind Geryon are the figures of the herdsman Eurytion and his dog Orthros, the latter seated on the ground, the former stooping forward. Eurytion wears a pileus or conical leather cap, and carries a chlamys over his left arm. He is armed with a spear and sword, Under the handle appears the figure of Athena with hands raised, one of them holding a spear, round which twines her serpent.

The types of Herakles and Geryon have been collected by Klein, Euphronics (2nd edn.), p. 59, and those on Brit. Mus. vases in the Catalogue, it. p. 17; nor do there appear to be any additions to make to the list. The one that approximates most nearly to our example appears to be the r.f. kylix illustrated by Klein on p. 81, but only in our vase is Herakles turned towards the left. Again, nowhere else but on our vase does Herakles kneel even when using the bow (which is also seen on Munich 407 and Brit. Mus. B 442); the attitude in this case seems to be borrowed from the east pediment of

the Aegina temple, where Herakles appears as a kneeling archer.

Another new feature is the position of Eurytion and the dog, who are usually represented as lying wounded or dead; and finally we note the rock, which often indeed forms the centre of a scene on b.f. vases (cf. the Brit. Mus. Troilos hydria B 324) but never otherwise occurs in a Geryon-scene; in fact Herakles is generally too close to Geryon to use any weapon but a club or sword. It may be that the painter put in a rock here to give the idea of distance.

⁴ Also in Novi des Vargurs, Etrarre, 2 pl. 25.



FIG. 7. -LERYTHOS: HERARIES AND GEHTON.

VIII.

Panathenaic ampheriskos, \$\frac{1}{6}\$ in, high, with black figures on red ground and white details (Fig. 8). This little vase can hardly be regarded as belonging to the class of Panathenaic amphorae, although it has all their characteristics in miniature. It was presumably a child's plaything, as many vase-paintings seem to indicate that toy vases were popular in the Greek nurseries.\(^1\)



FIG. 8.—PANATHENAIC AMPRORISEDS.

Small as it is, it is by no means devoid of interest. In date it must be quite late, perhaps of the 4th cent. s.c., to judge by the free and careless execution. The figure of Athena is of the usual type, but on the reverse is what appears to be an entirely new subject for a Panathenaic amphora, viz. a runner in the torch-race (λαμπαδηδρομία). This subject is common on late r.f. and Graeco-Italian vases of the fifth-fourth century (e.g. F 50 and E 380 in Brit. Mus., and Tischbein, Hamilton Vases, ii. Pl. 58). The runner

P 101, E 527, E 534, E 535, &c. in Brit. Mus.; also Jahn in Ber. al. suchs. Genellech. 1854, p. 243 ff.

wears a large wreath with several upright crests over the forehead, painted in white.

An almost identical vase has lately been acquired by the Cassel Museum. Instead of the torch-runner, an athlete of Polycleitan type is depicted on the reverse.

H. B. WALTERS.

Juhröneh, xiii. (1898), Ameiger p. 192, fig. 11.

A DEDICATION TO ARTEMIS

THE coin of Sicyon, of the obverse of which a drawing by Mr. F. Anderson (made over a photograph) is given here, has been twice published both times by Professor Percy Gardner.



States of Sictor (British Museum). Enlarged 2 diameters.

It is a stater of the fourth century B.C., of the usual types:

Obverse: SE Chimagra to r.

Reverse: Dove flying r.; behind it, over the tail, a small bow. The whole in an olive-wreath. Concave field. Slightly double-struck on both sides.

Weight 188 grains (12 182 grammes).

The inscription on the obverse, which lends special interest to this piece, is unique among adscititious inscriptions upon Greek coins, not only in its elaborate character, but in the manner of its execution. Such inscriptions are in other cases graffiti, scratched with a point; this is pricked into the metal with a pointed instrument.

Herris Namism. 1874-77, pp. 325 f. To his list add the coins of Pheneus, J.H.S. svit p. 85, and Corinth, Rev. Nuct. 1898, p. xlift, and R. M. Catal. Corinth, nos. 8, 131, 226.

VIII. Fig. 5, from a drawing by F. Lees); Brit. Mus. Catal. Poloponnesses, p. 41, no. 65, (Pl. VII. 26, autotype);

^{*} They have been collected by F. Lemmmant,

Professor Gardner, in publishing the inscription, reads it

APTAMITOS TAS EAKETAS AMON.

He adds that the T of the third word may be a T, the A of the fourth word is indistinct, and that 'at the end of that word is a mark which might stand for I, although I believe it merely to indicate the end of the inscription, there being a similar mark at the end of the first word.' These difficulties are, however, small in comparison with that connected with the meaning of laketas (or tather election, if it is an adjective formed from the verb election). None of the explanations connecting the word with electrons to me entirely satisfactory.'

Under these circumstances a further examination of the inscription

seemed worth the making. My results are as follows.

In the first place, as will be seen from the drawing, the initial letter of the inscription is most probably that which stands under the chimaera's tail, behind the left hind leg. I make no doubt that the letter is τ and not Γ , which could hardly be represented with the same number of points in both strokes, even in a carelessly punctured inscription (which this is not). But if it is τ , its position in regard to the other letters can only be explained by its being the first letter of the inscription. In beginning the dedication, it was natural to hold the coin so that the type stood the right way up. But the writer found out his mistake when he came to make the second letter. If on the other hand this τ is not the first letter in the inscription, its position is much less explicable.

The inscription offers no further difficulty until we come to the first letter of the second (outer) circle. This is read by Mr. Gardner as A. All that is visible is Δ. It might be supposed that the lower parts of the two legs of A were omitted owing to want of room. But this supposition is excluded by the fact that in other cases of confined space the punctures are carried over the edge of the coin, as may be plainly seen in the letters κε behind the tail of the chimaera. Hence there seems little doubt that the letter in question is

A and not A.

After the letter N comes the last sign in the inscription; Mr. Gardner conjectures this to be a stop of the same kind as occurs at the close of the word ARTAMITOS. But while the latter stop is made with two strokes of the instrument, effecting marks much larger than any others in the inscription, the sign at the end is made in exactly the same way as the letters. It is safe, therefore, to suppose it to be I and not a stop.

Thus read, the inscription becomes

TAKARTAMITOKTAKEAKE AMONI

which I interpret τa_s 'Ap $\tau a_{\mu \tau \tau \sigma s} = \lambda(\lambda) \Delta(a) \kappa \epsilon \delta(ai) \mu \sigma v_i$.

formation; and the formiliation eres would at any rate have a passive force.

trouble, 'helper in childbirth.' It is also questionable whether (here's is a possible

The omission of the second letter of the preposition is of course quite in order.\(^1\) But the emission of the vowels in the word \(\textit{AaxeSai\textsuper}\) certainly gives pause. The first \(\textit{A}\) could, however, easily escape, owing to the \(\textit{A}\) immediately preceding it; the \(\textit{A}\) must have been sacrificed for reasons of space. It was more necessary to preserve the dative termination than the vowels in the middle of the word.\(^2\)

On Greek coins of the Imperial period, especially at the beginning of third century, it is common to find the word AYTOKPATOP abbreviated AYTKP or AYTKPA. This form occurs so often that it can hardly be due to a more blunder. In the CB which is sometimes found instead of CEB(aστός), the loss of the E may perhaps be explained by its likeness to C. Forms such as AOYKIC for Λούκιος, on the other hand, are probably neither abbreviations nor blunders, but, like HMIOBEAIN, anticipations of the later Greek terminations -is, -ip. After the βavs of the coins of Smyrna, the carliest instance of syncopated abbreviation known to me in official inscriptions is the monogrammatic form of KAP for Kaiσap which Imhoof-Blumer has described from coins of Chalcedon and Byzantium struck at the beginning of the Empire. But many methods might have been allowed in monograms which were unusual in ordinary writing.

These notes are sufficient to show that the syncopated method of abbreviation existed, though sporadically, at an earlier period than is generally supposed,

* Numina, Chron. 1898, p. 5.

Granfall, du Alexandrian Erwis Fragment etc., no. 24.

* E.g. at Pennthus, Berlin Besche, A. and Managa, i. p. 214, non. 41, 43.

⁶ J.H.S. 1897, p. 82; Januaria, Historical Grad Pronumer, 4 301, 302.

¹⁰ Journal International d'Arch Numeron L. (1898), pp. 15 L.

⁽p. roll) Asserbanavidis (undoubtedly the right restoration) Olympia Isselv. 252. In other cases the double A is written: A Asserbainese, Olympia, in 171; A Asserbainese, Olympia, in 171; A Asserbainese, Meister, Or. Dial. Institution, 4430. But its outsiden is in accordance with the rule which gives us early, verds for var var, var var, and other single writings of double letters.

In APTAMTS, which seems in an inscription on a metal vessel (Hoffmann, Gr. Dial. Inschr. 1600; Purgold, Arch. Zeibung al. (1882) p. 393), the first \$ is probably omitted by a more accident. The epithet preceding should perhaps be completed [AIC]-EPATS; for the warship of Artenia at Ageira see Paga vii. 26. 2 f.

[&]quot;No instances are given by J. Simon, Abburmoney only yr. Inwhr. in the Zeitsehr. f. d.

interrence. Operation, 1891, p. 579 ff. For a form like KN for Kurdovupa (p. 709), even if the restoration were certain, would hardly count.

⁶ E.g. Mionnet, iil. p. 190, no. 217 | Supplyi, p. 302, no. 1391.

⁷ Mr. Konyou points out that there is room for more than ere, and that the word appears to be Barislown very cursively written.

It remains only to admit that it is impossible to ascertain to which of the many goddesses named Artemis in Lacedaemon this coin of Sicyon was dedicated. If, however, the dedication was pricked on the coin before the worshipper came to Lacedaemon, the want of closer definition does not seem uppatural.¹

Since the above remarks were put into type, the inscription with which they are concerned has been interpreted in yet another way by Professor O. Rossbach. In most of the preliminaries to an explanation we are agreed; as, for instance, in the identification of the initial letter, and in the interpretation of the final word as a dative. The 17th letter, however, he takes to be γ , and his transliteration is accordingly

Τας Αρτάμιτος τας έγ Κεδμώνι.

This interpretation has the one great advantage of dispensing with the abbreviation which I have assumed. On the other hand, two considerations lead me to adhere to the interpretation I have proposed. In the first place, as Prof. Rossbach himself admits, the place-name Κεδμών is entirely unknown. The invention of this name is not entirely justified by any philological probability it may possess, or by the addition it makes to our list of sanctuaries of Artemis. Secondly, the form A for γ, although by no means impossible in Peloponnesian alphabets, is much less common than γ. The probabilities are therefore in favour of the value which has hitherto been given to the sign in this inscription.

G. F. HILL.

Berliner Philolog, Weekenschrift, 20 Aug. 1898, p. 1053.

At the shrine of Zeus Kasios in Corcyra a strang with the name of the god, Ande (name grammatically written) Kazie, was impressed on dedicated coins (Brit. Mrs. Catal. Thessay to Actobio, p. 158, nos. 615-632, including coins

of Lacestermon and Chittee, as well as of Corayra itself). It would seem that the stamp in this case was provided by the temple authorities.

INSCRIPTIONS FROM EASTERN ASIA MINOR.

The following inscriptions are some of the epigraphical results of three journeys in Eastern Asia Minor. The first two of these, in which Prot W. M. Ramsay, Mr. D. G. Hogarth, the Rev. A. C. Headlam, and Mr. J. A. R. Minoro took part, were made in the summers of 1800 and 1891, the third, which was organised by Mr. Hogarth and in which I took part myself, was made in the summer of 1894. The geographical results of these expeditions have been published in the Proceedings of the Royal Geographical Society in the form of a paper by Mesars. Hogarth and Munro, entitled 'Modern and Ancient Roads in Eastern Asia Minor' (R.G.S. Suppl. Papers, iii. pp. 643-739) and a paper by myself 'A Journey in the valley of the Upper Euphrates' (Geographical Journal, viii. pp. 318-335 and 453-474).

The inscriptions are arranged under the places where they were found without reference to their probable dates or the language in which they are written. It would have been possible to classify them either in respect of age or of subject, but they do not fall readily into any such divisions. Comparatively few of the inscriptions are without interest, but special attention may be drawn to Nos. 1, 2 which are interesting as belonging to the historical Cilician Gates, to No. 14 (copied curiously enough in Loudon) from Samosata which adds another to the remarkable series of inscriptions on the monuments of the Nemrud Dagh and neighbourhood, and to the legionary tiles from Sadagh which establish the identification of this place with Satala, for which apigraphical evidence has hitherto been wanting. No. 45 a fine inscription of Justinian and No. 34 which gives a fixed point on the frontier road along the Euphrates north of Melitene are also worthy of note.

I am indebted to Prof. Ramsay, Mr. Hogarth and Mr. J. G. C. Anderson for many suggestions which are not always acknowledged in the text.

In every case the initials of the copyist and the year in which the copy was made are given above the inscription.

CHEMA.

No. 1. D.G.H. 1894. Cilician Gales.

IMPCV	Imp. C[nesar Marcus A]u-
RELIVS VS	relius [Probus ? Pi]us
FELIXINVIC AVG.	Felia Invic[tus] Aug[u]
STV8 . 0	stus [P]o[nrifex Maximus]
VIAMIN	riam [latiore tramite feet; ?]
OEOII	"O(p)or K[iligor]
S	1.0

The inscription, which is cut on a panel in the rock at the narrowest part of the Gates, is the same as Le Bas-Waddington, No. 1520 and C.I.L. iii. 228 where Mommsen restores vilus lations [transite from AMIATIORE). It was copied by Mr. Hogarth with the aid of an improvised ladder made of two fir poles and pieces of cord. With an ordinary ladder it would doubtless be possible to decipher the whole of the inscription, which is fairly well preserved.

Na 2 D.G.H., V.W.Y. 1804 Ibid.

I . . . I . AM (vi)am

EI . . . OPILIS e[t pontes] (a) P(y)lis

VSC . . ILXAV . SM usq[ue ad A]l(exan)[dri](s)m

EXIN . CR . CAES** . IVI. ex in[te]gr[o] (r)est[i]tui[t].

On a pillar cut out but not detached from the living rock on the modern road about 100 yards below (on the south side of) the Gates. It is the same inscription as that given in Le Bas-Waddington, No. 1519 and C.I.L. iii. 227. I owe the interpretation of this and the foregoing inscription to Prof. Ramsay, who read, at the end of the first, OPO: ... AIKON, and the second, from viam onwards, in full as here restored. The new inscription enables us to restore the end of Le Bas-Waddington, no. 1495; usque A[lexan]-dria[m e]x in[teg]ro [rest]i[tuit].

No. 3. D.GH., V.W.Y. 1894 Missis (Mapunestia)

MOYCEOCEMPIACIPPOAN/////// ΥΠΟΤΡΥΦωΝΟΣΤΟΥΑΔΕΛΦΟΥΠΙΣ TEYCACAYTWTHNIPACINTWNIEW/// MIWNHANTWNEIKOCAETIAC /// AEROTEAOFICTEYCACAYTONKAIA ///E//HOEICYTOAYTOYKATATANTAKA /MHAYNAMENOCATINIPOCAYTON TOPPARMANEIMOMENOCKAITHECHM// //WTPODHKAINAPABIATAXYTEPONTEAEI WNTONBIONETIKANOYMAIKATATPYOW NOCTOYALEADOYMOYKAITWNTEKNWN AYTOYTOYCENOYPANIOYCOEOYCKAI TOYCKATAXOONIOYCKAIRACANA PANKAIAYCCANXOAWOHNAIAYTOIC ENOAWTWBIWAYTWNKAITATEPAMH EZONAYTWHOIHCAIKATAMHAENA TPOTONMHAEDCTOYNMOYCAAEYCAI **EITOYMNHMADIOYICTONAIWNAHTPY** INDINA PARE STANDAR ANTHON A SHANWA

10

TITWNENTWMNHMEIWMHAETONAPAKE
MENONMOIEMBOAAAINOPYZAITINAME
NEINAEEMOIAKEPEONEOOAOYTOECWOEN
TWNCYNKEIMENWNAIOWNEKTOCEIMH
EANMAFNAMONHOEAHCHHCY///CKH//OC
MOYHNKAIEANTICAAIKHCHHEMETIC
BAAYHAAIKWCKEX//AWMENOIAYTO////
///FENOINTOOI//YT//IGEOI

1////NO////W

23

Μουσεος έμ πῶσι προλη[μφθείς] ὑπό Τρύφωνος τοῦ ἀδελφοῦ, πιστεύσας αὐτῷ τὴν πρῶσιν τῶν γεω[ργ]ίων πάντων εἰκοσαετίας, [οὐ]δέ ποτε λογιστεύσας αὐτὸν καὶ ἀ[π](α)[τ]ηθείς ὑπὸ αὐτοῦ κατὰ πάντα κα[ί] μὴ δυνάμενος ἄγιν πρὸς αὐτὸν τὸ πρᾶγμα, λειπόμενος καὶ τἢ ἐφημ[ερί]ψ τροφἢ καὶ παρὰ βἰα ταχύτερον τελείων τὸν βίον, ἐπικαλοῦμαι κατὰ Τρύφωνος τοῦ ἀδελφοῦ μου καὶ τῶν τέκνων αὐτοῦ τοὺς ἐνουρανίους θεοὺς καὶ τοὺς καταχθονίους, καὶ πῶσαν ἀρὰν καὶ λύσσαν χολωθῆναι αὐτοῖς ἐν ὅλφ τῷ βἰφ αὐτῶν καὶ τὰ ἱερὰ μὴ ἔξὸν αὐτῷ ποιῆσαι κατὰ μηδένα τρόπον, μηδὲ ὁστοῦν μου σαλεῦσαι ἐ(κ) τοῦ μνημαδίου ἰς τὸν αἰῶνα ἡ Τρύφωνα ἡ ἄλλον τινά μηδὲ ἐξαφανίσαι τι τῶν ἐν τῷ μνημείφ, μηδὲ τὸ παρακείμενόν μοι ἐμβολάδιν ὁρύξαι τινά, μένειν δὲ ἐμοὶ ἀκέρεον ἐφ΄ ὅλου τὸ ἔσωθεν τῶν συνκειμένων λίθων, ἐκτὸς εἰ μὴ ἔαν Μάγνα μόνη θελήση ἡ σύ[ν]σκη[ν]ός μου. ἡν καὶ ἔαν τις ἀδικήση ἡ ἔμέ τις βλάψη ἀδίκως κεχ[ο]λωμένοι αὐτο[ἐς] γένοιντο οὶ [α]ὐτ[ο]: θεοί.

On a stone lying close to the road from Adana to Missis, about five minutes before entering Missis. It was copied by V. Langlois and is published in Waddington and Le Bas, No. 1499, but as their copy is far from perfect and the inscription is interesting, I have given our copy in full.

The Greek is now quite straightforward, the only doubt being the interpretation of ἐμβολάδιν (line 21). Waddington and Le Bas take this to be for ἐμβολάδιον the diminutive of ἐμβολάς 'a grafted tree.' Can it, however, be an adverb, expressing violent τυμβωρυχία! Μουσέος and ἀκέροις are for Μουσάος and ἀκέροιος.

In line 24, we may restore σύνσκηνος = contabernalis with certainty.

The letters at the bottom of the inscription are undecipherable; they possibly may have recorded the infliction of penalties for violation of the tomb.

No. 4. D.G.H. 1894. Ibid.

EGENDIONTO A EMOICETPATIATAN
AHMHTPIOCACH . . . A A GYCAIA
HETPANIA A EN INTO CYTA A DE A DE
KAITO ICCONEYCIMNHMHCX APIN

άν έθεν δίον πολέμοις στρατιώταν.

Δημήτριος 'Ασκ[ληπι]ά[δ]ου(?) Γαίφ Πετρωνίφ (Μ)ενίππ(φ) τῷ ἀδελφῷ καὶ τοῖς γονεῦσι μνήμης χάριν.

The first part of the inscription is evidently metrical Mevinnov, the genitive, seems to be written for Mevinnov, the dative, as often. Demetrius and Menippus were sons of Asklepiades(?); Menippus became a soldier and at missio honesta received the citizenship as usual, and took the name C. Petronius, perhaps after his commander.

No. 5. D.G.H. 1894. Ibid.

ZENTINIANO €TVSIZENTENI €7 ** * ASIANO ΠΙΑΧΙ* ** VICIORIIVI ΓΕΙ ** Ι ** ΑΥςς ΙΑΧΙ**

[Va]lentiniano et V(a)lenten(o) et [Gr]atiano (m;axi[mis] vic[t]ori[b]u(s) se[mper] Augg

On a column, much defaced, in a graveyard below the village on the right bank of the Jihan. It is evidently a milestone. For the form Valenteno for Valenti cf. C.I.L. viii. 10352 where Valentino occurs. A copy of this inscription is given by Heberdey and Wilhelm in their work Reisen in Kilikien (Wiener Deakedriften vi. p. 13), but as it differs slightly from the above I have thought it advisable to publish our copy.

No. 5. D.G.H., V.W.Y. 1894. Ibid.

ACIOCOO OCT CATIOCICXYPOCATIOCAGANATOC

άγιος ὁ θ[εό]ς, άγιος ἰσχυρός, άγιος άθάνατος, ὁ στ[αυρ]ωθὶς δι' ἡμᾶς έλεῆσον ἡμᾶς. On two fragments of a long marble block lying in a graveyard on the right bank of the Jihan (Pyramus). The second half of the inscription has also been copied by Davis (Life in Asiatic Turkey, p. 67); he has AIHMAC in the second line. This form of the τρισώγων was introduced by Peter the Fuller at Antioch (he died 477). It was afterwards adopted by the Syrian Monophysites.

No. 7. V.W.Y. 1894. Farsount.

ΘΕΨΘΕΨΝ θεών ΔΙΙ Δεὶ ΜΕΓΙΣΤΨΙ μεγίστωι

No. 8.

Αθηνα 'Αθήνα

No. 9.

 Α////////ΗΛΙΑΛΙΑΤΡω
 Α[ψρ]ηλία Ματρώ

 ΝΑΖωςαξαγτ
 κα ζώσα ἐαυτ

 ΗΚΑΙΑΥΡΗΛΙω
 ϔ καὶ Αὐρηλίφ

 ΗΛΙΟΔωρωτ
 Ἡλιοδώρφ τ

 ω ανδρί μν Ηλιης χάριν

Nos. 7 and 8 are on cippi in the courtyard of a private house, No. 9 on a sarcophagus lying close to the mosque. Yarsowat is a small town showing no sign of untiquity about 12 miles on the road from Missis to Osmanich. The inscriptions may denote an ancient site.

No. 10. D.G.H., J.A.R.M. 1891, Siz (Flaviopolis ?).

In the courtyard of the Serai; badly cut and defaced, readings very doubtful.

ANTINATPWMACIPYAL AMELAIPELA OYYO////AYTOYTHNKAGE PANEYNOLAXXAPIN

Perhaps

'Αντιπάτρφ Πασι[κ]ρ(άτης) οτ Πασι[φί]λ[η οτ -ος] άμ' έ[τ]αιρείμ(?) [έσ](τη)σε τ-(φ) ὑ(φ) αὐτοῦ τὴν καθέδ]ραν εὐνοίας χάριν.

In line 3 we have the genitive \(\tau\)job \(\delta\)o(\(\delta\)) as often.
In line 2, the last five letters are apparently CETCT

No. 11. D.G.H. 1891. Ibid. Cippus in a small cometery in the town; very faint.

> ETOYCEME . F . . IIPO KAAYAIA , MAPKOY ///KASTHNFYNEKAAYTOY //////MNHMHC

> > "Ετους εμσ' -[ὁ δείνα] Κλαυδία[ν] Μάρκου τὴν] κάστην γυνέκα αὐτοῦ ἔνεκα] μυήμης.

Sis was formerly identified by Ramsay with Flaviopolis (Hist. Geogr. p. 385). The era of this city was A.D. 74 which will make the date of the inscription A.D. 319, if the identification, which he is now inclined to abandon, is correct.

No. 12. D.G.H. 1891. Marash (Germanicia?). Cut on the rock over temb-doors in a street.

> (1) EVEVY YXIA FABOKAIA OYAEICAB ANATOC

Εὐ < ευ > ψύχι(=ει) 'Α- γαθοκλία ουδεὶς ἀθ ἀεατος.

Εὐψύχη(= ει) Σ-[αλω?)μη. υὐδεὶς] άθάνα]τος.

No. 13, J.A.R.M. 1891, Ibid.

Fragments of stele, round at the top, broken below and chipped to right, built into the wall of a private house; the rest is built in close by, but the writing is hidden.

> BEQETHED ZAPIHIC BAPNAIDY CTPATHFOC EYPONANEC THCENYFIEPT

θεῷ ἐπηκόφ Ζαρίηις Βαρναίου στρατηγός εὐρὸν ἀνέστησεν ὑπὲρ τ-

[ης σωτηρίας έαυτοῦ κ.τ.λ].

410

COMMAGENT

No. 14 D.G.H., V.W.Y. 1895. Sumsat (Samosata).

BAL DEAIKAIOCETIÓANE **ΦΙΛΕΛΛΗΝΟΓΚΒΑΓΙΛΕΩ** NIKOYKAIBACIAICCHEA AGOYTHEEKBACIAEDEANT MHTOPOEK & AINIKOYTOYT HENOMONTEKOINHEEYEE (ΠΑΝΤΑΠΡΟΝΟΙΑΙΔΑΙΜΟΝΩ EEΠΙΕΡΑΙΣ . ΕΓΩΠΑΝΤΩΝΑΓ 19 CINBEBAIOTATHNAAAAK INTOILENUMEATH TEKPICINKAILYNAMEDEL KAPIETHEAITIANEEXON *DOHNATACIBACIAEIACEM* THNKAI . EPYINAMEIMHTON 16 THTALIAKAIKINAYNOYEME ΔΙΕΦΥΓΟΝΚΑΙΠΡΑΞΕΩΝΔΥCE **EDEKPATHCAKAIBIOYDOAYETO** PROHNET OF A TPRIANBACIAE! ΔΙΟΣΤΕΩΡΟΜΑΣΔΟΥΚΑΙΑΠΟΛΛ MOYKALAPTATNOYHPAKAEOYE MENOCHANALACAYNAMEQE MHCHAIKIQTINGEQNMETAAQ ENIEPAITEAIOEIAIMIACHEPIO NIDICXAPAKTHPAMOPOHEEMHC VEICAEE ACTIAPECTHEAME EDNAGANATOYOPONTIAGE

I have indicated the corner of the stone round which the inscription runs with crosses × ×.

> βασ[ιλεύς μέγας 'Αντίοχος θεός δίκαιος ἐπιφανή[ς φιλορώμαιος καὶ φιλέλλην ὁ [ε]κ βασιλέ[ως Μιθραδάτου καλι]νίκου και βασιλίσσης Λ[αοδίκης θεᾶς φιλ

δ αδέ]λφου τῆς ἐκ βασιλέως 'Αντ[ιόχου θεοῦ φιλο]μήτορος καλινίκου τοῦτ[ο εὐσεβεία γνώμης ε]μῆς νόμου τε κοινῆς εὐσε[βείας σεβόμενος τὰ πάντα προνοίαι δαιμόνω[ν λιθείαις ἀπέδειξ' ἐπ' lepais. ἐγὰ πάντων ἀγ[αθῶν οῦ μόνου κτῆ-

10 σιν βεβαιστάτην άλλα κ[αι ἀπόλαυσιν ἡδίστην ἀνθ]ρώποις ἐνόμισο τὴ[ν εὐσέβειαν, τὴν αὐτήν τε κρίσιν καὶ δυνάμεως ε[ὐτυχοῦς καὶ χρήσεως μακαριστῆς αἰτίαν ἔσχον, [παρ' όλον τε τὸν βίον ώφθην ἀπᾶσι βασιλείας ἐμ[ῆς καὶ φύλακα πιστοτά-

15 την καὶ [τ]ἐρψιν ἀμείμητον [ήγούμενος τὴν ὁσιότητα. Δι' ὰ καὶ κινδύνους με[γάλους παραδόξως διέφυγον καὶ πράξεων δυσε[λπίστων εὐμηχάνως ἐπεκράτησα καὶ βίου πολυετο[ῦς μακαρίστως ἐπληρώθην. ἐγὰ πατρωίαν βασιλει[αν παραλαβών ἀπὸ

20 Διός τε 'Ωρομάσδου καὶ 'Απόλλ[ωνος Μίθρου 'Ηλίου 'Ερμού καὶ 'Αρτάγνου 'Ηρακλέους ['Αρεως, καὶ ποιησά]μενος παλαιᾶς δυνάμεως [καὶ τύχης νέας τῆς ἐμῆς ἡλικιῶτιν θεῶν μεγάλω[ν τὴν ἀρχαίαν τιμὴν ἐν ἰερᾶι τε λιθείαι μιᾶς περιο[... δαίμοσιν οὐρα-

25 νίοις χαρακτήρα μορφής έμης [έπηκόοις σύνθρουσν είς δεξιάς παρέστησα, με[ίμημα δίκαιον φυλάσσων άθανάτου φροντίδος

On one side and the back of a broken slab of black basalt in the possession of H. J. B. Lynch, Esq., of 33 Pont St., London. This slab was brought to England some years ago by Mr. Lynch's father from the banks of the Euphrates near Samosata. On the front of the slab a human figure is carved in relief. Only the upper part of the figure is preserved; it is turned to the left with right hand extended and wears a radiate crown. The whole slab measures 2 ft. 7 in, in height, 1 ft. 2 in, in breadth and 9 in, in width. The depth of the relief in which the figure is carved is at the forchead 1½ in, and at the breast 3 in.

From the character of the inscription and relief, the material and the general correspondence in measurement, there can be no doubt that this stone belongs to a series of reliefs, one of which has been found already at the village of Sclik near Seenset (Samesata) and is published in Humann and Puchstein's book (Reisen in K.A. p. 369, ff.). The subject of this relief is very similar to that of one of the reliefs found on the Nemrad Dagh in which King Antiochus of Commagene is represented in converse with Heracles whose hand he grasps, and it has an inscription which is almost word for word the same as a portion of the long inscription which Humann and Pachstein found on these monuments. Hence they infer that a second series of reliefs on a much smaller scale with the same subjects and inscriptions was put up by Antiochus at or near Samosata, for it is not certain that the monument at Schik is in site. The inscription on Mr. Lynch's stone in the

same way corresponds almost exactly with the beginning of the long inscription on the Nemrud Dagh; it is written in the same manner, that is, partly on the side and partly on the back of the slab, and the figure of the relief is turned with extended hand as if in converse with another figure. By the analogy of another of the reliefs belonging to the large monuments this figure may be identified almost certainly with Apollo, who wears here as there a radiate grown (Humann and Puchstein, op. cit. taf xxxviii. 2). The only discrepancy between this slab and the slab found by Humann and Puchstein is in the measurement of the depth. Our slab measures 9 inches, theirs 22 inches, but there is no reason why the slabs should have been all of the same thickness.

The restoration of the inscription presents little difficulty. Lines 1-0 are the same as the beginning of the inscription on the Nemrud Dagh (H. and P. op. oit p. 272, lines 1-7) and lines 9-19 of our inscription correspond exactly with lines i. a. 10-24 of theirs. The rest of the inscription can be easily restored with the exception of line 19. Mr. Hogarth suggests $\pi e \rho io[\chi \hat{\eta} \hat{s}]$. Mr. G. F. Hill $\pi \epsilon \rho io[\delta o \nu]$ (i.e. a stone relief filling one circuit of the monument). The expression ϵlc $\delta \epsilon \xi i \hat{a} \varsigma = 1$ in converse does not occur on the large inscription, but doubtless there was a relief on this monument representing Antiochus and Heracles grasping hands as on the Nemrud Dagh

No. 15. D.G.H., V.W.Y. 1894. Ibid.

//// SYMPCCBCEBANTICTP/////

... ου $\pi \rho(\epsilon) \sigma \beta(\epsilon \upsilon \tau o \bar{\upsilon}) \ \Sigma \epsilon \beta(u \sigma \tau o \bar{\upsilon}) \ \dot{u} \upsilon \tau \iota \sigma \tau \rho [u \tau \dot{\eta} \gamma o \upsilon] ...$

Cut in large letters on a big squared stone built into the kald at Samosata. Unfortunately the name of this 'legatus Augusti' is missing.

No. 16: D.G.H. 1894. Ibid.

ΛΙΦ - 3 Θ Λ ΦΥ C ΛΕΤΙΤΙΝΟΤΝΟ Λ ΔΙΛΥΟΙΜΑ ΥΟΙ ΙΜ

Mattenmanning 1919090

On a pedestal in the court of an Armenian house,

No 17, D.G.H., V.W.Y. 1894. Rid.

LEG XvI

[I] (O) M. Legjio] XVL F[lavia] F[irma]

On a cippus in a private house

No. 18. D.G.H., V.W.Y. 1894. Ibid.

LECIONSXVIFE

Legion(i)s XVI. F[laviae] F[irmae]

Retrograde. On a tile shown to us. The Legio XVI. Flavia Firms was brought into existence by Vespasian, and is already known to have been stationed here (v. C.I.L. vol. vi. p. 1404, and Mommsen's Provinces, vol. ii. p. 119).

No. 19. D.G.H. 1894. Krakhta.

OPTIEP . E .	$o(b)\pi\epsilon\rho$ ϵ -
KYAAINE .	κύδαινε[ν
ΦΙΛΑΔΕΛ	Φελάδελ-
фосетечи	φος έτευξία-
TOBUMON	το βωμόν.
ANAZIN	"Avaξiv.

Hexameter. On an altar in a private house. Philadelphus dedicated the altar to one of the kings of Commagene, meaning the reigning king to be understood, while he adds a dedication at the end to all the kings (past and present).

No. 20. V.W.Y., D.G.H. 1894. Ibid.

At the Roman bridge on the column nearest the left bank of the Kiakhta Chai, almost completely erased. It is on the same column as that on which the name of Julia Domna is inscribed (v. C.I.I. iii, suppl. 6714).

IMPCAES



The letters are all so doubtful that it is useless to hazard any conjecture as to the Emperor referred to, but the existence of the inscription is important, as it points to the probability of this bridge being the work of an earlier Emperor than Septimins Severus. It is improbable that the crasure

can be that of Geta's name, for, as Humann and Puchstein have shown, there must have been a fourth column belonging to the bridge on which his name would naturally have been inscribed. The copies of all the inscriptions belonging to the bridge, with the exception of the above, which was not noticed by Humann and Puchstein, are to be found in the Corpus (C.I.L. iii, suppl. 6709-6714). In i. 13 of 6714 we read MVNIFICENTISSIMVM.

No. 21. V.W.Y. 1894. Pervin (near Adiaman, the ancient Perre).

 ΥΥΧΕ
 ψυχ(αὶ)

 ΓΑΙΑΝΟΥΚΑΙ
 Γαιανοῦ καὶ

 ΜΑΡΟΑΝΗΣ
 Μαροάνης

 ΤΑΥΤΑΓΑΡ
 ταῦτα γάρ.

On a recess cut in the rock; to the right of the inscription are the figures of a reclining man and sitting woman roughly sculptured in the rock. It is one of many tombs cut in the rock which abound on the site. There are probably many more inscriptions to be found on these, but time was short and my investigations were curtailed thereby. ταῦτα γὰρ = for this (is what they are). Prof. Ramsay compares οὖκ ἡμην ἐγενόμην. οὖκ ἔσομας οὖ μέλει μοι. ὁ βίος ταῦτα (Ramsay's Cities and Bishoprics of Phrygia, i. p. 700 and B.C.H. 1884, p. 233)

No. 22. V.W.Y. 1894. Ibid.

ΜΑΜ Μαμ-ΒΟΓΕΨ βογέω. ΑΛΕΣΑΝΔΡΟΥ Αλεξάνδρου. ΘΕΟΦΟΥ Θεόφου. CEΛΕΥΚΟΥ Σελεύκου.

The name Maμβογέος or Maμβογέως = Maμβογαίος is interesting.¹ Mabug or Mambug was the native name of Hierapolis in Syria, which became in Greek Βαμβύκη. The modern name is Membidg.

CAPPADOCIA.

No. 23. D.G.H. 1891. Shahr (Comuna Cappadociae). On a marble mural tablet finely engraved.

ΘΕΑΜΕΓΙΣΤΗ//// Θεῷ Μεγίατη
ΤΗΣΧΩΡΑΣΚΑ τῆς χώρας κα///////ΧΑΡΙΣί/// τὰ εὐ]χαρισ[τίαν
ΙΟΓΛΤΩΧΜΗ Μ]ιθρατώχμη[ς

¹ The many [M]a@Soyaios has been suggested by Ramsay as a restriction in a Syrian merription (Wright and Souter in Pal. Explor. Fand, Quart. St. 1895, p. 58)

The name Μιθρατώχμης occurs in another inscription copied at the same place and published by Waddington (v. B.C.H. vii. 135). He draws attention to the interest of the name. The goddess is evidently Mâ (v. Strabo xii. 535).

No. 24. D.G.H. 1891. Ibid. On a cippus of fine limestone in a yard near the top of the town.

> ΒΑΣΙΛΕΑΑΡΧΕΛΑ ΦΙΛΟΠΑΤΡΙΝΤΟΝ ΚΤΙΣΤΗΝΚΑΙΣΩΤΗΡΑ ΟΔΗΜΟΣ

Βασιλέα 'Αρχέλα ον φιλόπατριν τον κτίστην καὶ σωτήρα ά δήμος.

This is evidently an inscription in honour of Archelaus, King of Cappadocia from a.c. 36 to a.D. 17.

No. 25. D.G.H., J.A.R.M. 1891. Ibid. Stele in the house of Badiller.

> TIAPABHE KAIMIOPHETIAPA BEITQINATPI

Τιαραβής καὶ Μίθρης Τιαραβεῖ τῶι πατρί.

No. 26. D.G.H., J.A.R.M. 1891. Ibid.

On a small marble stells now in the hammam at Hadjin, nine hours from Shahr (Comana), but brought from the latter place according to native testimony.

CEMEIPAMIS
DEAPZANDY
DAMNIATHA
HTHBYFA
HAIAANATHE

Σεμείραμις
'Αρι]οβαρζάνου
'Απ]ολωνία τἢ ἀγαπ]ητἢ θυγατρ]] ιδία - -

The last word, which is quite clear on the stone, may possibly be meant as a contraction for avanavauevy.

No. 27, W.M.R. 1890, D.G.H. 1891, Ibid. Pedestal in a wall in the main street.

TATONKAICAPA IEPOTOAEI
TWNHBOYAHKAIOAHMOC

Πούβλ(ιου) Λικίνυ(ιου) Κορυηλιου Οὐαλεριανόυ του ἐπιφανέατατου Καίσαρα Γεροπολειτῶν ἡ βουλή καὶ ὁ δήμος.

The name is that of the older son of the Emperor Gallieaus, and corresponds with the form given in C.I.L. viii. No. 2383 and C.I.L. iii. Suppl. No. 6956. For a discussion of the names of the two sons of Gallieaus v. C.I.L. viii. p. 1051, and Prosopographia, s.rv. An inscription of the father has already been found in this district (v. B.C.H. vii. p. 132).

No. 28. D.G.H. 1890. Ibid. Stale.

> HΔΥΒΙΟC ΔΑΜΑΟΥ ΑΡΝΑΤΟ ΠΑΤΡΙΜΝΗ ΜΗСΧΑΡΙΝ

Ἡδύβιος Δαμά Οὐάρνα τῷ πατρὶ μυήμης χάριν.

No. 29. W.M.R. 1890. Ibid.

PAIANUTU

CYMPITKAI

XPHTUAAEA

ФШМИНМНЕХА

PIN

Αὐρ. Ἡλιοδώρα Γο]ρδιανῷ τῷ ἀ]συνκρίτῷ καὶ χρηστῷ ἀδελḥῷ μνήμης χάριν.

For the same name in this district v. B.C.H. vii. 137, Nos. 18 and 19.

No 30. D.G.H. 1891. Ibid.
On a marble stele. The inscription runs round the head of a large cross.

+ ENGAKATAKITEOTHCMAKAPIACMNHMHCBAXXOC

+ "Ενθα κατάκιτε ὁ τῆς μακαρίας μνήμης Βάχχος.

No. 31 J.A.R.M. 1891. Ibid. In the main street. Broken R.

WNOPONONAPXIEPHWN +

είχων (θ)ρόνου άρχιερήων +

I am unable to explain the monogram.

No. 32 J.A.R.M. 1891 Scraijik

In a cometery near Seraijik. Quadrangular altar or base ornamented with wreaths.

PANIOCEIOYAL OCKATAKEAEN CIN Wreath Μεγάς Ζεύς Ούρώπος Εἰούλιος κατὰ κέλευσεν θεο[ῦ.

The inscription is the same as that published in B.C.H. vii. p. 147, said to have been copied at Hutchbil; this copy however is an improvement.

No. 33. D.G.H., V.W.Y. 1894 Malatia (Melitene).

IMPMIES

[I]mp. [Cae]s

miniminimini

FLIVLIMIM

Fl. Juli[us Constantius]

ETFLIMMM

et Fl. J[ulius Constans]

CEMBERAYO

PPFFMA////// P.P.F.F. Ma[ximi Victores]

SEMPERAYS Semper Augusti

On a pillar, certainly a milestone, forty minutes on the road from Malatia (Eski Sheyr) to the bridge of Kirkgeuz Keupru. The stone is defaced above and hacked away below. It is probably the same inscription as that copied by Fischbach and published in the Corpus (C.I.L. iii, Suppl. 6893), though comparatively few of our letters agree with those of his copy. The milestone may have belonged to either the Melitene-Sebastea or Melitene-Satala road, perhaps more probably to the former, as what appears to be a milestone was seen on the line it must have taken in the plain of Hassan Badrik by Brant (s. Ritter, Endkunde, k. p. 863), and we found no milestones on the line most probably followed by the road Melitene-Satala.

ARMENIA MINOR.

No. 34. D.G.H., V.W.Y. 1894.

Close to the remains of a Roman bridge over the Kara Budak, a short distance from its junction with the Euphrates on the road from Divrik to Kemakh, 5 hours 40 minutes after leaving the village of Zimarra, I hour 30 minutes before reaching the village of Hassan Ova.

IMP·CNES·L·M∘ T TRAIAN ØSE®IOPIOFE LI®S AVC PIVS·F° P° NT IEXICM AXIMVSPOPOEMS VIFLVMINISABR'NA
FPOTITVIT PER CVAI

CRITVLLIMAN-LAVG-PR-PR

> Imp. Caes. C. Mo[es]. Traiana s D lesio Pio Feh(ci) I Aug Pius Fe Ponti(f)ex Maximus P(rinceps) O(ptimus) po(n)tem sulph flumini Sabrinao (res)tituit per C. Va[l. Terltullum l. Aug. pr. pr.

In the first four lines there seems to be considerable confusion between the nominative and dative, Trainnus is followed by Desio, etc. In the third line we have Prus Fc, repeated after Pio Felies in the second line and the inscription generally is the work of a poor Latin scholar. Attempts at correction (felic, for felius, pontific, for pontifex) may afterwards have been made. Where we should expect to find restituit we have a strange word politicit or pollibuit, every stroke of which is plain on the stone.

For the title of P. O. (princeps optimus) in connection with Trajan

Decins, compare C.I.L. ii. 4958.

The name of the legatus Augusti, though it cannot be restored certainly

from the inscription, is new (v. Liebenam Furschungen, p. 119). Possibly we should read Tertullianum.

The bridge, the restoration of which is here recorded, must have belonged to the Satala-Melitene road (see my paper in Geograph, Journa, viii. 467-8). The name given to the Kara Bucisk by the Romans, as far as it can be deciphered from the inscription, seems curiously enough to be the same as that given by them to our own Severa.

No. 35. D.G.H. 1894.

In a garden, opposite Pingan on the bank of Euphrates, belonging to Mesardurian Bartolomens. It is not far from the spot where the inscription of Ala II. Ulpia Auriana was found (Arch. Epigr. Mitth. Oester. 1884, p. 239.)




No. 36. Sadagh (Satala). On tiles. D.G.H., V.W.Y. 1894.

(1) Picked up.




(2) In threshold of house of Mehemet Suleiman.

(3) In house of Hadji Hassan.



(4) Ibidem.



(5) toutom.

LEGXV

Legio XV. Apollinaris was stationed at Satala (v. Notit. Dignat. Orient. cap. xxxv.) and the discovery of these tiles places the identification of Sadagh with Satala, which has been generally accepted, beyond doubt. Other inscriptions of the same legion have been found at Carmintum in Pannonia (v. Arch. Epigr. Mitth. Oester. vol. v. pp. 208 f. f.).

No. 37. V.W.Y. 1894. Ibid. In the graveyard.

 ΕΝΘΑΔΕΚΑΤΑ
 ἐνθάδε κατά

 ΚΙΤΕΟΜΑΚΑ
 κιτε ὁ μακά

 ΡΙΟΚΑΝΔΡΈΑΟ
 ριος 'Ανδρέας

 ΚΕΑΝΑΓΈΝωΟ
 κὰ ἀναγενώσ

 ΚΟ///ΤΕΟΕΥΣΑΟ
 κο[ν]τες εὐξασ

 ΤΕΥΠΕΡΕΜΟΥ
 τε ὑπὸρ ἐμοῦ.

αναγενώσκηντες is for αναγιγνωσκοντες. For the formula compare No. 44 from Nicopolis. Many similar epitaphs exist at Sadagh, but those that we were able to decipher are of little or no interest.

No. 38. D.G.H. 1894. Ibid.

. . IVS AMMON C, Iul]ius Ammou-IVSE . CIVLI ius e[t] C, Iuli[us RVS . . . SF . AT Rus[ticu]s f[r]at[res

No. 39. V.W.Y. 1894 Ibid.

On stone built into the roof of the mosque. Apparently the end of an inscription. Broken above and to left.




The first letter of the inscription is evidently an R from which we must infer a vowel between R and M, and though the tail of the intermediate letter is quite plain on the stone and it should be I, it is best on the whole to

restore it as E (perhaps F for E by error). Mater Castrorum is doubtless Julia Domna,

No. 40. D.G.H., V.W.Y. 1894. Ibid.

In room of house of Bal Oglu Hassan. At the bottom of an oblong slab 4 ft. high, broken to r. The inscription is in a very bal light, and being built into the living room of a house, it was impossible to have it moved. Consequently the readings are doubtful.



Lins L. L may be R. Line 4: there may be another letter between R and F.

Mr. Hogarth suggests

Al[a [S]ecunda [A]rme[niaca Const-] antia Justini[ana] Mi[lia] perfecta ca[str]

I have not however been able to find other instances of the formula 'milia perfecta,' and Justiniana is an unlikely name for an als, at least none of the known also take their names from so late an Emperor.

Armeniorum is an alternative to Armeniaca. There was an als secunda Armeniorum at the Oasis Minor in Egypt (Not. Digs. xxv. A 9). For Armenians in the Reman army, v. Arrian (**xra**is 29)

No. 41. D.G.H., V.W.Y. 1894. Ibid.

On an altar built into the wall of the house of Suleiman Selim Chaoush.

GEN-CoL LE-FECIT Gen(io) Col(oniae) Le(gio) fecit

...)N S F

s(acris) f(acrundis)?

On another side of the same below a wreath.

COR

Cor(ona)

This appears to indicate that Satala was a colony, a fact not known from other sources. That it may have been a colony and yet have struck no coins

is not without parallel, v. Ramsay Hist, Geogr. p. 284.

To these inscriptions of Satala may be added one of the Emperor Aurelian found there by Taylor in 1868 (Journal R.G.S. xxxviii, p. 288), which may be restored from his copy as follows: Imp. Caes. L. Dom Au(r)[eliano] P[io] (F)[elici] Invicto Augiusto] Pontif[ici] Ma[ximo].

[P]ar[thico] Ma[ximo]. The letters ARMA of his copy may also be C]ar[pico] Ma[ximo] as in another inscription (Orelli 1029). I draw attention to the inscription as it has not found its way into the Corpus.

We also found a milestone in the village, but it is in such had condition

that little more than the letters IMP could be made out.

No. 42. J.A.R.M. 1891. Purk (Nicopolis).

†THAEKATAKITAIOTHCMA
KAPIACMMHICCUTHPIKOC
OCTOMPICMENONAYTWIA
PAET XPONOBINCAC TOTTA
CIKOINOMATAPETH TONTY
BISTICPACEAEZATOTHTAN
KOCMIONTHCANACTACEMIC
TTEPIMENMENTIAA †

Τήδε κατάκιται ό τής μακαρίας μυήμης Σωτηρικός
δε του ώρισμένου αὐτῷ παρὰ Θ(σοῦ) χρόνου βιώσας τὸ πᾶσι κοινὸυ κὰπαρέτητου τοῦ
βίου πέρας ἐδέξατο τήν πανκοσμιου τῆς ἀναστάσεως
περιμένων ἐλπίδα +

No. 43. D.G H. 1891. *Ibid.*Altar-stele now used to form the altar of the lower church. Broken below.

OTHOCMAP
KOCBIWCAC
KAAWCEYC
EBWNMAPK
OCOTHOCAB
YAACYIOCA
NECTHCENB

Όπιος Μάρκος βιώσας καλώς εὐσεβών Μάρκος Όπιος 'Αβύλας υίδς ἀνέστησεν β[ω]μόν μνη[μης χαριν.]

No. 44. D.G.H. 1891. Ibid. On a small stell very rudely engraved.

+ ENGAΔE KOM + Endábe alatá-

KITAIHM KITAI HILLE-

PIWTFEW, $\rho_i(s)$ ('O) $\tau(\rho)$ & $\phi_i(s)$ or $\rho_i(os)$ $\Gamma_{ew}[\rho_{Y}(ov)]$.

OIMNATINGC of [d]vayuvist-

KONTECEY KONTES ED-

IAC BAITTEPI Eartai Tepl

AYTHC airtis

A similar formula occurs in one of our inscriptions from Satala (No. 37), and also in Lycaonia, see Ramsay's note in Jahreshefte des Ocst. Inst. L., Beiblatt, p. 95.

PONTUS.

No. 45 D.G.H., J.A.R.M. 1891. Kejint.

Limestone slab in the graveyard, ornate letters deeply and very carefully cut between ruled lines. The slab appears to have been let into a wall. Native Armenians reported that it had been brought from Sivri Tepe, where are rains of a church, two hours in an easterly direction from Kejiut.

H OPACKS MOAYMA MICATAGOYK & 1Λο

XPICTOY ΔΕ ΕΠΟΤΟΥΦΙΛΟΤΙΜΙΑΝ

ΙΟ ΕΤΙΝΙΑΝΟ Ε΄ Α ΤΟΥ ΕΤΟ ΕΑ ΤΟΚΡΑΤωρ

ΝΙΚΗ ΜΕ ΕΤΡΟ ΕΘ ΕΘ ΧΟ Ε ΑΕΙ ΕΕΒΑ ΕΤΟ Ε

ΑΝΕ ΕΙΡΕΝΜΑΣ ΔΕ ΕΠΟ ΔΗΚ ΠΡΟΝΟΙΑ

ΘΕ Ο ΔΙΜΜΟΥ ΤΟ ΕΝΔΟ Σ΄ ΚΟΜΗΤ Τ WN

ΚΑ ΘΟ ΔΟ ΜΚΙΚ ΘΕΙΟΥ ΚΟΥ ΡΑΤΟ ΡΟ Ε

ΜΠΙΕ WTHPIATW NEAYTO OIKHT WN+

όρᾶς κὲ θαυμά[ξ]ις ἀγαθοῦ κὲ φιλοχρίστου δεσπότου φιλοτιμίαυ.
 Ἰουστινιανος Αύγουστος αὐτοκράτωρ

νικη[τη]ς τροπεούχος άεισέβαστος άνέγιρε . α . δε σπουδή κὲ προνοία Θεοδ[οσί]ου το(ῦ) ἐνδόξ(ου) κόμητ(ος) τῶν καθο(στουμένων) δομ(εστικών) κὲ θείου κουράτορος ἐ]πὶ σωτηρία τῶν ἐαυτοῦ οίκητῶν +

In line 5 either ανέγιρε ταύτα or αν. τὰ τῆδε may be suggested.

Mr. C. H. Turner has supplied the restoration of line 7. Theodosius was comes devotissimorum domesticorum and curator of the sucred buildings (cf. Novell, Tiberii, c. 1, 2, 4: οἱ ἐνδοξότατοι καὶ μεγαλοπρεπέστατοι κουράτωρες have charge τῶν θείων οἴκων).

No. 46. D.G.H., J.A.R.M. 1891.

Kavsa, i.e. Thermae Phazemonitarum (Strabe) in the wall of the mosque, marble stele, broken to left.

AXO OMENA ITOTIAP O I O ENETWORK DATA ON INVITATION ON THE PRODUCTION OF THE PRODUCT

Νύμφαι ἀκοσμήτοις ἐνὶ δώμασι ναιετάουσαι
'Αχθόμεναι τὸ πάροιθεν ἐτ[ή]ρ[ε]ο(ν) ἄγλαον [ὕδωρ·]
'Ηχθετο δ' "Ηφε(σ)τος νῦν δ' ὅπασε Ἰδβινος αὐταῖς
'Η]γεμόνων δχ' ἄριστος, ἐπ' εὐτύκτοις θαλάμοισιν
Αυσιπόνοις νύμφαισι καλόν στέφος, ὅφρα καὶ αὐταὶ
'[μ]ε[ρ]ταῖς (ϸ)ἔζωσιν ἀγαλλόμεναι Χαρίτεσσ(ι)ν.

For previous publications and discussions of this epigram, see Hubert in Rev. Arch. xxiv. p. 308, Bubensohn, Berl. Phil. Work. 1895, col. 380 and 603. The present copy would suggest tripeer in v. 2, and confirms Wilhelm's suggestion of treprais in v. 6 (cf. Anth. Pal. ix. 669).

No. 47. D.G.H., J.A.R.M. 1891.

Kavsa, in the mosque wall. A late stell made almost illegible by the scratchings of a native decipherer.

ITAMOEZHEACBION AT A O ONETPOTTO OP GONK EMMINIMUMONTO NEANICKOMHABONEIC THAC ZWETTOINGA WEMAY TWOEC IN DY **NAKTHPION** CYNTHYNE KIMO DOMNHEBICEZICA KANWCKEETEKNWE MMEXAPINETHAH EXAPAZAWWWWE **CATHPMETEPANKATA** CIMHAINAETTANYZE KEETEPONKHAOL KATABINEEANAETIC ETTANYZHKEETE PONHACEKATAGH **AUCITUTAMIU** TIPOETIMOYX BO EAUKEALEBIAIN FO線然像EZL

"Ιταλος ζήσας Βίον άγαθου κὲ τρόπο[ν όρθον κέ [νου μο]ι δυτο[ς rearloso v hator eig γήρας. ζω(ν) [έ]ποίησα έμαυτώ θέσι[ν] Φυλακτήριον σύν τη γυνεκί μο υ. Δόμη ΕΘΗς, έζησα καλώς κὲ ε(ὑ)τέκνως. μνήμης χάριν στήλη ν έχαραξα κ(ατομνύ)ων με-(τ) α τη (ν ή) μετέρον κατά (θεσιν μηδίνα έπανύξε κέ έτερου κήδος κατα(θ) ενε έδυ δέ τις έπανύξη κὲ έτερον κήδος καταθή δώσι τω ταμίω προστίμου * ΒΦ Ebwice acreBials

1 -- 2 -11

The inscription seems to have been written by Italos, who records the preparation of the tomb for himself and wife, and the erection of a στήλη in his memory, and adds the usual curse against violators of the tomb. For the corrupt form of κατομεύων compare Ramsay's Cities and Bishoprics, i. pt. 2, p. 734, etc. The last line probably gives the name of the violator and the amount of penalty paid, but it is impossible to restore it satisfactorily.

V. W. YORKE.

ARCHAEOLOGY IN OREECE, 1897-8.

THE past year has not been one of startling discoveries. The effect of the disastrous war has been a paralysing one and the difficulties in the way of archaeological work have been great. While the political situation was so complicated, new undertakings were almost out of the question: it is to be hoped, however, that the report on 1898-9 will be able to speak of Crote as having been thrown open to the scientific world. The most interesting archaeological event has been the foundation of a new Austrian Institute, under the guidance of Prof. Benndorf in Vienna. Dr. A. Wilhelm, the wellknown epigraphist, and Dr. W. Reichel, whose brilliant essay on Homeric Armour has won for him a prominent place among archaeologists, are permanently stationed at Athena, and a building is contemplated in the near Dr. R. Heberdey will be stationed at Smyrna and Dr. Kalinka at Constantinople, so that the new Austrian Institute will be a powerful agency for the discovery and preservation of Hellenic antiquities. The old publication 'Archaologisch-spigraphische Mittheilungen aus Oesterreich' is now brought to a conclusion, and is replaced by the Jahreshefte des österreichischen Archaologischen Institutes, of which vol. i. has appeared. The contemplated international congress of archaeologists at Athens, which the war of 1897 rendered out of the question, was announced for Easter 1898 to synchronize with the celebration of the fiftieth anniversary of the foundation of the French School, but this year as before practical difficulties caused its postponement. The adjourned festivities at the French School took place as arranged. If the congress is to assemble at a future date, it will be necessary that arrangements should be made for it long enough beforehand to ensure its success.

The work of the German, American, and British Schools has continued on the usual lines. During the early months of the year Dr. Dorpfeld took a six weeks' trip to Egypt and briefly recounted his impressions at a meeting of the German School on March 31. His remarks about the Temples of Philae in counexion with the contemplated water-atorago reservoir at Assonan were exceedingly just. It was hoped, that the protest of British scholars would have had effect in causing the abandonment of any plan, by which the island would be submerged at all. It appears, however, that according to the modified plan Philae will still be covered every season with a few feet of water. It cannot be too strongly insisted, that this means destruction equally with the old plan, only that the process will be more gradual. The utility of the scheme is clear and no greater benefit could be bestowed on Egypt, but even if the expense of building two

L Borchardt, 'Rericht uber die Correction des Sitzungaber, der Berl Akad. 1898, 23.

reservoirs instead of one be incurred, it is surely better than that the British occupation of Egypt should suffer under a deserved imputation of needless Vandalism.

The first thing that has struck the eye of the visitor to Athens this spring has been the solid scaffolding on the west front of the Parthenou. The suspension of the work of repairs has been due not merely to the war but to the difficulty of securing sufficiently large blocks of marble from Pentelicus to replace the shattered parts of the architrave. Several blocks when brought were found to be useless and are lying on the Acropolis. A new company has however been formed, which is beginning to quarry on the Marathon side of the mountain, and it is hoped that it will shortly be in a position to supply blocks of the requisite size and arrength. It has been rather a shock to the eye for visitors to see this scaffolding, but there is reason for thankfulness that the serious earthquake of 1894 did not bring down the whole west front. At any rate the work in hand will prevent any

further destruction of the great fabric.

The excavations on the north slope of the Acropolis in the previous year resulted, it will be remembered, in the complete clearing of the caves of Apollo and Pan and the uncovering of an interesting way of access to the Acropolia, while the chief actual find was the inscription which finally settles the date of building of the Temple of Nike. Part of the construction laid bare by this excavation under the caves is now regarded by Dr. Dorpfeld as belonging to the north enclosing wall of the Pelargikon, which in this direction extends just beyond the Clepsydra so as to bring it within the fortification of the Acropolis and its slope. The wall in question abuts on the citadel rock just under the western of the two caves. Another wall uncovered which runs down northwards towards the town he regards as part of the so-called wall of Valerian. The most interceting find made this year is an inscription containing part of a vijourus proposed by Alcibiades. As it has been published with commendable promptitude by M. Kayvadias (Eph. Arch. 1898, 1-2), in whose charge the excavations have been, it is not necessary to say more than that it is similar to C.I.A. iv. 1. p. 18, No. 61a, an inscription found in the Asklepicion and containing a decree which confirms the arrangements of the arparayof with the people of Selymbria. Thucydides (viii, 23) tells us that the Athenians occupied Clazemenae, while the anti-Athenian party refired to Daphnus, and that (viii, 31) Astyochus made an attempt on Clazomenae later. This decree ratifies the arrangements of the generals with the Clazomenians, who occupied Daphnus. Either therefore the anti-Athenian party made their submission and received terms, or the Spartans were successful in expelling the Athenian party to Daphnus, with whom the Athenian generals then made a covenant. The decree supplements the narrative of Thuoydides, though not to the extent of making the whole series of events quite clear. It must have been proposed during Alcibiades' stay at Athens in 408. In the rumed Byzantine church of the Seraphim, which had been covered by the debris from the Acropolis excavations, other inscriptions were found including an architrave block inscribed Kurukov,

Work has also been progressing at the Stoa of Attalos under the charge of M. Mylanas, with a view to its complete clearing. A beginning was made at the south side, and on the west side traces were found of an old road. The chief finds include an inscription of the fourth century i.c. referring to Zebs φράτριος and Αθήνη, a portrait-head (probably of one of the Pergamene

royal family), and a small female head of the best period.

Thirdly the Greek Archaeological Society has been excavating in the peribolos of the Olympieion, the work being in charge of M. G. Nikolaides Since Mr. Penrose's work, nothing has been done, and the large precinct has never been thoroughly investigated. It was also thought that some of the standing columns required strengthening. The whole foundation of the temple has been dog round and the stylohate has been found to consist of three steps, the upper of marble and the lower two of peros. The lowest is only half the width of the other two on the north, south and west sides, and was apparently only used as a step on the east side, though smoothed and polished and so intended to be visible. In many places the whole structure has been removed. A drain for the purpose of carrying off the rain-water from the temple was discovered running along the outside. The foundations of the remaining columns have been strengthened, and in the precinct by the north wall, a unmber of inscriptions and sculptured fragments of Roman times have been found. South of Kallirhoe on the Hissus M. Skias has found a few foundstions which appear to belong to the Ionic temple by the Illssus of Stuart and Revett ; and Dr. Dorpfeld regards this as the temple of Artemis Agrotera.

The excavations of the German Institute in Athens have also been After laying bare the apxala ayana Dr. Dorpfeld's chief object has been to investigate the extent of the later Agora by discovering, if possible, some of the buildings which surrounded it. Beneath the so-called Theseion on its east side, it will be remembered that he had already found two buildings, one of which, a quadrangular hall, may well have been the famous Ston Basileios. Anyhow, in these buildings he sees with great probability the western side of the Agora (Ath. Mitt. xxi. 458, xxii. 225). This season he has attempted to fix the position of the south side of the Agora on the north slope of the Areopagus, and in an open space by the little church of the Prophet Elias actually came upon the corner of an old Greek building running east and west, surrounded by several later walls. There is great probability that this is part of the foundations of one of the buildings on the south side of the Agora, perhaps the Metroon or the Bouleuterion. If, as Dr. Dörpfeld thinks, the so-called Ston of the Giants also marks a side of the Agora, the dimensions of the latter are nearly ascertained. At the same time an excavation on a piece of land belonging to M. Kalliphronas, the demarch of Athens, higher up on the north slope of the Areopagus, resulted in the discovery of six graves of the Dipylon period. These graves dated from a time when the whole of the Areopagus lay outside the fortified wall of the Polis, i.e. the Acropolis and its western and south-western slope. Two

A recent important newspaper report seems to rafer to the linding of the leasts of the sultan-status.

iron swords, an iron knife, and a bropze lance-head were found with characteristic geometric vases of the earlier Dipylon period. The interest of the discovery lies in the fact that traces were found of both burying and burning the corpses, so that it is no longer possible to hold that cremation was a much later practice than burying. Both seem to have existed side by side at a very early period. No success attended Dr. Dörpfeld's efforts to locate the Thesmophorion and the Eleusinion. He has no doubt that the latter sanctuary must have been situated on the west slope of the Acropolis in the great bend of the carriage-road, and south of the Amyneion discovered by himself, but hardly even foundations remained traceable on this spot Similarly while he still maintains the identity of the temple of Demeter Kore and Triptolemos seen by Pausanias 'above the Enneakronnos' with the Thesmophorion, holding that the Pnyx had the same relation to it as the Bouleuterion to the Metroon, no remains were discovered in the spot where he looked for them. Some time was devoted to clearing the great subterranean aqueduct between the theatre of Herodes and its terminus beneath the Pnyx. To the investigation of the water-system and its numerous side rumifications, one of which seemed to extend to the Acropolis itself, he has devoted much attention, and pronounces several of the channels and receptacles to be older than the great aqueduct. In order to avert the falling in of the rock over the aqueduct, a shaft thirteen metres deep was sunk from above at a point half way to the theatre of Herodes. Dr. Dorpfeld will before long be able to publish ample details and plans, which will make us intimately acquainted with the watersystem of ancient Athens. Later on in the spring, he commenced an excavation on a piece of ground north of the Kolonos Agoraios and just the other side of the railway. Here a new house was being built, and before its foundations were laid a part of the great street leading from the Dipylon gate to the Agora was unmistakably discovered. When the cutting was made for the extension of the Piragus railway to the Place de la Concorde, it must have gone through this road, but nothing was observed at the time. It is also contemplated to make trial diggings on the Kolonos itself round the 'Theseion,' in the hope of obtaining further light on the identification of this temple.

Mr. C. N. Brown of the American School has been investigating the outside of the Acropolis with a view of finding inscriptions. His researches carried on with considerable risk to life and limb have been rewarded by the discovery of a number of unknown or lost stones. Dr. Cooley of the same school has been investigating the traces left by the pedimental sculptures of the 'Theseion,' and it is announced that Dr. Sauer will shortly follow up his similar work on the Parthenon with a dissertation on this subject.

Not much change in the Museums of Athens is to be reported. The sculptures of one of the pediments of the old Athena temple, the subject being Athena in the Gigantomachy, have been set up in the Acropolis Museum, and will surprise those who have not seen them both by their mexpected completeness and also by the complete contrast they offer to the Aeginetan marbles, from which they cannot be far removed in time. In the

smaller museum a sample of the architectural members of this temple has also been mounted, which will give a good idea of its external appearance. The National Museum every year is getting into more complete order, but discoveries come so quickly, that the process of mounting and exhibiting everything is necessarily slow. The collection of bronzes, increased by those from the Acropolis and Olympia, has received a noteworthy addition in the shape of an archaic bronze nude statue of Poseidon, found by a fisherman in pieces pear Dombrens and the site of the ancient Krousis. In spite of the restorations, which have unfortunately been coloured so as to resemble the bronze, the general effect is very striking. The feet are perfect, the left leg being advanced. The head is bearded and much resembles the Zeus-head from Olympia. The arms are broken off; the left was raised, but as the weight of the body rests on the left leg, probably did not rest on a sceptre, but may have brandished a trident. The lowered right arm perhaps held a tunny-fish. The head has the hair carefully incised with parallel lines starting from the grown. There is a plain circlet and two rows of fourteen forehead curls. The eyes are hollow. The beard is wedge-shaped and has the small interior wedge below the lower lip, as in the case of the bronze head [of a strategos I) from the Acropolis. The nipples were like the eyes, specially inserted. The total height of the figure is about 1:18 metres. The thickness of the bronze proves its genuineness-if proof were necessary.

At Eleusis, M. Skias has been digging for some years on the south slope of the Acropolis hill and in the neighbourhood. He has now published the interesting results of his work. The importance of his discoveries is that he found the layers of succeeding ages undisturbed. Immediately over the layers of Myeannean sherds, he found Geometric potters containing some of the rude ware with scratched patterns like that found at Aphidna and argues from his finds that the Dipylon art must have been developed elsewhere and imported into Attica full-blown. He is strongly of opinion that it came in from north Greece with the Dorians. The practice of cremation seems to have been the rule at Eleusis. The same enterprising archaeologist is also reported to have found traces at Eleusis of a sanctuary of Asklepios carlier in date than those at present known. At Megara Dr. Dörpfeld has been investigating the topography and water-system of the ancient town in company with M. Stambolas, a native who has studied Megarian antiquities and contemplates writing a monograph on the subject. The most interesting conclusion, at which he has arrived, is that which takes the converse view to Lulling's with respect to the sites of Nisaea and Minca. Lolling regarded the low hill called Paleokastro with the mediaeval tower as Minon, and placed the Acropolis of Nisaea on the much higher hill crowned by a small chapel of St George to the east. Dr. Dörpfeld is, however, confident that the reverse is the case. On the latter hill he has discovered a wall which he thinks is probably part of the fortifications erected by the Athenians on Minoa To this view Prof S. P. Lambros, in making known a boundary stone inscription from Megara of the fifth century with Dios Milkeylo Harpino at a meeting of the German Institute, has given his support.

The American school continued its work at Corinth this season and the excavations lasted for about three months ending on June 12. The main result was the excavation of the Peirens of Pausanias, the site of which is now definitely fixed at a spot about 100 yards directly south of the Platia of the modern village. Hitherto there had been two views, according to one of which it was the spring on Acro-Clorinth (so Strabo, viii, p. 379, a view mentioned by Pans, ii, 5, 1) now covered by a Turkish well-house, while the other identified it with the 'bath of Aphrodite' so-called, below the village of Old Corinth in the direction of Lechnento (see Frazer, Pans. vol. iii. p. 24). Prof. Richardson writes to me as follows: 'There can be no doubt of the identity. In has six chambers with natural rock covering, but back, front and sides architecturally equipped, and so fits exactly the phrase of Pausanias οἰκήματα ountaious card radra (ii 3, 3). The façade which was in two storeys, had the marble revetment mentioned by Pausamas, as is evidenced by holes and by masses of fragments of thin plates of marble. One of these fragments was Besides the adjustment, which dates from the time of enscribed PIREP. Pausanias, un older as well as a later adjustment is plainly discernible. Two rock-out channels, traced to an aggregate of about 300 yards, still bring water down from the direction of Acro-Corinth past the two ends of the façade supplying the modern village. In front of the façade which faces north, was nucovered a semi-circular building closely connected with it, which is likely to be the περίβολος of Apollo πρός τη Πειρήνη of Pausanias (ii. 3, 3). The agora may now be located within very narrow limits just south of Peirene. The old temple appears now to be the temple of Apollo.' (It at first seemed likely that the old temple was to be identified with the vaci bear a nev Διὸς ὁ δ' Ασκληπιού (ii. 4, 5), since the division into two separate parts has been proved by Dr. Dörpfeld. In the light of the new identifications it seems natural to point to the old temple of Athena on the Acropolis of Athens and to conjecture that the western cella at Corinth also was used as a treasure-house). 'Two more columns of this temple, the seventh and eighth on the south side, reckoning from the west end, were found lying, just where they fell outward. A flight of porce steps was found leading from the temple down in the direction of Peirene, and a flight of marble steps. quite imposing, leading up past the west end of Peirene towards the agora. West of this latter flight of steps, a long building, probably a stoa, with walls standing to a height of from eight to twelve feet, was brought to light, closing the valley on its side towards the temple. There were also found six large marble statues without heads, a great quantity of old Corinthian ware mostly fragmentary, one whole geometric amphora, two interesting bronze figurines and a great many Roman inscriptions mostly fragmentary, as well as several Greek. Among the latter the most interesting is one of the age of the Dveinias-inscription,' (which was also found near Old Corinth by Lolling Athen. Mitt. i. p. 40, Pl. I.) and another of uncertain date; but as late American school is greatly to be congratulated on the success of a campaign, where great patience and considerable outlay were required. Another season's work will add Corinth to the number of those Greek sites, whose topography has been practically elucidated.

The Austrian school undertook an excavation on the site of the temple of Artemis at Lousoi in North Arcadia, near to the village of Sudhena, on the slopes of Mt. Khelmes and not very much further from the town of Kalavryta. The interest attaching to this site was increased by the mention of it by Bacchylides in the ode in which he recounts the legend of the healing of the daughters of Proetus (x. [xi.] 96, 110 Blass): clearly it must have been, therefore, a well-known sanctuary in the fifth century B.C. Unfortunately, Drs. Wilhelm and Reichel did not meet with the success that was hoped, as the site had already been plundered by private persons. Even in such an out-of-the-way spot as this, this danger has to be faced by intending excavators and it is but few who are lucky enough in Greece to find an actually virgin site. Little else is to be noted from the Peloponnesus in the way of excavation or discovery during the past year. The Museum at Olympia has yielded up its bronzes to the National Museum at Athens, but for want of a resident ephor has not yet been completely arranged. The museums at Sparta, Megalopolis, and Tripolis are becoming more and more worthy of visit. At Arges, however, failing a separate building, few things are allowed to remain in the Demurchy, and the sculpture fragments from Bursian and Rhangabe's excavation at the Heraion, as well as the American finds, have been transported to Athens. It appears that the Athena statuette, the importance of which has been emphasized by Mr. Cecil Smith, has not yet been taken to Athens from Patras, and the fine mosaic in the square at Patras should certainly not be left covered up: if it cannot be taken to Atliens, the citizens of Patras ought to take proper care of it in their own town, but as they have allowed their Roman Odeion to be stripped of nearly every fragment of marble it possessed, it is clear that they are not to be trusted with any antiquities, and that all should be removed to Athens if possible.

In North Greece, owing to the unsettled condition of things after the war, very little has been done. Mr. Arthur Hill of Athens is endeavouring to have the Thessalian marble quarries worked once more, which it appears are by no means exhausted. In the course of the hasty works, which were thrown up for the protection of the Greek army at Thermopylae, when a Turkish advance was imminent, the remains of an ancient watch-tower! were discovered guarding a path over Callidromos, possibly the very path by which Ephialtes led the Persians, and one kilometre south of the warm springs an ancient cemetery was discovered, as to which particulars have not come to hand. But the archaeological centre of interest on the mainland has been Actolia. Considerable interest has been directed lately to this little-explored country, and particularly to the site where all recent authorities have agreed to place Thermon, namely at the Palmobazári of Kephalóvryso, east of Lake Trichonis. The latest discussion of the question is to be found in Mr.

^{*} This was described as a small Durio temple in the newspapers at first (Ath. Mill. 220. 1-2, 220).

Woodhouse's Aetolia, where it is conclusively settled; and it only remained for excavation to confirm his view. This has now been done. The Greek Archaeological Society has been digging in the sacred enclosure or Altis, and found the great hall of assembly, numerous statue bases, and inscriptions, but the destruction wrought by Philip V. seems to have been very thorough, for apparently the site has remained undisturbed since then. It is, however, possible that subsequent digging will result in the find of some, at any rate, of the statues which were dedicated here in such numbers. Everywhere, however, in Actolia there is little actual 'plunder' to reward the excavator, so far as present experience goes, and if Thermon proves a blank. no other site is as likely to tempt future workers. In unother part of Actolia Dr. Herzog and Dr. Ziebarth conducted on behalf of the German Institute a short excavation this spring, in the little themtre at the kastro of Irene, an hour and a half from Mesoloughi, the site generally identified with New Pleuron. Unfortunately there was not a single inscription found which in any way proved this identification to be true. Nevertheless, the conclusion, accepted by Mr. Woodhouse in his book on Actolia (p. 119), may still be regarded as highly probable. It will be remembered from Mr. Woodhouse's description and plan that this, the smallest of all Greek theatres preserved, abuts closely on the town wall just where a quadrangular tower juts out from it. As the distance from the furthest point of the orchestra circumference to the wall is only 11.15 metres, it was natural for Mr. Woodhouse to disbelieve in the existence of a proskenion; asvertheless Dodwell was right, for the stylobate of the proskenion with one door in the centre has been discovered by the German excavators. From the back of this to the town-wall is only a distance of 1.94 metres. The floor of the orchestra is the natural rock slightly levelled; one better seat was discovered and fifteen rows of ordinary seats. Dr. Herzog thinks that owing to the small dimensions of this theatre it has an important bearing on the stage question, and certainly it must have been difficult to see the actors on an elevated stage from the lower seats of such a theatre as this. The evidence supplied by this theatre will clearly have to be carefully examined when published. No further light was thrown by the excavations on the carious constructions described and photographed by Mr. Woodhouse (p. 121) and locally called σταίς φολακαίς, and whether they were corn magazines, cisterns, dungeons, or what purpose they served, must cemain an unsolved problem.

At Delphi little or no work has been done this year. It is announced that the Athenian banker, M. Syngros, has undertaken to build a museum here as he did at Olympia, and as the temporary building is more than full already, and not by any means waterproof, this is good news, though it is to be hoped that the building will be unobtrusive. With the finishing of the work at the Stadium, the chief part of the French School's great work is over, and in the Bulletin (1897, Sept.-Oct.), we have three provisional plans giving some idea of the vastness of the work. It remains to pull down the chapel of Hag, Elias built over the foundations of the Amphictyonic συνέδριον, which are plainly visible at the north-west end of the site on the spur overlooking

new Kastri, and to clear the ground south of the Arachova road, where stood the gymnasium and other buildings mentioned by Pausanias (x. S. 6).

The chief scene of archaeological activity in Greece Proper this year has been the islands. The important vase find at Aegina has been made known by Dr. Paliat's publication in Ath. Milt. xxii., pt. 3. Whether Aegina ever possessed a local industry which rivalled those of Corinth, Athene, or Chalcie, is an interesting question. Dr. Pallat does not deny to Aegua a local fabric; and thinks it lasted on in spite of foreign importation. That there was a fabric of vessels for household use is proved by Herodotus, but Dr. Loescheke denies a separate art-fabric to Aegina, and Dr. Hoppin takes this view too. The so-called proto-Corinthian ware seems to have been manufactured in the Argolid, and it is this which is so largely represented in the Aeginetan find. At the same time, it must be plainly confessed, that this question cannot yet be regarded as settled. The publication of the American finds at the Heraion will do much to throw light on these early vase fabrics. The work done by Drs. Hiller von Gaertringen and Dragendorff in the island of Thera does not fall into this year, but Dr. Tsountas excavated last summer in Paros, Naxos, and Despotiko. He found there a quantity of pre-Mycenaean ware resembling that of Pelos some cornelian beads, and one piece of gold jewellery in the shape of a stephane. His excavations bear out the view that the early incised ware is contemporary with the Cycladic marble figures, and is distinctly prior to the painted pottery.

This summer an interesting work has been going on at Paros. will be remembered that early in 1897 a fragment of the Parian Chronicle was discovered in a piece of ground close to Paroikia, the present capital of the island of Paros. The stone 1 contained the account of the years from the death of Philip to 299 B.C. (thus supplementing the Oxyrhynchus papyrus which contains the chronology of the period 355-315 B.C.), and as a period of 19 years separated it from the Ashmolean marble and the complete stone went down at least to 264 n.c., it was natural to hope that the remainder might be found. Dr. Rubensohn has been conducting excavations on the site of ancient Paros this summer on behalf of the German Institute. Though the Parian Chronicle has not been further enlarged and only a lucky accident may bring further fragments to light, these excavations have been singularly successful. The Temenos of Asklepios has been found close to the sea containing a spring, a quadrangular court with an altar in the centre, many architectural fragments and inscriptions, and a round archaic basis of Parian marble on which an inscription contains the name of Mikkiades and the letters Phoib ... That this is the Chiot artist and that the statue was a dedication to Apollo seems extremely probable. In fact another of the early 'Apollo' figures was also found complete with the exception of the feet. Of this statue we hear that the archaic smile is very pronounced and that its execution is comparable for care with that of the Apollo of Tenea. It is to be hoped that the circumstances of the find may

Ath. Matt. xxii, 1, 2, p. 183 [Kriepl and Wilhelm].

throw some light on the question of the identification of this early nude male type. Dr. Rubensohn has also laid bare the foundations of the town walls on the three sides facing the land, which are preserved in part to the height of a metre, and pronounces them to be of fifth century construction. He has also identified a sanctuary, which he discovered on a neighbouring height, as the temenos of Aphrodite, and on a site underneath the summit another as that of Eileithyia. Finally it is satisfactory to learn that a museum has been formed for the reception of the Parian finds and that the inhabitants have brought to it antiquities previously in their possession. If this sort of thing had happened twenty or even ten years ago in various parts of Greece, how much barbarous destruction of ancient monuments would have been avoided. A museum has also been started at Vathy in Samos. The excavation of the Heraion by Dr. Sarre, to whom permission has been granted. has apparently not yet taken place. Lastly, there has been the second season of the British School's work in Meles. The work will be described alsewhere; it can here be said without exaggeration that in Phylakopi a second Troy has been found. Nowhere else, except at Hissarlik, have the Mycenaean and pre-Mycenacan strata been discovered in so little disturbed a condition. Three distinct strata representing different settlements have been found practically undisturbed, and the finds of pottery especially will when worked up throw much light on early Aegean civilization. It may be fairly said that no excavations of the past year in Greece have been more interesting or valuable.

It remains to say a few words about archaeological work in Asia Minor. Besides the explorations of Prof. Körte in Phrygin, and Mr. Anderson in Galatia, there have been two important excavations. The Austrian Institute, under the guidance of Prof. Benndorf, has been conducting excavations at Ephesus, of which a provisional report has appeared from Prof. Benndorf and Dr. Heberdey, first in the Anzeiger der philosophisch-historischen Klasse der Kais. Akademie der Wissenschaften in Wien, 1897, n. v.-vi., 1895, p. vii.-viii., and repeated in the first number of the Jahreshefte of the Institute.

The first work was carried on in some ground close to the scene of J. T. Wood's labours, on the north and west of the Artemision, outside the wall which marks off the ground belonging to the British Museum. On the north side no fragments of the temple-building were found, on the west it was hoped that the altar might be discovered. This was not the case, but at a distance of about 55 to 60 mètres from the west front of the temple a pavement of polygonal marble blocks, with sculptured fragments and potsherds of the sixth and fifth century, was brought to light. Beandorf thinks it likely that the altar by nearer the temple under the earth heaps thrown up by Wood's excavation. Similar trust excavations on the presumed site of the Lysimachean city, which were superintended by the lamented Humann, showed that digging on a large scale would be abundantly justified. From April to December, with a respite in the two hottest months, the work was carried on chiefly under the supervision of Dr. Heberdey. The 70 mètre square

H.S. - VOL. XVIII.

marble-paved court surrounded by a colonnade with halls and rooms opening upon it, and entered by a propylaion on the east side, could be nothing but the Hellenistic agora which seems to have been mainly destroyed by the Goths in 263 A.D. and only partly rebuilt subsequently. The theatre is pronounced to show three periods of construction, one of the time of the foundation of the city, one rebuilding about 150 A.D., and later restorations. A round monument on the adjacent hill, of which the architectural members were found in such numbers that it could be restored in plan, is conjectured to be a trophy of victory, possibly of the Ephesians at Kyme over the pretender Aristonious in 133 B.C. Important finds have been made, including a bronze statue of a nude youth, over life-size, which seems to be an original of the later Attic school, and a free reproduction of the Attic work of the 5th century representing an athlete anointing himself, of which copies exist in the Uffizi, Louvre, and Vatican, a marble statue of a scated naked boy with a duck, suggesting the works of Boethos, a group in black baselt representing a sphinx tearing a nude youth, which can be paralleled with the centairs by Aristeas and Papias of Aphrodisias in the Capitoline Museum, and a beautiful bronze incense-vessel in the shape of a candelabrum. The most interesting inscription mentioned is a letter of M. Aurelius and L. Verus ordering that the statues of previous emperors shall not be remodelled to represent themselves

Since 1895 the important exeavations of the Berlin Museum at Prience have been progressing, first under the supervision of Karl Humann of Pergamon fame, and since his death of Dr. T. Wiegand, his successor in his post. They have resulted in the laying bare of another Pompeii. Prienc lies on the lower terraces of Mykale and is crowned by a lofty Acropolis, which could only be reached from the town by a steep path and on the south falls away so abruptly that no wall of defence was required. The town is divided by a network of streets crossing at right angles into about seventy nearly equal rectangles. The only departure from this absolute regularity occurs in the agora, where more open space was required. The difficulty of laying out a town so regularly on such an uneven hilly site must have been enormous, yet no labour of cutting into the rock or terracing up was avoided, in order to preserve this absolute uniformity of plan. Below the Temple of Athena so well-known from the Dilettanti Society's publication and the excavations of Pullan, in a distance of 30 metres at least 1000 cubic metres of rock had to be removed to give the main street from the west gate a more practicable slope upwards to the agora. The streets are carefully paved with blocks of breecin, but there are no raised pavements at the side. Down the centre of the street generally runs a fresh water channel connecting with the private houses and fountains at the street-corners. Each of the rectangles surrounded by streets is divided into four parts, each quarter being the superficies of a dwelling-house. The whole town must have been built at one period and according to a single plan, which was no doubt conceived in the age of Alexander the Great. It is interesting to see how the traditions of Hippodamos were carried on in Asia Minor. The plan of the private house is generally that of a rectangle with a four sided court in the centre surrounded by pillars with the rooms opening into it on all sides. The front to the main street is a blank wall, the door that gave access to the court is in the side street. The decoration resembles what is called the first style at Pompeii, i.e. real architectural ornament consisting of half-columns, triglyph friezes and cornices, with actual sculptured additions, applied to the surface of the wall. Of the public buildings discovered, apart from the temple of Athena, the chief were the Asklepicion, a rectangular but theatre-like building, probably a place of assembly or Boulenterion, the Prytancion, and the Theatre. In the latter the stage buildings are wonderfully preserved. The front row of seats, a plain marble bench with back, is interrupted by five marble thrones. If the circle of the proedria be continued it touches the front of the proskenion. An altar was actually discovered, not in the centre of the orchestra, but close to the front row of seats. It bears an inscription of the third century B.C. The complete publication of these extraordinarily interesting discoveries will be engerly numited

G. C. RICHARDS.

A SUMMER IN PHRYGIA:

Some Corrections and Additions.

(See vol. vein., p. 396 ff. and willi, p. 81 ft.)

In my second article on Phrygia, Vol. xviii,, pp. 101 and 109, mention is made of some Latin inscriptions which were reserved until the stones should be re-examined. I had the opportunity of seeing them again this summer, and I now publish them, together with a few corrections and additions to both papers.

Vol. xvii., p. 401, l. 18. Read the small river nearest but one to Sarat

Keui on the east '; see the inset map, Pl. IV,

P. 418 ff. This inscription is discussed by A. Schulten in a paper entitled Libello dei coloni d'un demanio imperiale in Ann in Mitth des Instituts, Rôm. Abtheil., 1898, pp. 231-247. My restorations, which had to be made very hurriedly and with an inadequate knowledge of the special literature of the subject (e.g. of the important inscription of Skaptoparene, which throws so much light on our document.), were merely tentative suggestions; but it seemed better to publish the inscription at once for the benefit of scholars than to hoard it up until an exhaustive commentary could be written on it. But while Schulten's restorations are generally a great improvement on mine, they frequently pay scant regard to the conditions; e.g. in lines 14 and 15 he restores twenty-one and thirty-four (or more) letters, where the stone can hardly have had more than thirteen and fifteen. The main part of the inscription, I. 4 ff., is engraved on a sunk panel and the lines were therefore of equal length.

I should state that the reproduction gives on p. 418 does not quite accurately represent my copy in some slight details; and I take this opportunity of giving an improved reproduction of some portions of the inscription, made directly from an impression. I also add some notes on the text and a few corrections, which a careful re-examination of the atome has rendered necessary.

L. I. The names were no doubt erased, as Hulsen supposes (ap. Schulten, p. 233 n.). They seemed to me to have been merely wern away, but erasures not infrequently have this appearance.

2. PER was doubtless intended, but it is certainly not on the stone. The stone-cutter did not understand Latin.

^{*} Published in Kit. der banyngsliftenny J. Richtspeich . xii p. 340.

EADIDY AND WALL GENERURY PROCO TUTE U, G PERSPECTALIDEE PRUMA QUINIURIOSECERATURA DIOCUCITUDINEMAS ULA MA REUOCA DITA

Hillsen's suggestion PROCONSULE V(ir) C(larissimus) is probably correct.
[The occurred also to Mr. F. Haverfield.]

 The fourth letter is probably a cursive d. The same form of letter stands for b in dabit (1 26, see below), and the b of

revocabit is represented by a similar letter.

The latter of the two enigmatical letters at the end of the line is not A but A (which has become blurred in the reproduction).

4 The second 6 in EYCEBEI is of semi-circular form.

5. Read EFAEKY. [Schulten is wrong in supposing that the K was omitted by the engraver and then inserted above the line.]

KOINOMOFTEANWN

7. Read ALOTTEANWN. A re-examination of the stone revealed traces of a letter between O and T, and the impression shows it to be in all probability a T. The space is narrow, and evidently the engraver had omitted it at first and then inserted it. This improved reading confirms the correction κοιν(οῦ Τ)οττεανῶν.

10. Read TW, as suggested in the note (p. 420).

15, MITE; there seems to be no ligature between M and I.

20 fin. As I suspected, when editing the text, I have omitted a syllable. The correct reading is BOALANF.

24. The last letter is certainly E.

26. The outline of the blurred sixth latter is \triangle , which probably stands for b, as in revocabit. Mr. Haverfield tells me be has come across a similar case. The form \triangle which occurs on ceins, e.g. of Olbasa (B.M. Catalogue of Lycia, etc. pp. 229, 230) is more intelligible.

30. The first letter is € (it cannot be Θ).

31. Read EPIMOYEGAL

The following articles may be recommended to the attention of those who are interested in the Imperial Domains .—

Toutain, L'inscription d'Henchir Mettich, in the Mémoires presentes par divers suvants à l'Acad. des Inser, et Belles-Lettres, t. xi. 1897.

Cuq. Le colonal purtiaire, in the same volume.

Beaudouin, Les grands domains dans l'Empire Romain d'après des travaux récents in the Nouvelle Revue histor, du droit, 1897, pp. 543 ff. and 673 ff.

Schulten, Die lex Manciana in Göttingen Abhandlungen, 1897.

P. 424, No. 22. A certain Optimus was proconsul of the province of Asia in 250-1 A.D. He is described as preconsul apud Asiam (or apud
Asiam provinciam) sub Decio imperatore (249-251 A.D.) in the Acta S. Maximi

Printed also in Nouv. Resue hut du droit, 1897, p. 375 ff.

Martyris (Rumart Acta Sincera, p. 157), and in the Acta S. Martyris Petri, Andreas, etc (Ruinart, p. 160), and Waddington assigned him to 250-1 A.D. inasmuch as the proconsul of the preceding year is known (Frates des proc. Asiat., No. 176). Dr. Dessau has recently questioned the authority of these Acta, and expressed the opinion that the proconsul's name is corrupt and that the real name was perhaps Aristus, which became Optimus in the Latin translation of the Acta (Prasopographia imp. Row. p. 437). But our inscription shows that there is no reason to doubt the name and distrust the Acta on that score. We are indeed tempted to identify the proconsul of the Acta with the Flavius Optimus of the inscription. But, as Prof. Ramsay has shown in the Expository Times (August 1898, p. 496) the identification is not possible; for Fl. Optimus bears the title διασημότατος, perfectissimus, which marks him as belonging to a lower grade of governors, and to a later era. In 250 A.D. the governor of Asia had the rank \aumporarge, claristineus; and the inscription must be referred to the fourth or fifth contury, when Asia had been broken up, and Meiros was part of Phrygis Salutaris, administered by a process perfectissimus." [He goes on to show, with much plansibility, that apud Asiam, with the variants apud Asiam prov., in Asia civitate, apud Ambiensem provincium, is probably a corruption of apud Apiam.]

Vol. XVIII., p. 87, No. 24. The most probable restoration of the name of the κατοικία is perhaps ['O]λβοις, a proposal first made to me by Prof Ramsay and recently repeated by Dr. Körte in a letter. The name is well known in Cilicia Tracheia, and appears in Pamphylis or Lycia (Steph. Byz s.v. Olbia). I had introduced this restoration at first, but I afterwards ent it out, as there are other possibilities and certainty is, therefore, not

attainable

P. 101, l. 14 f. The inscription in question is now in the village of Oktchalar. The letters are mostly quite clear, and I did not re-examine the stone this year. My copies of 1896 and 1897 agree.



Fines loci q[nem en pulsade
pertinente[m
conduci conf[ir5 m]ateio t vicane[ru]m Polynteno[e
um Hermiene[or(u)m [Maragocomest ...

The interpretation of the first line was suggested by Mr. Haverfield, that of L 7 f. is due to Prof. Ramsay, confirmatio in L 4 occurred to all three of us.

Another inscription, exceedingly worn, now at the village Alp Arsian, seems to be a companion stone. The difficulty of deciphering it is greatly increased by the roughness and irregularity of the engraving.



Fines [low quem
ex p]a[I]u[de

v icanorum [Polynteis norum Hermi[oncorum Mo[r]agoc[omes'] emdu[x]e[runt]

The following remarks embody suggestions made by Prof. Ramsay. The palus is clearly the marshy part of the valley beside Oktchular, the lowest point in the plain, where in winter the water of the hand-locked ora collects and forms a lake, which becomes a marsh again in spring and dries up entirely in the height of summer (cf. CB. ii. p. 747). It seems probable that we have here the boundary stones of another Imperial Estate, stretching from Oktchular to Alp Arsian and containing two or three vici (Caesaris), the first of which is Polynta and the second the Hermo-kome of the Tekmorian Lists (Sterrett, Wolfe Exp. 375, 10, Ramsay, Hist. Geog. p. 412), while the third is uncertain. The inscriptions seem to refer to some kind of union of these vici. For the other Imperial Estates in Asia Minor whose existence has been proved by Prof. Ramsay, cf. Schulten, Röm, Mitth. Le. pp. 221–231.

P. 109, l. 8. The inscription is cut on the rocks on the hill-side, just at the point where a causeway and a low bridge carry the road over the marsh.* It contained four lines. A second trial enabled us to read the name Fronto quite clearly,

C. Carist[an]s[a]s
Fronto cos.(1)

. c]husu[mt . . .

. . . aperuit.

In the map (Plate V.) the hills (Kara-knals

Dogb; are inaccurately represented; the slopes run down quite close to Armudii and they touch the porth-east edge of the march.

My lirst copy has ERVN, which is clearly right (and may be traced on the impression)

It is unfortunate that this inscription is so badly worn. Gains Caristanins Fronto was legatus Aug. pr. pr. of the province Lycis-Pamphylia in the reign of Domitian (Sterrett, Epigr. Journ. No. 108: cf. B.C.H. 1886. p. 46, No. 2). At that time he was of practorian rank. After his consulship he evidently became proconsul of Asia,

In the fragmentary state of the inscription, it is impossible to say what was the precise nature of the work undertaken by Fronte. It may be noted. however, that while the enormous marsh which now fills the centre of this plain is almost entirely the result of Turkish neglect, there was probably always a certain amount of marsh near the point where the inscription is engraved; for there is no possible exit for the large volume of water which flows down into the plain from the copious springs at its south-west edge-(below Geneli). Perhaps, then, the accumulation of water at this point had made an impassable barrier, and Fronto opened a new road over it.

P. 112, No. 52. In 1. 8 read την σην οίκτρο[τά]την. In 1. 9, probably γενεή δέ μαι. In l. 10 there appears to have been one letter, apparently a Δ.

between φίλοι and έθευτο; τροφήςς seems certain.

P. 113, No. 53 bis. M. Franz Cumont points out to me that the two symbols are anchors (cp. Kraus, Realeneye, der Christ, Alterthum, s.v. Ancora), thus adding one more confirmation of the theory (already well proved) that the formula έσται αὐτῷ πρὸς του θεον is Christian. This seems to be the only example of the anchor known in Phrygia,

P. 123, I. S from the foot. Delete perhaps also in Marsianns, stc. Markiary) is the Latin Macciana, as Prof. Ramsay points out in Classical

Review, 1898, p. 342, n. 2.

P. 128. A letter from Prof. Ramsay asking me not to publish his NOTE at the end of my second article failed to catch me, as I had left England for the East. His note was written under the impression, derived from a too hasty perusal of my proof-sheets, that his view in Hist. Geogr. differed from mine both about Kaballa and about Tzibreli-tzemani. In reality he inclined to the same conclusion about the latter place as that which I had reached; see his note + on p. 359.

J. G. C. ANDERSON,

MR. G. B. GRUNDY ON PYLOS AND SPHACTERIA.

It is with personal relactance that I, like Mr. Grundy, again take up the argument. It is probably, however, better for the reader if the two sides thrash it out. The main reason why so many of the full-dress debates of archæology, on the \(\lambda\geta\geta\geta\epsilon\) for instance, or the 'Old Temple,' are still obscure for the non-combatant, is because the protagonists seem to get bored with each other's arguments, and pass them over in silence as self-evident fallacies. The result is endless, indecisive summarizing by those not imme-

dintely concerned.

In the present number of the Journal, p. 234, Mr. Grundy expresses his astonishment that the walls on Pylos and Sphaeteria, as photographed in Plates VII., IX. and X., of the preceding number present no more definite marks of date. This is surely a failure to recognize the conditions of the problem. It is a question of "What went ye out for to see!" Did Mr. Grundy expect for the παλαιδε έρυμα a master-piece of Mycenacan splendour, a Lion's Gate or a Tirynthian Gallery! Did he hope that an obliging Athenian sailor had marked wall L on Pylos with an o = ω! The remains exactly answer to Thucydides' description (see J.H.S. xvi. pp. 66, n. 40), and the fact that wall BB of the παλαιδε έρυμα (Figs. 2 and 8) strikes Mr. Grundy as the same in character as wall L (Figs. 6 and 7), though less perfect, is an evidence for my identification and not against it. Thucydides uses the same distinguishing word for both; λίθων λογάδην πεποιημένου in iv. 31, 2, λογάδην φέροντες λίθους in iv. 4, 2.

Mr. Grundy then, if his theory of Cumberland sheepfolds be right, can only say that any such wall as Thucydides describes would defy dating. This he should have said two years ago, and not only after seeing my photographs. What he means by now saying (p. 234) that he has "seen" the walls marked Figs. 2 and 8, it is difficult to determine. He has not been to Pylos since 1895. We have both hitherto assumed that be then either did not see the walls, or mistook them for the stratification of the limestone rock (C.R. Nov., 1896, p. 371. Feb., 1897, p. 2). Is it possible that this is not so, and that Mr. Grundy realized that the remains which Dr. Schliemann, Mr. Bosanquet, and Mr. Crowfoot have accepted as the παλαιόν έρυμα were walls, but thought them so undoubtedly modern that they were not only not worth arguing about, but not even worth mentioning. The second alternative is more damaging to him than the first.

Must we acquiesce, however, in the theory of sheepfolds? Certainly not. We must consider under what circumstances walls of this \$\lambda \circumstances\$ walls of this \$\lambda \circumstances\$ wall BB, three metres as wall C (J.H.S. xviii. pp. 153, 156) could have been made. It is certain in the first place from their position as well as their thickness that one and all of them were military walls, and not houses or sheep shelters. This does not carry us far, but it clears the ground. In the second place it shows want of discrimination to say of the walls on Pylos and Sphacteria that "either might belong to any age" (p. 235). They must be treated separately. The case for Pylos is a strong probability.\(^1\) For Sphacteria it is a practical certainty.

To take Pylos first, then, what military operations could have taken place there of which wall L would be a normal result? I have already applied this test to later classical and mediaval times (J.H.S. xvi. pp. 66-67), and will not multiply proof. If it be urged that the building of wall L in the fifth century 5.c. would have been as abnormal as the building of it at any subsequent time, I can only reply that Thucydides tells us that the Atheniaus built abnormally, and why they did so, and that it is indeed an example of 'another man of the same name,' to turn from an actual abnormal event for the occurrence of which you have detailed reasons given, to an hypothetical one of which you know absolutely nothing. That the survival of an early rough wall is no difficulty has been convincingly proved by Mr. Bosanquet (J.H.S. xviii, p. 156).

The War of Independence, and the historical fact of the siege of Palaeo

Kastro (our Pylos) in 1825 is, indeed, another matter.

It is true that the Greek Insurgents were without knowledge of building, and therefore somewhat in the position of the Cumberland shapherd. It is true, too, that they were given to erecting temporary cover in the shape of 'tambouri.'

It is possible also, though not probable, that their line of defence was here. But though they may have used wall L, it is almost inconceivable that they built it. In the first place so scrious a piece of work could scarcely have been carried through without constant use of the masses of squared stones that stood near at hand. Secondly, 'tambouri' were flimsy cover for markamen, not great continuous walls eight feet thick. But—final, and, I think, conclusive reason—Bory de St. Vincent (Rélation, p. 155) saw 'un tambour' of 1825 during his visit to Pylos in 1829. And it is Bory who was convinced of the very uncient character of wall L. (J.H.S. xviii. p. 156).

But if it is difficult to imagine any circumstances in which wall L on Pylos could be so naturally built as by Demosthenes, the evidence for identification is quite another matter when we turn to Sphacteria. On Sphacteria it is no longer merely a question of a style of building normal

See J.H.S. avi. p. 68, n. 47.
 de St. Vincent, Atlas, Place IV. Estation,
 See James Emerson Diary, p. 148 Hory p. 155.

only at one or two epochs. We have a ground plan which is conceivable only under particular conditions, and we possess detailed information as to military operations in that very period of history where style helps us least. None of the Sphacteria walls could have been built during the Greek War of Independence. We have definite first-hand information in the pages of Collegno and Millingen as to what was done and what was not done on Sphacteria right through the siege of New Navarin up to the day when Ibrahim attacked the island, and the Greeks fled headlong before the charge of the Arab infantry. Collegno in particular was often on the island, 'cosi gaia e favorita,' turning in relief from the squalor and confinement of the besieged town to the "delizie della mia isola" (p. 46). The Greeks put one or perhaps two small batteries in position on the South Point, facing New Navarin, and another at the principal-probably the Panagia landing-place. It is certain that they built no fort on the North Peak. Bur was it the Turks who built the fort? 'It was here, says Mr. Grundy (p. 235), that the Egyptians established their batteries in 1825 in the attack on Pylos. Pylos was maintained by the insurgent Greeks for six weeks against the assaults of Ibrahim Pasha's force (p. 234). One would hardly imagine from this language that the Egyptians were in possession of Sphacteria for less than two full days before Pylos, that is Palaeo Kastro, capitulated. Nor that the evidence for their having during these two days established any batteries at all on this spot, is so shadowy as to be safely neglected. As a matter of fact, it concerns my argument not at all whether they did so or not. Even if they did post a battery on the summit, it is inconceivable that the walls of Mr. Crowfoot's plan (J.H.S. xviii. p. 152, Fig. 10) were built by them to protect it. Their ground plan precludes the possibility of their being built for an attack on Pylos. On the actual summit, the point which does command Pylos, the main frontage of wall BB is to the west and not to the north, to the island itself, and not to Pylos. The north wall of the Hollow (C) fronts north-west, but is in a worse position for commanding Pylos than dozens that could be chosen further west. The south wall of the Hollow (D) is meaningless.

We can put aside then all question of the War of Independence. As certainly can we disregard incidizeval or later classical times. The only use

from Collegno, Jourdain (pp. 170-172), who is worthless, Gordon (pp. 202-205), who was not in Greece at the time, Gouin (L'Egopts on ric-Siècle, pp. 882-384), Prokesch-Osten (i. pp. 363-4), Mendelssehn-Bartholdy (ii. pp. 354-355), Triceuple (iii. pp. 205-206) and Finlay (vi. pp. 359-363). The difference between the Greek and West European Calendars has worked have in the dates. The right dates are midday Sunday, May 8th (our reckoming), for the fall of Sphasieris, and early morning Tuesday, May 10th, for the capitalistica of Palaco-Kastro,

The battle of Navaruse in 1827 gives no scope for wall building on the north. There is mention (Finley, vit. pp. 17-18) of Turkish

The avinious for all this would be of little interest here. I have, however, examined the question with some minuteness, and submitted the details to the criticism of several submitted the details of the creek including Mr. R. C. Bossmont. In latef, I follow primarily the avidence of those eye witnesses, Collegno (Diarro, pp. 42-62), Grasses (apped Emerson, pp. 172, 175) and (with aligh) exceptions) Millingson (Messors, pp. 250-310). Emerson is also, with some qualiterations, a good source, writing his Diary (pp. 130-151) from secondary writing his Diarry (pp. 130-151) from secondary authorities I have laid secons to are Pecchia (apped Emerson, pp. 169-115), who heard the steep

then likely to have been made of the summit was for a watch-tower, and it was pointed out by me in my original article (J.H.S. xvi. p. 63, a. 27) that Leake saw such a tower, and by Mr. Bosanquet (J.H.S. xviii. p. 156) that traces of its presence still exist. The ground plan of our fort, however, is incontestably not that of a watch-tower. It is a stronghold of an early half-civilized people, either pirates themselves, as suggested by Mr. Crowfoot (J.H.S. xviii. 153), or **repixriore* in fear of pirates, as suggested by Mr. Bosanquet (Ib. p. 156). It was built to face an attack by land with short-range missiles, and it guarded against surprise by climbing. The resources of its defence were adequate to meet the resources of attack in those early days. And then alone could it have been built. Of its fitness to be the **valuetor** *Fpupa* of Thucydides' narrative I have already said enough (J.H.S. xvi. pp. 59-63, C.R., Feb. 1897, pp. 1-2).

Mr. Grundy, however, has suggested (p. 235) that the fort has not got a plan at all, that the walls do not make up a homogeneous whole. As regards the south he may have been misled by the fact that Mr. Crowfoot, as stated in the text (J.H.S. xviii. p. 154), did not see wall D, and hypothetically located it too far north. To doctor his plan would have deprived it of all value as evidence, and to wait till he again could visit the spot would have indefinitely delayed publication. The defence on the south is however, in point of fact, unbroken. Wall D does not guard the approach from the interior of the island at all. It was built to bar the gorge to climbers. It is the south-east corner of wall RB that prevented approach to the south of the hollow from the interior (J.H.S. xvi. p. 60). It is possible there was once a wall connection for the yard or two which separates the south-east corner of BB from the precipice. It is possible that a yard or two of cliff has broken down. But there is no difficulty or break of connection. As things stand you could only pass within sword distance of the wall.

Mr. Grundy, however, would answer that the north wall of the hollow shows manifest disconnection with wall BB (p. 235). By this he does not

gum on the wouth of Sphacteria, but no mention at all of the north. If indeed it was at any period thought necessary to but the entry to the Sikia Channel from the side of the island, the point chasen would for a currainty not have been the summit, but the slightly lower hill on the west, which stands between it and the sea-Not only therefore is a modern date impossible. has the possibilities of a mediaval one are conalderably limited. Our walls sould at that period only have been built by a force holding Pyles in prevent an enemy from communiting ii. But not only are the arguments as to style of building as valid here as for wall I, but the fortheation of a small detached outwork, too weak to resist any force that could hope to attack the Great Castle, without a water supply, without means of communication, would be no act of fully of which neither Frank nor Venelian would be guilty, an anomaly in the history of Mediaval Way. They would at least have worked as far as possible on the Burbican prinsiple, and continued the western walls down to the foot of the Sikia Channel.

In point of fact the abort range and small power of artillery up to 1572, when New Kastro (New Kastro) was built, and Palaco Kastro sank into insignificance, would have rendered the tortification of the north of Sphaeteris an annecessary precantion. The great point was to have as small a line as possible open to stack by land. A breach in the south wall of Palaco Kastro, which could only be reached by sea, would be as nothing compared with the exposure of a large part of the garrison to annihilation by land.

merely mean that the evidence for the existence of remains of the connecting wall is not conclusive. He means, as his further words show, that the builders of wall BB would not have built C at such an angle. They would have run it to meet the north-east corner of BB, so that this odd receding

angle would never have been necessary.

Yet it is this very point which gives as clear an indication of date as the hoyábny character of the walls. Where was the gate of the fort? Clearly, as Mr. Besanquet suggested to me many months ago, at the apex of this angle. It was a principle with the makers of early fortifications that the approach to a gate should be covered by two walls, that the enemy should be open to attack from both sides. The builders of the \piahanoidad \text{epopa} were doing with their simple resources what was elaborately provided for at Tiryns and Mycenae.\(^1\) That the principle was not put out of date by the knowledge of flanking towers we see from the presence of such towers in both these citatels.

On other points I have little to say. Mr. Grandy now (p. 228) lays far greater stress than he did originally (J.H.S. xvi. p. 11 par. 1, p. 12 par. 4) on the physicgraphical evidence for the dating of the southern sandbar. Nothing but the decided opinion of an experienced geologist would warrant us to treat this as a case where historical and archæological argument must bow before a law of nature. We have no such opinion. Meanwhile it must not be forgotten that the Boidis Koilia sambar was admittedly formed first. This being so, Mr. Grandy cannot expect us to treat as a scientific certainty for the fifth century s.c. the following remarkable combination of unprovable assertions.

(1) The lagoon must have been navigable right up to Boidia Koilia, so that engines could be landed there.

(2) The southern sandbar must have reached to within about 200 yards

of the south-east corner of Pylos.

(3) No sand could have drifted to this south-east corner,

In regard to the south-east corner Mr. Grundy dwells (p. 233) on the misleading character of photographs to those who have not first-hand knowledge of the ground. He should notice that Mr. Bosanquet had such first-hand knowledge (J.H.S. xviii, p. 158), and that nothing could be more definite than the confirmation which he gives on this point to my views. The reason, of course, that Demosthenes' ships were not destroyed (p. 232), is the one given us by Thucydides (iv. 9, 1), that he protected them by a stockade.


On p. 233 a. 1 Mr. Grundy makes another of his unfortunate charges of misunderstanding. I can only ask the reader who cares to take the trouble, to compare Mr. Grundy's remarks in C.R., Nov. 1896, p. 372 col. 1, my answer in C.R., Feb. 1897, p. 2. col. 2, p. 3 col. 1, his quotation of them C.R., April, 1897, p. 156 col. 1 fin. and col. 2, and my quotation of that quotation in J.H.S. xviii. p. 149. He will see that the misunderstanding is not my

² Schuchhandt's Schliemann, Esp. Trans., pp. 103, 104, 195, 132, 155, 298. Frazer's Processing, Vol. R. pp. 100, 221.

fault. But he will also see that we have both been guilty of obscurity in describing this south-east corner. It should be thought of, not us two distinct slopes, but as a shoulder sloping two ways, to the sandbar on the east, to the Sikia Channel on the south. A glance at Figs. I and 4 (J.H.S. xviii. Plates VII. and VIII.) will extricate the reader from a muddle into which our language may easily have led him.

RONALD M. BURROWS.

INDEX TO VOLUMES XVII., XVIII.



INDEX

TO VOLUMES XVII. XVIII.

I.—INDEX OF SUBJECTS.

Annaevation in inscriptions, xviii 201 Abrettenes, Zeus, xvii. 283
Achaems, late entry into Greece, xviii. xxxiv. Fair-loured, xviii xxxiv. Acropolis on coin of Americles, xviii. 169 Adriania (Mysiai, zvii. 290 Aegean Script, xvii. 227; relation with proto-Egyptian or Egypto-Libyan, xvii. 383 Aegina, antiquities from : Mycensesu bronze knife, xvil. 65; Mycensean marble pyzis, ibid.; Mycennenn pottery, zvii. 77; find of ruses, aviil. 336 Asgis of Athena, xvii. 314: on coin of Solot, writt. 105 Aegium (Achaen), com, xvil. 82 Acathylas, archaeological points in Esmenides, xviil, xu Aske, site, zviii, 83 Africa North, vine-massics, xviii. 69 Agia Paraskevi (Cyprus), bronze-age mcropolis, xvii. 134 Agon on rein, zvil. 80 Agora at Athens, xviii. 330; at Males, xvii Aides = Actes, xviii 83 Algeri (Cilicia), coins, xviii. 161 Akcheler, nr. lake Apollomia (Mysis), in er, IVIL 269 Aksakal, fifteen miles from Panderms (Mysin), lusur, xvii 274 Akshaher, xviii, 113 Al Baladhuri, xviii, 182 Alabiades, prephism of, aviii 329 Alexander of Macadem at Plataiai, xviii. 43 Alp Arelan, Inser., xviii, 343 Al Tabart, xviii. 182

Amazon, wounded, various types, xviii. 142 Ammonina, quotad in de Subdistinte, xvii.

Amounthments at Plateini, rviil 54

Al Ya'kuld, xviii 182 Amalthea and Zeus, xvii. 52 Ammin taken by Araba, xviii. 193

H.S. VOL XVIII.

Amon-cull, degradation under Prolemies, WHIL 239 Amorgos, Mycenasan gams from, xvii, 70: oil-press in, avili. 216 Amorion, Arabs at, xviii. 183, 192, 204 Amphiara a, departure of, aviil. 200 Amphilochos at Mallos, xviii. 163; ar Tarass, xviii. 170 Amphilochos at sacrifice of Polyxons, zvin. 295 Amphitriis of Malos, xviii., iii So also Poseidon imphotan, Types from Grance Phoenician tombs, Larnaka, xvii. 160 Amaya-Sanaos, xvii. 413; insen, xviii. 90 Anazarbos, colne, xviii. 161 Anchor (Christian symbol), aviil, 344 Androcrates, heroon near Plataiai, xviii. 38. Animals, combinations of, in sorly art, XVII 371 Antignotes, sculptor, xvii. 325 Antiochia (Pividiau), Arabs at, xviii. 183 t. Antiochia (Syrian), in the Arab wars (641-750), xril. 183 L Antiochus I, of Commageno, avril. 312 Antiphates at sacrifice of Polyxens, xviii. Aphrodity, Homeric Hymn to, xviii 23. Riding on bull, with 165; of Males, Svill. alt. of Prexiteles, on coin of Chidne, zvii. 89; A. and Eros playing morro, zviii. 129; with bird, zviii. 132 Apollo, an Achasan deity, vriil, txv.; Homaric Hymn to, xvii. 241. On Neutral Dagh reliefs, xviil. 314; I on votive terracotta relief, xvil. 316; on coins of lamos, xviii. 163; of Selinus-Traianopolis, xviii. 164; of Pompelopolis, xviii. 167-169; Lykeios or Tarseus on coins of Tarses, xviii. 173-174 Apollonia ad Rhyndagum, inser, avil 289 Apollonia-Sozopolia, inset, aviii, ba Apollopiemu, Apellonos-hisran, aviil 89 Apotripl spring xvill, 37

1 4

Alquainucha, Sviil., warr Arabs in Asia Minor (A D. 841-750), aviii, 182 Arutos, poviralt, zviii. 167 Arcadian League, federal buildings commed to southern half of Megalopolis, xviii. 18 Archaeology in Greece, 1807-8, xviii. 328 Archelans of Cappulosia, inscr. in honour of, xviil, 317 Archemores, death of, zviii. 270 Arkut Khan, inser., xviii. 124, 127 Armenia, Araba In, xviii. 190 f. : A. minor. inscriptions, zviii. 320) Armudli (Kinnaborion) xviii, 100 Artemis of Aigeira (1) dedication to, xviii. 304 ; A. Hecate, relief from Emed, xvii. 281; A. in Lasedsemon, dedication to, xviii, 302 Artemizium, battle of, avii. 212 Asia Minor, Arab invesions (a.u. 641-750), zwiil. 182 Eastern . rend-system, zwil. 22 f.; inscriptions, xviii. 306 Asopus, River (Bocotla), zviii, 56, 236 Asopos, River (Phrygia) = Gunnah Tohai, Evil. 405 Assar Keni, nr. L Simav (Phrygia), inscr., ES2 Hyz Assarlar, inser., zvii. 283 Athena, on votive terra-cotta reliefa xvii. 307 : Ergane, svii. 308 : Poliss, svii. 310 ; Promochos, xvii 312; Dedication, xvii. 310. See also Happing. Athenian version of battle of Platalat, xviii. Athens, excavations, 1807-5, xviii. 320 Athlete, head of, belinging to Dr. Nelson, xviii. 141 AtH Hissar-Sibidounda, xviii. 105 Attenda, site and inser., xvii, 398 Augusta (Cilicia), coin, xviil, 162 Augusteum at Constantinople, zvil. 109

B

Austrian Institute, foundation, xviii, 325 Azzre (Azar Keul), instr., xviii, 113

B, form in Lahm spagnaphy, xxm. 341
Bacchylldes, Illustrations to, xviii, 267
Baddelu (Phrygia), inser., xviii, 288
Baharlar, inser., xviii, 87
Palat (Mysia), inser., xviii, 290
Balia Madan (Mysia), inser., xviii, 293
Baljik Hissar, xviii, 103, 106
Balki Hissar, xviii, 103, 106
Balki Keni, inser., xviii, 119
Balukiser (Mysia), inser., xviii, 292
Badil, campaign of 876-7, xviii, 34 f.; of 872,
41
Basilies at Constantinople, xvii, 111
Basmaktehi Yalla, inser., xviii, 92
Beyja (Mysia), inser., xviii 270
Bithynia, coin, xvii, 84
Boress and Oreithyis on a late Attic vase, xviii, 136
Borels of Laodiesa, xvii, 408

Brasidas, rocks of, zviil. 148 Bria (Phrygia), site and Inser, xvii, 415 British Museum, antiquities in : Mycenagan; gold fibules (Cyprus), zvit. brome knives (Suris and Aegina), zvil. 64, 65 ; chisel (Suria), xvii. 65 : colt (Saria), avii. 63 marble pyxis (Asgino), xvit. 65 engravel gema (various sites), xvii 05 f. pottery (various sites), xvii, 71 f. vases: B 160, xviii, 274; acquired 1698-1698, xviii, 280 ff. Breuze statuerte (Eros playing morra). XYIIL 131 Gold ring (Aphrodite and Eros), aviil. 1.03 Coins, xvii, 78 f. Brunzu-age nemopoleis in Cyprus: Agia Pamakavi, xvii. 134; Kalopaida, xvii. 135 : Laksha tu Rin, xvii. 147 Ball: led by two men, on Mycenasan gent, xvii. 70; goddess riding on, xviii 165; ball-Bacchos, xviii. 166 Balladan = Apoltonizron, aviii. 80

C (see also K)

CAROTLINA Theorems, Ivin 103 Carnets and the Container, on Harrow vase, xvii. 204; the meening of the legend, 200 Caestreia (Cappalosia), conda from to nest. avil 28 L; to muth, 28 L; to Cilleia, 20 f. : from Schastein to, 31 Calabria, Mycenasan gem from xxii. 69 Calymna, Mycenamh gem from, xvii. 68 a Mycenaean pottery, 75 : oil presses, xviii-210 L Canal of Xerxes, xviil., xzzviil Cambaros, unusual in pottery, xviii. 288 Cappadocia, Byzantine campaigus in, xvii. 33 ; luteriptiona, avili, 316 Carian oil-presses, xviii. 200 C. Caristonius Fronto, aviii, 343 Catagusa (corayoura), xvii, 310 Celt, bromse, from Suria, avil, 63 Centrary and Cornens, avii 254; spirits of the forest, 300 Corres, vasa with Impribed lumar characters, xvii. 349 Chalcidire I cain of rvii 79 Chalcoprateia (Constantimpie), zvii., 111. Chelldung Dinas (Kara-dilli), zviii. 101 Chepne, pr. lake Manias (Mysla) instr. zvii 276 Chisel, bronze, from Suria, xvii, 64 Choban Tepch (Tread), tamnine at, avii. 319 Chrysippos, statue and buss on coins of Pompeicpolia, xviii. 167 Chrysenhous, R at Hierapolis, 13 ii. 113 "Churches, Three," Melos, xvii. 122

Cisero, quoted in de Sublimitate, avii. 195 Cilleia, macriptions from, aviil. 306; cointypes of Cilician cities, xviii. 161; Cilician Gates, inscriptions, zviii, 306

Cherlationa, xviii. 349

Clazomenas, poephian of Aloihindes con-cerning, sviii. 320

Chidus, coin, xvii 89

Colus acquired by B M. (1887-96), xvii. 78; of Ciliain, xviii. 161 Coloneis, Arabe at, xviii. 184

Coloni on Imperial estates, zvii. 421; zviii. 340

Colosses, inser., xviii, 90

Common (Coppidocia) inscr., zviii. 316 Commonene, inser, zviii. 312; passes from Melitene to, zvii. 30

Commantinopie, Arabs near, griti. 184; toptgraphy of Imperial quarter, xviii. 100 Corinth, excessions, avii. 333 Corybantes, avii. 50

Cotys, portraits of, avii. 321

Creeilae, Amazon attributed to, xvnt. 142 Crete, meeting point of Thesco-Phrygian and Libyan alements, xvii. 372; connection with Egypt and Libys, xvii. 362; oil-presses in, xviii. 210; Mycanaan gam from xvii. 67; script, xvii. 327; com-paned with Libyan and Tuareg alphabots,

rvil 365 Crimson, prophylactic, avill., any.

Crossus, story in Bacchylides and vasepaintings, kviii. 267

Crusade, first (1997), xvii. 39

Curator respublicae, wii. 403. See also Kanparan

Cypras, Mycenaean objects from zvil 03; excavations (1894), xvli. 134

Cyrone I coin al, avii. 79

1)

D, form in Lazin epigraphy, xviii 241 Danaides as well-nymphs, avil., azer Death and the Borse, will I Delphi, statues of two Pates at, avail, and Demeter, Homeric hymn to, zvil 49 Devrent, xviii. 84 Diadumence heads, xviii. 144 Dictaean Cave, libation table, &c. from, xvii. Dinne, Ses Chelidonia. Diouyana, Homeric hymna to, xvii. 48; xviii. 28, 31; bearded and horned, xviii 165; bust on coins of Augusts, aviil 168; with Corybantes, aviil 90. Secules Apxi-Bangas, Borpus, Spectreds, Epraveios, Tpierry perce, whene Dioscurt, Homeric hymns to, xviii, 31

Doghan Asar, iner., xviii. 118

Dolichenus, kvlii. 170

Doriseus, site, xviii., azzau.

E

Exuation, silver, from brunze-ago tomb (Cyprus), xvii. 136 Ecclesia personified, xviii. 161 Edinjik (Mysm), inser., xvii. 278 Egypt, "Mycennean" pottery from, xvii. 74; early connection with Urete, aviii. 362 See also Ptolomies Eireslas in Hameric Hymn to Apollo, avil. 242 Elegats, excavations, xvlii, 332 Eldesh, liiser., xviii. 123, 125, 127 Ellesler, inser, tviii. 115 Elpis on coins of Anasarous, &c., zviii. 162 Emal, Inser, avii 281 Ephesus, coin with housing, avii. S7; exeavelieus, 1897/8, xviii 337 Etinyos, xvini., alli-Eres playing morra, xviii. 129 f. Eski Manias, inser., xvii. 276 Etwocler and Polyneices | on b.f. cantharon, XVIII. 290 Eteografes, xviii, xxxiv. Euboca, coins with facing horsemen, xvii. Euphromius, Thesens cap, xviii, 276; Carneus vass of his school, xvii, 207 Eupowia, Aurelia, xviil. 76 Ev iller, inser., xviii. 93 Ezara. See Amara

F

FATES and Furies in Assolutius' Esmenides, Aviil., abl. Female element in Osirio cycle, aviii. 240; succession in Egypt, aviit. 268 Festival coins of Pompolopolis, aviil, 166-Fetishism in Greece, avill. exer. Fibulae, gold Mycensean, from Cyprus, xvii. Fish in Melos Mossie, xviii, 71; fishing, methods of, xviii, 72; with trident, xvii, 22 Flaviopolis = Sis I xviii, 311 Fort, ancient, on Sphacteria, aviii. 151 Fronto, O. Caristanius, zviil 344 Furies in Acchylus' Emeraides, 27111, 201

G.

Gata I present at cape of Oreithyia, aviil Galaxidi, Mycenaesu gem from, xvil. 69 Gargaphia spring xviii, 38, 235 Gazelle in Molos Messic, xviii, 71 Gedil Keni inser., xviii, 113 Gems, engraved, Mysenasan, from various sites, xvii. 65 f.; from Larnaks, xvii 132. 158. See also Beal stones

George Culranus on Nika riot, xvii, 104
Germaniceia (Marush), road from Caesarcia
to, xvii, 28; from Sebesteis to, xvii, 31;
insariptions, xviii, 21]
Geryon. Ses Heracles
Getshid Kent, insar, xviii, 112
Geune, raine near, xviii, 112
Geune, raine near, xviii, 112
Geune Oluk = Taeaxhoon, xviii, 107
Giazz, in insar., xviii, 113
Glass tesseras in Melos Mossic, xviii, 66
Graeco-Phoenician type of lamp (Kalopeida, broass-age, Cyprus), xvii, 139; sanctuary (Laruska, Kamelarga), xvii, 164; tamba (de.), xvii, 152
Graeco-Roman tombs at Larnaka, xvii, 168

H

Gryphen and Apollo, zviii, 209 Gymnasiarch, functions of, xviii, 07

Harres, association with horses [xviii] Hadriani (Mysia), xvii, 200 Hadrianopolis-Sebasto, site and insex., xviii. 110 Hammanli Keni, above Cyzirus, mecr., xvii 275 Herate, in Homeric Hymn to Demeter, xvii, 51; associated with Men in N. Phrygia, zvii. 283. See also Artemis, Exero Melisson, river dividing Megalopolis, aviii. Hellenistic tombs at Larnaka, avii. 162 Herneles, lest sacrifice of aviil, 274; H, and Gerron on b f. lekythan, xviii, 298; H. and Kerberos, xviii, 269; on b. f. vass in B.M., zviil. 292; list of representations. on vases, zviii. 296; H. and Nemean lion, on votive terra-cotta relief, zviii. 317; strangling-motive, aviii. 274 Hernion near Plataini, aviii, 50 Hermas, Homeric Hymn to, xvil. 252; at Phonous, xvii. 83 Hermocome I zwiit. 342, 343. Herodotus on Artemulium and Thermopy lao. avil 212; on Salamis, xvil 230, on the Greeks at Plataial, zvili. 33 Hestia, Homeric Hymns to, xviii. 31. Hierapolis (Phrygla) and its villages, xvii. 411 Hierophant, pertrait of, from Melas, xviii. 74 Holmot (Phrygia), aviil 109 Homeric Hymne, Text of, avii. 45, 241 zvili, 23 Homomoia Sebuste, xvii. 8-1 Horse, association with Death I svill, 1 Horseman to front on coins, etc., xvii. 81 Hydra, Mycemasan gem from, xvii. 58

T

IBS AL ATRIB, xviii. 182
Ibm Wadhich, xviii. 182
Ikcuiou taken by Araba, xviii. 198
Ilghin, luser., xviii. 123, 125
Imperial Betates in Asia Minor, xvii. 431 |
xviii. 340, 342 f.
Ionia, coin with two lions, xvii. 87
Ipsoa. See Julia.
Iris I bead, on Lampsacene coin, xvii. 85
Issuria, Arals in, xviii. 183 (note), 189, 194
(note)
Ishakh, luser, xviii. 111
Isia, importance in Osirie cycle, xviii. 240
Island on field of Plataid, xviii. 37, 50 f.

J

Joux the Lydiau, on Nika riot, xvii, 94 John Malales, on Nika riot, xvii, 95 Julia Ipses, xviii, 110 Jupiter Ballchemes, xviii, 170

K (me delso C)

Kaballa, alto, Evill 120, 128, 344 Kadi Kani, inser, from, xviii, 86 Kadmos, H., zvii. 407 Kallatebos, xviii 86 Kalopsida (Cyprus) bronze-age settlement and necropoles, xvii. 138 Kepron R - Gook Bunar Su, avii. 400 Kara Budak = Sabrina, xviii. 339 Karadilli = Khelldonia, xviil. 104 Karadja-Oren (Holmoi), xviii. 100 Karuum, sile, xvii. 398 Kassaha Kirmusti (Mysia), inscr., xvii. 277 Raysa, inscr., xviii. 326 Kebmit (Mysia) inscr., avii. 201 Kelint, inser, xviil 323 Kenalan, amrifice on, aviii 275 Kerboros, number of houls, avii am. See also Heracles. Kestelek (Mysia), inscr. xvii. 275 Klatab Al Uyun, aviii, 182 Khoma (on the Ak Dagh), xviii. 94 Kiakhta, luses, xviii. 315 Kidramos site (Budjak Keui), and inser. 17TL 306 Kinnsborion, site, xviii 100, Kithairon, Mt., Greek position on, before Plataial, sviii. 35 Knife, brouze, from Surla, xvii. 64, fr Asgina, 65 Kotchash (Hadrianopolia), xviii, 117, inscr. 115 Krobylon, zvii. 90 Krones on coin of Tarson, zviii, 176 Kynoserges, stelae from xvii. 174

1.

hazana ve Rio (Cyprus); bronze age necropolis with Wycenaean vases, zvil. 147

Lames (Cilicia), coin, xviii. 163 Lampe, meer., aviil. 94

Lampacus, coins, rvil. 85 Laodiceia ad Lycum, the rivers of, rvii. 404; limor, 408

Landicela in Syria, burnt by Romana, zviii. 195

Larnaka, inveriptions from, avil. 171; Grasco-Phoenician and Hellenistic tomba at Turnhi Teké, avii, 152; Gracco-Phoenician sanctuary at Kamelarga, xvii 164; excavations at Rutsales, zvil. 170

Lausna, Palaco of (Constantinople), avii

Legio XV. Apollinaris at Satala, xviii, 321 Legio XVI. Fluria Firma at Samsat, aviil 315

Lesbos, oil-presses in, xviil. 217 Libation-table, inscribed, from Diktasan cave, avii, 350

Libyans in the Nile valley, avii, 300; comnection with Greeks, avil 373; Libyan elements in Cretan culture, will 372; alphabets compared with Cretan and Aegean ecript, xxii, 385.

Lione, two, confronted, on electrum coin, xvii. 87. Lion and bull, coin-type of Taraoa, xviii. 175

Longinus, Dionysius, Treatise on the Sub-

lime ascribad to, xvii. 170 Lopadium (Mysia) inser., xvii. 271 Lousel, excavation, xviii. 334: Proctidus at, xviii. 271.

Lycia, coin, xvii. 90 Lyme river, xvii 405 ; bridge over, xviii 89 Lysias, xviii, 107

Mackbox, Philip II., com of, xvii. 70 Massade and satyre dancing, on Nikosthenes vase, xviil 202 Mahmud Aver, inacz., rvill 129, 124, 126 Mulatin. See Malitone Males, descent through, xviii., xxxv Mallos (Cilicia), coin, xviii. 163 Mantinea, area compared with that of Megalopulis, xviii. 20 Mantingan basis, xvii. 120 Maresh. See Germaniccia Marcellinus on Nika Riot, xvii. 92 Marriage of brother and sister in Egypt, rvili. 244 Mater austropum, xviii. 822 Maurus, Terentianus, xvii. 205 Megalopolis, a. double city, zviii, 15; compared in area with Mantinea, xviii, 20 Megara (Greece), excernations, xviii, 232 Melampus and Proceidae, xviii, 271

Melesger, death of, zviii: 269 Melissa, site, xviii: 106

Melitene, roads from Cassareia, xvil. 22. passes into Commagene, xvii, 30; Amba in, xviii. 184, 190 f.; inscriptions, xviii

Meles, suscriptions, swil 1; Myconacan gem. xvii. 68; oil-press, xviii. 213; Aphredite of M. xviii. xii.; excavations on sits of 'Three Churches,' xvii. 122; agora, xvii. 131; hall of the Mystae and mossic, xviii. 60

Men and Hecate in N. Phrygia, xvii. 283 Meron (Phrygia) site and inser, avii. 422, xviii. 341, 342

Mesopotamia, frontier were (641-750), aviil.

Metropolis, roads to Synnada, xviii. 191 Mikhalich (Mysia) inser., xvii. 271 Mikkindes, name of, on basis at Paros, zviil. 336

Milatopolis (Mysis), zvit. 271 Minotant' scheme in early art, xvii, 370 Missia (Mopementia), inset., xviii. 307 Mocris, lake, reclaiming of, xviii. 251 Moimul (Mysia) Inset., xvii. 281 Monandry in Homer, xviii., xxxv. Moni near Amatine, fibulae from, xvii. 63 Moragocomo i xvill. 342, 343 Morra, the game, xviii. 129 Mousie from Meles, xviii. 60

Moses, quoted in Tomtise on the Sublime, 1vil 194

Mucina (Q.) Smevals, zvil. 277 Mycenae, gem from, xvii 00; Mycenaean antiquities in R.M., xvii. 03; Mycenaean vases from Laksha tu Riin xvii, 151

Myela, inemiptions, xvii. 288 Myelae, Hall of, at Melos, xviii. 80; societies in Greecz, 78 Mytilene, coin, xvil. 86

N

Nancinan (Mysia) izner., xvii. 279 Necklace described in Homeric Hymn to Apollo, xvii. 244

Necropoleie in Cyprus: bronze-age, at Agia Paraskavi, xvii. 184; Kalepsida, xvii. 188, 140; Laksha in Rin, xvii. 147; Graeco-Phocuician and Hellenistic, Larmaka, xvii. 159

Numera Lion. Sea Heracles Nomrad Dagh, reliefs and inser from, aviil 313

Neoptolemos merificing Polyxena, aviil. 285 Nika rlot, xvil 92

Nike, head of I, on Lamp-mone coln, avii 85; temple of N. Apteres, inecr xviii 329

Nikopolis (Armenia Minor), xviii. 32-1 Nikosthones, b. f. kyathos by, xviil. 292 (0)

Octagon (Constantinople), zvii. 112
Oil-presses, zviii. 209
Oinan = Lysias, zviii. 107
Oinos besieged by Archidamus, zviii. 225
Okeanide, names of, zvii. 60
Oktchular, inser., zviii. 342
Olympicion (Athens), excavationa, zviii. 330
Omar Keni, nr. Penderma (Myses), inser., zvii. 273
Omphales, Apollo on, zvii., zz.
Onchestus in Homeric Hymns, zvii. 247, 255
Optimus, proconsul of Asia, zviii. 341
Oreithyia and Boress, zviii. 136
Osiris-worship under the Piolemies, zviii. 239

P

Parago Kastno in 1825, xvill 346 Pallas, winged, xviii. xitti Pan, Homeric hymn to, xviii. 29 Panathenaic amphoriskos, xviii. 300 Panderna (Mysia), inser., xvii. 274 Parorsios, Phrygis, zviil, 110 Paros, discoveries in, zviii, 336; Parian Chronicle, new fragment, aviii 336 Parthenon, repair of, 1847/8, xviii. 329 Paschal Chronicle on the Nika Biot, xvii. Pausanias at battle of Plataini, zviii. 36 f. Peirene (Corinth), excavation, xviii. 333 Peresiae in Homeric Hymn to Apollo, zvii. 949 Pelasglans, xviii., azaiv. IL "Pelopomesian" vases, xviii. 283 Perfectinimus, xviil 342 Perrin, inser., xviii, 316 Perseus on coius of Tarsos, xviii. 174 Phagres, site, xviii., xxxvi Phazemonitarum Thermae, inscr., xviii. 326 Pheneus, cain, avil 83 Philae, threatened ruin of temples, xviii. Philemon (f), portrait on come of Pompeio-polis, aviii 168 Philip II. of Macedon, coto, avii 70 Philometico, inser., xviii 111 Phorasa, coin, xvii. 89 Phradmon (I), head by, xviii. 145 Phrygia, explorations in, avii. 396; aviii 81, 340 Phrygo-Lydian frontier, xviii. 81 Pictographs, Cretan; xvii, 331 Pingan, luser, kviii. 22) Plataes, the Greeks at, xviii, 33; Thukydidee description of the siege, zviii. 218: importance of the place, aviii, 225; criticism of Woodhouse's theory of the bettle, xviii. 235 Plenrem (f), New, aviil. 335

Poemanenum (Mysla), xvii. 271 Polycephalous monsters, zvii., zu Polynta, xviil. 342, 343 Polyxens, sacrifice of, xviii. 284 Pompeiopolia. See Soloi Pampeius on coins of Pompeiopolis, xviii. 166 Pontus, macr., xviii. 325 Pesciden, Pelasgie, gvill, grav ; strohaic branze statue from Dombréna, zviii. 332 ; P. of Melos, zviii zu ; with Amphitrite at Tenes, with the his trident, will, El. Pressos for clive-cil, zviii. 200 Priene, excavations, 1897/8, xviii. 338 Priest-class under the Ptolemies, zviii. 238 Proceeding on the Nika Ring, xvii. 92 Proctos, daughters of, xviii. 271 Province of Asia, accidence, xvii. 277 Ptolemies, their policy of marriage and succession, xviii 243; women in their age, aviil 238 Purk (Nicopolis), inser., xviii. 324 Pylas Ciliems, xviii, 307 Pylos and Sphaeteria, xvili. 147; Thucydi-des' description of the operations, xviii. 218, 228; criticism of Burrows' theory, xviii. 233; of Grandy's, xviii. 345 Pyxis, marble, from Asgina, xvii. 65

Q

QUADRIGA seem to front on coins and vasm, xvii. 81

H

Rap, prophylactic significance of, xvni., sity.

Rhaescuporis, King, xvii. 322

Rhodes taken by Araba, xviii. 187, 189

Ring, gold, from Lampsacus with morra, xviii. 129; in R.M. with Aphrodits and Eros, xviii. 132

Road-system of Eastern Asia Minor, xvii. 22; Royal Read, xvii. 41

Romanus IV, campaign of 1088/9, xvii. 36

Royal read, xvii. 41

Russiler (Mysia), inser., xvii. 200

S

Sabaixa, river = Kara Badak, zviii. 320 Sadazh See Satala Saujilar (Phrygia), inser., zvii. 236 Sala, site of, zviii. 51 Salamis, battle of, zvii. 230 Samesata (Samest), inser., zviii. 312 Sanace, See Anava "Sanlanapalus, monument of," zviii. 189 Saria. See Suria Satale, meer, xviit. 321; a colony, xviii. 255

Salyis duncing, on Corinthian vasse, xviii. 287; with Macnads, on Nikosthanes kyathos, xviii. 202

Scal-stones (Cretan), with linear characters and figures, xvii. 329-346; with early pictographs, 331; with conventionalised pictographs, 334; surly presussed from Karnak (Egypt), 362. See also Game

Schuste Hadrianopolie, ette uml insar xviii. 110

Schattela taken by Arabs, will, 123; results radiating from, xvil. 31

Selene, Homeric hymn to, xviii 31 Selencia ad Calycultum, soin, zvii: 90 Selinda, site (Sclind), xviii 115 Selinus-Trainnopolis, ccina, xviii 164 Seraijik, inser., xviii 319 Shahr, inser., xviii. 310 Schulennia zviii 104 Siblia, in inser, xviii, 03

Slegs operations as described by Thurvilides, xviii. 218; a new feature in 6th century, krili. 219

Sikyon, coin with dedicatory user, zviii.

Simay, lake (Phrygan, tuser, avii. 285 Siren on oenochoe from Aegina, xviii. 281 Sia (Siaian), road from Caesarcia to, xvii. 🕮 ;

ineer, aviii. 310 Sivri Tepe, inscr., xviii. 325 Siava, city of the, xviii. 194 Smyrns, coin with Boos, xviii. 304 Soloi-Pompeiopolis, coins, xviii. 165

Secopolis, See Apallonia Sparta, Mycenseen gem from xvii. 69

Splincteria. Ses Pylos Stanoikes of Crprus, coin, xvii. 165 Stelse from Kynostrges, xviii. 174; grasping

of the terist on Attic Stelne, aviii. 133 Sublime, treatise on, aviil, 170; its authorship, 180

Suria (ur. Karpathes), brouse implements from xvii. 64

Sybrita, codn, xvii. 83

Symbols (conventionalised), on Creum pretographic salacavii. 339

Synnada, roads from Metropolis, xviii. 101 Symmer, Thueydides description of the tinge, xviii 218

Syria, frontier wars (641-750), xviii, 203

T

TACHTALL, near Bruss, luser, xvii, 268 Tacitits, Dialoger compared with de Sublimitate, xvii. 200 Tames, coins of, sviii. 169 Tash Kani (Mysis), inser, xvil 289 Tavaluanii (Mysia), inser., xvii. 279 Tar Klei plain: xviii; 91

Tchadsly) Keul (Hghin lake), xviii. 124. 120

Tchigil, meer., xviii. 119

Tchivrili tchemani, aviil. 121, 138, 344

Tegents at Platniai, zviii. 41 Tekke Keui, inscr., aviil, 127

Tembrion, Imperial Estate at (inscr.), xvii

Tephrike, road from Schasteia to, xvil.

Terahtianum, addressed in de Sublimitate, zviil 105, 203

Terra-cottas, votive, from Larraka, xvil. 164; reliefs in Acropolis Mussom, xvil.

Theatre of New Pleuron (7), xviii. 335 ; of Prienc, xviii, 339

Thebe on vase of Assteas, aviii. 271 Theodovidas, son of Daistrates, dedication by, XVIII., XII.

Theodorus, quoted in de Sublimitate, zvii

Theodorus Lector on Nika Riot, xvil. 94 Theophanea on Nika Riot, xvii. 101 Thermae Phazemonitarum, Inscr., Iviii 326

Thermon, excavations, xviii. 335 Thermopylus, battle of, xvii. 215 Theseus and the ring, aviil. 276

Thracian colonists at Apollonia-Sozopolis. aviii. 96

Thraco-Phrygian elements in Cretan culture, SVIL 272

Throwdides, his detailed account of sieges, swill 218

Thymbrion, xviii. 116 Thynnaros, hero of Synnada, aviil. 108 Tiryus, Mycamican pottery from, xvii. 75 Tombs. See Necropoleis

Totemism in Greece, xviii, xxxx. Trainopolis. See Selinus Tralla, sits of / xviii, 83, 65

Trapezopolis, site and inscr., xvii. 401 Tree-spirits: Caenens and Centaurs, xvii. 202

Trident of Poseidon, xvii, xi Tripolitan oil-presses, xviii. 200 Trophimus, M. Marius, hierophant, xviii.

Tuareg alphabet compared with Cretan and Aegean script, xvil. 385 Tumnius of Choban Tepch (Troad), excava-

tion, xvii. 319

Tyana taken by Arabs, xviii. 191, 192 Tyche on coins, seated, xviii. 161, 163, 166, 179; adoring, 166, 167

Tyclafon, timen, xviil. 121

U

ULCBAD (Lopadium), inser., xvii 271 Ulaboriu, inser., zviii 95

Valentrus = Valent, zviii. 300 C Va[[](criss) [Ter]tallies or [Ter]talliams, lighter day, pr. pr., xviii 320 Victor Tennenness, on the Niks Rist,

zvii. 94

Vine-moratos, zviii. 69 Votive figures from Larnaka, zvii. 164 : terra-cotia reliefs in Acropulta Museum, xrii. 306

Watt-son Pylos and Sphnotonia, xvlii, 234, 345 Warrior, departure of (b.f. cantheron), xviii, 289, Warriors playing with record, eviii, 294; preparing for battle (b.f. kylix), xviii 291; combas over fallan warrior, xviii, 289

Woman in Ptolemaic Egypt, xviii. 238 Wreath adorned with human heads, on come of Tarsos, aviil. 179

Wrist, grasping of, as greeting, xviii 133

X

XERES, march of, zvill, xxxvil.

YAKA SINEK, IBSET., EVILLA III Yarsawat, itser., tviii. 310 Yemishli (Phrygia), inesr., xvii. 889 Yemish Keni, inser., xviii. 118 Yemije, n. of Assar Kale (Mysia), inser., xvii. 293 Yenije Keni, nr. Emed (Mysia), meen, xvii-283 Venije Kem, nr. Panderms (Mysis); mec.,

Z

Zaumanias of Mytilene, continuation of, on the Nika Blot, avil 95 Zázukas (Cyprus), lato bronze-age site, xvii

171

Zens, avii 416; Homeric Hymn to, aviii. 30 ; Z. ami Amalthua, xvii, 82; See also Abitettetres, Karmelarae, Koansymia, Migroros, Ospainos, Hardquee, Zárqu Zibatra, xviii. 208, note, ami Corrigendum

Zonaras on Nika Blot, xvil. 101

H.-GREEK INDEX.

Αγκιστρεία, κγίϊ, 72
Αδράστημ (gamus), κνίι, 410
Αδραστος, Μίσηρ, κνίι, 400
Αδραστος, Μίσηρ, κνίι, 400
Αδραστος, Μίσηρ, κνίι, 400
Αδραστος, Μίσηρ, κνίι, 400
Αδραστος βουλη καὶ δημος, κνίι, 200
Αδημαίρ (ματικό), κνίι, 204
Αλεξασδραστός (Tarnos), κνίιι, 178
Ασταδραστός (Tarnos), κνίιι, 173
ἀποδραστός (Tarnos), κνίιι, 173
ἀποδραστός κνίι, 86
ἀποδραστός κνίι, 86
ἀποδραστός κνίι, 86
ἀποδραστός κνίι, 410
Αραγονησοί, κνίι, 410
Αραγονησοί, κνίι, 413
Αρκοδραστός κνίι, 413
Αρκοδραστός κνίι, 70
Αρχιδοδραδος, κνίιι, 73
Αρχιδοδραδος, κνίιι, 73
Ατζιδοδραδος βουδραστός κνίι, 414, 416
Αττακόσου ὁ δημος, κνίι, 414, 416
Αττακόσου ὁ δημος, κνίι, 300
ἀφημως, κνίι, 245

4 1

Baseline, xviii. 73

Bakken, xviii. 73

Bakken, xviii. 73

Bakken, king, xviii. 96

Bakken politon, xviii. 242

βaux = βu(σιλε) ψτ an coins of Smyrns, xviii. 304

Bakken politon, xviii. 91

Bakken politon, xviii. 98

Barris Σορνών, xviii. 98

Barris Σορνών, xviii. 175

Barris Σορνών, xviii. 175

Barris (Dionyman), xviii. 178

Baukenin yedn 'Arrislie (Laudices), xvii. 408

Bpeliorio (Hionyman), xviii. 78

[Bplande, xviii. 416

Perendurin, aviil. 107

Δεία Σεβαστά οδοσφενικό, ενίι. 410 Δία, ενίι. 410 διασφεύτοτος, ενίιί. 342 διατοεία, ενίίι. 72 H.S.—VOL. KVIII. διωγμίται, χντιι. 123 δαμεστεκών, εδμης τών, χντίτ. 326] δώς, χντί. 54

Edvor, devos, aviil. 24 Εβρ[αίων συν]ογωγή, ανίίί. 333 είρηνάρχης, ανίίι. 123 elerkaerina, zvii. 410 sianovčios - anovčnios, XVIII. 126 Ecclifoid personified, sviii. 161 Exera, xvii. 283. See Dareino, Dargon. PAIR AVIEL 1 /aBohāda, xviii. 308 /Ferancai (Lasdices), xvii. 408 /Engylai, y', xviii. 181 /Engway, 600 (Marash), xviii. 311 experiment, xvii, 402, 403 extremos LeSurrão, avii. 200 empariarares Kaurop, aviii. 101, 318 spomorai, triil 78 Epivers, xviii., x14 έρομα, πολικόν, on Sphaoteria, xviii, 132, 234 είγενείτ πιανοί θεοφιλείς Μακεδόνες (Aignai), zviii. 161 remulio, xvii. 261 Eignemaridae, xviii. 216. ebyá, svil. 83

'Hμιόβελιν, xvil. 93 'Ηρόκλειπ (games), xvii, \$10

Och Meyiorn (Mā), xxiii. 316 Ochologia, xxiii. 75 Ochologia. Sie régionic Guadami, xxiii. 78 Ocho of tombs, xxiii. 05

'teparojan, xvii. 87
'Isponoleiros | Comano, xviii. 218 | Hierapolis, Phrygia, xvii. 411
ispocioreus, xvii. 14
'Thaidys for 'Οιλαίδης, xviii. 280
[Tooliy]no, xvii. 110

B B

Kallagioguros Esperariros, xviii. 326 Kampuy (river), zvil. 403 rapog, ivi, triii. 134 sarayus, avil. 310 Karaufaras Zeils, xvii. b. O. Karauffargs. carnein, y Mesopenie, Xvil, 423 estronou de l'Olaßas l xvlii 87, 312 | estrono, tviil 28 Kidpor (suggested place-name), xviii, 300 Kagaganess xvii, 420 ed = soi, xviii. Ol Ripes Bowley, with all σωντικρόρος, χνικι. 70 Alau ro Arriande, avii 119 ederós, xviii. 0 Avránakos, zviil I ελυνός, απίξε. 1 ποινός δήμος Μοξεανών Σοησών, απίξε. 410 esharol aviil 90 κόμης τών αυθοσωυμένων δομεστικών, χνίτι. 326 secrement, Trill. 72 Körne Samilier, XVII. 322 experience, Office, arill 320 spaniver, xrii, 263 Kumphyide Zele, xvil. 293 sparapiapyor, xviii, 70 suprem, sopre, xviil. TX count of Histapolis, avil, 411 saluloya, zvii, 412, 420

Δομουδηδρομώι on Panathenaic amphoriskos, xviii, 200 λομογρόνοντας, xviii, 342 λουμοφόμος, xviii, 70 λογοντήν ab Trapezopodis, xvii, 403 Λυκόκοπρος (river), xvii, 405 Λυκον (river), xvii, 405

Må (goddens of Comana), aviil. 317

Maßleyaier, Maµßleyaier, aviil. 316

Marrôlier. Ser répresir

Màs ô Handrer, aviil. 283

Méyer Zeir Odphano, aviil. 310

Méyerrer Zeir, aviil. 403, aviil. 310

Méyerrer (Morrearder) Logrador öğund daridi, aviil. 410, aviil. 311

Maserier, aviil. 270

Maserier, aviil. 13, aviil. 78

pearrepain, aviil. 275

Neism "Appear, 27th 275 Newsonchelrys, 2vii, 275 seen, of (Attinta), 2vii, 399 sounds, 2vii, 59

z in Melian spigraphy (I), zvil 6

Oδμη δζει, 1916. 50
olson, olson = Intl of Mystan, xviii. 50
olson, olson = Intl of Mystan, xviii. 50
olson, μέσρη, είσελαστικά εἰς τὴν, xvii. 410
nhoseprinen, xvii. 410
olyosel, κότοικοι ἐν, xviii. 87, 342
Oλυμπια, πνii. 410
olyosela, πνii. 410
olyosela, πνii. 410
olyosela, πνii. 27
Oμοπία (tribe), xvii. 84
doyselev, xviii. 27
doyselev, xviii. 78
doyselev, xviii. 50
Oμοκ Κιλίκων, xviii. 300
Oνωίνων Zels, xviii. 310

ŧ

Harmony, Mar. Tvil. 283 managenimen, Xvii., all. Hardquar, Zeve, xvil. 280 mpompilaces, xvii. 411 тартрикатты, күй. 412 Hapdoor, xxin., xill. marpus vos makeas, avil. 408 Harpeos (Persua), zviii. 177 Harpeo (Aphrodite), zvii. 291 verterrapisol dymers, zvii. 410 verisiones, zvil. 18, zviil. 79 seegol, XVIII. 291 reard. See edgesels -rokes in compounds, svlii. 3 nposabe(oping (Tatsos), xviii. 173 mountainer rip without, Evil, 402 spierovkor, zviii. 98 mourningsgrass, Avil 202 sporance rije dvdije, avis. 408 svdijšćeoc, avis. 283 aupipa, xvili. 200 makrioban, xviil. 3 rolog aviii. 1; in compounds, xviii. 3

Treesecoda, xviil 288

Σουπηνών ὁ δήμος, xvil. 414
Σεβουτὰ οἰεσομετικά (Δεία), xvil. 410
Σεβουτὰ οἰεσομετικά (Δεία), xvil. 410
Σεβουτὰ ὁ βούσια, xvii. 84
Σεβουτὰ (Φιολγασι), xvii. 78
Σορκών Βέρνει, xvii. 384
Σορκών Μοξειινών (Τοττεπινών) και δι δήμος, xvii. 410
[στε βμιορφήρος, ετίι. 414
στοιά, xviii. 88
στριτόρχηι, ενίι. 410
στριτηγούν ἐπὶ τῆς χώρος, ενίii. 123
σύσιτημος, xvii. 308
Σωντίμη Ένικτη, xvii. 294
Σωντίμη Εκίκτη, xvii. 294
Σωντίμη Εκίκτη, xvii. 293
Σωντίμη Κείκτη, xvii. 293
Σωντίμη, Σκίκ Μέγιστος, xvii. 408
Σωντίμη, Σκίκ Μέγιστος, xvii. 408
Σωντίμη, χνii, 276

Tapar, Tvill. 401 rément des rols, Xvil. 48 restaufantes, Xvill. 3 Terrand, xvii 420, xviii 311
Temrfordative βουλή, xvii 403
τράφοι = τίκροι, xviii 63
Τοιμθοία, Τεμισθούς, Γρεμυθία, xviii, 62
τρίσιου, xvii. (xii.)
τρωδοττα, τρώδουτ, xvii. (xi.)
Τρατησίκου Διάνουσε, xvii. (xi.)

Υλοπόμον, χνίλ 56 Ιποβρυχίας, χνίλ 257 Δπατάμεσε, χνίλ 56 represental by O, avii. 89
 4ddoor on rase with dunth of Maleager aviii, 269
 4λλως (Dignysen), aviii, 76
 4ρατροοτ, Ζευτ, ανiii, 330
 φολυκίτει, ανiii, 412
 φολη Βενίτων, ανiii, 98

Approphisaros, Kriita 3

r in Molian ophyraphy, xvii. 5

REMARD CLAY AND SONS, LIMITED, LONDON AND RESULT.



























BOREAS AND OREITHYIA.






FIG 1. PYLOS, S.E. KROM FAND-HATT



FIL 2. SPHACTERIA WALL RE N.W CORNER.



FR & FYLOS. WALL BEHIND L





Fig + POLOS, FROM IN MALTERIA



FIG. 5: MYLDS S.W. BIGASIDAS HOOKS






FIG 8. PYLOS. WALL L



FIG. T. PYLOS. WALL L. FROM A DISTANCE.






FIG B. SPHACTERIA, WALL BB. S.W. CORNER.



FIG. 9. SPHACTERIA. WALL D.




THE R RELIEVED TO THE PARTY OF THE PARTY OF










CILICIAN COINS

Polygraphuschen hashital A.6. Zarech







CILICIAN COINS


Polygiaphowhasi hastrias A-U Tarach





















FIG. L COMBAT OF WARRIORS



FIG. 2. KYATHOS BY HIKOSTHENES.







"A book that is shut is but a block"

A book that to some process of the sound to the sound to

Please help us to keep the book clean and moving.

S. S. SAR, OR DELECT